



Avid® Media Composer® and NewsCutter® Effects and Color Correction Guide

Legal Notices

Product specifications are subject to change without notice and do not represent a commitment on the part of Avid Technology, Inc.

This product is subject to the terms and conditions of a software license agreement provided with the software. The product may only be used in accordance with the license agreement.

Avid products or portions thereof are protected by one or more of the following United States Patents: 5,267,351; 5,309,528; 5,355,450; 5,396,594; 5,440,348; 5,467,288; 5,513,375; 5,528,310; 5,557,423; 5,568,275; 5,577,190; 5,584,006; 5,634,020; 5,640,601; 5,644,364; 5,654,737; 5,724,605; 5,726,717; 5,745,637; 5,752,029; 5,754,180; 5,754,851; 5,799,150; 5,812,216; 5,828,678; 5,842,014; 5,852,435; 5,905,841; 5,929,836; 5,930,445; 5,946,445; 5,959,610; 5,986,584; 5,987,501; 5,999,406; 6,016,152; 6,018,337; 6,023,531; 6,038,573; 6,057,829; 6,058,236; 6,069,668; 6,091,778; 6,105,083; 6,118,444; 6,130,676; 6,134,607; 6,141,007; 6,141,691; 6,198,477; 6,201,531; 6,211,869; 6,223,211; 6,249,280; 6,269,195; 6,330,369; 6,353,862; 6,336,093; 6,404,435; 6,407,775; 6,426,778; 6,477,271; 6,489,969; 6,512,522; 6,532,043; 6,546,190; 6,552,731; 6,553,142; 6,570,624; 6,571,255; 6,583,824; 6,596,031; 6,618,547; 6,665,450; 6,678,461; 6,687,407; 6,704,445; 6,728,682; 6,747,705; 6,763,134; 6,763,523; 6,766,063; 6,766,357; 6,791,556; 6,810,157; 6,847,373; 6,871,003; 6,871,161; 6,901,211; 6,907,191; 6,928,187; 7,043,058; 7,081,900; 7,103,231; 7,266,241; 7,280,117; 7,403,561; 7,433,519; 7,441,193; 7,512,885; 7,545,957; 7,671,871; 7,684,096; D352,278; D372,478; D373,778; D392,267; D392,268; D392,269; D395,291; D396,853; D398,912. Other patents are pending.

Avid products or portions thereof are protected by one or more of the following European Patents: 0506870; 0635188; 0674414; 0752174; 0811290; 0811292; 0811293; 0857293; 0976108; 0988756; 1050048; 1068723; 1068734; 1111910; 1173850; 1629675. Other patents are pending.

This document is protected under copyright law. An authorized licensee of Avid Media Composer, NewsCutter, or Symphony may reproduce this publication for the licensee's own use in learning how to use the software. This document may not be reproduced or distributed, in whole or in part, for commercial purposes, such as selling copies of this document or providing support or educational services to others. This document is supplied as a guide for Avid Media Composer, NewsCutter, or Symphony. Reasonable care has been taken in preparing the information it contains. However, this document may contain omissions, technical inaccuracies, or typographical errors. Avid Technology, Inc. does not accept responsibility of any kind for customers' losses due to the use of this document. Product specifications are subject to change without notice.

Copyright © 2010 Avid Technology, Inc. and its licensors. All rights reserved.

The following disclaimer is required by Apple Computer, Inc.:

APPLE COMPUTER, INC. MAKES NO WARRANTIES WHATSOEVER, EITHER EXPRESS OR IMPLIED, REGARDING THIS PRODUCT, INCLUDING WARRANTIES WITH RESPECT TO ITS MERCHANTABILITY OR ITS FITNESS FOR ANY PARTICULAR PURPOSE. THE EXCLUSION OF IMPLIED WARRANTIES IS NOT PERMITTED BY SOME STATES. THE ABOVE EXCLUSION MAY NOT APPLY TO YOU. THIS WARRANTY PROVIDES YOU WITH SPECIFIC LEGAL RIGHTS. THERE MAY BE OTHER RIGHTS THAT YOU MAY HAVE WHICH VARY FROM STATE TO STATE.

The following disclaimer is required by Sam Leffler and Silicon Graphics, Inc. for the use of their TIFF library:

Copyright © 1988–1997 Sam Leffler
Copyright © 1991–1997 Silicon Graphics, Inc.

Permission to use, copy, modify, distribute, and sell this software [i.e., the TIFF library] and its documentation for any purpose is hereby granted without fee, provided that (i) the above copyright notices and this permission notice appear in all copies of the software and related documentation, and (ii) the names of Sam Leffler and Silicon Graphics may not be used in any advertising or publicity relating to the software without the specific, prior written permission of Sam Leffler and Silicon Graphics.

THE SOFTWARE IS PROVIDED "AS-IS" AND WITHOUT WARRANTY OF ANY KIND, EXPRESS, IMPLIED OR OTHERWISE, INCLUDING WITHOUT LIMITATION, ANY WARRANTY OF MERCHANTABILITY OR FITNESS FOR A PARTICULAR PURPOSE.

IN NO EVENT SHALL SAM LEFFLER OR SILICON GRAPHICS BE LIABLE FOR ANY SPECIAL, INCIDENTAL, INDIRECT OR CONSEQUENTIAL DAMAGES OF ANY KIND, OR ANY DAMAGES WHATSOEVER RESULTING FROM LOSS OF USE, DATA OR PROFITS, WHETHER OR NOT ADVISED OF THE POSSIBILITY OF DAMAGE, AND ON ANY THEORY OF LIABILITY, ARISING OUT OF OR IN CONNECTION WITH THE USE OR PERFORMANCE OF THIS SOFTWARE.

The following disclaimer is required by the Independent JPEG Group:

This software is based in part on the work of the Independent JPEG Group.

This Software may contain components licensed under the following conditions:

Copyright (c) 1989 The Regents of the University of California. All rights reserved.

Redistribution and use in source and binary forms are permitted provided that the above copyright notice and this paragraph are duplicated in all such forms and that any documentation, advertising materials, and other materials related to such distribution and use acknowledge that the software was developed by the University of California, Berkeley. The name of the University may not be used to endorse or promote products derived from this software without specific prior written permission. THIS SOFTWARE IS PROVIDED "AS IS" AND WITHOUT ANY EXPRESS OR IMPLIED WARRANTIES, INCLUDING, WITHOUT LIMITATION, THE IMPLIED WARRANTIES OF MERCHANTABILITY AND FITNESS FOR A PARTICULAR PURPOSE.

Copyright (C) 1989, 1991 by Jef Poskanzer.

Permission to use, copy, modify, and distribute this software and its documentation for any purpose and without fee is hereby granted, provided that the above copyright notice appear in all copies and that both that copyright notice and this permission notice appear in supporting documentation. This software is provided "as is" without express or implied warranty.

Copyright 1995, Trinity College Computing Center. Written by David Chappell.

Permission to use, copy, modify, and distribute this software and its documentation for any purpose and without fee is hereby granted, provided that the above copyright notice appear in all copies and that both that copyright notice and this permission notice appear in supporting documentation. This software is provided "as is" without express or implied warranty.

Copyright 1996 Daniel Dardailier.

Permission to use, copy, modify, distribute, and sell this software for any purpose is hereby granted without fee, provided that the above copyright notice appear in all copies and that both that copyright notice and this permission notice appear in supporting documentation, and that the name of Daniel Dardailier not be used in advertising or publicity pertaining to distribution of the software without specific, written prior permission. Daniel Dardailier makes no representations about the suitability of this software for any purpose. It is provided "as is" without express or implied warranty.

Modifications Copyright 1999 Matt Koss, under the same license as above.

Copyright (c) 1991 by AT&T.

Permission to use, copy, modify, and distribute this software for any purpose without fee is hereby granted, provided that this entire notice is included in all copies of any software which is or includes a copy or modification of this software and in all copies of the supporting documentation for such software.

THIS SOFTWARE IS BEING PROVIDED "AS IS", WITHOUT ANY EXPRESS OR IMPLIED WARRANTY. IN PARTICULAR, NEITHER THE AUTHOR NOR AT&T MAKES ANY REPRESENTATION OR WARRANTY OF ANY KIND CONCERNING THE MERCHANTABILITY OF THIS SOFTWARE OR ITS FITNESS FOR ANY PARTICULAR PURPOSE.

This product includes software developed by the University of California, Berkeley and its contributors.

The following disclaimer is required by Nexidia Inc.:

© 2006 Nexidia. All rights reserved.

Manufactured under license from the Georgia Tech Research Corporation, U.S.A. Patent Pending.

The following disclaimer is required by Paradigm Matrix:

Portions of this software licensed from Paradigm Matrix.

The following disclaimer is required by Ray Sauers Associates, Inc.:

"Install-It" is licensed from Ray Sauers Associates, Inc. End-User is prohibited from taking any action to derive a source code equivalent of "Install-It," including by reverse assembly or reverse compilation, Ray Sauers Associates, Inc. shall in no event be liable for any damages resulting from reseller's failure to perform reseller's obligation; or any damages arising from use or operation of reseller's products or the software; or any other damages, including but not limited to, incidental, direct, indirect, special or consequential Damages including lost profits, or damages resulting from loss of use or inability to use reseller's products or the software for any reason including copyright or patent infringement, or lost data, even if Ray Sauers Associates has been advised, knew or should have known of the possibility of such damages.

The following disclaimer is required by Videomedia, Inc.:

"Videomedia, Inc. makes no warranties whatsoever, either express or implied, regarding this product, including warranties with respect to its merchantability or its fitness for any particular purpose."

"This software contains V-LAN ver. 3.0 Command Protocols which communicate with V-LAN ver. 3.0 products developed by Videomedia, Inc. and V-LAN ver. 3.0 compatible products developed by third parties under license from Videomedia, Inc. Use of this software will allow "frame accurate" editing control of applicable videotape recorder decks, videodisc recorders/players and the like."

The following disclaimer is required by Altura Software, Inc. for the use of its Mac2Win software and Sample Source Code:

©1993–1998 Altura Software, Inc.

The following disclaimer is required by Ultimatte Corporation:

Certain real-time compositing capabilities are provided under a license of such technology from Ultimatte Corporation and are subject to copyright protection.

The following disclaimer is required by 3Prong.com Inc.:

Certain waveform and vector monitoring capabilities are provided under a license from 3Prong.com Inc.

The following disclaimer is required by Interplay Entertainment Corp.:

The "Interplay" name is used with the permission of Interplay Entertainment Corp., which bears no responsibility for Avid products.

This product includes portions of the Alloy Look & Feel software from Incors GmbH.

This product includes software developed by the Apache Software Foundation (<http://www.apache.org/>).

© DevelopMentor

This product may include the JCifs library, for which the following notice applies:

JCifs © Copyright 2004, The JCIFS Project, is licensed under LGPL (<http://jcifs.samba.org/>). See the LGPL.txt file in the Third Party Software directory on the installation CD.

Avid Interplay contains components licensed from LavanTech. These components may only be used as part of and in connection with Avid Interplay.

Attn. Government User(s). Restricted Rights Legend

U.S. GOVERNMENT RESTRICTED RIGHTS. This Software and its documentation are "commercial computer software" or "commercial computer software documentation." In the event that such Software or documentation is acquired by or on behalf of a unit or agency of the U.S. Government, all rights with respect to this Software and documentation are subject to the terms of the License Agreement, pursuant to FAR §12.212(a) and/or DFARS §227.7202-1(a), as applicable.

Trademarks

003, 192 Digital I/O, 192 I/O, 96 I/O, 96i I/O, Adrenaline, AirSpeed, ALEX, Alienbrain, AME, AniMatte, Archive, Archive II, Assistant Station, AudioPages, AudioStation, AutoLoop, AutoSync, Avid, Avid Active, Avid Advanced Response, Avid DNA, Avid DNxcel, Avid DNxHD, Avid DS Assist Station, Avid Liquid, Avid Media Engine, Avid Media Processor, Avid MEDIAArray, Avid Mojo, Avid Remote Response, Avid Unity, Avid Unity ISIS, Avid VideoRAID, AvidRAID, AvidShare, AVIDstripe, AVX, Axiom, Beat Detective, Beauty Without The Bandwidth, Beyond Reality, BF Essentials, Bomb Factory, Boom, Bruno, C|24, CaptureManager, ChromaCurve, ChromaWheel, Cineractive Engine, Cineractive Player, Cineractive Viewer, Color Conductor, Command|24, Command|8, Conectiv, Control|24, Cosmonaut Voice, CountDown, d2, d3, DAE, Dazzle, Dazzle Digital Video Creator, D-Command, D-Control, Deko, DekoCast, D-Fi, D-fx, Digi 003, DigiBase, DigiDelivery, Digidesign, Digidesign Audio Engine, Digidesign Development Partners, Digidesign Intelligent Noise Reduction, Digidesign TDM Bus, DigiLink, DigiMeter, DigiPanner, DigiProNet, DigiRack, DigiSerial, DigiSnake, DigiSystem, Digital Choreography, Digital Nonlinear Accelerator, DigiTest, DigiTranslator, DigiWear, DINR, DNxchange, DPP-1, D-Show, DSP Manager, DS-StorageCalc, DV Toolkit, DVD Complete, D-Verb, Eleven, EM, Euphonix, EUCON, EveryPhase, Expander, ExpertRender, Fader Pack, Fairchild, FastBreak, Fast Track, Film Cutter, FilmScribe, Flexevent, FluidMotion, Frame Chase, FXDeko, HD Core, HD Process, HDPack, Home-to-Hollywood, HYBRID, HyperControl, HyperSPACE, HyperSPACE HDCAM, iKnowledge, Image Independence, Impact, Improv, iNEWS, iNEWS Assign, iNEWS ControlAir, Instantwrite, Instinct, Intelligent Content Management, Intelligent Digital Actor Technology, IntelliRender, Intelli-Sat, Intelli-sat Broadcasting Recording Manager, InterFX, Interplay, inTONE, Intraframe, iS Expander, ISIS, IsoSync, iS9, iS18, iS23, iS36, ISIS, IsoSync, KeyRig, KeyStudio, LaunchPad, LeaderPlus, LFX, Lightning, Link & Sync, ListSync, LKT-200, Lo-Fi, Luna, MachineControl, Magic Mask, Make Anything Hollywood, make manage move | media, Marquee, MassivePack, Massive Pack Pro, M-Audio, M-Audio Micro, Maxim, Mbox, Media Composer, MediaFlow, MediaLog, MediaMatch, MediaMix, Media Reader, Media Recorder, MEDIAArray, MediaServer, MediaShare, MetaFuze, MetaSync, MicroTrack, MIDI I/O, Midiman, Mix Rack, MixLab, Moviebox, Moviestar, MultiShell, NaturalMatch, NewsCutter, NewsView, Nitris, NL3D, NLP, Nova, NRV-10 InterFX, NSDOS, NSWIN, Octane, OMF, OMF Interchange, OMM, OnDVD, Open Media Framework, Open Media Management, Ozone, Ozonic, Painterly Effects, Palladium, Personal Q, PET, Pinnacle, Pinnacle DistanTV, Pinnacle GenieBox, Pinnacle HomeMusic, Pinnacle MediaSuite, Pinnacle Mobile Media, Pinnacle Scorefitter, Pinnacle Studio,

Pinnacle Studio MovieBoard, Pinnacle Systems, Pinnacle VideoSpin, Podcast Factory, PowerSwap, PRE, ProControl, ProEncode, Profiler, Pro Tools LE, Pro Tools M-Powered, Pro Transfer, Pro Tools, QuickPunch, QuietDrive, Realtime Motion Synthesis, Recti-Fi, Reel Tape Delay, Reel Tape Flanger, Reel Tape Saturation, Reprise, Res Rocket Surfer, Reso, RetroLoop, Reverb One, ReVibe, Revolution, rS9, rS18, RTAS, Salesview, Sci-Fi, Scorch, Scorefitter, ScriptSync, SecureProductionEnvironment, Serv|LT, Serv|GT, Session, Shape-to-Shape, ShuttleCase, Sibelius, SIDON, SimulPlay, SimulRecord, Slightly Rude Compressor, Smack!, Soft SampleCell, Soft-Clip Limiter, Solaris, SoundReplacer, SPACE, SPACESHift, SpectraGraph, SpectraMatte, SteadyGlide, Streamfactory, Streamgenie, StreamRAID, Strike, Structure, Studiophile, SubCap, Sundance Digital, Sundance, SurroundScope, Symphony, SYNC HD, Synchronic, SynchroScope, SYNC I/O, Syntax, TDM FlexCable, TechFlix, Tel-Ray, Thunder, Titansync, Titan, TL Aggro, TL AutoPan, TL Drum Rehab, TL Everyphase, TL Fauxlder, TL In Tune, TL MasterMeter, TL Metro, TL Space, TL Utilities, tools for storytellers, Torq, Torq Xponent, Transfuser, Transit, TransJammer, Trigger Finger, Trillium Lane Labs, TruTouch, UnityRAID, Vari-Fi, Velvet, Video the Web Way, VideoRAID, VideoSPACE, VideoSpin, VTEM, Work-N-Play, Xdeck, X-Form, Xmon, XPAND!, Xponent, X-Session, and X-Session Pro are either registered trademarks or trademarks of Avid Technology, Inc. in the United States and/or other countries.

Adobe and Photoshop are either registered trademarks or trademarks of Adobe Systems Incorporated in the United States and/or other countries. Apple and Macintosh are trademarks of Apple Computer, Inc., registered in the U.S. and other countries. Windows is either a registered trademark or trademark of Microsoft Corporation in the United States and/or other countries. All other trademarks contained herein are the property of their respective owners.

Footage

Arri — Courtesy of Arri/Fauer — John Fauer, Inc.
Bell South "Anticipation" — Courtesy of Two Headed Monster — Tucker/Wayne Atlanta/GMS.
Canyonlands — Courtesy of the National Park Service/Department of the Interior.
Eco Challenge British Columbia — Courtesy of Eco Challenge Lifestyles, Inc., All Rights Reserved.
Eco Challenge Morocco — Courtesy of Discovery Communications, Inc.
It's Shuttletime — Courtesy of BCP & Canadian Airlines.
Nestlé Coffee Crisp — Courtesy of MacLaren McCann Canada.
Saturn "Calvin Egg" — Courtesy of Cossette Communications.
"Tigers: Tracking a Legend" — Courtesy of www.wildlifeworlds.com, Carol Amore, Executive Producer.
"The Big Swell" — Courtesy of Swell Pictures, Inc.
Windhorse — Courtesy of Paul Wagner Productions.

Arizona Images — KNTV Production — Courtesy of Granite Broadcasting, Inc.,
Editor/Producer Bryan Foote.
Canyonlands — Courtesy of the National Park Service/Department of the Interior.
Ice Island — Courtesy of Kurtis Productions, Ltd.
Tornados + Belle Isle footage — Courtesy of KWTV News 9.
WCAU Fire Story — Courtesy of NBC-10, Philadelphia, PA.
Women in Sports – Paragliding — Courtesy of Legendary Entertainment, Inc.

Avid Media Composer and NewsCutter Effects and Color Correction Guide • 0130-30394-01 Rev B •
December 2010

Contents

	Using This Guide	17
	Symbols and Conventions	17
	If You Need Help	18
	Accessing the Goodies Folder	19
	Avid Training Services	19
Chapter 1	Effects Concepts and Settings	21
	Types of Effects	21
	Real-Time Effects and Non-Real-Time Effects	24
	Color Coding on Effect Icons	25
	Understanding the Effect Palette	26
	Displaying and Adjusting the Effect Palette	26
	Working with Effects in HD and in Progressive Frame Projects	27
	Changing Timeline View Settings for Effects	29
	Adjusting Trim Settings for Effects	30
	Setting Effect Grid Options	30
	Setting Effect Aperture Options	31
Chapter 2	Basics of Effects Editing	35
	Applying Effects	35
	Deleting Effects in a Sequence	39
	Sizing Effects to Fit the Media	40
	Adjusting Effects	41
	Updating and Reverting Existing Effects in Sequences	44
	Working with Effect Templates	47
	Promoting Existing Effect Templates	49
	Playing Effects	50
	Basics of Effects Rendering	53
Chapter 3	Applying and Customizing Effects	63
	Applying Dissolve Effects	63
	Working with the Quick Transition Dialog Box	66

	Adjusting Transitions in the Timeline	74
	Modifying Transition Effects in the Timeline	75
	Preserving Effect Transitions in the Timeline	77
	Replacing an Effect in Effect Mode	78
	Using the Effect Preview Monitor	78
	Stepping Through Field-Based Media	88
	Using the Effect Editor	89
	Manipulating Effects Directly in the Effect Preview Monitor	98
Chapter 4	Working with Keyframes	101
	Understanding Keyframes	101
	Track Types for Advanced Keyframes	103
	Viewing Advanced Keyframe Graphs	104
	Manipulating Advanced Keyframes	111
	Controls and Settings for Advanced Keyframes	142
	Working with Standard Keyframes	148
Chapter 5	Playing Effects, Rendering Effects, and Managing Effect Media Files	151
	Real-Time Playback of Video Effects	151
	ExpertRender	158
	Creating and Using Render Settings	167
	Render Settings Options	168
	Using Partial Render	171
	Using 16-Bit Processing Support for Rendered Effects	172
	Ensuring the Quality Level of Precomputed Clips	174
	Rendering 3D Effects Using the HQ (Highest Quality) Option	176
	Rendering Effects for the Media Station XL	177
	Managing Effect Media Files	181
Chapter 6	Working with Plug-In Effects	185
	Understanding AVX Plug-Ins	185
	Freeing Memory Used by AVX 1.x Plug-ins	186
	Installing AVX Plug-ins	187
	Locating the AVX 1.x Plug-Ins Folder (Windows Only)	188
	Updating and Promoting AVX Plug-ins	189
	Assigning Multiple Tracks in Plug-in Effects	190

	Using AVX Plug-In Controls	191
	Using the Client Monitor to Preview a Plug-In Effect	192
	Troubleshooting AVX Plug-Ins	192
	Working with the Avid After Effects EMP Plug-In (Windows Only)	194
	Considerations for Using the Avid After Effects EMP Plug-in (Windows Only)	195
Chapter 7	Creating and Customizing Motion Effects	197
	Understanding Motion Effects	198
	Creating Traditional Motion Effects	199
	Playing and Rendering Motion Effects	207
	Understanding Timewarp Effects	210
	Creating Timewarp Effects	213
	Promoting a Traditional Motion Effect to Timewarp	213
	Using the Motion Effect Editor	215
	Scaling a Graph Display in the Motion Effect Editor	217
	Using the Source Anchor Frame	218
	Using Adaptive Deinterlacing	219
	Motion Effect Editor Reference	219
	Rendering Options for Timewarp Effects	223
	Timewarp Speed Graph Reference	226
	Timewarp Position Graph Reference	228
	Timewarp Effect Examples	229
	Understanding FluidMotion Timewarp Effects	238
	FluidMotion Workflow	238
	Using FluidMotion Edit	239
	Example of Correcting FluidMotion Artifacts	242
	Timewarp Preset Effects	246
	FluidFilm Preset Effects	247
	Setting Source and Output Options for Format Conversion with Timewarp Effects	248
Chapter 8	Layered and Nested Effects	251
	Key Effects	251
	Working with Imported Graphics and Animation	265
	Nesting Effects	267
	Submaster Editing	275

	Collapsing Layers into a Submaster Effect	277
	Performing a Video Mixdown	278
Chapter 9	Working with Camera Effects	281
	Using the Reformat Effects	281
	Working with the Pan and Scan Effect	282
	Using Avid Pan & Zoom	293
Chapter 10	Motion Tracking and Stabilization	307
	Understanding Motion Tracking	308
	Workflow for Motion Tracking	310
	Effects and Effect Parameters That Use Tracking Data	311
	Understanding the Tracking Interface	312
	Opening The Tracking Window	314
	Tracking Window Components	315
	Setting Up an Effect for Tracking	317
	Preparing to Generate Tracking Data	318
	Generating Tracking Data	328
	Offset Tracking	330
	Understanding Tracking Data	332
	Customizing the Display of Tracking Data	334
	Setting the Reference Frame for a Tracker	335
	Understanding the SteadyGlide and Smoothing Options for Tracking	336
	Using SteadyGlide or Smoothing to Process Tracking Data	337
	Selecting, Deleting, and Moving Tracking Data Points	338
	Moving Tracker Data Points Outside the Frame Boundary	341
	Stretching a Range of Tracker Data Points	341
	Limiting the Effect of Position Tracking Data to a Single Axis	343
	Playing Effects That Use Tracking Data	344
	Understanding Stabilizing	344
	Stabilizing an Image	346
	Reviewing and Adjusting a Stabilized Image	348
	Guidelines for Using Multiple Trackers When Stabilizing	349
	Using the Region Stabilize Effect	350
	Making Adjustments to the Region Stabilize Region of Interest	352

	Editing Segments That Use Tracking Data	352
	Reusing Existing Tracking Data	354
	Copying and Pasting Tracking Data	354
	Conforming Symphony Meridien Sequences with Tracking Data	356
	Examples of Effects Using Motion Tracking	356
Chapter 11	Working with 3D Effects	361
	Understanding 3D Effects	361
	Applying the 3D Warp Effect	362
	Using Xpress 3D Effects	363
	Promoting 2D Effects to 3D Effects	364
	Using Matte Keys with 3D Effects	364
	Real-Time Playback of 3D Effects	366
	Understanding 3D Geometry and Degrees of Rotation	366
	Working with 3D Effects Parameters	368
	Manipulating 3D Effects Directly	368
	Applying 3D Effects: Examples	370
Chapter 12	Creating Titles	381
	Opening the Title Tools	382
	Using Marquee	383
	Overview of Title Creation in the Title Tool	383
	Installing Fonts for Use in the Title Tool	384
	Understanding the Title Tool	385
	Toolbar Reference for the Title Tool	386
	Using the Selection and Text Tools	388
	Understanding the Drawing Environment	389
	Setting Up the Drawing Environment	391
	Creating Text	392
	Sizing and Positioning Text Objects	393
	Editing a Text String	394
	Formatting Text	394
	Creating Graphic Objects	400
	Creating Rolling and Crawling Titles	401
	Modifying and Manipulating Title Objects	407

	Modifying Box Corners, Lines, and Borders on Title Objects	408
	Understanding Color and Transparency Controls in the Title Tool	411
	Selecting Colors and Setting Transparency	412
	Adding Shadows to Title Objects	415
	Adjusting Shadows on Title Objects	416
	Manipulating Title Objects	418
	Saving Titles	421
	Revising a Title in a Bin	424
	Creating and Using Title Templates	425
	Saving and Recalling Title Styles	426
	Exporting a Title as a Graphics File	430
Chapter 13	Editing with Titles	431
	Displaying Title Clips and Frames in Bins	431
	Editing a Title into a Sequence	432
	Removing a Title	436
	Replacing a Title	437
	Fading a Title	437
	Setting Marks in a Rolling or Crawling Title	437
	Trimming the Duration of Rolling and Crawling Titles	438
	Adjusting Title Effect Parameters	438
	Revising a Title in a Sequence	440
	Replacing Fill Tracks in a Title	441
	Rendering Titles	441
	Re-creating Title Media	442
	Troubleshooting Titles	443
Chapter 14	Working with the SubCap Effect	447
	Understanding the SubCap Effect	447
	How the SubCap Effect Handles Caption Files	449
	Applying the SubCap Effect	451
	Entering Caption Text Directly in the Effect Editor	452
	Importing a Caption File	453
	Adding Information to a SubCap Effect	455
	Editing Text in the Master Caption List	456

	Adjusting SubCap Effect Parameters	456
	Synchronizing SubCap Effect Parameters and Information	457
	Exporting SubCap Effect Data to Caption Files	458
	Working with Unicode Text in the SubCap Effect	460
	Working with SubCap Effect Stylesheets	461
	Examples of SubCap Effect Parameter Adjustments	463
Chapter 15	Intraframe Editing	467
	Understanding the Intraframe Effects	467
	Rendering Intraframe Effects	469
	Applying the Paint or AniMatte Effect to a Sequence	470
	Effect Editor Reference for the Paint and AniMatte Effects	470
	Using the Intraframe Drawing Tools	473
	Working with Vector-Based Objects	485
	Using the Previsualization Marker Tool for Film Projects	494
	Manipulating Intraframe Objects	496
	Layering, Grouping, and Locking Intraframe Objects	501
	Exporting a Matte Key Created With the AniMatte Effect	503
	Scratch Removal.	504
	Intraframe Editing Examples.	519
	Working with the Blur Effect and Mosaic Effect	531
Chapter 16	PlasmaWipe Effects	535
	Understanding PlasmaWipe Effects	535
	Folder Structure for PlasmaWipe Effects	537
	Using PlasmaWipe Effects	538
	Creating Gradient Images for PlasmaWipe Effects.	538
	Understanding PlasmaWipe Frame and Border Effects	548
	Applying and Adjusting PlasmaWipe Frame and Border Effects	549
	Creating Custom PlasmaWipe Border and Frame Effects	551
	Using PlasmaWipes with HD Projects	553
Chapter 17	Effects Reference	555
	Blend Effects	556
	Box Wipes	559
	Conceal Effects	560


Edge Wipes	561
Film Effects.	562
Generator Effects	564
Illusion FX Effects.	564
Image Effects	570
Key Effects	575
L-Conceal Effects	579
Matrix Wipes.	580
Motion Effects.	581
Peel Effects	582
PlasmaWipe Effects	584
Push Effects	585
Reformat Effects.	586
Sawtooth Wipes	587
Shape Wipes	588
Spin Effects	590
Squeeze Effects	591
Timewarp Effects	592
Title Effects.	598
Xpress 3D Effects.	599
Comparison of Similar Effects	601
Chapter 18 Effects Parameter Reference	603
Color Parameter Controls.	604
Common 2D Effect Parameters	605
Film Effects Blowup Parameter	616
Generator Effect Parameters	616
Illusion FX Effect Parameters.	626
Image Effect Parameters	652
Key Effect Parameters	676
Motion Effect Parameters.	694
Reformat Effect Parameters.	697
FluidMotion Edit Parameters for Timewarp Effects	698
Rolling Title and Crawling Title Effect Parameters	702

	3D Effect Parameters	703
Chapter 19	Understanding Color Correction Mode	727
	Overview of Color Correction	727
	Reasons for Making Color Corrections	728
	Entering and Exiting Color Correction Mode	729
	The Color Correction Monitors	730
	The Color Correction Tool	734
	Working with Color Correction Effect Templates	742
Chapter 20	Performing Color Corrections	747
	General Workflow for Making Color Corrections	747
	Using Automatic Color Corrections	749
	Using the Color Match Control	756
	The HSL (Hue, Saturation, Luminance) Group	762
	The Curves Group	770
	Keyframing Color Corrections	782
	Working with the Waveform Monitors and Vectorscope Monitor	786
	Applying Color Corrections to an Entire Sequence	796
	Using the Color Correction Effect	797
Chapter 21	Color Correction Techniques	801
	Guiding Principles for Color Correction	801
	Examples of Color Correction Problems	806
Chapter 22	Safe Colors	813
	Overview of Safe Color Limits	813
	Safe Color Settings Options	814
	Understanding the Graphical View of Safe Color Settings	815
	Understanding Safe Color Warnings	817
	Managing Safe Color Warnings	819
	Making Adjustments to Achieve Safe Color Values	820
	Safe Color Limits with Waveform and Vectorscope Information	821
	Working with the Safe Color Limiter Effect	823
	Index	827

Using This Guide




This guide provides conceptual information and step-by-step instructions for the effects and color correction features of your Avid® editing application. It also provides reference information for every effect and effect parameter available in your application.

Unless noted otherwise, the material in this document applies to the Windows® and Mac OS® X operating systems. The majority of screen shots in this document were captured on a Windows system, but the information applies to both Windows and Mac OS X systems. Where differences exist, both Windows and Mac OS X screen shots are shown.

 *The documentation describes the features and hardware of all models and applies to both the Windows and Mac OS X operating systems. Your system might not contain certain features and hardware that are covered in the documentation, and might not be available on both Windows and Mac OS X.*

Symbols and Conventions

Avid documentation uses the following symbols and conventions:

Symbol or Convention	Meaning or Action
	A note provides important related information, reminders, recommendations, and strong suggestions.
	A caution means that a specific action you take could cause harm to your computer or cause you to lose data.
	A warning describes an action that could cause you physical harm. Follow the guidelines in this document or on the unit itself when handling electrical equipment.
>	This symbol indicates menu commands (and subcommands) in the order you select them. For example, File > Import means to open the File menu and then select the Import command.
▶	This symbol indicates a single-step procedure. Multiple arrows in a list indicate that you perform one of the actions listed.

Symbol or Convention	Meaning or Action
(Windows), (Windows only), (Macintosh), or (Macintosh only)	This text indicates that the information applies only to the specified operating system, either Windows or Macintosh OS X.
Bold font	Bold font is primarily used in task instructions to identify user interface items and keyboard sequences.
<i>Italic font</i>	Italic font is used to emphasize certain words and to indicate variables.
Courier Bold font	Courier Bold font identifies text that you type.
Ctrl+key or mouse action	Press and hold the first key while you press the last key or perform the mouse action. For example, Command+Option+C or Ctrl+drag.

If You Need Help

If you are having trouble using your Avid product:

1. Retry the action, carefully following the instructions given for that task in this guide. It is especially important to check each step of your workflow.
2. Check the latest information that might have become available after the documentation was published:
 - If the latest information for your Avid product is provided as printed release notes, they are shipped with your application and are also available online.
 - If the latest information for your Avid product is provided as a ReadMe file, it is supplied on your Avid installation CD or DVD as a PDF document (README_ product.pdf) and is also available online.

You should always check online for the most up-to-date release notes or ReadMe because the online version is updated whenever new information becomes available. To view these online versions, select ReadMe from the Help menu, or visit the Knowledge Base at www.avid.com/readme.

3. Check the documentation that came with your Avid application or your hardware for maintenance or hardware-related issues.
4. Visit the online Knowledge Base at www.avid.com/online support. Online services are available 24 hours per day, 7 days per week. Search this online Knowledge Base to find answers, to view error messages, to access troubleshooting tips, to download updates, and to read or join online message-board discussions.

Accessing the Goodies Folder

Avid supplies a Goodies folder located on the editing application DVD. Access the Goodies folder by browsing the DVD. This folder contains programs and files you might find useful when trying to perform functions beyond the scope of your Avid editing application.

The information in the Goodies folder is provided solely for your reference and as suggestions for you to decide if any of these products fit into your process. Avid is not responsible for the manufacture, support, or sales of these products. Avid is also not responsible for any loss of data or time, or any other adverse results related to the use of these products. All risks of using such products or accessing such Web sites are entirely your own. The Web sites listed in the Goodies folder are not under the control of Avid, and Avid is not responsible for their content, any changes or updates to them, or the collection of any personal data or information by the operators of such Web sites. All information and product availability is subject to change without notice.

Avid Training Services

Avid makes lifelong learning, career advancement, and personal development easy and convenient. Avid understands that the knowledge you need to differentiate yourself is always changing, and Avid continually updates course content and offers new training delivery methods that accommodate your pressured and competitive work environment.

For information on courses/schedules, training centers, certifications, courseware, and books, please visit www.avid.com/support and follow the Training links, or call Avid Sales at 800-949-AVID (800-949-2843).

1 Effects Concepts and Settings

This chapter describes concepts you should understand before you begin creating effects and common settings adjustments that affect how you work with effects:

- [Types of Effects](#)
- [Real-Time Effects and Non-Real-Time Effects](#)
- [Color Coding on Effect Icons](#)
- [Understanding the Effect Palette](#)
- [Displaying and Adjusting the Effect Palette](#)
- [Working with Effects in HD and in Progressive Frame Projects](#)
- [Changing Timeline View Settings for Effects](#)
- [Adjusting Trim Settings for Effects](#)
- [Setting Effect Grid Options](#)
- [Setting Effect Aperture Options](#)

Types of Effects

You can divide the effects in Avid editing applications into a number of groupings, which are described in the remainder of this topic.

There is considerable overlap within these groupings. For example, Timewarp effects are one of the main types of *motion effects* in Avid editing applications, but they are also examples of *segment effects*. The following descriptions give you a basic understanding of the range of effects available, and an introduction to some of the terminology Avid uses in its effects documentation.

Transition Effects

You apply transition effects at the cut point between two video clips that are on the same track (the same video layer) in a sequence. Examples of transition effects are dissolves, fades, and wipes.

Segment Effects

You apply segment effects to an entire clip or group of clips in a sequence. For example, you might apply a Color Effect to several segments in a sequence to tint those segments, suggesting that the action they contain is taking place in the past.

Segment effects fall into two subgroups:

- **Single-layer**

You apply a single-layer segment effect to a segment on one video track. A single-layer segment effect only needs one stream of video to create its effect. For example, the Mask effect lets you mask out some parts of the video in a segment, replacing it with a solid color.

- **Multilayer**

You apply a multilayer segment effect to the top layer or a middle layer of segments that contain two or more video tracks that will play simultaneously. A multilayer segment effect requires more than one video stream to create its effect. For example, a Picture-in-Picture effect displays video from an upper video track inside video from a lower track.

Motion Effects

Motion effects manipulate the motion characteristics in a clip, for example, by freezing action or by varying the speed at which a clip plays. You create motion effects either by generating new clips with fixed motion characteristics, or by using the Timewarp effects to change the motion characteristics of clips already in a sequence. For information on motion effects, see [“Creating and Customizing Motion Effects” on page 197](#).

Title Effects

Title effects contain text and graphic objects that you create with one of the title tools in your Avid editing application. You save title effects into bins as a special clip type, and edit them onto their own layers in a sequence, usually above all other video layers. For information on title effects, see [“Creating Titles” on page 381](#).

2D Effects and 3D Effects

Effects in Avid editing applications are either 2D or 3D. 2D effects appear to be acting in the two dimensions of the screen the viewer is watching and do not give an impression of depth. 3D effects give an impression of depth, for example, by wrapping a video image around a sphere. Some Avid effects are 2D only or 3D only, while others have both 2D and 3D versions, or can be promoted from 2D to 3D. For specific information on working with 3D effects, see [“Working with 3D Effects” on page 361](#).

Nested Effects

You apply nested effects inside other effects on the same video layer. Effect nesting allows you great flexibility to apply multiple effects to the same segment in a sequence. For example, you might want to apply a color effect within an existing Picture-in-Picture effect. To do this, you can nest the color effect inside the Picture-in-Picture. For more information, see [“Layered and Nested Effects” on page 251](#).

Key Effects

Key effects use specific rules to define how parts of one image show through another image. The best-known example of a key effect is a chroma key, for example, where an actor shot in front of a blue or green screen appears to be standing in front of another background. The key effect replaces the blue or green color in the foreground shot with parts of the background shot. For more information, see [“Layered and Nested Effects” on page 251](#).

Camera Effects

Camera effects control aspect ratio, format, or the apparent motion of the camera. For example, Avid editing applications can reformat video media to different aspect ratios, allowing you to select the area of video that is preserved in the new aspect ratio. For more information, see [“Working with Camera Effects” on page 281](#).

Motion Tracking and Stabilization Effects

Motion tracking lets you track the motion of an area in an image and then use the tracking data to control the motion of another effect. You can also use tracking to stabilize an image to compensate for camera motion. For more information, see [“Motion Tracking and Stabilization” on page 307](#).

Intraframe Effects

Intraframe effects let you perform paint or animated matte effect operations within one or more individual frames in a clip. For example, you can identify part of an image with drawing tools and apply a blur to only that part of the image. You can also use this technique to repair scratches and other flaws on individual frames. For more information, see [“Intraframe Editing” on page 467](#).

PlasmaWipe Effects

PlasmaWipe effects use gradient image bitmaps to create highly-customizable wipes and segment effects. You can use one of the many preset effects or create your own using new gradient images. For more information, see [“PlasmaWipe Effects” on page 535](#).

AVX Plug-In Effects

Avid editing applications support the Avid Visual Extensions (AVX™) standard. AVX is a cross-platform technology that allows software effect modules (plug-ins) to be dynamically linked to an Avid editing application. Some effects that Avid supplies with your Avid editing application use the AVX technology, while others do not. In general, you work in exactly the same way with both types.

Third-party developers use AVX to create effect plug-ins that you can purchase, install, and use to extend the effects functionality of your Avid editing application. Third-party AVX plug-in effects might have controls that look very similar to standard Avid effect controls, or they might have custom user interfaces.

For more information on working with third-party plug-ins, see [“Working with Plug-In Effects” on page 185](#).

Real-Time Effects and Non-Real-Time Effects

Effects in Avid editing applications can be either *real-time* or *non-real-time*. A real-time effect is one that you can apply to a sequence and play without having to render it first. *Rendering* is a processing operation that your Avid editing application performs to merge effect layers, creating one stream of digital video for playback in real time. (Rendering takes time and creates a new media file that occupies drive space.) You must render non-real-time effects before you can play them back. You can preview non-real-time effects, or play them as an outline, without rendering them.

A real-time effect has a small green dot in the Effect Palette and within the effect icon in the Timeline. Effects that you must render have a small blue dot within the effect icon in the Timeline. For more information, see [“Color Coding on Effect Icons” on page 25](#).

You can create a sequence that has any number of real-time and non-real-time effects. However, there are limits on how many real-time effects your Avid editing application can play at once without rendering or otherwise reducing the amount of processing necessary during playback. For more information, see [“Real-Time Playback of Video Effects” on page 151](#).

When you want to play a sequence that includes effects at full quality, you might have to render some of the effects. You will have to render any effect that is non-real-time, and you might need to render some of the effects that are normally real-time.

The exact number of effects that you must render for output depends on the following factors:

- Whether or not you have Avid input/output hardware attached to your system. If you do not have Avid input/output hardware attached, you must render all effects before you perform a digital cut.
- How complex your sequence is, and especially how your effects are layered on multiple video tracks. If you have Avid input/output hardware attached to your system, real-time effects might cause dropped frames during a digital cut. You can have your Avid editing application select and render real-time effects that might cause dropped frames. For more information, see “Recording a Digital Cut to Tape (Remote Mode)” and “Recording a Digital Cut to Tape (Local Mode)” in the Help.

If you attempt to play or output a sequence that your Avid editing application cannot play in real-time, you can display information in the Timeline that shows where the demands of the sequence are preventing successful real-time play. For more information, see [“Understanding Real-Time Playback Information in the Timeline” on page 152](#). You have several options for how to proceed in these circumstances:

- For playing alone, you can use the Video Quality menu or Video Display settings to ease the playback demands by reducing the display quality of the video. For more information, see [“Options for Controlling Real-Time Effects Playback” on page 154](#).
- For output, where anything less than the best quality is not an option, you can use the ExpertRender feature to identify the minimum number of effects that you must render in order for the sequence to play in real time. For more information, see [“ExpertRender” on page 158](#).


Color Coding on Effect Icons

Effect icons in the Effect Palette and in the Timeline display colored dots to help you determine whether an effect is real-time or non-real-time.

Real-time effects show a green dot. Real-time effects play in real time in a sequence, subject to the playback capabilities and constraints of your Avid editing system. For more information, see [“Real-Time Playback of Video Effects” on page 151](#).

Non-real-time effects have no dot in the Effect Palette. In the Timeline, the effect icon shows a blue dot until you render the effect.

1 Effects Concepts and Settings



In the Effect Palette (left), green dots indicate real-time effects. (Real-time effects might not be playable in real time depending on system resources and the complexity of your sequence.) Non-real-time effects have no dot in the Effect Palette. Non-real-time effects have a blue dot in the Timeline (right) until they are rendered.

All colored dots disappear in the Timeline when you render effects.

Understanding the Effect Palette

The Effect Palette lists all transition and segment effects, and some motion effects, that are available for your Avid editing application. The Effect Palette is the primary tool that you use to apply effects to your sequences. For information on accessing the Effect Palette, see [“Displaying and Adjusting the Effect Palette” on page 26](#).

The left side of the Effect Palette displays a list of effect categories. The right side shows the various effects that are available for the currently selected effect category.


The Effect Palette displays all of the effect categories available for your Avid editing application, including any third-party AVX plug-in effects you have installed. If you save any effect templates to a bin, and have that bin open, those templates also display in the Effect Palette. For reference information on all Avid effects, see [“Effects Reference” on page 555](#).

Displaying and Adjusting the Effect Palette

This topic provides basic information on displaying and adjusting the Effect Palette. For information on the organization and purpose of the Effect Palette, see [“Understanding the Effect Palette” on page 26](#).

To display the Effect Palette:

- In the Project window, click the Effects tab.


**To resize the Effect Palette:**

- Click the lower right corner of the palette, drag the palette to the size you want, and release the mouse button.

To display effect templates saved to a bin in the Effect Palette:

1. Open the bin containing the effect templates.
2. If the Effect Palette is not already open, in the Project window, click the Effects tab.
3. Click the bin name below the effect category list to view the effect templates in the bin.

In the following illustration, the bin named “Effect Templates” is selected below the effect category list and the templates in that bin appear on the right.



Working with Effects in HD and in Progressive Frame Projects

Many video effects work the same way regardless of the project type or video format. This topic describes several situations where effect behavior varies depending on whether a project is SD or HD, or is interlaced or progressive.

Effects Considerations for HD Projects

Effects that use square geometry automatically use the correct pixel aspect ratios. These effects include Titles, Box Wipes, and certain paint modes like Mosaic. Effects such as Color Correction, Color Effect, and Luma keys automatically use the correct color space (ITU-709 for HD).



The Safe Color Limiter effect converts from 709 to 601 color space before limiting unsafe colors, and then converts back to 709 color space. For more information, see “Understanding the Safe Color Limiter Effect” on page 823.

Note the following:

- You do not need to generate 4:3 media for titles.
- Timewarp effects use a 60p input and output format in 720p/59.94 projects.

Effects Considerations for Progressive Frame Projects

Effects in progressive frame projects are frame based rather than field based, so their normal behavior is slightly different from effects in interlaced projects. In particular, temporal artifacts might appear in some effects under certain circumstances. This topic explains when temporal artifacts might appear and suggests ways to create effects that do not show perceptible temporal artifacts.

Effects that do not involve any movement across the screen — for example, masks, Color Effects, and dissolves — always look the same in progressive projects as they do in interlaced projects.

Effects that involve movement across the screen — for example, wipes, 3D shapes, or moving titles — might look different in 24p or 25p projects from their equivalents in interlaced projects for the following reasons:

- Because the effect uses 24 or 25 progressive frames per second (24p or 25p), motion across the screen is interpolated in 24 or 25 increments per second. (Contrast the 50 increments per second for a PAL interlaced project or the 60 increments per second for an NTSC interlaced project.) For example, the edge of a 1-second Horizontal Edge Wipe effect appears in 24 or 25 different positions across the screen. For effects of short duration in particular, this difference might be perceptible to the viewer.
- When the 24p or 25p media is output (to the interlaced Client monitor or as a digital cut), it is interlaced again and pulldown is inserted to achieve 60 fields per second (NTSC). Your Avid editing application inserts pulldown by duplicating some of the existing frames to create the correct number of fields per second. Viewers might notice temporal artifacts created by this duplication process. This behavior is a normal result of the pulldown insertion process and is often perceptible in conventional transfers of films to video formats.



PAL output with pulldown also duplicates certain frames but is less likely to exhibit perceptible temporal artifacts since fewer frames require duplication.

Motion effects that you create in 24p or 25p projects, such as Variable Speed effects, might also look different from motion effects that you create in interlaced projects. For more information on 24p or 25p motion effects, see [“Considerations for Motion Effects in Progressive Projects”](#) on page 209.



For more information on how your Avid editing application handles 24p or 25p material, see “Displaying 24p and 25p Media” in the Help.

If an effect in a 24p or 25p project does not look completely smooth, do one or more of the following:

- Slow down the effect.

For example, a 2-second Horizontal Edge Wipe effect, while it is still performing at the same rate (24 increments per second), moves across the screen in 48 steps. These smaller movements make the wipe appear smoother to the viewer.

- Soften the edges of the effect.

The more the edges of the effect are blurred, the less noticeable are the movements between the increments of the effect.

- When working with moving titles, avoid small font sizes and sharp edges.

In a moving title such as a roll, lines of small text might move less smoothly than lines of larger text.



In a 24p or 25p project, if you select Output to DV Device from the Video Quality menu in the Timeline, the Realtime Encoding option is automatically turned off. For more information, see “Playing Back to a DV Device” in the Help.

Changing Timeline View Settings for Effects

All effect icons display in the Timeline by default. You can change the Timeline settings to display all effect icons, all effect icons except Dissolve Effect icons, or no effect icons. If you change the setting to display no effect icons, you must reset it before you begin applying effects. The fewer effect icons you display, the faster your Avid editing application refreshes the screen.


To change the Timeline settings:



1. In the Timeline window, click the Fast Menu button, and then do one of the following:
 - ▶ To display all effect icons in the Timeline, select Effect Icons.

1 Effects Concepts and Settings

- ▶ To display all effect icons except Dissolve icons, select Effect Icons and deselect Dissolve Icons.
 - ▶ To display no effect icons, deselect Effect Icons. Dissolve Icons appears dimmed and is now unavailable.
2. (Option) To save your Timeline settings, click the Timeline View Name button, select Save As, and type a view name.



Timeline View Name button and menu below Timeline

Adjusting Trim Settings for Effects

In Trim mode in some Avid editing applications, you can control whether or not the effects you apply are computed immediately on the screen (that is, on-the-fly) or appear later when you render them. For example, viewing transitions as cuts (*without* rendering on-the-fly) can make trimming easier.



For more information on changing Trim settings, see “Trim Settings Basics” in the Help.

To change the Trim settings for Render On-the-Fly:


1. In the Project window, click the Settings tab.
The Settings list appears.
2. Double-click Trim.
The Trim Settings dialog box opens.
3. Click the Features tab, and then select or deselect Render On-The-Fly.
4. Click OK.

Setting Effect Grid Options

You can display a grid in the Effect Preview monitor in Effect mode to guide you as you create and adjust effects. For information on using the grid, see [“Understanding the Effect Grid” on page 83](#).

The Grid Settings dialog box lets you customize the grid.

To set the default grid values, do one of the following:

- ▶ In the Settings list of the Project window, double-click Grid.
-  ▶ If the effect you are working with has a Grid parameter group, click the Other Options button for the Grid parameter group in the Effect Editor.

The Grid Settings dialog box opens.

For information on the Grid Settings options, see “Grid Settings” in the Help.

Setting Effect Aperture Options

In some Avid editing applications, the Effect Aperture setting lets you control the number of horizontal lines of an image that are used to create an effect. For example, if you are working with DV media and notice black lines above and below Picture-in-Picture effects, you can instruct the system to ignore the lines by changing the effect aperture.



The Effect Aperture feature applies only to NTSC projects.

For uncompressed and non-DV resolutions, your Avid editing application uses all 243 horizontal lines per field to display the image. For DV media, your Avid editing application uses 240 lines for the image and adds two black lines above the image and one black line below the image. The effect aperture lets you decide whether or not to use the three black lines when you create effects.

In a DV project the black lines can become visible when you create effects such as Picture-in-Picture or Squeeze effects.

The following illustrations show four PIP effects. In the first illustration, which uses the default ITU 601 aperture, you can clearly see the black lines between the effects. The second illustration displays the same media with the DV25 effect aperture — the black lines do not appear between the effects.

1 Effects Concepts and Settings




In a project that uses only DV media, it is useful to switch to the DV 25 aperture setting. In a project using uncompressed or mixed resolution media, use the ITU 601 aperture.

To change the effect aperture:

1. In the Settings list in the Project window, double-click General.

The General Settings dialog box opens.



2. Select one of the following Effect Aperture options:

Option	Description
ITU 601 (720x 486)	Select this setting when you are using uncompressed media or mixed resolutions. This is the default setting.
DV25 (720 x 480)	Select this setting when you are using DV media exclusively.

3. Click OK.

2 Basics of Effects Editing

This chapter provides basic procedures for creating, adjusting, playing, and rendering effects:

- [Applying Effects](#)
- [Deleting Effects in a Sequence](#)
- [Sizing Effects to Fit the Media](#)
- [Adjusting Effects](#)
- [Updating and Reverting Existing Effects in Sequences](#)
- [Working with Effect Templates](#)
- [Promoting Existing Effect Templates](#)
- [Playing Effects](#)
- [Basics of Effects Rendering](#)

Applying Effects

You apply most effects to video material after you edit it into a sequence. This section describes basic methods for applying effects using the Effect Palette and the Fade Effect button.

You can also apply and adjust basic transition effects using the Quick Transition button and the Quick Transition dialog box. For more information, see [“Working with the Quick Transition Dialog Box” on page 66](#)

You can also create titles and some types of motion effects as new clips that you then edit into a sequence. For more information, see [“Creating Titles” on page 381](#) and [“Creating and Customizing Motion Effects” on page 197](#).



You cannot apply effects to clips on a data (DI) track.

Applying Effects From the Effect Palette

You can apply effects either to transitions or to segments. Most effects are only suitable for one of these applications. For example, you cannot apply every effect in the Effect Palette to a transition. For more information on the use of an individual effect, see the reference information for the effect in [“Effects Reference” on page 555](#).

To apply an effect to a single transition or to a single segment in the Timeline, do one of the following:


- ▶ Click the effect’s icon in the Effect Palette, drag the icon over the transition or segment in the Timeline, and release the mouse button.
- ▶ In Effect Mode, click the transition, and then double-click the effect’s icon in the Effect Palette.
- ▶ Select the segment in the Timeline, and then double-click the effect’s icon in the Effect Palette.

For more information on selecting segments, see [“Selecting and Deselecting Segments”](#) in the Help.


If there is not enough incoming or outgoing media to apply a transition effect at its default length, the Insufficient Source dialog box opens. For more information, see [“Sizing Effects to Fit the Media” on page 40](#).

To apply an effect to multiple transitions in the Timeline:

1. Enter Effect mode, for example, by selecting Toolset > Effects Editing.
For more information, see [“Entering Effect Mode” on page 41](#).
2. Click the first or last transition to which you want to apply the effect.
3. Click above the Timeline and begin dragging to activate a selection box. Continue to drag down and either to the left or right to include additional transitions in the selection.




4. Release the mouse button when the selection box includes all the transitions you want.
Your Avid editing application highlights the transitions that you select, and the position indicator moves to the first transition.



5. (Option) Shift+click any transition to deselect it.
6. In the Effect Palette, double-click the icon for the effect that you want to apply to the transitions.


your Avid editing application applies the effect to the selected transitions in the Timeline.



If there is not enough incoming or outgoing media to apply the transition effect at its default length to one or more of the transitions, the Insufficient Source dialog box opens. For more information, see [“Sizing Effects to Fit the Media” on page 40](#).


To apply an effect to multiple segments in the Timeline:

1. Enter Effect mode, for example, by selecting Toolset > Effects Editing.
For more information, see [“Entering Effect Mode” on page 41](#).
2. Click above the Timeline and to the left of the *leftmost* segment that you want to select and begin dragging to the *right* and *down* to activate a selection box.
3. Continue to drag to the *right* until the selection box includes the *rightmost* segment that you want to select.




4. Release the mouse button.
Your Avid editing application highlights the segments that you select.

2 Basics of Effects Editing



5. (Option) Shift+click a segment to deselect it.
6. In the Effect Palette, double-click the icon for the effect that you want to apply to the segments.

Your Avid editing application applies the effect to the selected segments in the Timeline.



Using the Fade Effect Button

You can use the Fade Effect button to create basic fades for segment effects.

The Fade Effect feature creates keyframes for the effect automatically. You can access the keyframes in the Effect Editor.



The Fade Effect button appears in the FX tab of the Command palette and, for some Avid editing applications, in the Tool Palette. You can map the Fade Effect button to another location. For more information, see “Mapping User-Selectable Buttons” in the Help.

To fade one or more segment effects in a sequence:

1. Select the segment effects in the Timeline:
 - ▶ To fade a single segment effect, move the position indicator to the segment.
 - ▶ To fade multiple segment effects, click one of the segment tools on the Timeline Palette, and then Shift+click the segments.



Segment tools in the Timeline palette



2. Click the Fade Effect button.

The Fade Effect dialog box opens.

3. Type the number of frames to fade up and fade down, and click OK.

You can view the Fade effect by playing the segment or segments.


Deleting Effects in a Sequence

You can delete transition effects from a sequence in Source/Record mode (editing mode on NewsCutter systems), Trim mode, or Effect mode.

To delete a single effect:

1. Move the position indicator to the Timeline segment containing the effect's icon.
2. If there are multiple tracks that contain effects at the same position in the Timeline, select only the track that contains the effect you want to delete.

In this example, only track V3 is selected.




3. Do one of the following:



- ▶ In Source/Record mode (editing mode on NewsCutter systems), click the Remove Effect button.
- ▶ In Effect mode, select the effect and press Delete.
- ▶ When trimming (for transition effects only), either press Delete or click the Remove Effect button.

Your Avid editing application removes the effect.

2 Basics of Effects Editing



When you delete a rendered effect from a sequence, you do not delete the associated media file (precompute). To delete the effect's media file, you must manually remove it from the drive. Your Avid editing application operates this way so that you can undo the deletion of an effect or undo the change you made to an effect. For more information, see “Managing Effect Media Files” on page 181.

To delete multiple transition effects:

- ▶ In Effect mode, Shift+click each transition effect you want to delete, and then press Delete.

To delete multiple segment effects:

1. If you are not in Effect mode, click one of the segment tools on the Timeline palette.



Segment tools in the Timeline palette

2. Shift+click each segment that contains a segment effect you want to delete.
3. Do one of the following:



- ▶ Click the Remove Effect button.
- ▶ Press Delete.

Sizing Effects to Fit the Media

Transition effects usually require additional frames of source media beyond those you edit into the sequence. For example, if a dissolve begins 15 frames before the cut point between clips, your Avid editing application needs 15 frames of video from before the cut point on the incoming clip to create the beginning of the dissolve.

When you edit and apply effects, be aware that you might need these extra frames. Editors usually allow for these extra frames by marking IN and OUT points on source clips far enough away from the beginning and end of the clip that extra frames are available for transition effects. These extra frames are commonly known as “handles.”

When you apply a transition effect from the Effect Palette and there are not enough extra source frames available for the effect to use, the Insufficient Source dialog box opens and indicates whether the source that has insufficient material is Media A (outgoing) or Media B (incoming).

You can choose to cancel the effect or have your Avid editing application resize the effect to fit the available media. The result might be a shorter transition effect, or an effect with a changed alignment. For example, if no extra frames are available before the cut to an incoming clip, a transition effect cannot start before the cut point, so its alignment must be “Starting at Cut.”

To automatically size an effect to fit the media:

- ▶ Click Size To Fit in the Insufficient Source dialog box.

Your Avid editing application sets the duration of the effect to fit the available media. If you have selected an alignment, your Avid editing application attempts to preserve it.

To change the alignment or duration of the transition effect, see [“Applying a Dissolve Effect Using the Transition Parameters”](#) on page 64.

Adjusting Effects

After you apply an effect to a transition or segment in your sequence, you can adjust its appearance and operation. To make most effect adjustments, you enter Effect mode and work with the Effect Editor and the Effect Preview monitor.

This section explains how to enter Effect mode and provides basic information on how to use the Effect Editor and the Effect Preview monitor.

For more advanced information, see [“Applying and Customizing Effects”](#) on page 63.

Entering Effect Mode

After you add an effect to a sequence, you must enter Effect mode to change the parameters of the effect.

To enter Effect mode, do one of the following:




- ▶ Click the Effect Mode button.
- ▶ Select Toolset > Effects Editing.

2 Basics of Effects Editing

Your Avid editing application opens the Effect Editor and the Record monitor becomes the Effect Preview monitor. If the position indicator in the Timeline is on an effect, the controls for adjusting that effect display in the Effect Editor.

Understanding Effect Mode

The following illustration shows the main components of Effect mode, the Effect Editor (left) and the Effect Preview monitor (right).



Each property of an effect that you can control is known as an effect *parameter*. For example, a Picture-in-Picture effect has a Position parameter that controls where the picture-in-picture is located on the screen. The Effect Editor displays controls that let you adjust each of an effect's parameters, as well as other buttons that help you adjust effects. As different effects have different sets of parameters, the Effect Editor display changes depending on the effect you select.

For more detailed information on the Effect Editor, see [“Using the Effect Editor” on page 89](#).

The Effect Preview monitor displays the selected effect in the sequence where the position indicator is located in the Timeline. The position bar below the Effect Preview monitor represents the length of the selected effect, not of the entire sequence.

For some effects, the Effect Preview monitor displays tools that let you adjust the effect directly in the monitor. For example, a Picture-in-Picture effect normally displays with a wireframe outline and adjustment handles that you can use to reposition or resize the

picture-in-picture. A direct adjustment like this is equivalent to adjusting the effect with parameter controls in the Effect Editor, but it is often easier and more intuitive to make the adjustment directly in the monitor.

For more detailed information on the Effect Preview monitor, see [“Using the Effect Preview Monitor” on page 78](#).

Making Basic Effect Adjustments

This topic describes a general procedure for selecting and adjusting effects, including some simple examples of types of adjustments.

You can find more detailed information elsewhere in this guide. For example, for full details of how to use effect adjustment controls, see [“Applying and Customizing Effects” on page 63](#). For details of the parameters available for a specific effect, see the reference information for that effect in [“Effects Reference” on page 555](#).

To make basic effects adjustments:

1. Enter Effect mode, for example, by selecting Toolset > Effects Editing.
For more information, see [“Entering Effect Mode” on page 41](#).
2. In the Timeline, click the effect you want to adjust.
3. In the Effect Editor or the Effect Preview monitor, adjust the effect’s parameters until you achieve the look you want.

For example, depending on the effect, you might want to do one or more of the following:

- ▶ Adjust a parameter by dragging its slider control in the Effect Editor.
- ▶ Reposition an effect such as a Picture-in-Picture by dragging the effect in the Effect Preview monitor.
- ▶ Resize an effect such as a Picture-in-Picture by dragging one of the adjustment handles that display around the edge of the picture-in-picture in the Effect Preview monitor.
- ▶ Select an option for a parameter by clicking its Fast menu in the Effect Editor and selecting an item from the menu.
- ▶ Select a color for a parameter that uses color by clicking the parameter’s Color Preview window, dragging the eyedropper to the Effect Preview monitor, and releasing the mouse button over the color you want to use.
- ▶ Select a color for a parameter that uses color by clicking the Other Options button for the parameter and selecting the color from the Windows Color dialog box or the Macintosh Colors panel.

2 Basics of Effects Editing

- ▶ Select an alignment option for a transition effect by clicking the Transition Effect Alignment button in the Effect Editor and selecting an option from the menu.
- ▶ Define a custom duration for a transition effect by clicking in the Transition Effect Duration box in the Effect Editor, typing a duration, and pressing Enter.

Moving Through an Effect

The position bar in the Effect Preview monitor represents only the length of the currently selected effect. You can use the Effect Preview monitor's position bar to move through an effect in the same way that you use the position bars in Source/Record mode (editing mode on NewsCutter systems) to move through a clip or a sequence.

To move to a different point in an effect, do one of the following:


- ▶ Click a location in the position bar to move the position indicator to that location.
- ▶ Drag the position indicator to a location in the position bar.

Updating and Reverting Existing Effects in Sequences

If you are working with a sequence that already contains effects, you might need to update some of those effects.

If you apply color corrections to a sequence in the current version of your Avid editing application, you might need to save a duplicate version of the sequence with a reverted color corrections format that you can open in older versions of Avid editing applications.

The following table summarizes the types of effects that you can update or revert to their original format:

Effect Type	Description
Standard keyframe effects	<p>In the current version of your Avid editing application, many effects use advanced keyframes only. You can no longer apply or use standard keyframe versions of those effects.</p> <p>If an existing sequence contains standard keyframe versions of any effects that now use advanced keyframes, you must update those effects to their advanced keyframe versions.</p> <p> <i>This also applies to Title Effect clips in a sequence that still use standard keyframes. When you update these, you change the clip in the bin as well as the Title Effect segment in the sequence itself.</i></p> <p>You can update the standard keyframe effects in a sequence by loading the sequence or by using the Update Effects command.</p>
Color Correction	<p>You must update color corrections in sequences created in older versions of Avid editing applications that did not support keyframeable color correction before you can work with them in the current version. Color corrections in recent versions store parameter information differently to support keyframing.</p> <p>If you apply color corrections to a sequence in the current version of your Avid editing application and want to open that sequence in a version of an Avid editing application that does not support keyframeable color correction, you must revert the color corrections to the earlier format. This creates a duplicate sequence that stores color correction parameter information in an appropriate format for use in the older version.</p> <p>You can update color corrections in a sequence by loading the sequence or by using the Update Effects command.</p>
Traditional motion effects	<p>You can update traditional motion effects in a sequence to Timewarp effects by using the Update Effects command. This provides you with superior tools for adjusting the effects.</p>
Promotable, missing AVX1 plug-ins	<p>You can update these effects to AVX2 effects by using the Update Effects command. For more information on AVX effects, including other options for promoting AVX1 effects, see “Working with Plug-In Effects” on page 185.</p>

To update standard keyframe effects or color corrections by loading a sequence:

1. Load the sequence, for example, by dragging it to a monitor.

The Update Sequence dialog box opens.

If the sequence contains standard keyframe versions of effects that are now available in advanced keyframe versions, a message informs you that you must update the effects.

2 Basics of Effects Editing

If the sequence contains incompatible color corrections from an older version of your Avid editing application, a message informs you that you must update the color corrections.

2. (Option) If you want your Avid editing application to update sequences that you open in the future without displaying the Update Sequence dialog box, select “Do not ask again when loading a sequence.”
3. Click OK.

Your Avid editing application creates a copy of the sequence, updates the effects and color corrections in the copy that require updating, and opens the copy.

The name of the new sequence uses a suffix indicating that it is an updated sequence. If the original sequence is named *MySequence*, the updated copy is named, for example, *MySequence.updated.01*. Both the original sequence and the updated copy are available in the bin.

To update effects and color corrections in a sequence using the Update Effects command:

1. Select the sequence in a bin.
2. Right-click the sequence, and select Update Effects.

The Update Sequence dialog box opens.

Messages inform you if the sequence contains standard keyframe effects or color corrections that require updating.

If the sequence contains motion effects or AVX effects that you can choose to update, check boxes appear for those effect types.

3. (Option) Select the optional effect types that you want to update.
4. Click OK to update the effects, or Cancel to take no action.

If you click OK, your Avid editing application creates a copy of the sequence and updates the effects and color corrections in the copy that require updating or that you chose to update.

The name of the new sequence uses a suffix indicating that it is an updated sequence. If the original sequence is named *MySequence*, the updated copy is named, for example, *MySequence.updated.01*. Both the original sequence and the updated copy are available in the bin.

To save a sequence with reverted color corrections that you can open in older versions of Avid editing applications:

1. Select the sequence in a bin.
2. Right-click the sequence, and select Revert Effects.

A message box appears.

3. Do one of the following:

- ▶ If the message box indicates that the sequence includes color corrections that you must modify for use in versions of Avid editing applications that do not support keyframeable color correction, click OK to save a new version of the sequence, or Cancel to take no action.

If you click OK, your Avid editing application saves a new version of the sequence. The name of the new sequence uses a suffix indicating that it is a compatible copy, for example, *MySequence.reverted.01*.

- ▶ If the message box indicates that you do not need to revert any effects, click OK.



Working with Effect Templates

If you apply an effect and make a set of adjustments to it, you might want to be able to quickly recreate the same look elsewhere in your sequence or project. Your Avid editing application lets you save an effect with its parameter settings as a template. You can then apply the template to other effects or video clips at any time.

You can save any effect to a bin as an effect template. You can also save a segment effect with its source media. This is useful when you want to save an imported PICT file or Matte Key clip for future editing into a sequence.

When you save a title effect template, your Avid editing application includes the source media by default. You can also save a keyframe-only template, which retains the movement of the title without the source media.

You can apply an effect template with all its parameters directly to segments or transitions as you would any other effect. You can also apply specific parameters from the template.



In this example, a 3D Picture-in-Picture effect template is applied repeatedly to a series of segments to achieve the same cropping and positioning of foreground footage

2 Basics of Effects Editing


To save an effect template:

- ▶ Drag the effect icon from the Effect Editor to a bin.

A new effect template appears in the bin, containing the parameter setting information for the effect. The new effect template is identified in the bin by its effect icon.



Effect icons for open bins also display in the Effect Palette.



To save a segment effect with its source media, or save a title effect as a keyframe-only template:

- ▶ Press and hold the Alt key (Windows) or Option key (Macintosh) while you drag the effect icon from the Effect Editor to a bin.

To rename an effect template:

- ▶ In the bin, click the template name below the icon and type a new name.

To apply a specific parameter from an effect template:

1. In the Timeline, select an effect transition or segment.
2. Select Tools > Effect Editor.
3. Open the parameter group you want to change.

For example, the following illustration shows the Position parameter group.




4. Click the effect template icon in the bin or in the Effect Palette, and drag it to the specific parameter group in the Effect Editor.



Do not drag the effect template through the Timeline because this deselects the effect.

Your Avid editing application applies the effect template only to the effect parameter group you selected.



Promoting Existing Effect Templates

In the current version of your Avid editing application, many effects use advanced keyframes only. You can no longer apply or use standard keyframe versions of those effects.

You might have effect templates that you created in an older version of an Avid editing application. If you created these templates from standard keyframe versions of effects that now use advanced keyframes only, you can still apply them in the standard ways described in [“Working with Effect Templates” on page 47](#). You can apply the template to create a new effect in the Timeline, in which case the new effect uses advanced keyframes, or you can apply the template to a specific parameter in an effect. You can also choose to promote the template itself to advanced keyframes.

To promote a standard keyframe effect template:

- Right-click the template in the bin, select Promote Effects, and then click OK in the Promote Effects dialog box.

Your Avid editing application creates a copy of the template in the bin and promotes the effect information in the copy to advanced keyframes.

The name of the new template uses a suffix indicating that it is a promoted template. If the original template is named *MyColorEffect*, the promoted copy is named, for example, *MyColorEffect.Promoted.01*. Both the original template and the promoted copy are available in the bin.

Playing Effects

There are several situations where you need to play effects:

- While you are adjusting effects in Effect mode, you might want to play an individual effect to check its look. Depending on your needs, you might want to see the effect playing in real time and at high quality, or you might be able to accept playback at lower quality or in less than real time. Alternatively, you might only need to play an outline preview of the effect's movement.
- At any point in your project workflow, you might want effects in a sequence to play when you play all or part of the sequence. Depending on your needs, you might want to see the effects playing in real time and at high quality, or you might be able to accept playback at lower quality or in less than real time.
- When you are ready to output your project, you need all the effects in the sequence to play in real time and at full quality.

Depending on the capabilities of your Avid editing application and the complexity of your sequences, you might need to render some effects before you can play them back in real time.

For more information, see [“Real-Time Playback of Video Effects” on page 151](#) and [“Basics of Effects Rendering” on page 53](#).

Playing an Effect in Effect Mode

While you are in Effect mode, you can:

- Play all or part of an individual effect once.
- Play an individual effect in a continuous loop.
- Play an outline preview of an effect (a wire-frame representation of the effect's position, scale, and path of motion).

To play an effect in Effect mode:

1. In the Timeline, select the effect.
2. In the position bar of the Effect Preview monitor, move the position indicator to the location where you want play to begin.
3. Click the Play button or press the space bar.



Play continues until the end of the effect, or until you click the Play button or press the space bar again.

To play an effect in a continuous loop in Effect mode:

1. Move the position indicator in the Timeline to the effect you want to play.
2. Click the Play Loop button.



Play begins at the start of the effect and continues until you press the space bar.

To play an outline preview of an effect in Effect mode:

1. In the Timeline, select the effect.
2. In the position bar of the Effect Preview monitor, move the position indicator to the location where you want play to begin.
3. Click the Play Preview button.



Play continues until the end of the effect, or until you click the Play Preview button again or press the space bar.

Playing Real-Time Effects

A *real-time effect* is an effect that you can typically apply to a sequence and play without having to render it first (rendering takes time and disk space).

Real-time effects have a small green dot within the effect icon in the Timeline. Effects that you must render have a small blue dot within the effect icon in the Timeline. For more information, see [“Color Coding on Effect Icons” on page 25](#).

You can create a sequence that has any number of real-time and non-real-time effects. While any individual real-time effect plays in real time without rendering, multiple real-time effects in complex sequences might not all play in real time. The maximum real-time playback capabilities of your Avid editing application vary depending on system capabilities and the complexity of the sequence.

If your sequence contains a combination of effects that exceeds the real-time playback capabilities of your Avid editing application, you can still achieve successful playback in many cases. See [“Options for Controlling Real-Time Effects Playback” on page 154](#).

Real-time effects might cause dropped frames during a digital cut. You can have your Avid editing application select and render real-time effects that might cause dropped frames. For more information, see [“ExpertRender” on page 158](#).



If you do not have Avid input/output hardware connected to your system, you must render all effects before performing a digital cut. Software-only systems ignore unrendered effects during a digital cut. For example, unrendered transition effects play as cuts.

Using Render On-the-Fly for Effect Preview

When you preview effects in a sequence, you can use Render On-the-Fly to control how your Avid editing application displays frames with effects.

When Render On-the-Fly is selected, you can step through your sequence and preview any frame to check the look of the effects that apply to it, regardless of the type or number of those effects. Whenever you change the frame you are monitoring, your Avid editing application updates to show the image that results from any effects applied to that frame. Depending on the number and complexity of effects, there might be a perceptible delay before the image updates in the Composer monitor.

When Render On-the-Fly is deselected, your Avid editing application shows the monitored frame as if no effects are applied to it. You can deselect Render On-the-Fly to avoid delays in image updating when you are not concerned about the look of effects.

Using Render On-the-Fly can slow down your editing of a sequence. If you are compositing in a very complex, effects-intensive sequence, you might need to wait a noticeable period of time for a single frame to render when you change the frame you are monitoring. Instead of waiting for rendering to finish, you can interrupt Render On-the-Fly. Interrupting Render On-the-Fly interrupts only the rendering of non-real-time effects.

Render On-the-Fly only controls how your Avid editing application displays a frame when the position indicator is stationary at that frame. During playback (that is, while the position indicator is in motion), your Avid editing application's ability to display effects depends on whether real-time effects are enabled and on other associated factors. For more information, see [“Real-Time Playback of Video Effects” on page 151](#).

To display effects immediately during effects editing:

- ▶ Select Special > Render On-the-Fly (Clip > Render On-the-Fly on NewsCutter systems).

To interrupt Render On-the-Fly, do one of the following:

- ▶ Drag the position indicator in the Timeline.
While you are dragging, the sequence appears in the Composer monitor as it would if Render On-the-Fly were not selected from the Special menu.
- ▶ If you click in the Timeline and rendering begins, quickly move to another location in the Timeline.
This interrupts the rendering process until you release the mouse button.

Basics of Effects Rendering

The topics in this section provide basic information about rendering effects in Avid editing applications, along with instructions for rendering effects manually.

You can also render effects with the help of the ExpertRender feature. ExpertRender determines which effects you need to render for successful playback of a sequence. For more information, see [“ExpertRender” on page 158](#).

Understanding Effects Rendering

In Avid editing applications, *rendering* is the process of calculating and storing video information for the finished look of an effect so that the effect always plays in real time at full quality. Avid editing applications store a rendered effect and its media file as a precomputed master clip (often referred to as a precompute).

There are two main situations in which you render effects:

- Before you output a sequence, you must render any effects in the sequence that cannot play in real time during output. Avid editing applications can use the ExpertRender feature to identify and render these effects for you, so that you do not spend time and storage rendering effects that do not need rendering.
- At any time in your workflow, you must render any effects in a sequence that cannot play in real time if you need to view those effects in real time and at full quality. (If you can accept effects playback that is less than real time or less than full quality for preview purposes, you do not need to render.) Information in the Timeline can help you to see which parts of a sequence cannot play in real time, and you can use the ExpertRender feature to identify and render those effects that cannot play in real time. The ExpertRender feature can operate across a whole sequence, a marked part of a sequence, or a single location in a sequence.

You can render a single effect after you create it, or you can render multiple effects at the same time.

You can also interrupt a render in progress and choose to save or discard the completed portion. You can finish the render later by resubmitting the effect for rendering.

The key to rendering quickly is to render only those effects that require it. With vertical and nested effects, for example, you do not have to render every layer to play the effect in real time. If the top track covers the entire duration of the tracks below, your Avid editing application renders the composite result of all tracks into the top track.

2 Basics of Effects Editing

One useful way to minimize rendering time is to use the Submaster effect by applying it to a track above layered effects and rendering only the Submaster effect. For more information, see [“Submaster Editing” on page 275](#).



When you render an audio effect on an AMA media clip, all audio media files are written as PCM (MXF), regardless of what you set for the audio file format.

Rendering Effects

You have the following options for rendering effects:

- Render a single effect.
- Render multiple effects at a particular point in the Timeline (for example, effects on several stacked video tracks).
- Render multiple effects for a whole sequence or a portion of a sequence, by marking IN and OUT points.

You can configure your Avid editing application to send an email notification when a render operation completes. This lets you leave your Avid editing application unattended when a long render operation is taking place, yet still know when the render completes. For more information, see [“Email Settings” in the Help](#).



Save your sequence before you render by marking IN and OUT points. Depending on the number, type, and complexity of the effects, the rendering process can take a long time.



For information on preparing a RED clip for rendering, see [“Preparing your Red Clip for Transcode, Mixdown or Render” in the Help](#).

To render a single effect:

1. Move the position indicator to the effect in the Timeline.


Make sure the track containing the effect is selected.

2. Do one of the following:



- ▶ Click the Render Effect button.
- ▶ Select Clip > Render at Position.

The Render Effect dialog box opens.



To prevent the Render Effects dialog box from opening, press and hold the Alt key (Windows) or Option key (Macintosh) when you click the Render Effect button. Your Avid editing application uses the last drive selected and you do not need to follow the remaining steps in this procedure.

3. Click the Drive button, and select a drive for the rendered media.

The *Effect Source Drive* selection refers to the drive where the media on the outgoing shot of a transition resides.

4. Click OK.

For information on displaying the estimated time required for the render, see [“Displaying Estimated Render Time” on page 57](#).

If there is not enough room on the drive, your Avid editing application displays a message box that gives you the following choices:

Option	Description
Stop	Stop the rendering process and return to the Render Effect dialog box, and then select another drive before continuing.
Continue	Attempt to render the effect anyway, in case there might be enough room on the drive.


Your Avid editing application renders the effect and stores a precompute master clip on the drive you select.

To render multiple effects at position:

1. Move the position indicator to the effects in the Timeline.
2. Select all tracks that contain effects you want to render.
3. Select Clip > Render at Position.

The Render Effects dialog box opens.

2 Basics of Effects Editing



4. Click the Drive button, and select a drive on which to store the rendered effects.

The *Effect Source Drive* selection refers to the drive where the media on the outgoing shot of a transition resides.

5. Click OK.

For information on displaying the estimated time required for the render, see [“Displaying Estimated Render Time” on page 57](#).

If there is not enough room on the drive, your Avid editing application displays a message box that gives you the following choices:


Option	Description
Stop	Stop the rendering process and return to the Render Effect dialog box, and then select another drive before continuing.
Continue	Attempt to render the effect anyway, in case there might be enough room on the drive.

Your Avid editing application renders the effect and stores a precompute master clip on the drive you select.

To render multiple effects using IN and OUT points:

1. Select all tracks that contain effects you want to render.
2. Mark an IN point before the start of the first effect you want to render, and then mark an OUT point after the last effect you want to render.
3. Select Clip > Render In/Out.

The Render Effects dialog box opens.



4. Click the Drive button, and select a drive on which to store the rendered effect.

The *Effect Source Drive* selection refers to the drive where the media on the outgoing shot of a transition resides.

5. Click OK.

For information on displaying the estimated time required for the render, see [“Displaying Estimated Render Time” on page 57](#).

If there is not enough room on the drive, your Avid editing application displays a message box that gives you the following choices:

Option	Description
Stop	Stop the rendering process and return to the Render Effect dialog box, and then select another drive before continuing.
Continue	Attempt to render the effect anyway, in case there might be enough room on the drive.

Your Avid editing application renders the effect and stores a precompute master clip on the drive you select.

Displaying Estimated Render Time

To display estimated render time during render:

- ▶ Press the T key.

Press the T key again to clear the display.

To display how much of the render is completed as a percentage:

- ▶ Press the P key.

Clearing Rendered Effects

When you have one or more effects in a sequence that you want to return to unrendered status, you can clear the rendered effects within a range marked by IN and OUT points.

Clearing rendered effects does not delete the effects or their precomputes, but it disassociates the precomputes from the sequence so that the effects appear unrendered. If you want to restore the renders after clearing them, you can use the Undo feature.

If you want to clear one or more effects at a particular point in the Timeline (for example, effects on several stacked video tracks), you can clear just the rendered effects at that position.

You can also choose to clear all rendered effects except motion effects and any effects that your Avid editing application does not recognize (third-party plug-in effects that are not installed on your system).




If you clear an unknown effect — that is, one marked by a blank effect icon — you cannot rerender it on your system because the necessary AVX plug-in is not installed. For more information on blank effect icons, see “Troubleshooting AVX Plug-Ins” on page 192.

You can store effect precomputes on a drive separate from your media. If this drive is offline, rendered effects in the Timeline appear to be unrendered. Clearing these rendered effects does not change their appearance in the Timeline, but you cannot restore the rendered effect by bringing the effect drive online as the sequence has lost the information stored in the precompute. For more information on setting the effects drive, see “Media Creation Settings” in the Help.

To clear rendered effects using IN and OUT points:

1. Select all tracks that contain rendered effects you want to clear.
2. Mark an IN point before the start of the first effect you want to clear, and then mark an OUT point after the last effect you want to clear.
3. Select Clip > Clear Renders In/Out.

The Clear Renders dialog box opens.



4. Select the appropriate options:

Option	Description
Skip Motion Effects	Retains all motion effects in the marked range.
Skip Unknown Effects	Retains all effects with blank effect icons in the marked range.

5. Click OK.

Your Avid editing application clears all rendered effects between the IN and OUT points. The effect icons in the Timeline change from rendered to unrendered (the render dot appears in all cleared renders).

To clear rendered effects at position:

- 1. Move the position indicator to the effects in the Timeline.
- 2. Select all tracks that contain effects you want to clear.
- 3. Select Clip > Clear Renders at Position.

The Clear Renders dialog box opens.

4. Select the appropriate options:

Option	Description
Skip Motion Effects	Retains all motion effects at the position indicator.
Skip Unknown Effects	Retains all effects with blank effect icons at the position indicator.

5. Click OK.

2 Basics of Effects Editing

Your Avid editing application clears all rendered effects at the position indicator. The effect icons in the Timeline change from rendered to unrendered (the render dot appears in all cleared renders).

To restore cleared effects, do one of the following:

- ▶ Select Edit > Undo.

The cleared effects are restored only if Clear Renders was the previous action.

- ▶ Select Edit > Undo/Redo List, and then select Clear Renders.

All the previous commands, including the Clear Renders command selected from the submenu, are undone or redone as appropriate.

Rerendering Effects

In some situations you need to rerender an effect that you have already rendered. For example, you might have rendered a series of effects at a low resolution, and now need to rerender them at a higher resolution. This situation might occur if you are working with multiple resolutions. For more information, see “Using MultiRez and Dynamic Relink” in the Help.



You cannot use ExpertRender to rerender effects.

To rerender a single effect:

1. Move the position indicator to a single effect in the Timeline.
2. Shift-click the Render Effect button.
3. Click OK.



For more information, see [“Rendering Effects” on page 54](#).

To rerender multiple effects at one position:

1. Move the position indicator to the effects in the Timeline.
2. Select all tracks that contain effects you want to render.
3. Hold down the Shift key and select Clip > Render at Position.

For more information, see [“Rendering Effects” on page 54](#).

To rerender multiple effects using IN and OUT points:

1. Select all tracks that contain effects you want to render.
2. Mark an IN point before the start of the first effect you want to render in your sequence, and then mark an OUT point after the last effect you want to render.
3. Hold down the Shift key and select Clip > Render In/Out.

For more information, see [“Rendering Effects” on page 54](#).



You can also rerender effects using the shortcut menu Render commands. On the Macintosh, Shift+Ctrl-click in the Timeline to display the shortcut menu, and then press and hold the Shift key while you select Render at Position or Render In/Out. On Windows, Shift+right-click in the Timeline, and then select Render at Position or Render In/Out.

3 Applying and Customizing Effects

This chapter contains further information on applying and customizing effects that builds on the information presented in [“Basics of Effects Editing” on page 35](#).

- [Applying Dissolve Effects](#)
- [Working with the Quick Transition Dialog Box](#)
- [Adjusting Transitions in the Timeline](#)
- [Modifying Transition Effects in the Timeline](#)
- [Preserving Effect Transitions in the Timeline](#)
- [Replacing an Effect in Effect Mode](#)
- [Using the Effect Preview Monitor](#)
- [Stepping Through Field-Based Media](#)
- [Using the Effect Editor](#)
- [Manipulating Effects Directly in the Effect Preview Monitor](#)


Applying Dissolve Effects

You can apply a Dissolve effect using any of the following methods:

- Select the Dissolve effect from the Effect Palette.
For more information, see [“Applying Effects From the Effect Palette” on page 36](#).
- Click the Quick Transition button.
For more information, see [“Using the Quick Transition Button” on page 69](#).
- Type a duration in the Transition parameters in Trim mode or in the Effect Editor.
For more information, see [“Applying a Dissolve Effect Using the Transition Parameters” on page 64](#).
- Use the Head Fade button or the Tail Fade button.
For more information, see [“Adding Dissolves with the Head Fade and Tail Fade Buttons” on page 64](#).

Applying a Dissolve Effect Using the Transition Parameters

You can create a Dissolve effect by using the Transition parameters that display in Trim mode and in the Effect Editor. Enter the duration for the effect, and your Avid editing application adds the Dissolve effect to the sequence.



Transition Effect Alignment button (left, with menu below) and Transition Effect Duration text box (right) in the Effect Editor

To create a Dissolve effect by using the Transition parameters:

1. Click a transition in the Timeline while in Trim mode or Effect mode.
2. In the Transition Effect Duration text box in the Effect Editor, type the dissolve's duration.



The Duration setting above the Record monitor determines the duration format — for example, seconds:frames.



Your Avid editing application adds the Dissolve effect at the transition, and the Dissolve Effect icon appears in the Timeline.

3. Click the Transition Effect Alignment button, and select the effect's position relative to the cut point.

For an explanation of the Transition Effect Alignment menu selections, see [“Transition Parameters” on page 615](#).

Adding Dissolves with the Head Fade and Tail Fade Buttons

You can use the Head Fade button and Tail Fade button to add a dissolve for selected audio and video tracks.

When you use the Head Fade button and Tail Fade button, all selected tracks, including layered tracks, receive the effect.



When you use the Head Fade button and Tail Fade button with filler, your Avid editing application treats the filler like another video clip. You can use the Tail Fade button, for example, to fade from filler at the beginning of a sequence into the opening video clip.

To add a fade (dissolve):

1. Move the position indicator to a clip where you want the dissolve to end or begin.

Your Avid editing application uses the location of the position indicator to begin or end the dissolve. For example, if you move the position indicator ten frames after the beginning of the clip and then use the Head Fade button, your Avid editing application creates a ten-frame dissolve that lasts from the beginning of the clip to the location of the position indicator.

2. Select the tracks on which you want to create dissolves.

If you select more than one track, your Avid editing application creates dissolves of appropriate lengths for each track, as shown in the following illustration.



Tail Fade example — your Avid editing application creates two dissolves of different lengths on the two tracks

3. Select Tools > Command Palette.
4. Click the FX tab, and then click Active Palette.
5. Click the Head Fade button or the Tail Fade button.



Head Fade button (left) and Tail Fade button (right)

The dissolves appear in the Timeline. If a dissolve begins or ends at the edit point between two clips, the dissolve crosses between the two clips. Otherwise the dissolve is a fade from or to black.

6. (Option) If, for any selected track, there is insufficient source media to create a dissolve of the length you specified with the position indicator, the Insufficient Source dialog box opens. Do one of the following:

- Click Size to Fit.

Your Avid editing application creates the longest dissolve possible. For more information on sizing effects to fit available media, see [“Sizing Effects to Fit the Media” on page 40.](#)

- Click Skip Track.

Your Avid editing application does not create a dissolve on the track with insufficient source material but does create dissolves on any other selected tracks with sufficient source material.

3 Applying and Customizing Effects

- Click Cancel.

Your Avid editing application does not create any dissolves.


Working with the Quick Transition Dialog Box


The following topics provide instructions and information for using the Quick Transition button and the Quick Transition dialog box to apply basic transition effects without using the Effect Palette or entering Effect mode.

- Detailed information about the graphical controls in the Quick Transition dialog box.
- Procedures for applying a single transition effect.
- Procedures for applying effects to multiple transitions at one time.

The Quick Transition Dialog Box

The graphical display of the transition effect in the Quick Transition dialog box lets you control the length and position of the effect with frame accuracy simply by dragging. You can select specific tracks to apply the effect to, and you can quickly reset the position of the effect by using the three alignment buttons.



Element	Description
1 Track Selection buttons	Let you specify the tracks to which you apply the effect. When you open the Quick Dissolve dialog box, all tracks selected in the Timeline are also selected in the dialog box by default. However, selecting tracks in the Quick Dissolve dialog box does not affect track selection in the Timeline itself.
Add effect menu	<p>Lets you select a specific transition effect:</p> <ul style="list-style-type: none"> • Dissolve • Film Dissolve • Film Fade • Fade to Color • Fade from Color • Dip to Color <p> <i>When you select a color transition with Quick Transition, the default color is black. You must enter Effect mode to select another color. For more information, see “Using the Effect Editor” on page 89.</i></p>
Position menu	<p>Lets you specify where to position the effect:</p> <ul style="list-style-type: none"> • Ending at Cut • Centered on Cut • Starting at Cut • Custom
Duration	Lets you set the duration of the transition effect (in frames). The duration depends on the amount of available footage.
Start <i>n</i> frames before cut	Lets you specify how far before the cut (in frames) the transition effect begins. The number of frames depends on the amount of available footage.
2 Outgoing media	Provides a graphical representation of the outgoing (A) media for the transition to which you apply the effect.
3 Transition effect icon	Shows the effect icon and indicates the length and position of the effect in relation to the media. You can adjust the effect by dragging this part of the display. For more information, see “Adjusting a Transition Effect by Dragging in the Quick Transition Dialog Box” on page 72.

3 Applying and Customizing Effects

	Element	Description
4	Handle on outgoing media	The amount of handle available for each piece of media is indicated as a darker area on the graphic. If you have multiple transitions between an In point and an Out point, the handle refers to the transition closest to the position indicator (see “Using the Quick Transition Button to Apply Effects to Multiple Transitions” on page 72).
5	Frames of outgoing media	Lists the amount of handle available for each piece of media as a number of frames.
6	Handle on incoming media	The amount of handle available for each piece of media is indicated as a darker area on the graphic. If you have multiple transitions between an In point and an Out points, the handle refers to the transition closest to the position indicator (see “Using the Quick Transition Button to Apply Effects to Multiple Transitions” on page 72).
7	Alignment buttons	Allow you to quickly reposition the effect so that it either ends at the cut point, is centered on the cut point, or starts at the cut point. These buttons appear when you select Custom from the Position menu or click in the graphical display. For more information, see “Repositioning the Dissolve Effect with the Quick Transition Alignment Buttons” on page 74.
8	Incoming media	Provides a graphical representation of the incoming (B) media for the transition to which you apply the effect.
9	Frames of incoming media	Lists the amount of handle available for each piece of media as a number of frames.
	Target drive	Lets you select the drive where you store the effect if you choose to render it. The default Effect Source Drive is the drive where the media on the outgoing shot of a transition resides.
	Apply to All Transitions	Applies the transition effect to all transitions between the In point and the Out point.
	Skip Existing Transition Effect	Applies the transition effect only to transitions that do not have an effect already applied.
	Add button	Adds the effect to the sequence without rendering it.
	Add and Render button	Adds the effect to the sequence and renders all applied transition effects.
	Cancel	Closes the Quick Transition dialog box without applying any transition effects.

Using the Quick Transition Button

You can use the Quick Transition button to apply the following transition effects without using the Effect Palette and to adjust them for position and duration without entering Effect mode:

- Dissolve and Film Dissolve
- Fade to Color, Fade from Color, and Film Fade
- Dip to Color

The Quick Transition button appears on the Tool palette, in the Timeline top toolbar, and in the FX tab of the Command palette. For more information, see “Using the Tool Palette,” “Displaying the Timeline Top Toolbar,” and “The Command Palette” in the Help.

You can add the same transition effect to multiple transitions by marking In and Out points in your sequence that select all the transitions to which you want to apply the effect. When you click the Quick Transition button, the Quick Transition dialog box contains a check box for Apply to All Transitions (In -> Out). For more information, see [“Applying Effects From the Effect Palette” on page 36](#).

You can select which tracks to apply the effect to from within the Quick Transition dialog box. The Track Selection buttons in the Quick Transition dialog box match the Track Selection panel in the Timeline. However, selecting tracks in the dialog box only determines which tracks the effect applies to, not which Timeline tracks are active. You can apply the effect to active or inactive tracks, depending on your selection. Timeline shortcuts for selecting tracks — for example, lassoing a track selector to reverse the current track selection — also work in the Quick Transition dialog box, with the exception of Ctrl+A and Shift+Ctrl+A to select and deselect all tracks.

Creating a Transition with the Quick Transition Dialog Box


To create an effect by using the Quick Transition button:

1. Move the position indicator to the transition in the Timeline.
2. Click the Quick Transition button.



The Quick Transition dialog box opens.

3 Applying and Customizing Effects



The dialog box shows a graphical display of the outgoing media (A) and incoming media (B), with the Dissolve Effect icon applied to the transition. Your Avid editing application scales the graphical display to show the relative size of the Dissolve effect and the media available for the effect. For more information on Quick Transition options, see [“The Quick Transition Dialog Box” on page 66](#).

3. Click the Track Selection buttons to select the tracks to which you want to apply the effect.
4. Click the Add menu and select a transition effect.

For reference information on individual effects shown in the menu, see [“Blend Effects” on page 556](#).



*When you save a Dissolve effect template into a bin named **Quick Transitions**, the effect template appears in the Add menu. For more information, see [“Working with Effect Templates” on page 47](#).*

5. Set the transition duration by doing one of the following:
 - ▶ Type the duration in frames in the Duration text box. You cannot type a number greater than the number of frames available for the effect.
 - ▶ Click either the left or right edge of the Dissolve Effect icon and drag it to change the duration.

The graphical display changes to reflect the new duration. The size of the effect icon increases or decreases, and the numbers in the Duration and Start text boxes change.

6. Adjust the position of the effect relative to the cut point by doing one of the following:

- ▶ Click the Position menu, and select a command to have the effect end at the cut point, center on the cut point, or start at the cut point.
- ▶ Click the Position menu, select Custom, and then type a number in the Start text box to specify how many frames before the cut point you want the effect to begin. You cannot type a number greater than the number of frames available for the effect.
- ▶ Click the effect icon and drag it to position the effect with respect to the cut point.
- ▶ Click one of the alignment buttons below the graphical display.

These buttons appear when you select Custom from the Position menu or click in the graphical display.

Your Avid editing application positions the effect, and updates both the graphical display and the value in the Start text box.

If you select an alignment for which there is not enough media, your Avid editing application comes as close as possible to the alignment you request.

7. If you click the Dissolve Effect icon and drag it, the Position menu changes to Custom. Indicate where you want the effect to start — that is, how many frames before the cut you want to include in the effect — by doing one of the following:

- ▶ Click near the middle of the effect icon and drag it to change the number of frames dynamically.
- ▶ Click one of the alignment buttons below the graphical display to specify the effect as ending at cut, centered on cut, or starting at cut.
- ▶ Type the number of frames in the Start text box. You cannot type a number greater than the number of frames available for the effect.

The graphical display changes to show the relative amount of media available and the relative position of the effect, and the new value appears in the Start text box.

8. Click the Target Drive menu, and select a drive on which to store the effect if you choose to render it.

The Effect Source Drive is the default drive where the media on the outgoing shot of a transition resides.

9. (Option) If you have In and Out points marked in your sequence, do one of the following:

- ▶ Select Apply to All Transitions (In -> Out) to overwrite all existing transition effects between the In and Out points.
- ▶ Select both options to avoid overwriting any existing transition effects.



The Skip Existing Transition Effects option is useful when you want to add a number of dissolves to a sequence that already has transition effects.

3 Applying and Customizing Effects

10. Do one of the following:

- ▶ To add the effect without rendering it, click Add.
- ▶ To add the effect and render it, click Add and Render.

Your Avid editing application adds the effect to the selected transition and the selected tracks in the sequence, or, if you select Apply to All Transitions (In -> Out), to all transitions between the In and Out points on the selected tracks.



If there is not enough incoming or outgoing media material to apply the effect to a transition, a dialog box opens. For more information, see “Sizing Effects to Fit the Media” on page 40.

Using the Quick Transition Button to Apply Effects to Multiple Transitions

You can select multiple transitions by marking In and Out points. Then you can apply an effect from the Quick Transition dialog box in one of the following ways:

- Apply the effect to all transitions between the In and Out points.
- Apply the effect to only those transitions that do not already have an effect applied.

The graphical display in the Quick Transition dialog box always shows the transition closest to the position indicator. When you define an effect to apply to multiple transitions, the positioning details of any one transition might not be useful since you need to create an effect that will fit all the transitions. However, you might want to select one transition as a model. For example, you might use the transition with the least amount of handle as a model. If your effect fits that transition, it should fit all the others you have selected.

To apply an effect to multiple transitions by using the Quick Transition button:

1. Mark In and Out points around the transitions to which you want to add the effect.
2. (Option) If you want to see a particular transition in the graphical display of the Quick Transition dialog box, move the position indicator to that transition.
3. Follow the procedure for applying an effect with the Quick Transition button described in “Creating a Transition with the Quick Transition Dialog Box” on page 69.

Adjusting a Transition Effect by Dragging in the Quick Transition Dialog Box


You can control the length or position of the transition effect by dragging in the graphical display.

To adjust the length of the effect:

1. Do one of the following:

- ▶ To adjust the length of the effect without changing its start point, move the pointer over the right edge of the effect.
- ▶ To adjust the length of the effect without changing its end point, move the pointer over the left edge of the effect.

The pointer changes to a resizing arrow.



2. Do one of the following:

- ▶ To lengthen the effect, drag away from the effect icon in the center.
- ▶ To shorten the effect, drag toward the effect icon in the center.

The graphical display and the Duration text box update to reflect your adjustment. If you are dragging the left edge of the effect, the Start text box also updates to reflect the changed start point.

To adjust the position of the effect:

1. Move the pointer inside the effect.

The pointer changes to a hand.



2. Drag the effect to adjust its position with respect to the cut point.

The graphical display updates to show the new effect position, and the Start text box updates to show the new number of frames before the cut point.



You cannot drag an effect beyond the ends of the handles on the media because you cannot create a transition unless both incoming and outgoing media are available for every frame of the transition. You also cannot drag an effect beyond the cut point.




For information about preserving transition effects, see [“Preserving Effect Transitions in the Timeline” on page 77](#).

Repositioning the Dissolve Effect with the Quick Transition Alignment Buttons

You can use the alignment buttons below the graphical display in the Quick Transition dialog box to quickly reposition an effect so that it either ends at the cut, is centered on the cut, or starts at the cut. The buttons have the same effect as the Ending at Cut, Centered on Cut, and Starting at Cut commands in the Position menu.

To reposition the effect with an alignment button:

- ▶ Click one of the following buttons:

Button		Description
Ending at Cut		Aligns the effect so it ends at the cut point.
Centered on Cut		Aligns the effect so it is centered on the cut point.
Starting at Cut		Aligns the effect so it starts at the cut point.

Adjusting Transitions in the Timeline

You can adjust transitions directly in the Timeline using the Transition Manipulation tool and dragging either the transition handles or the transition effect icon in the Timeline. For more information, see [“Modifying Transition Effects in the Timeline” on page 75](#).

You can adjust transitions while you are performing Trim edits.

You can trim a transition effect by using the standard transition trim procedures. For more information, see “Working with Trim Edits” in the Help

In some Avid editing applications, you can also change the duration of transition effects by using the Transition Corner Display. For more information, see “Using the Transition Corner Display” in the Help.



The Transition Corner Display feature is only available in some Avid editing applications, and only when you are in Big Trim mode. To ensure that you enter Big Trim mode, select “Never use Small Trim mode” in the Features tab of the Trim Settings dialog box. For more information, see “Trim Settings” in the Help.

To customize transition effect parameters, see the procedures in [“Transition Parameters” on page 615](#).

Modifying Transition Effects in the Timeline

If you use the Transition Manipulation button in the Smart tool, you can edit transition effects by dragging the transition handles or by moving the transition effect icon. When you position your mouse pointer over a transition effect, the pointer changes to either a resizing arrow or a hand icon, which allows you to lengthen or shorten the transition by dragging to the left or right, or to move the transition by dragging the effect icon to another position in the Timeline.

Modifying a transition effect by dragging in the Timeline allows you to do the following, depending on the position of the transition effect:


- Dragging a transition handle away from or towards the cut point increases or decreases the duration of the transition in that direction.
- If you want to modify the duration of the transition equally in both directions (on the incoming and outgoing sides of the transition), you can press the Alt key (Windows) or the Option key (Macintosh) before dragging a transition handle. Similarly, dragging toward the transition decreases the duration of the effect in both directions.
- You cannot move a transition effect or drag a transition handle beyond the cut point itself.
- If you enable link selection or if you select more than one transition, you can modify transitions on multiple clips at the same time. If the transitions on the clips differ in the length of the effect or the duration of the available handles, you cannot lengthen the transitions beyond the limit of the shortest handle or beyond a cut point on any of the selected tracks. (For more information on editing with linked clips, see “Linked Clips” in the Help.)

To lengthen or shorten the duration of a transition effect in the Timeline:



1. Click the Transition Manipulation button in the Smart tool.
2. Position the mouse pointer over the transition handle on either the outgoing or incoming side of the transition.

The pointer changes to a resizing arrow.



3. Do one of the following:

3 Applying and Customizing Effects

- ▶ To lengthen the duration of a transition, drag the transition handle away from the effect icon in the center. You can press the Alt key (Windows) or the Option key (Macintosh) before you drag a transition handle to lengthen the duration of a transition equally in both directions.
- ▶ To shorten the duration of a transition, drag the transition handle toward the effect icon in the center. You can press the Alt key (Windows) or the Option key (Macintosh) before you drag a transition handle to shorten the duration of a transition equally in both directions.

The duration of the transition changes as you drag the transition handle. If you enable link selection, the duration of the transition in the Timeline changes for all linked clips.


The monitor display changes to a Transition Corner display, showing you six frames that you can use as reference points when trimming a transition effect.

To adjust the position of the effect in the Timeline:



1. Click the Transition Manipulation button in the Smart tool.
2. Position the mouse pointer over the effect icon for the transition you want to move.

The pointer changes to a hand.



3. Drag the effect to adjust its position with respect to the cut point.

The Timeline updates to show the new effect position. If you enable link selection, the transition moves on all tracks in the Timeline with linked clips.

The monitor display changes to a Transition Corner display, showing you six frames that you can use as reference points when trimming a transition effect.



You cannot drag an effect beyond the ends of the handles on the media because you cannot create a transition unless both incoming and outgoing media are available for every frame of the transition. You also cannot drag an effect beyond the cut point.

Preserving Effect Transitions in the Timeline

This topic describes the behavior of clips with transition effects when you trim and move them in the Timeline.

Segment Editing

When you move a segment with a transition effect into filler, the effect remains with the segment. Your Avid editing application does not remove the effect.

When you move a segment with a transition effect into another segment, the effect remains with the stationary segment.

For information about Segment editing, see “Working with Segments” in the Help.

Splicing and Overwriting

When you splice or overwrite a sequence onto another sequence, your Avid editing application preserves the transition effects at the marks in the source, depending on the position of the mark. For example:

If you:	The result is:
Place the Mark In at the cut	Your Avid editing application leaves the transition effect as is.
Place a Mark In before the cut	Your Avid editing application leaves the transition effect, but shortens the transition.
Place a Mark In after the cut	Your Avid editing application removes the transition effect.

Trim Mode

You can trim past the edge of the transition effect up to the cut.

For information about Trim mode, see “Working with Trim Edits” in the Help.

Cutting or Extracting

When you cut or extract a clip with a transition effect, the effect remains in the Timeline. Your Avid editing application does not remove the effect.

For information about extracting, see “Lifting, Extracting, and Copying Material” in the Help.

Replacing an Effect in Effect Mode

You can replace an existing effect in Effect mode. However, some effects cannot replace other effects. For example, some segment effects, such as the Mask effect, cannot replace transition effects. In addition, two-track effects, such as wipes, cannot replace three-track effects, such as matte keys.


To replace an effect:

1. If your Avid editing application is not in Effect mode, enter Effect mode, for example, by selecting Toolset > Effects Editing.
For more information, see [“Entering Effect Mode” on page 41](#).
2. In the Effect Palette, select an effect category.
3. Do one of the following to replace the effect:
 - ▶ Drag the new effect’s icon to the Timeline. To replace an existing effect, move the new effect’s icon on top of the existing effect’s icon.
 - ▶ Drag the new effect’s icon to the Effect Preview monitor.
 - ▶ Select the effect in the Timeline, and double-click the new effect’s icon in the Effect Palette.
4. Set the applicable effect parameters in the Effect Editor.

Using the Effect Preview Monitor

The Effect Preview monitor displays the selected effect in the sequence where the position indicator is located in the Timeline. The effect’s position bar, located directly below the Effect Preview monitor, represents only the selected effect, not the entire sequence.


For information on entering Effect mode and displaying the Effect Preview monitor, see [“Entering Effect Mode” on page 41](#).



The Effect Preview monitor. Top, left to right: tracking information, length of effect, and current position in effect. Bottom, left to right: scale bar (for expanding position bar), and position bar with position indicator (blue bar) and keyframe indicators (pink triangle).



If the effect you expect does not appear in the Effect Preview monitor, make sure that you have selected the Record Track Monitor button in the Track Selector panel. If a black frame appears in the Effect Preview monitor, the position indicator might be at a location in the Timeline where an effect has not been applied to the sequence. The following illustration shows the Record Track Monitor buttons.















Toolbar Buttons in the Effect Preview Monitor

You can use toolbar buttons in the Effect Preview Monitor to control effect position and adjustment. The following table describes these buttons.

The Effect Editor also contains controls that you use to adjust and preview effects. For more information, see [“Effect Editor Controls” on page 90](#).

3 Applying and Customizing Effects

Button		Description
Rewind		Places the position indicator at the first frame or field of the sequence.
Fast Forward		Places the position indicator at the last frame or field of the sequence.
Add Keyframe		Creates a keyframe at the current position of the position indicator in the effect's position bar. Alt+click (Windows) or Option+click (Macintosh) to delete the selected keyframe.
Step Backward One Frame		Moves the position indicator one frame backward.
Step Forward One Frame		Moves the position indicator one frame forward.
Play		<p>Plays the effect from the current position in the effect's position bar. Click again or press the space bar to stop play.</p> <p>Rendered effects play at full speed, and real-time unrendered effects play at full speed in most circumstances. For information on effect playback, see “Real-Time Playback of Video Effects” on page 151.</p>
Play Preview		Plays back a wire-frame preview of an unrendered effect.
Play Loop		<p>Plays back the current effect repeatedly in a loop. Click again or press the space bar to stop play.</p> <p>Rendered effects play at full speed, and real-time unrendered effects play at full speed in most circumstances. For information on effect playback, see “Real-Time Playback of Video Effects” on page 151.</p>
Dual Split		Click to divide the Effect Preview monitor in half, showing the image with and without the effect applied. Click again to remove.
Reduce		Reduces the size of the image in the Effect Preview monitor.
Enlarge		<p>Enlarges the size of the image in the Effect Preview monitor.</p> <p> <i>You can also Ctrl+click (Windows) or Command+click (Macintosh) in the Effect Preview monitor to enlarge the image.</i></p>

Using Big Effect Mode

Some Avid editing applications let you use Big Effect mode to work in an enlarged Effect Preview monitor. The Source monitor disappears, and the Effect Preview monitor becomes a larger working space that makes it easier to create effects and make changes to them.

To enter or leave Big Effect mode:

1. If your Avid editing application is not in Effect mode, enter Effect mode, for example, by selecting Toolset > Effects Editing.

For more information, see [“Entering Effect Mode” on page 41](#).



2. Alt+click (Windows) or Option+click (Macintosh) the Effect Mode button.

If your Avid editing application is in the default Effect mode, it enters Big Effect mode. You can click the Effect Editor and drag it to the left of the enlarged Effect Preview monitor.

If your Avid editing application is in Big Effect mode, it returns to the default Effect mode.



Once you enter Big Effect mode, it remains enabled until you Alt+click (Windows) or Option+click (Macintosh) the Effect Mode button again.

Mapping User-Selectable Buttons in Effect Mode

You can customize the buttons that are available in Effect mode by mapping user-selectable buttons directly from the Command palette to the Tool palette or to the area below the Effect Preview monitor.

To remap user-selectable buttons, enter Effect mode and use the procedure in “Mapping User-Selectable Buttons” in the Help.



When you customize the display of buttons in Effect mode, the new configuration appears in Effect mode only. The default editing mode buttons reappear when you exit Effect mode.

Understanding Tracking Information in the Effect Preview Monitor

The two boxes above the Effect Preview monitor display the length of the effect in seconds and frames and the current position in the effect’s position bar.

If you are working with two-field media, the current position display indicates the field that appears in the monitor. The current position display ends with .1 for the first field of a frame and with .2 for the second field. These boxes replace the name of the sequence that normally appears in this position.



If the position information boxes do not appear above the Effect Preview monitor, increase the size of the window.

Displaying Safe Title and Safe Action Guidelines in Monitors

Many effects can utilize the outer edges of the viewing screen area. If you are editing material that will be viewed on screens with more limited viewing areas, such as standard televisions, you can use the Safe Title and Safe Action options to provide visual guidelines in the Effect Preview monitor that replicate the actual viewable area on a standard television screen.

For example, you can use the Safe Title option as a template for the area in which you want the effect to operate. In this way, you can avoid the appearance of the effect floating off into a nonviewable area of a standard television screen.

You can also display safe title and safe action guidelines in other monitor types and in the Title tool. For information on displaying guidelines in the Title tool, see [“Setting Up the Drawing Environment” on page 391](#).

To display the Safe Title and Safe Action guidelines in the Effect Preview monitor:




► Click the Grid button in the Effect Editor.



You can customize the type of grid displayed by the Grid button. For more information, see [“Understanding the Effect Grid” on page 83](#).

Two outlined boxes appear in the Effect Preview monitor. The inner box is the safe title area. All text and objects should remain within the inner box. The outer box is the safe action area for video display



Understanding the Effect Grid

The Effect Grid helps you to position effects with accuracy and previsualize them in the Effect Preview monitor. The grid coordinates can be expressed in traditional fields or X–Y pixels in any resolution.

The following illustration shows a 12-field grid displayed in a video project.



You can use the Effect Grid to:

- Display the aspect ratios for film categories such as standard film, Academy, Super 35 mm, and Anamorphic, as well as the 4:3 safety area for the 16:9 aspect ratio.
- Show coordinate information to track the exact location of an effect in the frame.
- Use the snap-to-grid feature to easily position effects.

In film projects, you can also use the Effect Grid to:

- Create position information for the following effects: Paint, AniMatte™, Blowup. You can include this information in an optical list created using Avid FilmScribe™.
- Create position information for an effect you previsualize using the Previsualization Marker tool.

You can include this information in an optical list created using Avid FilmScribe. For more information, see [“Using the Previsualization Marker Tool for Film Projects” on page 494](#).

3 Applying and Customizing Effects

The Grid parameter category in the Effect Editor lets you customize the grid display for an individual effect. Grid parameters set in the Effect Editor apply only to that effect and temporarily override the current settings in the Grid Settings dialog box. For more information on the parameters available with the Grid parameter category, see “Grid” on page 610.

Displaying the Effect Grid in Effect Mode

To display the Effect Grid rather than the Safe Title/Safe Action guidelines:



- ▶ Press the Alt key (Windows) or Option key (Macintosh), and click the Grid button.

To switch between the Effect Grid and the Safe Title/Safe Action guidelines:

- ▶ Press the Alt key (Windows) or Option key (Macintosh), and click the Grid button until the appropriate grid is displayed.

To remove the display of either the Effect Grid or the Safe Title/Safe Action guidelines:

- ▶ Click the Grid button without pressing the Alt key (Windows) or Option key (Macintosh).

Displaying Position Coordinates for Effects

Your Avid editing application uses compass coordinates and X, Y coordinates to describe the position of an effect.

For compass coordinates, the point (0, 0) is the center of the axes. For X, Y coordinates, the point (0, 0) is the upper left corner of the monitor. X values increase to the right, and Y values increase as you move down.

The compass coordinates describe the effect’s position in terms of film optical house standards. Each compass coordinate begins with a direction (N, S, E, or W, the abbreviations for North, South, East, or West) followed by a numerical value. This numerical component reflects the Fields and Sub Fields parameters you select in the Grid Settings dialog box or the Grid parameter group.

The X, Y coordinates describe position in terms of the Source Scan Size parameters you select in the Grid Settings dialog box or the Grid parameter group.

To enable display of position coordinates:

1. In the Settings tab of the Project window, double-click Grid.

The Grid Settings dialog box opens.

2. Select Show Position Info, and then click OK.

3. Enable the Effect Grid as described in [“Displaying the Effect Grid in Effect Mode”](#) on [page 84](#).

To display position coordinates in Effect mode:

1. Deselect all tools in the Effect Editor (including the Outline/Path button and the Selection tool for Intraframe effects).



Outline/Path button (left) and Selection Tool button (right)

2. Press and hold the mouse button, and drag the pointer in the Effect Preview monitor.

To display position coordinates in Source/Record mode (editing mode on NewsCutter systems):

- Move the pointer to the Record monitor, press and hold the mouse button, and move the mouse.

Obtaining Position Information in a Film Project

Some Avid editing applications let you use the Effect Grid to include position information in a cut list for the Paint and AniMatte effects on a keyframe-by-keyframe basis. You can include both compass coordinate and X, Y coordinate information in a cut list for each corner of a Paint or AniMatte effect. For example, a rectangle you create with the Paint Effect shows four compass and four X, Y coordinates for each keyframe.

The following illustration shows the presentation of Paint Effect information for a rectangular object in a cut list.

3 Applying and Customizing Effects

```
Transfer: Full Aperture
Grid: Standard Film
Fields: 12
Subfields: 4
Scan Size: (X: 720, Y: 486)

Key Frame Information
KF Footage A Key #
(1) 0 5157+05
Shape1 Solid (R: 68, G: 46, B: 24)
(N: 0.0, W: 0.0) (X: 22, Y: 70)
(N: 0.0, W: 0.0) (X: 232, Y: 70)
(N: 0.0, W: 0.0) (X: 232, Y: 162)
(N: 0.0, W: 0.0) (X: 22, Y: 162)
```

Example of Paint Effect information in a cut list. Top to bottom: Grid information, keyframe number and reference numbers, Shape type and color information, Compass and (X,Y) coordinate information for each corner of the rectangle.

You can also display the position information for the first keyframe of a Blowup effect in a cut list. The event section of the cut list displays the compass coordinates of the effect at the first keyframe in the segment and the Fields parameter you have selected for the effect. You must enable the Effect Grid before you generate the cut list to display this information in the list.

The following illustration shows sample Blowup effect information in a cut list.

```
Transfer: Full Aperture
Grid: Standard Film
Fields: 12
Subfields: 0
Scan Size: (X: 720, Y: 243)

Key Frame Information
KF Footage A Key #
(1) 106 5701+03
(NO EDGE NUMBERS) Blowup Field:5 East:3 South:3
```

Example of Blowup Effect information in a cut list. Top: Grid information. Bottom, left to right: Keyframe number, Field parameter value, and Compass coordinates.



You generate film cut lists and change lists with Avid FilmScribe. For general information on using Avid FilmScribe, see the Avid FilmScribe Help.

You can also generate effect information in a cut list by using the Previsualization Marker Tool in the Paint Effect. For more information, see “Using the Previsualization Marker Tool for Film Projects” on page 494.

To include coordinate information in a cut list:

1. Enable the Effect Grid before you generate the list.
For more information, see “Displaying the Effect Grid in Effect Mode” on page 84.
2. In the Cut List tool within Avid FilmScribe, select the Key Frames check box in the Options pane for the optical list.

Moving an Enlarged Image in the Effect Preview Monitor

You can use the Enlarge and Reduce buttons in the Effect Editor or the Effect Preview Monitor toolbar to zoom in or out on an image in the Effect Preview monitor.

This lets you view parts of an image in detail or to view parts of effects and effect controls that extend beyond the limits of the standard-size image. For more information, see “Effect Editor Controls” on page 90 and “Toolbar Buttons in the Effect Preview Monitor” on page 79.

When you use the Enlarge button to increase the size of the image in the Effect Preview monitor, you cannot view the entire frame all at once. When you are creating an effect that requires great detail, you can reposition the enlarged frame in the monitor to view the areas that need your attention.



This feature applies only to an enlarged image in the Effect Preview monitor; not to a standard-size or reduced image.

To move an enlarged image within the Effect Preview monitor:

1. Click within the boundaries of the Effect Preview monitor.
2. Press and hold Ctrl+Alt (Windows) or Command+Option (Macintosh).

The pointer changes to a hand.

3 Applying and Customizing Effects



3. Drag the hand in any direction to reposition the image within the Effect Preview monitor.



You can also enlarge the frame in the Source monitor and move the frame around by pressing and holding Ctrl+Alt (Windows) or Command+Option (Macintosh). To access the Enlarge and Reduce buttons when you are not in Effect mode, use the Command palette, or map the buttons to your keyboard or to the user-selectable palettes. You can also use Ctrl+L (Windows) or Command+L (Macintosh) to enlarge the frame and Ctrl+K (Windows) or Command+K (Macintosh) to reduce the frame.

Stepping Through Field-Based Media

Your Avid editing application behaves differently when stepping through two-field media depending on the mode you are in.

In Effect mode, your Avid editing application displays each field in the media as you step forward or back using the standard controls, for example, the Step Forward and Step Backward buttons below the Effect Preview monitor.

In Source/Record and Color Correction modes (editing and Color Correction modes on NewsCutter systems), your Avid editing application displays only field 1 of each frame by default. If you need to view both field 1 and field 2 of each frame of video while in these modes, you can use the Step Forward One Field and Step Backward One Field buttons.

To step through footage one field at a time in Source/Record or Color Correction mode:

- Click the Step Forward One Field button or the Step Backward One Field button.



Step Forward One Field button (left) and Step Backward One Field button (right)

As you step, the number “2” appears in the upper right corner of the image display in the Record monitor whenever field 2 of the media is displayed. The number disappears during the display of field 1 (the default display).

Using the Effect Editor

You use the Effect Editor to adjust the parameters for an effect and to control other aspects of effects such as how they display and how you preview them.

Parameter controls are grouped in parameter categories in the main area of the Effect Editor. For example, the Border parameter category includes all the controls that you can use to define the color and appearance of an effect border.

Other controls and buttons are grouped on the right and at the bottom of the Effect Editor.

Displaying an Effect's Parameters in the Effect Editor

You display the Effect Editor by entering Effect Mode. The Effect Editor shows effect parameters for the effect currently selected in the Timeline.

To display an effect's parameters in the Effect Editor:

1. Move the position indicator to the effect's icon in the Timeline.
2. Make sure that the Record Track button for the track that contains the effect is selected in the Track Selector panel.
3. Enter Effect mode, for example, by selecting Toolset > Effects Editing.

For more information, see [“Entering Effect Mode” on page 41](#).

The Effect Editor opens. The name of the effect and its icon appear at the top of the Effect Editor and the parameters that pertain to the effect appear in the Effect Editor.



If the Effect Editor is already open and active, select the segment or transition effect to display the effect's parameters in the Effect Editor.

Understanding Parameters in the Effect Editor

Effect parameters are values that define the appearance of an effect. For example, you can set parameters that control the size and position of a Picture-in-Picture effect.

A number of parameters are common to many effects, such as parameters affecting size, position, or foreground level (transparency). You can adjust these parameters once for the entire effect, or you can use the Effect Editor along with keyframes to change the effect parameter over time. Other parameters can be adjusted only once for the entire effect, regardless of keyframe selection.

Not all effect parameters apply to all effects. Parameters that do not apply to an effect do not appear in the Effect Editor for that effect.




If the position indicator is not on an effect's icon in the Timeline, or if the track that contains the effect is not selected, the Effect Editor is blank.

For reference information on all of the available effect parameters (including which effect parameters apply to each effect), see [“Effects Reference” on page 555](#) and [“Effects Parameter Reference” on page 603](#).

Effect Editor Controls

This topic describes the controls in the Effect Editor. Not all controls apply to each effect. If a control is not applicable, it does not appear in the Effect Editor for that effect.

The following illustration is an example of the location of controls and buttons within a typical Effect Editor display. The exact number of controls and their appearance might vary for your Avid editing application.












1	Triangular opener	5	Parameter name	9	Transition Effect Duration box
2	Effect name and icon	6	Render Effect button	10	3D Promote button
3	Parameter group (parameter category)	7	Outline/Path button	11	Show/Hide Keyframe Graph button
4	Parameter adjustment slider	8	Transition Effect Alignment button	12	Additional buttons (exact set depends on the effect)















3 Applying and Customizing Effects

The following table describes the buttons that all effects have in common. Additional buttons appear in the Effect Editor, depending on the effect used. For example, if you are working with a 3D effect, a set of 3D-specific buttons appears along the right side of the Effect Editor. For more information on 3D-specific Effect Editor buttons, see [“Working with 3D Effects” on page 361](#).

When you are working with advanced keyframes, additional buttons appear in the bottom toolbar of the Effect Editor. For more information, see [“Effect Editor Controls for Advanced Keyframes” on page 142](#).

The Effect Preview Monitor toolbar also contains buttons that you use to adjust and preview effects. For more information, see [“Using the Effect Preview Monitor” on page 78](#).

Button or Control		Location in Effect Editor	Description
Triangular opener	 	Left side	Opens or closes the parameter group. A downward-pointing triangle displays the parameter group; a right-pointing triangle displays the parameter name.  <i>Triangular openers also appear to the left of keyframe graphs when you use advanced keyframes. For more information, see “Opening Keyframe Graphs” on page 104.</i>
Other Options		Inside some parameter categories	Opens additional parameters for some effects, including the Macintosh Colors panel or the Windows Color dialog box for color selection. For more information, see “Accessing Additional Parameters for an Effect” on page 96 .
Reduce		Right side	Reduces the image in the Effect Preview monitor.
Enlarge		Right side	Enlarges the image in the Effect Preview monitor.
Dual Split		Right side	Splits the Effect Preview monitor in half to show the image with and without effects applied to it.
Play Loop		Right side	Plays back a transition or segment effect in a loop.
Play		Right side	Plays the effect from the current position in the effect’s position bar for most 2D and 3D effects.

Button or Control		Location in Effect Editor	Description
HQ		Right side	Appears when a 3D effect has the HQ (Highest Quality) rendering option. Click to select the HQ implementation or the standard implementation with which to render the effect. The button is green when the HQ implementation is selected. For more information, see “Rendering 3D Effects Using the HQ (Highest Quality) Option” on page 176.
Tracking Tool		Right side	Appears when the effect can use motion tracking data. Click to open the Tracking window. For more information, see “Motion Tracking and Stabilization” on page 307.
Grid		Right side	Displays Safe Action/Safe Title guidelines or the Effect Grid. For more information, see “Displaying the Effect Grid in Effect Mode” on page 84.
Render Effect		Bottom	Renders the current effect.
Outline/Path		Bottom	Displays a wire-frame path to illustrate the movement of an effect from the first keyframe through the last keyframe.
Transition Effect Alignment	    	Bottom	Opens a menu from which you select the alignment of a transition effect relative to the cut point. The appearance of the button changes depending on which alignment option you have selected from the menu. For a detailed explanation of the Transition Effect Alignment menu and the Transition Effect Duration box, see “Applying a Dissolve Effect Using the Transition Parameters” on page 64.
 <i>The Transition Effect Alignment button shows the alignment of the transition effect applied at the cut point. If the cut point does not have a transition effect, the Transition Effect Alignment button appears as a vertical bar. If the cut point has an existing transition effect, the button indicates the alignment of the transition effect.</i>			
Transition Effect Duration box		Bottom	Sets a duration for the transition effect other than the duration displayed.
Promote to Advanced Keyframes		Bottom	Promotes an AVX 1.x effect to an AVX 2 effect. This button only appears for an AVX 1.x plug-in that is promotable to AVX 2. For more information, see “Updating and Promoting AVX Plug-ins” on page 189.
3D Promote		Bottom right corner	Promotes the effect to a 3D effect. Available for some effects, including titles, Picture-in-Picture, and imported matte keys.


Selecting a Parameter from a Menu in the Effect Editor

Some effects have parameters that you select from a menu (advanced keyframes) or from a Fast menu (standard keyframes). For example, border types for 3D effects are in the same menu.

To select a parameter from a menu:



- ▶ Click the menu or the Fast Menu button, and then select a parameter.



Example of a menu in an advanced keyframe effect (left), and of a Fast Menu button and its menu in a standard keyframe effect (right)

Changing a Parameter with a Slider in the Effect Editor

Many parameters have sliders for controlling parameters with a range of possible values.

Some parameters have a *thumbwheel*, a specialized slider that provides a window on a wide range of values and allows precise control over increments.



When you edit an effect that uses advanced keyframes, you can choose to display parameters with either sliders or thumbwheels. See “Effect Editor Controls for Advanced Keyframes” on page 142.

The parameter’s numeric value appears to the right of the slider or thumbwheel.



Examples of a parameter slider (left) and a thumbwheel (right)

Some parameters display a blank slider track until you click an Effect Editor tool that activates the control.

To activate a parameter that has a slider:

- ▶ Click the slider.

The slider changes to pink.

To change the value of a parameter that has a slider, use any of the following methods:

- ▶ Move the slider with the mouse.
- ▶ Use the Left Arrow or Right Arrow key to change the value by -1 or $+1$.
- ▶ Press the Ctrl key and use the mouse scroll wheel to change the value by increments of -1 or $+1$.
- ▶ Press the Shift key, and use the Left Arrow key or Right Arrow key to change the value by -10 or $+10$.
- ▶ Press the Ctrl and Shift keys, or the Ctrl and Alt keys, and use the mouse scroll wheel to change the value by increments of -10 or $+10$.
- ▶ Use the numeric keypad to type a new value, and, if you entered fewer than three digits, press Enter (Windows) or Return (Macintosh).

The parameter's numeric value (to the right of the slider) changes as you move the slider.

To move from one slider to the next slider:

- ▶ Press the Tab key.

To move from one slider to the previous slider:

- ▶ Press Shift+Tab.

Using Parameter Enable Buttons in the Effect Editor

You control some parameters using parameter Enable buttons. These parameters can either be active or inactive but cannot be adjusted over a range of values. For example, the Fixed Aspect parameter Enable button controls whether the aspect ratio of an image is maintained when you adjust one of its dimensions.

To turn a parameter on or off using a parameter Enable button:

- ▶ Click the Enable button.



Parameter Enable buttons, when the parameter is active (left) and when the parameter is inactive (right)

Accessing Additional Parameters for an Effect

Some effects have additional parameters that control their operation. For example, the Grid effect has additional parameters in which you set the number of columns and rows in the wipe.

When an effect has additional parameters, the Other Options button appears next to the effect name or in a parameter group.

To access an effect's additional parameters:



- ▶ Next to the effect name or in a parameter group, click the Other Options button.

A dialog box opens in which you set the additional parameters.



You also use the Other Options button to access the parameters for third-party plug-in effects and for the Windows Color dialog box or Macintosh Colors panel in effects that lets you change color parameters.

Adjusting a Color Parameter for an Effect


In addition to using the Hue, Sat (saturation), and Lum (luminance) sliders, you can change a color parameter or select a key color with the following methods:

- Select a color with the eyedropper.
- Specify a color in the Windows Color dialog box or Macintosh Colors panel.

The Windows Color dialog box is part of the Windows operating system and the Macintosh Colors panel is part of the Macintosh operating system.

To select a color using the eyedropper:

1. Position the pointer over the Color Preview window to activate the eyedropper.



Example of Color Preview window with eyedropper active


- 2. Press and hold the mouse button, then drag the eyedropper to the Effect Preview monitor, and release the mouse button on the color you want to select from the video image.

Your Avid editing application updates the parameter’s numeric values, and the selected color appears in the Color Preview window.

To open the Windows Color dialog box:

- ▶ Click the Other Options button next to a color parameter.

The Windows Color dialog box opens.



1	Default color choices	4	Current color	7	Color Selection text boxes
2	Custom colors palette	5	Color Solid box		
3	Color matrix	6	Color slider		

To use the Windows Color dialog box:

- 1. To select a color from the Basic colors palette, click the color you want.
- 2. To specify a custom color, do one of the following:
 - ▶ Click in the color matrix to select a color, and then drag the color slider to adjust the amount of white and black in the color.
 - ▶ Type numeric values for each color component in the color selection text boxes.The new color appears in the left side of the Color|Solid box.

3 Applying and Customizing Effects

3. When you are satisfied with the color, click Add to Custom Colors to add it to the Custom Colors palette.
4. To select a custom color from the Windows Color dialog box, click the color you want.
5. Click OK.

The Windows Color dialog box closes, and your Avid editing application applies the color to the parameter in the Effect Editor.

To open the Macintosh Colors panel:



- ▶ Click the Other Options button next to a color parameter.

The Macintosh Colors panel opens.



Select the appropriate icon at the top of the Colors panel to display the method you want to use for selecting the color. Options include RGB sliders, a crayon box, an HSV (hue, saturation, luminance) color wheel, a Web-safe color picker (Name), and CMYK (cyan, magenta, yellow, and black) sliders. For a complete description of how to use the Macintosh Colors panel, see the documentation that ships with your Macintosh.

Manipulating Effects Directly in the Effect Preview Monitor

You can make some adjustments to effects by manipulating them directly in the Effect Preview monitor. These adjustments use handles and wire-frame outlines that you can display in the monitor.

You can create a motion path that defines how the foreground image moves across the background video. You can also resize a foreground image, as in a picture-in-picture effect.

You can define how the foreground image of a multilayer effect moves across the background video by building a *motion path*, or string of keyframes. You can define a motion path on multilayer video effects such as Picture-in-Picture effects. Use the wire-frame preview feature when you want to see the path an image takes on the screen. You can also use the resize handles to set the size of the effect image at each keyframe location.


Create keyframes where you need them, make sure that the appropriate keyframe is selected, and then manipulate the wire frame and handles in the Effect Preview monitor. Drag the wire frame to reposition the effect. Drag the resize handles to resize the image — the top handle adjusts the height of the effect image, the side handle adjusts the width, and the corner handle adjusts width and height together, maintaining the aspect ratio. For more information on keyframing, see [“Working with Keyframes” on page 101](#).

When you are creating a motion path that moves beyond the viewing screen, you can use the Reduce button to view an outline of the image at a reduced scale. The reduced scale view shows the area outside the background image and lets you extend the motion path into that area. The Enlarge button returns the screen to full view.



Example of wireframe display in the Effect Preview monitor. The image area shows a background image on track V1 and a wire frame outlining the foreground image on track V2.

3 Applying and Customizing Effects



Example of a motion path in the Effect Preview monitor. Each dot on the path represents the location of the center of the PIP at a keyframe. The center handle and the resize handles are highlighted.

4 Working with Keyframes

This chapter describes how to use keyframes to change the behavior of an effect over time.

- [Understanding Keyframes](#)
- [Track Types for Advanced Keyframes](#)
- [Viewing Advanced Keyframe Graphs](#)
- [Manipulating Advanced Keyframes](#)
- [Controls and Settings for Advanced Keyframes](#)
- [Working with Standard Keyframes](#)

Understanding Keyframes

A *keyframe* is a point in an effect at which you can set parameters.

When you set parameters to different values in different keyframes, your Avid editing application animates your effect by calculating intermediate values for parameters between the keyframes. For example, if a Picture-in-Picture is set to be on the left of the screen at one keyframe and on the right of the screen at the next keyframe, the Picture-in-Picture moves from left to right across the screen over the period of time between the two keyframes.

Avid editing applications use two different kinds of keyframes, *advanced* and *standard*. In the current version of your Avid editing application, most effects use advanced keyframes only, while a small number of effects use standard keyframes only.



In previous versions of Avid editing applications, you could apply some effects as standard keyframe effects and subsequently choose to promote them to advanced keyframes. This workflow is no longer necessary or available. Effects either use advanced keyframes only or use standard keyframes only. For information on promoting existing effects in sequences, or existing effect templates, see “Updating and Reverting Existing Effects in Sequences” on page 44 and “Promoting Existing Effect Templates” on page 49.

Advanced Keyframes


Advanced keyframes let you establish independent keyframes for each keyframeable parameter in an effect, which provides flexibility and control for sophisticated effects adjustments. Most effects use advanced keyframes.

When an effect uses advanced keyframes, each keyframeable effect parameter has a separate *keyframe track* that opens to display a *keyframe graph* where you can set and customize keyframes. Keyframe tracks are also available for each parameter group, and for the entire effect. For more information on the three keyframe track types, see [“Track Types for Advanced Keyframes”](#) on page 103.

You can modify the keyframes for any single parameter independently from the keyframes for any other parameters. You can also modify the keyframes for various groups or combinations of parameters independently from the keyframes for any other parameters.

Alternatively, you can create and modify keyframes that affect all parameters at once, in which case you are using advanced keyframes as if they were standard keyframes. This approach limits your flexibility, but it might provide all the control you need for simple effect adjustments. You might also prefer this approach if you have done most of your keyframing work in the past using standard keyframes, at least until you become more familiar with the capabilities of advanced keyframes.

The following illustration shows part of the Effect Editor display for a Center Box effect, one of the many effects that uses advanced keyframes. The illustration shows the three types of keyframe tracks and an open keyframe graph.



Top to bottom: effect track (gray), parameter group tracks (darker blue), parameter tracks (lighter blue), and an open keyframe graph

Standard Keyframes

Some effects use standard keyframes, which apply to every parameter in an effect. The Effect Editor does not include keyframe graphs or any other mechanism for manipulating keyframes, so you need to use the position bar of the Effect Preview monitor for such operations as adding, selecting, and moving keyframes. You still use the Effect Editor to make parameter adjustments that affect selected keyframes.

Your Avid editing application always provides starting and ending keyframes when you create an effect that uses standard keyframes, and selects them by default. Any parameter changes are constant throughout the effect. Using techniques for adding, deleting, moving, selecting, and deselecting keyframes, you can begin to change the appearance and operation of the effect over time by applying parameter changes to specific keyframes.

Standard keyframe indicators appear as triangles in the position bar of the Effect Preview monitor when you select an effect and the Effect Editor is active. Before you make any keyframe changes to an effect, you see the default starting and ending keyframes at the ends of the position bar (both are pink, indicating that they are both selected).





Left to right: starting keyframe, Add Keyframe button, selected keyframe, and ending keyframe

For more information, see [“Working with Standard Keyframes” on page 148](#).

Track Types for Advanced Keyframes


Track Type	Description
Effect track	The keyframes in this track correspond to the keyframes in the Effect Preview monitor. When you select a keyframe in the effect track, the system automatically selects all of the keyframes at that point in time in the effect (all the keyframes directly under that keyframe in the Effect Editor). This makes it easy to move, delete, or perform other operations on many keyframes at the same time.
Parameter group track	This track shows all the keyframes in the specific parameter group. When you select a keyframe in the parameter group track, the system automatically selects all the corresponding parameter keyframes in the group. Parameter groups can have subgroups. For example, the Border parameter for many effects has Color and Blend Color subgroups.

 *Effect tracks and parameter group tracks provide similar functionality to the meta curve region available in Avid DS systems.*

Track Type	Description
Parameter track	<p>This track shows the keyframes for the individual parameter. Parameter tracks are lighter in color than parameter group tracks. You can open individual parameter tracks to fine-tune the parameter values in a keyframe graph.</p> <p> <i>Advanced keyframe functions are available even when a keyframe graph is closed to show only the keyframe parameter track.</i></p>

Viewing Advanced Keyframe Graphs

You can open a keyframe graph for any effect parameter that is keyframeable. Once a keyframe graph is open, you can customize your view of the graph in a variety of ways.

 *Parameters that are not keyframeable, such as the Fixed Aspect parameter, have tracks that do not show the parameter's name, default keyframes, or time marks. You can drag the effect's position indicator in these tracks, but you cannot add keyframes to them.*

Showing and Hiding the Keyframe Graph Display

You can choose to either show or hide the keyframe graph display area in the Effect Editor. Keyframe graphs are hidden when the Effect Editor first opens, so you need to show the display area to view or adjust the graphs. You might find it helpful to hide the graphs again to simplify your view of the Effect Editor when you do not need to make graph adjustments.

To show or hide the keyframe graph display:




- Click the Show/Hide Keyframe Graphs button in the bottom right corner of the Effect Editor.

The Show/Hide Keyframe Graphs button is highlighted when the keyframe graphs are visible.

Opening Keyframe Graphs

You open a keyframe graph by using the triangular opener to the left of the parameter track.

 *You do not have to open a keyframe graph to set and manipulate advanced keyframes. You can add and delete keyframes, customize keyframe interpolation options, and use the standard controls for each parameter to set the values for its keyframes while a keyframe graph is closed.*

To open a keyframe graph:

- Click the triangular opener.

The keyframe parameter track opens to display a keyframe graph.




Triangular openers and keyframe graphs in the Effect Editor. When the triangular opener points down, the associated keyframe graph is open.

Understanding Keyframe Graphs

In keyframe graphs, the horizontal axis represents the length of the effect and the vertical axis represents the range of parameter values. The graph area itself is very dark grey.

In the default view, a keyframe graph shows the full length of the effect on the horizontal axis and the full range of parameter values on the vertical axis.




Example of a keyframe graph. The horizontal axis represents the length of the effect. The vertical axis represents the range of values for the parameter.

You can scale and scroll a keyframe graph both horizontally and vertically, for example to concentrate on one part of the effect's length or one part of its parameter value range. When you do this, the boundaries of the keyframe graph might not be visible. For more information, see [“Zooming Keyframe Graphs” on page 107](#) and [“Scrolling Keyframe Graphs” on page 110](#).

The active keyframe graph is highlighted using a darker background. This lets you see which keyframe graph is active when multiple keyframe graphs are open. When you make another graph active, for example, by clicking a keyframe indicator in that graph, the background for that graph changes to the darker grey color.

In the following illustration, the Radius keyframe graph is active and is highlighted with a darker grey background.

4 Working with Keyframes



Resizing Keyframe Graphs

You can widen a keyframe graph or create space for expanding a keyframe graph vertically by resizing the Effect Editor window. You can expand or contract a keyframe graph vertically by dragging on the keyframe graph's bottom border.

- ▶ Click a corner of the Effect Editor, and drag it to resize the window.

If you make the Effect Editor window wider, the keyframe track area and any open keyframe graphs also become wider. If you make the Effect Editor window taller, you create extra space within which you can expand keyframe graphs vertically.

To change the height of a keyframe graph:



1. Position the pointer over the bottom border of the keyframe graph that you want to change.



The pointer changes to a vertical resizing pointer.

2. Click the edge of the graph, and drag it up or down.

The height of the keyframe graph gets smaller or larger.



Before (left) and after (right) vertical resizing

Zooming Keyframe Graphs

You can zoom (or scale) advanced keyframe graphs in several ways:

- You can zoom keyframe graphs horizontally using the horizontal scale bar at the bottom of the Effect Editor.


The horizontal scale bar expands or contracts the view in the keyframe graphs centered around the position indicator. This lets you either zoom in to focus on a specific area of your keyframe graph or zoom out to display the entire keyframe graph.

- You can zoom (or scale) any individual keyframe graph vertically using the graph's vertical scale bar, located to the left of the graph.

The vertical scale bar expands or contracts the view in a keyframe graph. This lets you either zoom in to focus on a specific area of your keyframe graph or zoom out to display the entire keyframe graph. You can zoom out beyond the limits of the parameter value range.

- You can use the Zoom to Curve Height feature to quickly scale a graph so that its keyframe curve fills the available viewing area for the graph.

For more information, see [“Using Zoom to Curve Height with Keyframe Graphs”](#) on page 108.




Top to bottom: horizontal scale bar, vertical scale bar, and Zoom to Curve Height button in the Effect Editor

To zoom in or out horizontally on a keyframe graph:

- Drag the horizontal scale bar to the right (to zoom in) or to the left (to zoom out).

The view in the keyframe graph expands or contracts horizontally to show more or less detail.

4 Working with Keyframes




Keyframe graph zoomed out (left) and zoomed in horizontally. In the zoomed in view, the graph shows detail of the middle of the effect's length, and start and end keyframes are not visible.



To zoom in or out vertically on a keyframe graph:

- ▶ Drag the vertical scale bar down (to zoom in) or up (to zoom out).

The view in the keyframe graph expands or contracts to show a smaller or larger range of parameter values.



Keyframe graph at default vertical zoom (the graph shows the full range of parameter values)




Keyframe graph zoomed in (left) and zoomed out vertically. The zoomed in view shows a reduced range of parameter values, and the zoomed out view shows an extended range of parameter values.

Using Zoom to Curve Height with Keyframe Graphs

The Zoom to Curve Height feature provides a quick way to focus on part of the keyframe graph.

Zoom to Curve Height centers the keyframe graph and scales the graph vertically so that the keyframe curve fills the available viewing area. This often makes it easier to read and manipulate graphs.




Keyframe graph before (left) and after (right) using Zoom to Curve Height




If the curve passing through a selected keyframe uses the Bézier interpolation option, the scaling ensures that the Bézier handles for the keyframe are also visible in the viewing area.

Zoom to Curve Height also takes account of the horizontal zoom setting of the graph. If a graph is zoomed in horizontally on a small time range in an effect, for example, Zoom to Curve Height scales the curve vertically while maintaining the horizontal zoom. By combining horizontal zooming and the Zoom to Curve feature, you can quickly make a keyframe graph easier to work with, even when keyframes are very close together and their parameter values are similar.



Zoomed out keyframe graph before (keyframes are very hard to see or manipulate)



The same keyframe graph after horizontal zooming and scrolling (left) and after using Zoom to Curve Height. After horizontal zooming alone, the curve remains flat and hard to read. After using Zoom to Curve Height, the zoomed in part of the graph is easy to see and interpret, and keyframes are easy to adjust.

4 Working with Keyframes

To zoom on a keyframe graph so the keyframe curve fills the available viewing area, do one of the following:

- ▶ Click the Zoom to Curve Height button.



- ▶ Right-click the keyframe graph and select Zoom to Curve Height.

Scrolling Keyframe Graphs

You can scroll the view in a keyframe graph horizontally by using the scroll thumbwheel at the bottom of the Effect Editor.



You can scroll the view in a keyframe graph both horizontally and vertically by dragging directly in the keyframe graph.

To scroll the view in a keyframe graph horizontally:

- ▶ Drag the scroll thumbwheel to the left or to the right.

The view in the keyframe graph scrolls so that part of the view disappears on one side and more comes into view on the other side.

To scroll the view in a keyframe graph horizontally or vertically:

1. Alt+click (Windows) or Option+click (Macintosh) the keyframe graph.
The pointer changes to a hand.
2. Drag the hand to reposition the view within the keyframe graph.

Resetting Keyframe Graph Views

If you move the view in a keyframe graph so that you can no longer see the keyframes, you can use the shortcut menu to recenter the keyframes in the keyframe graph.

To reset the view in a keyframe graph:

- ▶ Right-click the keyframe graph, and select Reset All Graph Views.

The keyframes appear centered in the keyframe graph.

Manipulating Advanced Keyframes

You can manipulate advanced keyframes in a wide variety of ways. You can:


- Add or delete keyframes
- Select or deselect keyframes
- Move keyframes
- Determine whether or not multiple keyframes move relative to one another
- Copy and paste keyframe parameters
- Control how effect parameters change at keyframes
- Reverse the order in which keyframes are applied over time in an effect
- Control how keyframes adjust when you trim effects
- Control how effect parameters change at bracketing (start and end) keyframes

You can also determine whether your keyframe manipulations apply to a single effect parameter or to multiple parameters.

Understanding Advanced Keyframe Display

When you add a keyframe to a parameter, corresponding keyframe indicators appear in the effect track, in the parameter group track, and in the Effect Preview monitor. The following illustration shows the result after keyframes are added to the Position parameters H Pos and V Pos.

4 Working with Keyframes



Top to bottom: keyframe in the effect track, keyframe in the parameter group track, new keyframes added to parameters in the Position group, new keyframe in the Effect Preview monitor's position bar

You should be aware of the following aspects of advanced keyframe display:

- Keyframe indicators in the Effect Editor's effect track or parameter group tracks are darker than those in individual parameter tracks, making it easier for you to distinguish between them.
- Keyframe indicators in parameter group tracks and in the effect track are linked to any keyframes that are beneath them in the parameter hierarchy. You can think of the keyframe indicators that appear in parameter group tracks and in the effect track as parent indicators, and the individual parameter keyframes beneath them as their children.

When you select a keyframe indicator in a parameter group track, any keyframes at that point in time for any individual parameters in that group are also selected and you can manipulate them together. When you select a keyframe indicator in the effect track, all keyframes at that point in time throughout the effect are also selected and you can manipulate them together.

Remember that a keyframe indicator in a parameter group track or in the effect track does not necessarily indicate that a keyframe exists at that point in time for *every* parameter in the group or in the effect. The keyframe indicator in the parameter group track or in the effect track might be the parent of one keyframe, or of several, or of a keyframe for every keyframeable parameter in the group or in the effect.

- Keyframe indicators in the Effect Preview monitor's position bar behave in the same way as keyframe indicators in the effect track of the Effect Editor. When you select a keyframe indicator in the Effect Preview monitor, the corresponding keyframe indicator in the effect track and all keyframes at that point in time in the effect are also selected.



Effect tracks and parameter group tracks provide similar functionality to the meta curve region available in Avid DS systems.

In some earlier versions of Avid editing applications, the system highlighted the keyframe in the Effect Preview monitor if you selected any keyframe in the associated column. Now the system highlights the keyframe in the Effect Preview monitor only if all the keyframes in the column are highlighted.

Adding Advanced Keyframes

You can add keyframes to any keyframeable parameters by using the following commands and buttons:

- The Add Keyframe command in the shortcut menu for the keyframe track.
- The Add Keyframe button in the Effect Editor.
- The Add Keyframe button in the Effect Preview monitor.

Depending on which method you use and how the Effect Editor is configured, you can add a keyframe to a single parameter, all the parameters in a group, every parameter in an effect, or any other custom combination of parameters.

You can use the Effect Editor shortcut menu to set a default Add Keyframe command that controls where keyframes are added when you use the Add Keyframe button in the Effect Editor or in the Effect Preview monitor. For more information, see [“Shortcut Menu and Settings for the Effect Editor” on page 146](#).



You cannot add keyframes to parameters that are not keyframeable (for example, the Fixed Aspect parameter). The graph area for these parameters does not display time marks, default keyframes, or the parameter name.

To add a keyframe by using the shortcut menu for the keyframe track:

1. Move the position indicator to the point in the effect's duration where you want to add a keyframe.
2. Right-click one of the following:
 - ▶ The keyframe graph or the parameter track for an individual parameter, to add a keyframe to that parameter only.
 - ▶ A parameter group track, to add a keyframe to every keyframeable parameter in that group.
The track displays the text "Apply to Group."
 - ▶ The effect track, to add a keyframe to every keyframeable parameter in the effect.
The track displays the text "Apply to All."
3. Select Add Keyframe.


Active keyframe indicators appear at the position indicator in all appropriate tracks. For more information on where keyframe indicators appear, see ["Understanding Advanced Keyframe Display" on page 111](#).

To add a keyframe by using the Add Keyframe button in the Effect Editor:

1. Move the position indicator to the point where you want to add a keyframe.
2. In the Effect Editor, click the Add Keyframe button.



The Add Keyframe Mode menu opens.



If the Add Keyframe Mode menu does not appear, you need to select Show Add Keyframe Mode Menu in the Effect Editor shortcut menu or in the Effect Editor settings. For more information, see ["Shortcut Menu and Settings for the Effect Editor" on page 146](#).

3. Do one of the following:
 - ▶ Click the Add Keyframe button a second time to select the command that has a check mark next to it.

This is the default command for adding keyframes that you can set by using the Effect Editor settings or the Effect Editor shortcut menu. For more information, see ["Shortcut Menu and Settings for the Effect Editor" on page 146](#).

- ▶ Select another command from the Add Keyframe Mode menu.

For more information on the command selections, see [“Keyframe Mode Menu Commands” on page 117](#).

Active keyframe indicators appear at the position indicator in all appropriate tracks. For more information on where keyframe indicators appear, see [“Understanding Advanced Keyframe Display” on page 111](#).

The command you select becomes the default command for adding keyframes and its Delete Keyframe equivalent becomes the default command for deleting keyframes. For more information, see [“Shortcut Menu and Settings for the Effect Editor” on page 146](#).

To add a keyframe by using the Add Keyframe button in the Effect Preview monitor:

1. Move the position indicator to the point where you want to add a keyframe.
2. In the Effect Preview monitor, click the Add Keyframe button.



Your Avid editing application adds one or more keyframes as determined by the current default command for adding keyframes in the Effect Editor shortcut menu. For more information on this default and how to change it, see [“Shortcut Menu and Settings for the Effect Editor” on page 146](#).

Active keyframe indicators appear at the position indicator in all appropriate tracks. For more information on where keyframe indicators appear, see [“Understanding Advanced Keyframe Display” on page 111](#).

Deleting Advanced Keyframes

You can delete advanced keyframes by selecting the keyframes you want to delete and then using one of the following:

- The Delete key.
- The Delete Keyframe command in the shortcut menu for the keyframe track.
- The Add Keyframe button in the Effect Editor.
- The Add Keyframe button in the Effect Preview monitor.

To delete advanced keyframes by using the Delete key or the Delete Keyframe command in the shortcut menu for the keyframe track:

1. Click a keyframe indicator to activate it.
2. (Option) Ctrl+click additional keyframes in the same graph or in other graphs.
3. Do one of the following:
 - ▶ Press the Delete key.
 - ▶ Right-click the keyframe graph or keyframe track, and select Delete Keyframe.

4 Working with Keyframes

Your Avid editing application deletes the selected keyframes.

To delete advanced keyframes by using the Add Keyframe buttons:

1. Click a keyframe indicator to activate it.
2. (Option) Ctrl+click additional keyframes in the same graph or in other graphs.
3. Do one of the following:
 - ▶ In the Effect Editor or in the Effect Preview monitor, press and hold the Alt key (Windows) or the Option key (Macintosh), and then click the Add Keyframe button.
Your Avid editing application deletes any selected keyframes that are affected by the current default Delete Keyframe Mode menu command. For example, if Delete From Open Graphs is the current default, your Avid editing application deletes any selected keyframes in open keyframe graphs.
 - ▶ In the Effect Editor, press and hold the Alt key (Windows) or the Option key (Macintosh), click the Add Keyframe button while still holding the Alt or Option key and pressing the mouse button, and then select a command from the Delete Keyframe Mode menu.

For more information on the Delete Keyframe Mode menu commands, see [“Keyframe Mode Menu Commands” on page 117](#).

The command you select becomes the default command for deleting keyframes and its Add Keyframe equivalent becomes the default command for adding keyframes. For more information, see [“Shortcut Menu and Settings for the Effect Editor” on page 146](#).



If the Delete Keyframe Mode menu does not appear, you need to select Show Add Keyframe Mode Menu in the Effect Editor shortcut menu or in the Effect Editor settings.

Removing Redundant Keyframes

When you work with advanced keyframes, you sometimes accumulate redundant keyframes in your keyframe graphs. For example, if three or more keyframes lie on a straight line segment in the graph for a single parameter, only the first and last keyframes are necessary to define the parameter change, and the other keyframes are redundant.

You can remove redundant keyframes from either a single parameter graph, or from all the graphs in a parameter group, or from all the graphs in an effect.

You can also remove redundant keyframes for all effects in a sequence at one time. This is one good way to reduce the amount of memory required when working with a complex sequence.

To remove redundant keyframes:

1. Right-click one of the following:
 - ▶ The effect track.
The track displays the text “Apply to All.”
 - ▶ A parameter group track.
The track displays the text “Apply to Group.”
 - ▶ A parameter track.
 - ▶ A keyframe graph.
2. Select Remove Redundant Keyframes.
Your Avid editing application removes redundant keyframes from the range of keyframe graphs you specified in step 1.

To remove all redundant keyframes in a sequence:

1. (Option) If you want to keep a safe copy of your sequence with all of the existing keyframe data, duplicate the sequence.
For more information, see “Duplicating, Copying, and Moving Clips and Sequences” in the Help for your Avid editing application.
2. Select the sequence in a bin.
3. Right-click the sequence, and select Remove Redundant Keyframes.
A message box warns you that the sequence will be modified.
4. Click OK to remove all redundant keyframes in the sequence, or Cancel to take no action.



When keyframes use the Bézier interpolation option, your Avid editing application might leave some keyframes that could be removed. This conservative behavior ensures that the Remove Redundant Keyframes command never removes needed keyframes.

Keyframe Mode Menu Commands

The Add Keyframe Mode and Delete Keyframe Mode menus provide commands that control how parameters are added or deleted when you use the Add Keyframe buttons in the Effect Editor or in the Effect Preview monitor. The same set of commands also appears in the Effect Editor shortcut menu.

When you select a command in one of these menus it becomes the default command when you add or delete keyframes using the Add Keyframe buttons. For more information, see [“Shortcut Menu and Settings for the Effect Editor” on page 146.](#)

4 Working with Keyframes

The Add Keyframe Mode and Delete Keyframe Mode menus mirror one another. When you change one, a corresponding change happens in the other.




Several of the menu command names include the word “group.” In these names, “group” refers to a parameter category.

The default command for adding and deleting keyframes applies to the keyframes in the Effect Preview monitor’s position bar just as it does to keyframes in the Effect Editor. For example, if “Add Keyframes to Open Groups” is the default command but no groups are open in the Effect Editor, you cannot add any keyframes to the Effect Preview monitor’s position bar. In this case, open a group in the Effect Editor before you add keyframes or change the command for adding and deleting keyframes.

Add Keyframe Mode and Delete Keyframe Mode Menu Commands


Command	Description
Add to Active Parameter (Add Keyframe Mode menu)	Adds a keyframe to or removes selected keyframes from the parameter track or keyframe graph for the active parameter only.
Delete From Active Parameter (Delete Keyframe Mode menu)	The active parameter is the parameter that is currently selected, for example, a slider that you clicked is highlighted.
Add Keyframes to Active Parameter (Effect Editor shortcut menu)	Corresponding keyframes appear in or are removed from the relevant parameter group track and the effect track.



Active parameter (left) and keyframes added when you use the Add to Active Parameter command (right)

Add Keyframe Mode and Delete Keyframe Mode Menu Commands (Continued)

Command	Description
Add to Active Group (Add Keyframe Mode menu)	Adds keyframes to or removes selected keyframes from the parameter tracks or keyframe graphs of all parameters that are in the same parameter category as the active parameter. If the category containing the active parameter is a subcategory of a larger category (for example, Color is a subcategory of Border), keyframes appear only in the subcategory and not in the larger category.
Delete From Active Group (Delete Keyframe Mode menu)	
Add Keyframes to Active Group (Effect Editor shortcut menu)	
	The active parameter is the parameter that is currently selected, for example, a slider that you clicked is highlighted.
	Corresponding keyframes appear in or are removed from the parameter group track and the effect track.




Active group (left, containing the active parameter) and keyframes added when you use the Add to Active Group command (right). In this case, the Hue, Sat, and Lum parameters each have a new keyframe.

4 Working with Keyframes

Add Keyframe Mode and Delete Keyframe Mode Menu Commands (Continued)

Command	Description
Add to Open Groups (Add Keyframe Mode menu)	Adds keyframes to or removes selected keyframes from the parameter tracks or keyframe graphs of all parameters in groups that are currently open, whether or not the group is enabled.
Delete From Open Groups (Delete Keyframe Mode menu)	
Add Keyframes to Open Groups (Effect Editor shortcut menu)	Corresponding keyframes appear in or are removed from the relevant parameter group tracks and the effect track.




Keyframes added when you use the Add to Open Groups command. Your Avid editing application adds new keyframes to all parameters in open groups, even if the keyframe tracks are closed.

Add to Enabled Groups (Add Keyframe Mode menu)	Adds keyframes to or removes selected keyframes from the parameter tracks or keyframe graphs of all parameters in groups that are currently enabled, whether or not the group is open.
Delete From Enabled Groups (Delete Keyframe Mode menu)	
Add Keyframes to Enabled Groups (Effect Editor shortcut menu)	Corresponding keyframes appear in all parameter group tracks and the effect track.

Add Keyframe Mode and Delete Keyframe Mode Menu Commands (Continued)

Command	Description
Add to Open Graphs (Add Keyframe Mode menu)	Adds keyframes to or removes selected keyframes from all open keyframe graphs, whether or not the group is enabled.
Delete From Open Graphs (Delete Keyframe Mode menu)	This command lets you add or delete keyframes from any custom grouping of parameters. Open the keyframe graph for each parameter, and then use the command.
Add Keyframes to Open Graphs (Effect Editor shortcut menu)	Corresponding keyframes appear in or are removed from the relevant parameter group tracks and the effect track.



Keyframes added when you use the Add to Open Graphs command. Your Avid editing application adds new keyframes to any parameters whose keyframe graphs are open, to the group tracks that contain these parameters, and to the effect track.

Add to All Parameters (Add Keyframe Mode menu)	Adds keyframes to or deletes selected keyframes from the keyframe tracks or keyframe graphs for every keyframeable parameter in the effect.
Delete From All Parameters (Delete Keyframe Mode menu)	Corresponding keyframes appear in all parameter group tracks and the effect track.
Add Keyframes to All Parameters (Effect Editor shortcut menu)	Choose this option if you want advanced keyframes to behave in the same way as standard keyframes.

Selecting and Deselecting Advanced Keyframes

You can select one or more keyframes at any level of the keyframe track hierarchy — open keyframe graphs, parameter tracks, parameter group tracks, or the effect track. When you select keyframes in parameter group tracks or in the effect track, you also select all the keyframes in the group or in the effect at that point in time.

To select a keyframe:

- ▶ Click the keyframe.
The keyframe changes to pink.

To select more than one keyframe:

1. Click the first keyframe that you want to select.
The keyframe changes to pink.
2. Ctrl+click each additional keyframe.
Each keyframe changes to pink.



In some earlier versions of Avid editing applications, you could single-click a keyframe in a different parameter group to select it. Now you must Ctrl+click the keyframe in a different group if you want to add it to a multiple-keyframe selection.

When you select more than one keyframe in a single keyframe track, your Avid editing application uses the most recently selected one as the reference keyframe for aligning and slipping keyframes. In addition, there are special considerations when you align keyframes in a track with both selected keyframes and deselected keyframes. See “Aligning Advanced Keyframes” on page 126.

To select all keyframes in a track:

- ▶ Right-click a parameter track, parameter group track, or effect track, and select Select All Keyframes.

To deselect a keyframe:

- ▶ Ctrl+click the keyframe.

To deselect all keyframes but one in a track:

- ▶ Click the keyframe you want to remain selected.
The keyframe indicator you click changes to pink. All other keyframes in the track appear gray and are deselected.

To deselect all keyframes in a track, do one of the following:


- ▶ With a parameter enabled (for example, the slider for the parameter is highlighted), select **Edit > Deselect All Keyframes**.

All keyframes in the enabled parameter's parameter track are deselected.

- ▶ Right-click a parameter track, a parameter group track, or the effect track, and select **Deselect All Keyframes**.

When you right-click a parameter group track, your Avid editing application displays the text “Apply to Group” in the parameter group track, as shown in the following illustration.

All keyframes for the parameter, group, or entire effect are deselected.



Moving Advanced Keyframes

You can move an advanced keyframe to another location in the keyframe graph.

This topic describes methods for moving keyframes by dragging in the Effect Editor or in the Effect Preview monitor. You can also move keyframes to the location of the position indicator by using commands on the shortcut menu for the keyframe track. For more information, see [“Understanding the Align Keyframes and Slip Keyframes Commands” on page 126](#).

For additional information, see [“Considerations When Moving Advanced Keyframes” on page 124](#).

To move a single keyframe, do one of the following:

- ▶ Drag the keyframe up or down in the keyframe graph to change its parameter value without changing its position in time.
- ▶ **Alt+Shift+drag** (Windows) or **Option+Shift+drag** (Macintosh) the keyframe horizontally to change its position in time without changing its parameter value.

4 Working with Keyframes

- ▶ Alt+drag (Windows) or Option+drag (Macintosh) the keyframe to move it freely both vertically and horizontally and so change both its parameter value and its position in time.

To move multiple keyframes:

1. Click one of the keyframes to select it.
2. Ctrl+click additional keyframes to add them to the selection.
3. Do one of the following:
 - ▶ Drag one of the keyframes up or down in the keyframe graph to change the parameter value of all the keyframes by the same relative amount without changing their positions in time.



With two keyframes selected in a parameter, drag one of the keyframes to move both vertically

- ▶ Press the Alt key (Windows) or the Option key (Macintosh) and then drag one of the keyframes.

When you Alt+drag (Windows) or Option+drag (Macintosh) multiple keyframes in an open keyframe graph, you can move the keyframe you are dragging both vertically and horizontally. The rest of the keyframes move horizontally (in time) but do not move vertically.




With two keyframes selected in a parameter, Alt-drag (or Option-drag) the top keyframe. The keyframe you drag moves in both time and value. The second keyframe moves in time only.

Considerations When Moving Advanced Keyframes

You should be aware of the following when you are moving advanced keyframes:

- You can move keyframes by dragging at all levels of the keyframe track hierarchy — open keyframe graphs, parameter tracks, parameter group tracks, and the effect track. However, only open keyframe graphs let you move keyframes vertically and so change their parameter values.
- When you move keyframe indicators in a parameter group track or the effect track, you move all keyframes at that point in time in the parameter group or in the entire effect.

- You can move a keyframe outside the time boundaries of the keyframe graph, so that the effect behaves as if parameter values are changing before the beginning or after the end of the effect. This works only for the time at which a keyframe occurs; you cannot move a keyframe to a parameter value outside the maximum or minimum value for the parameter.




Before (left) and after (right) moving a keyframe outside of the effect's time boundaries — in this case, to a position before the beginning of the effect

You can also move keyframes outside the time boundaries by using the Align Keyframes and Slip Keyframes commands. For more information, see [“Understanding the Align Keyframes and Slip Keyframes Commands”](#) on page 126.

- If you drag a keyframe for a parameter out of a column containing many keyframes, the system creates new keyframes on the effect track, on the corresponding parameter group track, and in the Effect Preview monitor.

The following illustration shows an example of what happens when one of the keyframes is dragged out of the column. In this example, the keyframe in the Sat parameter has been dragged to the left out of the column of keyframes at the location of the position indicator. New keyframe indicators appear in the effect track, in the Effect Preview monitor's position bar, in the parameter group track, and in the group track for the Color parameter subcategory.



4 Working with Keyframes

- You cannot move a keyframe past another keyframe. Keyframe movement is bounded by neighboring keyframes.
- If two or more effects are shown in the Effect Editor, only the top effect is editable. This means that if you have nested effects, you can move the keyframes in only one effect at a time.

Understanding the Align Keyframes and Slip Keyframes Commands

The Align Keyframes and Slip Keyframes commands in the shortcut menu for the keyframe track lets you move keyframes to the location of the position indicator.

- Align Keyframes moves the selected keyframe to the position indicator. The other keyframes in the keyframe track do not move.
- Slip Keyframes moves all the keyframes of the parameter so the selected keyframe aligns with the position indicator, and the rest of the keyframes maintain their relative location.

You do not have to select a keyframe from an open keyframe graph to use Align Keyframes and Slip Keyframes. You can select keyframes in any keyframe track.



Disabling Set Position To Keyframe can make it easier for you to use Align Keyframes and Slip Keyframes. See “Shortcut Menu and Settings for the Effect Editor” on page 146.

You can use Align Keyframes and Slip Keyframes within a single keyframe track by selecting a single active keyframe. You can also use Align Keyframes and Slip Keyframes to bring several parameters into alignment, by selecting an active keyframe in more than one parameter and then choosing where you invoke the shortcut menu. See “[Selecting and Deselecting Advanced Keyframes](#)” on page 122.

When you select more than one keyframe in a single keyframe track, your Avid editing application uses the most recently selected one as the reference keyframe for aligning and slipping keyframes. In addition, there are special considerations when you align keyframes in a track with both selected keyframes and deselected keyframes. See “[Aligning Advanced Keyframes](#)” on page 126.

Both Align Keyframes and Slip Keyframes can move keyframes outside the time boundaries of the keyframe graph. This lets you make the effect behave as if parameter values are changing before the beginning or after the end of the effect.

Aligning Advanced Keyframes

In the procedure below, the *reference keyframe* of any keyframe graph is the keyframe you activated most recently in that keyframe graph.

To align the reference keyframe to the position indicator:

- ▶ Right-click an open keyframe graph, a parameter track, a parameter group track, or the effect track, and select Align Keyframes.

The reference keyframe moves to the position indicator. If the reference keyframe is in a parameter group track or in the effect track, all the keyframes at that point in time in the parameter group or in the entire effect move to the position indicator.



Align Keyframes does not move the reference keyframe beyond an intervening keyframe (a keyframe between the reference keyframe and the position indicator). If there is an intervening keyframe, the reference keyframe moves to within one frame or field of it.



Before (left) and after (right) aligning a keyframe to the position indicator (no intervening keyframes)




Before (left) and after (right) aligning a keyframe to the position indicator. In this example, an intervening keyframe limits the movement of the selected keyframe.

Align Keyframes exhibits more complex behavior when you have multiple keyframes selected in one keyframe graph.

If you select all keyframes in one keyframe graph, Align Keyframes is equivalent to Slip Keyframes. The reference keyframe moves to the position indicator, and all other keyframes maintain their position relative to the reference keyframe.


Deselected (gray) keyframes do not move. All selected keyframes move as close to the target position as possible unless a deselected keyframe intervenes.

The following illustrations shows several examples (the second keyframe is the reference keyframe in all cases).



Before (left) and after (right) aligning keyframes with all keyframes selected. The reference keyframe moves to the position indicator and all other keyframes move to maintain their positions relative to the reference keyframe.

4 Working with Keyframes



Before (left) and after (right) aligning keyframes with one deselected keyframe. The reference keyframe moves to the position indicator, other selected keyframes move to maintain their position relative to the reference keyframe, but the deselected keyframe does not move.



Before (left) and after (right) aligning keyframes with two deselected keyframes. The reference keyframe moves to the position indicator, the other selected keyframe moves to maintain its position relative to the reference keyframe, but the deselected keyframes do not move.

Slipping Advanced Keyframes

In the following procedure, the *reference keyframe* of any keyframe track is the keyframe you activated most recently in that keyframe track.

To slip keyframes to the position indicator, in one keyframe track:

- ▶ Right-click an open keyframe graph, a parameter track, a parameter group track, or the effect track, and select Slip Keyframes.

All the keyframes move so that the reference keyframe aligns with the position indicator, and the other keyframes maintain their position relative to the reference keyframe. If the reference keyframe is in a parameter group track or in the effect track, all the keyframes at that point in time in the parameter group or in the entire effect move to the position indicator, and the other keyframes in the same parameters maintain their position relative to the reference keyframe.



Before (left) and after (right) slipping keyframes. The reference keyframe moves to the position indicator and other keyframes move relative to the reference keyframe.

Copying and Pasting Advanced Keyframe Parameters

You have several options for copying and pasting advanced keyframe parameters. You can:

- Copy and paste selected keyframes in a single parameter.
- Copy and paste selected keyframes in more than one parameter.

The selected keyframes can be in graphs or on tracks (that is, the graphs that contain the selected keyframes can be open or closed). If the selected keyframes are offset from one another, the pasted keyframes preserve the offset.

- Copy and paste all graph values at a specific position.

This option is available both in the position bar of the Effect Preview monitor and in the keyframe graphs in the Effect Editor.

This option does not require a keyframe in any parameter at the location you are copying from. Your Avid editing application takes all the parameter values at the copying location and uses them to create new keyframes (or replace existing ones) at the pasting location.

For illustrated examples of these options, see [“Examples of Copy and Paste Operations on Advanced Keyframe Parameters” on page 130](#).

To copy and paste an advanced keyframe in a single keyframe graph or track:

1. Click the keyframe you want to copy.
2. Select Edit > Copy, or press Ctrl+C (Windows) or Command+C (Macintosh).
3. Do one of the following:
 - ▶ Move the position indicator to the location where you want to paste.
 - ▶ Click a keyframe to select it.
 - ▶ Ctrl+click (Windows) or Command+click (Macintosh) multiple keyframes to select them.
4. Select Edit > Paste, or press Ctrl+V (Windows) or Command+V (Macintosh).

Your Avid editing application pastes the parameters from the keyframe that you copy to the keyframes that you select, or creates a new keyframe using the parameters that you copy at the location of the position indicator.

To copy and paste multiple selected advanced keyframes:

1. Ctrl+click (Windows) or Command+click (Macintosh) multiple keyframes to select them.
You can select multiple keyframes within a single parameter or across several parameters.
2. Select Edit > Copy, or press Ctrl+C (Windows) or Command+C (Macintosh).
3. Do one of the following:
 - ▶ Move the position indicator to the location where you want to paste.
 - ▶ Click a keyframe to select it and move the position indicator to that location.
4. Select Edit > Paste, or press Ctrl+V (Windows) or Command+V (Macintosh).

4 Working with Keyframes

Your Avid editing application pastes the keyframes that you copy to the location that you select. When the keyframes you copy are offset from one another, your Avid editing application pastes the leftmost keyframe at the location that you select and pastes the other keyframes in locations that preserve the original offset.

To copy and paste all parameter values at a position:


1. Do one of the following, either in the position bar below the Effect Preview monitor, or in the keyframe graphs in the Effect Editor:
 - ▶ Move the position indicator to the location from which you want to copy values.
 - ▶ Click a keyframe at the location from which you want to copy values.
2. Do one of the following:
 - ▶ If you are working in the position bar of the Effect Preview monitor, select Edit > Copy, or press Ctrl+C (Windows) or Command+C (Macintosh).
 - ▶ If you are working in the keyframe graphs in the Effect Editor, right-click in the graph area and select Copy All Values at Position, or press Ctrl+Alt+C (Windows) or Command+Option+C (Macintosh).
3. Do one of the following:
 - ▶ Move the position indicator to the location where you want to paste values.
 - ▶ Click a keyframe to select it and move the position indicator to the location where you want to paste values.
4. Select Edit > Paste, or press Ctrl+V (Windows) or Command+V (Macintosh).

Your Avid editing application creates new keyframes at the pasting location, or modifies existing keyframes. As a result of this procedure, every keyframe graph in the effect has a keyframe at the pasting location with its parameter value set to the value for that parameter at the copying location.


Examples of Copy and Paste Operations on Advanced Keyframe Parameters

The following illustrations show the effects of the various copy and paste operations that you can perform on advanced keyframe parameters. For more information and step-by-step instructions for copying and pasting advanced keyframe parameters, see [“Copying and Pasting Advanced Keyframe Parameters” on page 128](#).

Copying and Pasting Keyframes in a Single Parameter




Before (left) and after (right) copying and pasting a keyframe in a single parameter. Notice the difference in behavior between the top and bottom graphs in the example. The top graph is not active and the keyframe is not selected, so the keyframe is not copied even though it is at the same point in time as the selected keyframe in the bottom graph. The bottom graph is active and its keyframe is selected, so it is copied to the new location of the position indicator on the right.



Before (left) and after (right) copying and pasting multiple keyframes in a single parameter. Their offset from one another is preserved in the new copies.


Copying and Pasting Keyframes in Multiple Parameters




Before (left) and after (right) copying and pasting keyframes that you select in multiple keyframe graphs. Your Avid editing application pastes the leftmost selected keyframe at the new location of the position indicator, and preserves the offset of other keyframes from the leftmost one.

4 Working with Keyframes

Copying and Pasting All Parameter Values at a Position



Before (left) and after (right) copying and pasting all parameter values at a position. In this example, a keyframe exists for one parameter at the copying location, but no keyframes exist for the other parameters. Your Avid editing application uses the parameter values for each parameter at the copying location, regardless of whether a keyframe already exists, and creates new keyframes with those values at the pasting location. Any other parameters for the effect also get a new keyframe at the pasting location, even if (as in the top Level graph here) the new keyframe uses default values. If necessary, you can delete any redundant keyframes that this process creates using the Remove Redundant Keyframes command.



Before (left) and after (right) copying and pasting all parameter values at a position. In this example there are no existing keyframes at the copying location. Your Avid editing application uses the parameter values at the copying location to create new keyframes with those values at the pasting location.

Controlling Parameter Changes at Keyframes

The keyframe interpolation options control how an effect parameter changes at a keyframe. Interpolation refers to the method your Avid editing application uses to calculate the rate of change and the relative smoothness of change.

To select an interpolation option:

- ▶ Right-click the keyframe graph or keyframe track for the parameter with which you are working, and select one of the following:
 - Shelf
 - Linear
 - Spline
 - Bézier

For information on these options, see [“Advanced Keyframe Interpolation Options” on page 133](#).

Advanced Keyframe Interpolation Options




The following table describes the interpolation options available for advanced keyframes.

Advanced Keyframe Interpolation Options

Interpolation Option	Description
Shelf	<p>The parameter value does not change between keyframes and then changes abruptly to the new value. Some applications call this <i>Hold</i>.</p> <p>Use Shelf to hold a parameter value for a fixed length of time. For example, you can use Shelf with the Position parameters to create a Picture-in-Picture that appears to “pop” to a new location at each keyframe.</p>




Advanced Keyframe Interpolation Options (Continued)

Interpolation Option	Description
Linear	<p>The parameter value ramps smoothly between keyframes but then changes abruptly at each keyframe. The change in parameter value at a keyframe happens with no ease-in or ease-out.</p>  <p> <i>Effects with standard keyframes always make linear parameter changes (with the exception of Spline for motion paths and Acceleration for other parameters). With advanced keyframes, you can use the Linear interpolation option for some parameters and not for others, depending on the effect you want to achieve.</i></p>
Spline	<p>The parameter value changes smoothly at each keyframe, creating a simple ease-in or ease-out effect. Spline is sometimes called Natural Spline or Cardinal Spline because the line representing the parameter value always goes precisely through each keyframe.</p> <p>With two keyframes, the parameter value changes slowly at the beginning of the effect, speeds up the rate of change, and then slows down to come to rest gently at the end of the effect. Use three keyframes to create an arc.</p> <p>Use the Spline interpolation option (or the Bézier interpolation option) for any parameter for which you want to avoid abrupt changes, such as Scaling or Border width.</p> 

Advanced Keyframe Interpolation Options (Continued)

Interpolation Option	Description
Bézier	<p>The Bézier interpolation option is similar to the Spline interpolation option because the parameter value changes smoothly at each keyframe. The Bézier interpolation option also provides direction handles at each keyframe. You adjust the rate at which the parameter value changes by manipulating the direction handles.</p> <p>When you click a direction handle and drag it, you change the height and angle of the curve. The curve responds as if you were gently tugging it like a piece of string. The curve remains anchored to the keyframes on either side of the active keyframe.</p> <p>You have several options for how you manipulate Bézier direction handles. For more information, see “Adjusting Parameter Values with the Bézier Interpolation Option” on page 135.</p> <p>Use the Bézier interpolation option (or the Spline interpolation option) for any parameter for which you want to avoid abrupt changes.</p>



Adjusting Parameter Values with the Bézier Interpolation Option

You can adjust Bézier curves in the following ways:

- Symmetrically: Dragging a direction handle changes the length and rotation of both direction handles symmetrically.



Before (left) and after (right) dragging symmetrically. Dragging the left handle up and to the left causes both sides to rotate and increase in length.

- Asymmetrically: Dragging a direction handle changes the length of the selected handle, but not the opposite handle. The rotation of both handles changes as you drag the selected handle.

4 Working with Keyframes



Before (left) and after (right) dragging asymmetrically. Dragging the left handle up and to the left causes the left side to rotate and increase in length. The right side rotates but does not change in length.

- **Independently:** Dragging a direction handle changes both the length and rotation of the selected handle. The opposite handle does not change. You do this by “breaking” the handle.



Before (left) and after (right) dragging independently. The image in the center shows dragging with no rotation — dragging the left handle to the left causes only the left side to increase in length. The image on the right shows dragging and rotating — dragging the left handle up and to the left causes only the left side to rotate and increase in length. In both cases, the right side of the curve does not change.

The default adjustment method is symmetrical. You change the adjustment method using the Alt key (Windows) or Option key (Macintosh).

To use the Bézier interpolation option for adjusting a parameter value:

1. Select the Bézier interpolation option.

For more information, see [“Controlling Parameter Changes at Keyframes” on page 133](#).

2. Click a keyframe indicator to activate it.

The keyframe indicator changes to pink, and a direction bar with direction handles appears.

3. Position the pointer over one of the direction handles.

The pointer changes to a hand pointer.

4. Do one of the following:

- ▶ Drag the mouse to move the direction handle.

Your Avid editing application uses the currently active adjustment option. The direction bar and the curve change to show the new interpolation motion.

- ▶ Alt+click (Windows) or Option+click (Macintosh) the direction handle, and then drag the mouse to move the direction handle.

The use of the modifier key instructs your Avid editing application to use the next adjustment method in the sequence of adjustment options: symmetrical, asymmetrical, or independent.

For example, suppose you make an adjustment using independent direction handles, and then move the cursor away from the keyframe. To continue using independent direction handles, click the direction handle and make further adjustments. To change the adjustment method from independent to symmetrical, Alt+click (Windows) or Option+click (Macintosh) the direction handle.

5. Continue adjusting the direction handles to achieve the effect you want.

Reversing Advanced Keyframes

You can use the Reverse Keyframes command in the shortcut menu for the keyframe track to reverse the keyframes in time for an individual parameter, a parameter group, or an entire effect.

The Reverse Keyframes command is an enhanced version of the Reverse Animation command in the standard keyframe interface.

You should be aware of the following when working with the Reverse Keyframes command:

- Reverse Keyframes does not affect keyframe parameter values. It changes only the position of keyframes in time.
- Reverse Keyframes always applies to the entire effect duration. You cannot reverse the keyframes for a portion of the effect duration.
- If the effect is a transition effect that contains a Swap Sources button, your Avid editing application automatically enables the Swap Sources button when you reverse the keyframes on the entire effect. This maintains the shot continuity while reversing the movement.

To reverse keyframes in time:

- ▶ Right-click an open keyframe graph, a parameter track, a parameter group track, or the effect track, and select Reverse Keyframes.

Your Avid editing application reverses the appropriate keyframes in time:

- For an open keyframe graph or a single parameter track, the keyframes are reversed for that parameter.
- For a parameter group track, keyframes are reversed for all parameters in the group. The parameter group track displays the text “Apply to Group” when you right-click the track.
- For the effect track, keyframes are reversed for all parameters in the entire effect. The parameter group track displays the text “Apply to All” when you right-click the track.

Controlling Advanced Keyframe Behavior with Trimmed Effects

You can use the Elastic and Fixed commands in the shortcut menu for the keyframe track to control how advanced keyframes adjust when you change the length of an effect by trimming.

When you use the Elastic option, your Avid editing application scales the keyframes to fit the new duration. For example, if you trim out the start of a keyframed 2-second effect segment so that its length increases to 3 seconds, the gap between each of the keyframes increases by 50% and the original animation takes place over 3 seconds. Elastic is the default behavior for a parameter, and is also the behavior for standard keyframes.

The keyframe indicator for an elastic keyframe is a simple triangle, as shown in the following illustration.



When you use the Fixed option, your Avid editing application leaves the existing duration of your keyframe animation intact. For example, if you trim out the start of a keyframed 2-second effect segment so that its length increases to 3 seconds, the original animation still takes place over 2 seconds at the end of the segment. The one second of material you have added uses the parameter values of the first keyframe, so no movement or other change takes place until the first keyframe is reached. Fixed keyframes let you “pin” a parameter change to a particular timecode.


The keyframe indicator for a fixed keyframe has a mark or tail on its bottom edge, as shown in the following illustration.




You can select elastic keyframes or fixed keyframes for each parameter of an effect, so some parameters can have elastic keyframes while other parameters have fixed keyframes.

All keyframes for a parameter are either elastic or fixed. You cannot mix elastic keyframes and fixed keyframes within a single parameter.


The following illustrations show an example of the difference between elastic and fixed keyframes.



Two-second clip with four keyframes



The same clip, trimmed out to add 1 second at the head (shaded area) and using elastic keyframes. The time between keyframes stretches.



The same clip, trimmed out to add 1 second at the head (shaded area) and using fixed keyframes. The timing of events does not change.

Selecting Elastic Keyframes or Fixed Keyframes

To select elastic keyframes or fixed keyframes:

- Right-click the keyframe graph, parameter track, or parameter group track whose keyframes you want to affect, and select Fixed or Elastic.

The keyframes for the parameter or parameter group change to the selected keyframe type and the keyframe indicators for the parameter display the selected keyframe type. All subsequent keyframes you add to this parameter appear as the selected keyframe type.

Controlling Parameter Changes Outside First and Last Keyframes


Effects that use standard keyframes always have a starting keyframe and an ending keyframe that are fixed at the start of the effect and the end of the effect. You cannot move or delete the starting keyframe and the ending keyframe.

Effects that use advanced keyframes do not require a starting keyframe or an ending keyframe, so you can move or delete them.

In a keyframe graph, the first keyframe and the last keyframe are the *bracketing keyframes* for the parameter. Your Avid editing application determines parameter values beyond the bracketing keyframes using either Extrapolate or Hold.

When Extrapolate is enabled, your Avid editing application extrapolates — that is, estimates more values for — the parameter values at the start and end of an effect using the values at the bracketing keyframes. Parameter values continue to change over time. Your Avid editing application calculates new values using the interpolation option in effect for that parameter.

4 Working with Keyframes




Parameter values change before and after the bracketing (start and end) keyframes

In the previous illustration, the blue lines represent the parameter value before and after the bracketing keyframes and show the extrapolation of the parameter value.

For example, if the parameter value between the last two keyframes increases as the end of the effect approaches, the parameter value continues to increase until the end of the effect. Similarly, if the first keyframe is not at the very beginning of the clip, your Avid editing application extrapolates the parameter value from the start of the effect up to the first keyframe.

When Hold is enabled, your Avid editing application uses only the parameter values at the bracketing keyframes to set values at the start and end of the effect. The parameter values stay the same from the start of the effect to the first keyframe, and again from the last keyframe to the end of the effect.



Parameter values hold steady before and after the bracketing (start and end) keyframes


In the previous illustration, the horizontal blue lines indicate the parameter value before the first keyframe and after the last keyframe.

Extrapolate and Hold are useful any time you slip keyframes or align keyframes in such a way that a bracketing keyframe falls within the effect, or if you are using fixed keyframes for a parameter and you trim the effect in or out so that a bracketing keyframe falls within the effect.




The Extrapolate or Hold setting remains in effect if you trim the effect in or out.

In either case, you do not have an explicitly defined value outside the bracketing keyframes. Extrapolate and Hold can save you the trouble of individually setting new values for each parameter whenever you make changes to the position of keyframes or the length of the effect.




Keyframe graph before Slip Keyframes — bracketing keyframes included

When you select Extrapolate, your Avid editing application estimates more values for the parameter before and after the bracketing keyframes using the values at the bracketing keyframes. Parameter values continue to change over time. Your Avid editing application calculates new values using the interpolation option in effect for that parameter.



Keyframe graph after Slip Keyframes with Extrapolate enabled, The parameter value changes before the bracketing keyframe.

When you select Hold, your Avid editing application uses only the parameter values at the bracketing keyframes to set values before and after the bracketing keyframes. The parameter values are the same from the start of the effect to the first keyframe, and again from the last keyframe to the end of the effect.



Keyframe graph after Slip Keyframes with Hold enabled, The parameter value does not change before the bracketing keyframe.



As a result of slipping the keyframes in the previous examples, the last keyframe indicator moves out of the keyframe graph view but is still present and is still the bracketing keyframe. The keyframe indicator visible at the right edge of the keyframe graph (the third keyframe indicator) is not a bracketing keyframe. Therefore, the parameter values in effect from the third keyframe to the end of the effect are calculated along the curve between the third keyframe and the last (bracketing) keyframe.

You set Extrapolate and Hold independently for each parameter in an effect. The default condition is Hold.

Setting Extrapolate or Hold for an Effect Parameter

To set **Extrapolate** or **Hold** for a parameter:

- ▶ Right-click the keyframe track, and select **Extrapolate** or **Hold**.

The display changes to reflect the new setting.

Controls and Settings for Advanced Keyframes

This topic provides reference information for the following parts of the advanced keyframes user interface:

- Effect Editor controls that are specific to advanced keyframes.
- The shortcut menu for the keyframe track.
- The Effect Editor shortcut menu and the Effect Editor Settings dialog box.

You use commands in the Effect Editor shortcut menu or settings in the Effect Editor Settings dialog box to control certain aspects of advanced keyframe behavior, such as whether start and end keyframes are automatically added to parameters.

Effect Editor Controls for Advanced Keyframes




The toolbar at the bottom of the Effect Editor includes specific controls for advanced keyframes.



Left to right: Effect Editor buttons, Horizontal scale bar, and Scroll thumbwheel in the toolbar at the bottom of the Effect Editor

The following table describes the Effect Editor toolbar controls for advanced keyframes. For information on the buttons on the left side of the toolbar, see [“Effect Editor Controls” on page 90](#).

Control		Description
Rewind		Moves the position indicator one keyframe to the left and activates the keyframe. If there is no keyframe to the left, the position indicator does not move.
Fast Forward		Moves the position indicator one keyframe to the right and activates the keyframe. If there is no keyframe to the right, the position indicator does not move.

Control		Description
Add Keyframe		Creates a keyframe at the current position. Alt+click (Windows) or Option+click (Macintosh) this button to delete a keyframe. When you add or delete a keyframe, a menu gives you additional selections. For more information, see “Adding Advanced Keyframes” on page 113 and “Deleting Advanced Keyframes” on page 115 .
Horizontal scale bar		Zooms (or scales) the view of keyframe graphs horizontally so that you can focus in on a particular part of a graph. For more information, see “Zooming Keyframe Graphs” on page 107 .
Scroll thumbwheel		Scrolls the view of keyframe graphs horizontally so that part of the view disappears on one side and more comes into view on the other side. For more information, see “Scrolling Keyframe Graphs” on page 110 .

Accessing Settings for Advanced Keyframes

You access settings for advanced keyframes by displaying one of the shortcut menus available in the Effect Editor, or by opening the Effect Editor settings dialog box.

For more information on the settings themselves, see [“Shortcut Menus for Keyframe Tracks and the Motion Effect Editor” on page 144](#) and [“Shortcut Menu and Settings for the Effect Editor” on page 146](#).

To display the shortcut menu for a keyframe track:

- ▶ Right-click a keyframe graph, a parameter graph, a parameter group title track, or the effect title track.


To display the shortcut menu for the Motion Effect Editor:

- ▶ Right-click the active control graph.

To display the Effect Editor shortcut menu:


- ▶ Right-click the Effect Editor *outside* the keyframe track area.
The Effect Editor shortcut menu opens.

4 Working with Keyframes



To display the Effect Editor settings dialog box:

- In the Settings tab of the Project window, double-click Effect Editor.



Shortcut Menus for Keyframe Tracks and the Motion Effect Editor

Advanced keyframes use two shortcut menus. The shortcut menu for the keyframe track is available from the area of the Effect Editor that displays keyframe tracks and keyframe graphs. The Effect Editor shortcut menu is available from the part of the Effect Editor that does not display the keyframe tracks. For more information about the Effect Editor shortcut menu, see [“Shortcut Menu and Settings for the Effect Editor” on page 146](#).

Because the Motion Effect Editor uses advanced keyframes, the shortcut menu for the Motion Effect Editor and the shortcut menu for keyframe tracks are nearly identical. The differences stem from the multiple tracks available in the Effect Editor. In the following table, the listed commands appear in both menus unless otherwise stated.

Control	Description
Add Keyframe	Adds a keyframe at the position indicator. See “Adding Advanced Keyframes” on page 113.
Delete Keyframe	Deletes the selected keyframe. See “Deleting Advanced Keyframes” on page 115.
Remove Redundant Keyframes	Removes extra keyframes that you do not need to define parameter changes. See “Removing Redundant Keyframes” on page 116.
Copy All Values at Position	Copies parameter values at the current position for all keyframe graphs in an effect. You can then paste these values at another location to create new keyframes or replace existing ones. For more information, see “Copying and Pasting Advanced Keyframe Parameters” on page 128.
Select All Keyframes	For the Effect Editor, selects all keyframes in the section of the editor where you click to display the shortcut menu. See “Selecting and Deselecting Advanced Keyframes” on page 122. For the Motion Effect Editor, selects all keyframes in the active graph.
Deselect All Keyframes	Deselects all the keyframes in the currently active track, parameter group, or effect. See “Selecting and Deselecting Advanced Keyframes” on page 122.
Align Keyframes	Moves the selected keyframe to the position indicator. See “Understanding the Align Keyframes and Slip Keyframes Commands” on page 126. (Motion Effect Editor shortcut menu only) Moves the selected keyframe in one or more keyframe graphs to the position indicator, depending on which keyframes you select and on where you click to display the shortcut menu. See “Understanding the Align Keyframes and Slip Keyframes Commands” on page 126.
Slip Keyframes	Moves all the keyframes of the parameter so the active keyframe aligns with the position indicator, and the rest of the keyframes maintain their relative location. See “Understanding the Align Keyframes and Slip Keyframes Commands” on page 126.
Reverse Keyframes	Lets you reverse the keyframes in time for a parameter, a parameter group, or an entire effect. See “Reversing Advanced Keyframes” on page 137.
Shelf, Linear, Spline, Bézier	Defines how parameter changes occur at keyframes. See “Controlling Parameter Changes at Keyframes” on page 133.
Fixed Elastic	Defines how your Avid editing application moves keyframes when you trim an effect. Elastic keyframes change the time at which they occur when you trim an effect, in proportion to the new effect length. Fixed keyframes do not change. See “Controlling Advanced Keyframe Behavior with Trimmed Effects” on page 138.
Extrapolate Hold (Shortcut menu for the keyframe track only)	Determines how your Avid editing application sets parameter values before the first keyframe and after the last keyframe. See “Controlling Parameter Changes Outside First and Last Keyframes” on page 139.

Control	Description
Zoom to Curve Height	Scales the keyframe graph so that its keyframe curve fills the available viewing area for the graph. For more information, see “ Zooming Keyframe Graphs ” on page 107.
Reset All Graph Views	Resets all graph views. This includes removing any changes to the views made using the zoom sliders or the Zoom to Curve Height feature. See “ Resetting Keyframe Graph Views ” on page 110.


Shortcut Menu and Settings for the Effect Editor

The Effect Editor shortcut menu and the Effect Editor Settings dialog box give you options for adjusting the Effect Editor display, for controlling the playback of effects with advanced keyframes, and for setting a default command for the Add Keyframe button. The shortcut menu and the settings dialog box have some options in common, but others appear only in the menu or only in the settings dialog box. The table below indicates where options appear only in one of the locations.




The Effect Editor shortcut menu is available only for effects with advanced keyframes.

The following table describes the options for the Effect Editor shortcut menu and the Effect Editor settings dialog box.

Option	Description
Indent Rows	When this option is selected, parameter rows are indented from the parameter category row, and any parameter subgroups are indented again. When this option is deselected, the left edges of parameter rows line up with the parameter category row. 

Indented (left) and non-indented (right) parameter rows

Option	Description
Large Text	<p>When this option is selected, text in the Effect Editor appears in 12-point size. When this option is deselected, text in the Effect Editor appears in the default size, 10 points (Windows) or 9 points (Macintosh).</p> <div data-bbox="499 347 1268 555" data-label="Image"> </div> <p>Normal (left) and Large (right) text size</p>
Thumbwheels	<p>When this option is deselected, variable controls in the Effect Editor appear as the default slider control. When this option is selected, variable controls appear as thumbwheels. For information on using thumbwheels, see “Changing a Parameter with a Slider in the Effect Editor” on page 94.</p> <div data-bbox="499 755 911 824" data-label="Image"> </div> <p>Slider controls (left) and thumbwheel controls (right)</p>
Real-Time Update	<p>When this option is selected, your Avid editing application updates the rendered effect image in real time. Because the update can be slow for complex effects, you have the option to deselect updating in real time.</p>
Set Position To Keyframe	<p>When this option is selected, when you click a keyframe, your Avid editing application moves the position indicator to the keyframe. When this option is deselected, when you click a keyframe, the position indicator does not move. Deselecting this option lets you align a keyframe to the position indicator. See “Understanding the Align Keyframes and Slip Keyframes Commands” on page 126.</p>
Update Position While Playing	<p>When this option is selected, the position indicator in the Effect Editor moves while you play the effect. This option is deselected by default because using this option can cause video underrun problems in complex real-time effects.</p>
Show Add Keyframe Mode Menu	<p>When this option is selected, the Add Keyframe Mode menu (or the Delete Keyframe Mode menu) appears when you use the Add Keyframe button to add (or delete) keyframes. See “Keyframe Mode Menu Commands” on page 117.</p> <p>When this option is deselected, the Add Keyframe button performs the default command from the Add Keyframe button options list below, without displaying the Add Keyframe Mode menu or the Delete Keyframe Mode menu.</p>

Option	Description
Add Keyframe button options (Effect Editor shortcut menu only):	Select one as the default command for the Add Keyframe button. <ul style="list-style-type: none">When you deselect Show Add Keyframe Mode Menu, clicking the Add Keyframe button once performs the default command.When you select Show Add Keyframe Mode Menu, clicking the Add Keyframe button twice performs the default command. (The first click displays the Add Keyframe Mode menu so you can select another command.)
• Add Keyframes To Active Parameter	
• Add Keyframes To Active Group	
• Add Keyframes To Open Groups	 <i>The selection you make for the Add Keyframe mode is mirrored in the Delete Keyframe Mode menu, and vice versa. For example, when you change your selection to Add Keyframe To Open Groups, the Delete Keyframe mode changes to Delete Keyframe From Open Groups.</i>
• Add Keyframes To Enabled Groups	
• Add Keyframes To Open Graphs	For a description of each command, see “Keyframe Mode Menu Commands” on page 117 .
• Add Keyframes To All Parameters	These options are available only in the Effect Editor shortcut menu.

Working with Standard Keyframes

You can manipulate standard keyframes in the following ways:

- You can add standard keyframes at any point in the effect’s position bar.
- You can delete any standard keyframe that you create, but you cannot delete the starting and ending keyframes your Avid editing application creates.
- You can select one or more standard keyframes.

A keyframe indicator changes to pink when selected. For a quick way to jump to the next or previous keyframe indicator, use the Fast Forward and Rewind buttons on the Effect Preview Monitor toolbar.

- You can move a standard keyframe that you create to another position in the position bar below the Effect Preview monitor. You cannot move the starting and ending keyframes.
- You can adjust most effect parameters to a different value for each keyframe, allowing you to animate an attribute such as the position of the effect.

Some parameter categories, however, are not keyframeable, and you can only adjust these parameters globally for the entire effect. The reference topics for each parameter in “[Effects Parameter Reference](#)” on page 603 indicate when a parameter is not keyframeable.

- You can copy and paste parameters from one standard keyframe and apply them to another standard keyframe. You can also copy keyframe parameters from one effect to another effect.

To create a standard keyframe:

1. Click in the position bar below the Effect Preview monitor at the point in the effect where you want to add the keyframe.

The position indicator moves to that frame.

2. Do one of the following to add a keyframe:



- ▶ In the Effect Preview Monitor toolbar, click the Add Keyframe button.
- ▶ Manually adjust a parameter in the Effect Preview monitor (segment effects only).
For example, when you click a handle on an effect outline and drag to resize or reposition it, your Avid editing application automatically creates a new keyframe.

To delete a standard keyframe:

1. In the position bar below the Effect Preview monitor, click the keyframe indicator.

The keyframe indicator changes to pink when selected.

2. Do one of the following:



- ▶ Press the Delete key.
- ▶ Alt+click (Windows) or Option+click (Macintosh) the Add Keyframe button.

To select one keyframe:



- ▶ In the position bar below the Effect Preview monitor, click the keyframe indicator.

To select multiple keyframes:

- ▶ In the position bar below the Effect Preview monitor, Shift+click the keyframe indicators that you want to select.

To select all keyframes in the effect's position bar, do one of the following:

- ▶ Press Ctrl+A (Windows) or Command+A (Macintosh).
- ▶ Press and hold Ctrl+Alt (Windows) or the Command key (Macintosh), and click one keyframe indicator.

4 Working with Keyframes

To move a standard keyframe, do one of the following:



- ▶ Alt+click (Windows) or Option+click (Macintosh) the keyframe indicator, and drag it to its new position.
- ▶ Select a keyframe indicator, and click the Trim Left 1 Frame or Trim Right 1 Frame button or the Trim Left 10 Frames or Trim Right 10 Frames button.



Left to right: Trim Left 1 Frame button, Trim Right 1 Frame button, Trim Left 10 Frames button, Trim Right 10 Frames button



The Trim buttons are located in the Trim tab of the Command palette. You can map them to other locations. For more information, see “Mapping User-Selectable Buttons” in the Help.

To change a standard keyframe's parameters:



1. In the position bar below the Effect Preview monitor, click the keyframe indicator.
The keyframe indicator changes to pink when selected.
2. Adjust any of the applicable parameters in the Effect Editor.

To copy and paste standard keyframe parameters:



1. In the position bar below the Effect Preview monitor, click one keyframe indicator whose parameters you want to copy.
2. Select Edit > Copy.
3. Select one or more standard keyframes:
 - ▶ To copy the parameters to one keyframe, click the keyframe indicator.
 - ▶ To copy the parameters to multiple keyframes, Ctrl+click (Windows) or Command+click (Macintosh) multiple keyframe indicators.
 - ▶ To copy the parameters to all keyframes, select Edit > Select All.
4. Select Edit > Paste.

Your Avid editing application pastes the parameters that you copy to the keyframes that you select.

5 Playing Effects, Rendering Effects, and Managing Effect Media Files

This chapter provides information on playing and rendering effects that extends the basic information provided in [“Playing Effects” on page 50](#) and [“Basics of Effects Rendering” on page 53](#). It also provides information on managing your effect media files.

- [Real-Time Playback of Video Effects](#)
- [ExpertRender](#)
- [Creating and Using Render Settings](#)
- [Render Settings Options](#)
- [Using Partial Render](#)
- [Using 16-Bit Processing Support for Rendered Effects](#)
- [Rendering 3D Effects Using the HQ \(Highest Quality\) Option](#)
- [Rendering Effects for the Media Station XL](#)
- [Managing Effect Media Files](#)

Real-Time Playback of Video Effects

You can play back most video effects available in your Avid editing application in real time. This lets you play back sequences that contain effects and to review the appearance of those effects.

Real-time effects playback has no effect on the methods you use when you apply and modify the effects themselves.

For more information on playing effects, see [“Playing Effects” on page 50](#).

Understanding Real-Time Effects Processing

To display a frame from a sequence that has a video effect applied, your Avid editing application must calculate the result of the effect at that frame. For example, to display the midpoint frame from a dissolve, your Avid editing application must calculate, for each pixel in the frame, a 50 percent blend between the color and luminance values in the outgoing clip

5 Playing Effects, Rendering Effects, and Managing Effect Media Files

and those in the incoming clip. To display frames in real time, your Avid editing application must be able to perform enough of these effect calculations per second to maintain the appropriate display rate for your project, for example 30 frames per second (fps) for NTSC video.

Because your computer's processor and memory capabilities are finite, your Avid editing application's ability to play back effects in real time is limited. Effect calculations are more complex for some effects than for others, and still more complex when you adjust many effect options or when multiple effects apply to the same frame in a sequence. Even the fastest and most powerful system might eventually reach a point where it can no longer maintain real-time playback.

For most real-time effects, Avid editing applications automatically select the most efficient and highest performance processing resources available on your editing system. Depending on the particular effect and the graphics hardware available on your system, processing might be done by your graphics card's GPU or your computer's CPU (including all CPU cores for multicore processors).


A small number of effects, when certain parameters are enabled, use OpenGL processing. For these effects, you might want to select a processing method that emphasizes either image quality or playback performance. For more information, see "Select a Different OpenGL Mode" in ["Options for Controlling Real-Time Effects Playback" on page 154](#).

When your Avid editing application is unable to maintain real-time playback, it continues to play at the correct rate but does not display frames that it cannot process quickly enough. If your Avid editing application is having only a small amount of difficulty with the complexity of the sequence, you might perceive a short stutter in the video playback, but you might still be able to get a useful sense of how your effects will look once they are rendered. If your Avid editing application is having more difficulty, it is less likely that you can judge the look of the effects.

You have a number of options for controlling how real-time effects playback operates. For more information, see ["Options for Controlling Real-Time Effects Playback" on page 154](#) and "Playing Back to a DV Device" in the Help.

Understanding Real-Time Playback Information in the Timeline

When your Avid editing application is unable to maintain real-time playback of an effects sequence, colored bars appear in the timecode track of the Timeline when playback ends. The following illustration shows a typical set of colored bars.



Colored bars in the Timecode track of the Timeline

These bars provide you with information about the difficulties your Avid editing application had during playback. You can use this information to help you render only those parts of the sequence necessary to achieve real-time playback.

Bar Color	Description
Red	<p>Marks the ranges where your Avid editing application was unable to display frames.</p> <p>The ranges marked by red bars are ranges that your Avid editing application recommends for rendering to achieve successful real-time playback. If you mark IN and OUT points around these ranges, use the ExpertRender In/Out command, and then render the recommended ranges, your Avid editing application can preview your material successfully in real time. For more information, see “ExpertRender” on page 158.</p>
Yellow	<p>Marks the ranges that caused difficulty for your Avid editing application during playback because of processing power.</p> <p>No frames were dropped during play. This is only a warning.</p>
Blue	<p>Marks the location of frames that caused difficulty for your Avid editing application because of disk speed limitations.</p> <p>No frames were dropped during play. This is only a warning.</p>

Turning Playback Performance Indicators On or Off

To turn playback performance indicators on or off:

1. In the Settings list of the Project window, double-click Timeline.
 2. In the Display tab, select or deselect Highlight Suggested Render Areas After Playback.
- Playback performance indicators appear in the Timeline when you select this option. This option is selected by default.

Options for Controlling Real-Time Effects Playback

When your Avid editing application is unable to maintain real-time playback of an effects sequence, there are a number of ways you can attempt to ensure that the sequence plays back successfully in real time.

Start Playback Earlier in the Sequence

If possible, start playback earlier in the sequence, before the effects that are causing difficulties begin. This lets your Avid editing application begin processing some of the effects frames before it must display them, decreasing the chance of difficulties with playback.

Change the Bit Depth for Effects Processing

In some circumstances, you have the option to process effects during playback at either of two bit depths, 8-bit or 10-bit. 10-bit processing using the Full Quality 10-bit option in the Video Quality menu provides higher quality for some effects in a manner similar to that provided by using the 16-bit processing option when rendering effects (see [“Using 16-Bit Processing Support for Rendered Effects” on page 172](#)). However, 10-bit processing during playback uses additional system resources and might limit real-time playback capabilities.

If you are using 10-bit processing for playback and find that your Avid editing application cannot play your sequence in real time, you might be able to improve performance by switching to one of the other Video Quality Menu options, all of which use 8-bit processing.

The circumstances in which the Full Quality 10-bit option is available depend on several factors, such as your Avid input/output hardware, your project type (SD or HD), and the editing mode in which you are working. For more information, see [“Controlling Real-Time Effects Processing” on page 156](#) and [“Playing Effects Back at Different Video Qualities” on page 157](#)).

Select a Different OpenGL Mode

A small number of effects use OpenGL processing when certain parameters are enabled. For example, a 3D Warp effect with the Trail parameter enabled, or a Stabilize effect with the Tracking parameter enabled, uses OpenGL processing.

OpenGL processing can occur in two ways:

- Using the OpenGL capabilities of the graphics card that is installed on your system. This method allows effects to display in real time, but image quality is limited.
- Using a software implementation of the OpenGL application programming interface (API).

This method allows effects to display at the highest possible quality, but not in real time.

If you need both the highest effect quality and real time performance (for example, for final output), you must render the effects.

You can use a setting in the Video Display Settings dialog box to switch between the OpenGL processing provided by your graphics card and software OpenGL processing. This might be useful if you notice either unacceptable image quality or poor playback performance with 3D Warp or Stabilize effects. For more information, see [“Controlling Real-Time Effects Processing” on page 156](#).



Processing of 3D Warp effects is also affected by the Highest Quality option. For more information, see [“Rendering 3D Effects Using the HQ \(Highest Quality\) Option” on page 176](#).

Render using the Expert Render Command

Render those parts of the sequence where your Avid editing application had difficulties during playback. Your Avid editing application marks these parts of the sequence in the Timeline. For more information, see [“Understanding Real-Time Playback Information in the Timeline” on page 152](#) and [“ExpertRender” on page 158](#).



Consider rendering transition effects such as the Dissolve effect or wipe effects first because they take less time to render than titles or segment effects.

Select a Lower Playback Quality from the Video Quality Menu

This increases your Avid editing application’s ability to process effects at the expense of reducing image quality. For more information, see [“Playing Effects Back at Different Video Qualities” on page 157](#).

Use the Submaster Effect or Perform a Video Mixdown

For more information, see [“Submaster Editing” on page 275](#) and [“Performing a Video Mixdown” on page 278](#).

Reduce the Number of Real-Time Streams

Each Avid editing application supports a specific number of real-time streams. If your system does not have the capacity to run that many real-time streams, you can experience a degradation of system performance. Processor speed, system memory, and disk speed all affect system performance.

You can also experience performance degradation in an Avid shared storage environment when the demands on the system exceed the capacity of the Avid shared storage network to respond.

In either case, you can improve system performance by decreasing the number of real-time streams that your Avid editing application uses during playback. Use the Video Display Settings dialog box to change the number of real-time streams, as described in [“Controlling Real-Time Effects Processing”](#) on page 156.

Optimize your Drive Striping

Proper drive striping increases the speed at which your Avid editing application retrieves media. For more information, see the ReadMe for your Avid editing application and the [online Knowledge Base](#).

If your sequence contains multiple short clips with multiple real-time effects or images with a high level of complexity, you might exceed the capacity of your hardware to play these in real time, even if these effects do not normally exceed the real-time playback capabilities of your Avid editing application. This results in Video Underrun error messages. In this case, render some of the intermediate effects before playing the sequence. For more information, see [“ExpertRender”](#) on page 158.

Controlling Real-Time Effects Processing

To choose 10-bit effects processing, do one of the following:



- ▶ Click the Video Quality Menu button until it displays a green background and the number 10 (Full Quality 10-bit option).
- ▶ Right-click the Video Quality Menu button and select Full Quality 10-bit.
The Full Quality 10-bit option is only available with some system configurations. For more information, see [“Options for Controlling Real-Time Effects Playback”](#) on page 154.

To select the OpenGL mode:

1. In the Project window, click the Settings tab.
The Settings list appears.
2. Double-click Video Display.
The Video Display Settings dialog box opens.
3. In the OpenGL Hardware section, select one of the following:
 - Software OpenGL
 - The OpenGL video board installed on your system (listed by model number)
4. Click OK.

To set the number of real-time streams:

1. In the Project window, click the Settings tab.
The Settings list appears.
2. Double-click Video Display.
The Video Display Settings dialog box opens.
3. In the Stream Limit text box, type the number of real-time streams you want your Avid editing application to use for playback.
By default, this dialog box displays the maximum number of streams supported by your Avid editing application.
4. Click OK.

Playing Effects Back at Different Video Qualities

The Video Quality Menu button in the Timeline bottom toolbar lets you control the quality (display resolution) of the video playback. This feature lets you trade off video quality with smooth playback of real-time effects. If you notice missing frames or choppy video during real-time playback, switch to a lower quality setting. For more information about selecting a video quality, see “Video Quality Options for Playback” in the Help and “Setting the Video Quality for Playback” in the Help.

Some input/output hardware configurations also let you play back at Full Quality using a bit depth of 10-bits, which provides even higher quality processing for some effects (see “Change the Bit Depth for Effects Processing” in [“Options for Controlling Real-Time Effects Playback” on page 154](#)).

Your Avid editing application also provides an option that improves image quality during playback of mixed-format sequences where material requires resizing. You might need to deselect this option to avoid missing frames or choppy video during real-time playback.



If you switch from one video quality level to another during the course of your workflow, you might create precomputed clips that have not rendered with the quality that you need for your final output. You might need to manually purge the precomputed clips and re-render effects. For more information, see [“Ensuring the Quality Level of Precomputed Clips” on page 174](#).



On systems with an Avid input/output hardware device attached and selected for playback, real-time effects are always enabled. For information on playing real-time effects through a Host 1394 connection, see [“Playing Back to a DV Device” in the help](#).



Some older versions of Avid editing applications used the blue-dot mode feature to turn real-time effects off and on in software-only configurations. The replacement for this feature in current versions of Avid editing applications is the Realtime Encoding feature. For more information, see “Playing Back to a DV Device” in the Help.

To switch the video playback quality:

- ▶ Do one of the following:
 - In the Timeline bottom toolbar, click the Video Quality Menu button and cycle through the video quality settings to the one you want.
 - In the Timeline bottom toolbar, right-click the Video Quality Menu button and select the video quality setting you want from the menu.

When you change video qualities, immediate changes appear in the quality and the sharpness of the media displayed in the Source/Record monitor.

To prepare a sequence for output to a digital cut, switch to Full Quality mode and use ExpertRender. For more information, see [“ExpertRender” on page 158](#).

ExpertRender

ExpertRender determines which effects need to be rendered to achieve successful playback of a sequence.

You can use the ExpertRender feature in the same way that you use the standard Render commands. You can use the ExpertRender at Position command or you can mark IN and OUT points and then use the ExpertRender In/Out command. For more information, see [“Using the ExpertRender Command” on page 160](#).

If your Avid editing application has difficulty previewing effects in real time and displays playback information indicators in the timecode track of the Timeline, the steps you take when you use the ExpertRender In/Out command are somewhat different from the steps you take when you use one of the ExpertRender commands in other circumstances. For more information, see [“Using the ExpertRender Command After a Real-Time Playback Attempt” on page 162](#).

For more information on rendering, start with [“Basics of Effects Rendering” on page 53](#).

Understanding ExpertRender

When you render effects by using the Render at Position or Render In/Out command, your Avid editing application renders *all* effects in the selected material — all effects on the enabled tracks at the position or all effects on the enabled tracks between the marked IN and

OUT points. In most cases, your Avid editing application renders some effects that do not require rendering for successful playback, increasing the time to render and creating more precomputes than necessary.

For example, the following sequence includes seven effects on two tracks. If you use the Render In/Out command on this material, you render all seven effects. If you use the ExpertRender In/Out command on the material, the ExpertRender analysis recommends rendering only the three effects on the top track.



A sequence with seven effects (top) and the results of an ExpertRender analysis of this sequence. Only the three effects on the top track are highlighted, and these are the only effects that you need to render for successful output.

ExpertRender helps to solve the problem of unnecessary rendering by analyzing all the effects in selected material and determining which effects you need to render to achieve successful playback. You can choose to render the effects identified by ExpertRender or to modify the selections before submitting them for rendering.

ExpertRender attempts to generate a minimum set of effects to render for successful playback. If you render the effects recommended by ExpertRender, your material usually plays successfully in real time.

ExpertRender is particularly useful in the following circumstances:

- If you attempt to preview a sequence with effects and your Avid editing application is not been able to maintain real-time playback, you can use ExpertRender to help you render the minimum amount of material necessary to achieve successful playback for previewing. ExpertRender includes an option that lets you render effects only in the regions recommended by your Avid editing application for rendering after a playback

attempt. These are the regions marked by red indicators in the timecode track of the Timeline. For more information, see [“Understanding Real-Time Playback Information in the Timeline” on page 152.](#)

- If you are ready to output a sequence, for example, by performing a digital cut to tape, you can use the ExpertRender In/Out command and select the Prepare for Digital Cut option to determine which effects you need to render for successful output. In particular, when there are overlapping effects on multiple tracks, ExpertRender can calculate when the rendering of an effect on an upper track will incorporate picture information from lower tracks. In this situation, you do not need to render effects on the lower tracks separately. Depending on the complexity of your sequence, ExpertRender might save you both time and storage space by eliminating unnecessary rendering and precomputes.



On systems without Avid input/output hardware, you must render all effects before performing a digital cut.

- In most circumstances, ExpertRender enables you to render material quickly, easily, and with a high degree of storage efficiency. However, experienced Avid users might achieve an even quicker render of a complex sequence than that offered by ExpertRender — for example, using Submaster editing. For more information, see [“Considerations When Using ExpertRender” on page 166](#) and [“Submaster Editing” on page 275.](#)

You can configure your Avid editing application to send an email notification when a render operation completes. This lets you leave your Avid editing application unattended when a long render operation is taking place, yet still know when the render completes. For more information, see “Email Settings” in the Help.

Using the ExpertRender Command

Use the following procedure when there are no colored real-time playback information bars in the timecode track of the Timeline. You generally use this method to render a sequence so that it plays back successfully for output.


For information on using the ExpertRender command when colored real-time playback information indicators appear in the Timeline following a real-time playback attempt, see [“Using the ExpertRender Command After a Real-Time Playback Attempt” on page 162.](#)

To render effects by using the ExpertRender command:

1. Select all tracks in the Timeline that contain effects you want ExpertRender to analyze.
2. Do one of the following:
 - ▶ To render at position, move the position indicator to the effects in the Timeline.
 - ▶ To render between IN and OUT points, mark IN and OUT points around the effects.

3. Select Clip > ExpertRender at Position or Clip > ExpertRender In/Out.

ExpertRender analyzes the selected effects and highlights the effects that require rendering in the Timeline. The Expert Render dialog box opens and indicates how many of the effects require rendering.



4. Click the Drive button, and select a drive on which to store the rendered effects.

The *Effect Source Drive* selection refers to the drive where the media for the outgoing shot of the first transition resides.

5. Do one of the following:

- ▶ Click Cancel.

Your Avid editing application removes all ExpertRender highlighting and cancels the ExpertRender process without rendering any effects.

- ▶ Click Modify Selection.

The effects identified for rendering remain highlighted, and you can modify the set of effects to render. For more information, see [“Modifying ExpertRender Results” on page 164](#).

- ▶ Click OK.

Your Avid editing application renders the highlighted effects.

For information on displaying the estimated time required for the render, see [“Displaying Estimated Render Time” on page 57](#).

If there is not enough room on the drive, your Avid editing application displays a message box that gives you the following choices:

Option	Description
Continue	Attempt to render the effect anyway, in case there might be enough room on the drive.
Stop	Stop the rendering process and return to the Render Effect dialog box, and then select another drive before continuing.

Using the ExpertRender Command After a Real-Time Playback Attempt

Use the following steps when your Avid editing application has difficulty with real-time preview of effects and displays information indicators in the timecode track of the Timeline.



When you render recommended ranges in material by following this procedure, you can usually achieve analog output of the same material without further rendering. For DV output, however, you should use the ExpertRender command again for the duration of the material since you usually need to render additional effects.

For information on using the ExpertRender command under other circumstances, see [“Understanding ExpertRender” on page 158](#).


To render effects using ExpertRender after a real-time playback attempt:

1. Select all tracks in the Timeline that contain effects you want ExpertRender to analyze.
2. Mark IN and OUT points around the material you want ExpertRender to analyze.

If your sequence contains complicated effects and multiple layers, the IN and OUT points you mark might include parts of the Timeline marked by red indicators in the timecode track. For more information, see [“Understanding Real-Time Playback Information in the Timeline” on page 152](#).

3. Select Clip > ExpertRender In/Out.


The Expert Render dialog box opens and indicates the number of red indicator ranges that require rendering to achieve real-time preview of effects.



4. Do one of the following:
 - To render only the effects necessary to achieve successful real-time effects preview, select “Render recommended ranges,” and then click OK.

- ▶ To render all the effects that ExpertRender identifies for rendering within your marked selection, select “Render entire selection.”

The message in the Expert Render dialog box changes to indicate the number of effects that ExpertRender has identified for rendering across the entire selection. Using this option renders all the effects necessary for successful real-time playback of the marked region of the Timeline.



- ▶ If you are preparing for a digital cut, select Prepare effects for Digital Cut.

The message in the Expert Render dialog box changes to indicate the number of effects that ExpertRender has identified for rendering in order to create a digital cut. Using this option renders all the effects necessary for successful output of the marked region of the Timeline.



If you do not have Avid input/output hardware connected to your system, you must render all effects before performing a digital cut. Software-only systems ignore unrendered effects during a digital cut. For example, unrendered transition effects play as cuts.

5. Click the Drive button, and select a drive on which to store the rendered effects.

The *Effect Source Drive* selection refers to the drive where the media for the outgoing shot of the first transition resides.

6. Do one of the following:

- ▶ Click Cancel.

Your Avid editing application removes all ExpertRender highlighting and cancels the ExpertRender process without rendering any effects.

- ▶ Click Modify Selection.

The effects identified for rendering remain highlighted, and you can modify the set of effects to render. For more information, see [“Modifying ExpertRender Results” on page 164](#).

- ▶ Click OK.

Your Avid editing application renders the highlighted effects.

For information on displaying the estimated time required for the render, see [“Displaying Estimated Render Time” on page 57](#).

If there is not enough room on the drive, your Avid editing application displays a message box that gives you the following choices:

Option	Description
Continue	Attempt to render the effect anyway, in case there might be enough room on the drive.
Stop	Stop the rendering process and return to the Render Effect dialog box, and then select another drive before continuing.

Modifying ExpertRender Results

You can modify the results of an ExpertRender analysis, removing effects that you do not want to render and adding others that you do want to render.

In most cases, the results of an ExpertRender analysis offers the fastest rendering necessary for successful playback. You should only modify the results of an ExpertRender analysis if you are confident that your modifications are useful. For examples of situations where you might want to modify the results of an ExpertRender analysis, see [“Considerations When Using ExpertRender” on page 166](#).

If you render the results of an ExpertRender analysis without making any modifications, the material you submitted to ExpertRender usually plays back successfully in real time. If you render recommended ranges, the material plays back successfully for preview purposes. If you render the entire selection, the material plays back successfully for output.

To modify the results of an ExpertRender analysis:


1. Perform an ExpertRender by following steps 1 through 3 in [“Using the ExpertRender Command” on page 160](#) or in [“Using the ExpertRender Command After a Real-Time Playback Attempt” on page 162](#).
2. In the Expert Render dialog box, click Modify Selection.
3. Shift+click effects in the Timeline to add them or remove them from the set of effects to render.

Effects currently selected are highlighted.



4. When you are satisfied with your selections, click the Render Effect button in the Effect Editor or in the Tool palette.

The Render Effect dialog box opens.



To prevent the Render Effects dialog box from opening, press and hold the Alt key (Windows) or Option key (Macintosh) when you click the Render Effect button. Your Avid editing application will use the last drive selected and you do not need to follow the remaining steps in this procedure.

5. Click the Drive button, and select a drive for the rendered media.

The *Effect Source Drive* selection refers to the drive where the media on the outgoing shot of a transition resides.

6. Click OK.

For information on displaying the estimated time required for the render, see [“Displaying Estimated Render Time” on page 57](#).

If there is not enough room on the drive, your Avid editing application displays a message box that gives you the following choices:

Option	Description
Continue	Attempt to render the effect anyway, in case there might be enough room on the drive.
Stop	Stop the rendering process and return to the Render Effect dialog box, and then select another drive before continuing.

Your Avid editing application renders the highlighted effects.

To cancel ExpertRender during the modification process, do one of the following:

- ▶ Click in the timecode track to move the position indicator.
- ▶ Double-click one of the segment tools on the Timeline Palette.



Segment tools in the Timeline palette

- ▶ From the Clip menu, select an ExpertRender command, and then click Cancel in the Expert Render dialog box.

ExpertRender removes all its highlighting and cancels the ExpertRender process without rendering any effects.

Considerations When Using ExpertRender

When you work with ExpertRender, you should be aware of the following aspects of its operation:

- ExpertRender operates on all selected tracks in the Timeline, including any enabled tracks that might be above the currently monitored track. To view the material that you are submitting to ExpertRender accurately in the monitor window, make sure that you are monitoring the topmost selected track in the sequence.
- ExpertRender takes account of *all* tracks at or below the topmost selected track when determining what to render on the *selected* tracks to achieve successful playback. For example, if you have a sequence with tracks V1 to V4, and select tracks V3 and V4 when using ExpertRender, your Avid editing application considers tracks V1 and V2 when determining playback possibilities but highlights effects to render only from tracks V3 and V4.
- If the material you submit to ExpertRender includes an effect in a segment that also contains nested effects, ExpertRender always renders the effect on the top (outside) track rather than the effect inside the nest. In certain circumstances, this might limit your workflow flexibility. For example, you might anticipate the need to readjust the parameters of the effect outside the nest and the effect would then require rerendering. You can use the procedure described in [“Modifying ExpertRender Results” on page 164](#) to select the effect within the nest for rendering and deselect the effect outside the nest.
- In some circumstances where segment effects and transition effects are adjacent in a sequence, ExpertRender might recommend the segment effects for rendering when rendering the transition effects might be quicker or more convenient and still allow for successful playback. You can use the procedure described in [“Modifying ExpertRender Results” on page 164](#) to modify the combination of effects for rendering.

Creating and Using Render Settings

You can create one or more sets of render parameters and save them as a custom Render setting. For example, you can create one setting especially for rendering single-field motion effects and another for rendering two-field motion effects. You can then activate the setting that you need at each stage of your project.

To create a new Render setting:


1. In the Project window, click the Settings tab.
The Settings list opens.
2. Select All Settings from the Project window Fast menu.
3. Click Render.
4. Select Edit > Duplicate.
5. Name the setting by doing the following:
 - a. Click the custom name column (in between the setting name and the setting type identifier).
 - b. Type a name.
 - c. Press Enter (Windows) or Return (Macintosh).
6. Select options for the new Render setting as described in the table [“Render Settings Options” on page 168](#).

To activate a Render setting:

- In the Settings tab of the Project window, click in the column to the left of the setting name.
A check mark appears beside the setting that is currently active.

To adjust the options for a Render setting:

1. In the Settings tab of the Project window, double-click a Render setting.
The Render Setting dialog box opens.





2. Select the appropriate options, based on the descriptions in your Avid editing application in [“Render Settings Options” on page 168](#), and then click OK.

Render Settings Options

The following table describes the options available in the Render Setting dialog box.

Option	Suboption	Description
Render Completion Sound		Defines a sound that your Avid editing application plays once the rendering process is complete. This is useful when you are rendering multiple effects.
	None	Disables the rendering completion sound. This is the default.
	System Beep	The rendering completion sound matches the sound set for your operating system.
Motion Effects Render Using and Timewarp Effects Render Using	Render Sound	The rendering completion sound is a customized sound.
		These two menus determine the processing method when you render or rerender existing motion effects and Timewarp effects.
	Original Preference	Causes effects to render using the type they were when originally created.

Option	Suboption	Description
	Duplicated Field	<p>Displays a single field in the effect. For two-field media, this reduces the information stored by half because it drops one field of the image, resulting in a lower quality image. For single-field media, this is usually the best choice because of its speed (the other options do not improve effect quality for single-field media).</p> <p>With JFIF resolutions, selecting this option causes the effect to render in the shortest amount of time. With DV and MPEG resolutions, the effect renders approximately as quickly as it would if you select Both Fields as the rendering option.</p>
	Both Fields	<p>Displays both fields in the effect. For example, the first two frames of a half-speed (50%) slow-motion effect repeat the original Frame 1 (both fields) twice. This option is good for shots without inter-field motion, NTSC or PAL film-to-tape transfers, and still shots. With footage that includes inter-field motion, this method might result in minor shifting or bumping of the image because it disturbs the original order of fields: a Field 1 will appear both before and after the corresponding Field 2.</p> <p>The effect renders relatively quickly. For best results, you should use evenly divisible frame rates with this option.</p>
	Interpolated Field	<p>Creates a second field for the effect by combining scan line pairs from the first field in the original media. This option calculates the motion effect at the field level rather than the frame level. Because your Avid editing application considers all fields and does not disturb the original order of fields, the smoothest effect results.</p> <p>Effects you create using this option take the longest amount of time to render.</p>
	VTR-Style	<p>Creates a second field for the effect by shifting selected video fields of the original media by a full scan line. This technique is similar to that used by high-quality professional video decks when playing footage at less than normal speed. This option also creates the motion effect at the field level rather than the frame level. However, because pixels are not filtered, the final image is sharper than that created by the Interpolated Field option. The image might display some slight jitter at certain speeds.</p> <p>The time needed to render effects you create with this option is longer than the time for effects you create using either Duplicated Field or Both Fields but similar to the time needed for Interpolated Field.</p>

Option	Suboption	Description
	Blended Interpolated	<p>(Timewarp only) Blends (averages) pixels from the original frames or fields to create intermediate frames or fields. For example, at 25% speed, your Avid editing application creates three blended images between outgoing Image A and incoming Image B. The first blended image weights the pixels from Image A at 75% and Image B at 25%. The second blended image weights the pixels from Image A at 50% and Image B at 50%. The third blended image weights the pixels from Image A at 25% and Image B at 75%. Objects in motion from Image A to Image B appear to fade out of Image A and fade in to Image B.</p> <p>Timewarp effects you create using Blended Interpolated or Blended VTR render less quickly than Interpolated Field or VTR-Style.</p>
	Blended VTR	<p>(Timewarp only) Creates a second field for the effect by shifting selected video fields of the original media by a full scan line, then blending (averaging) pixels from the original frames or fields to create intermediate frames or fields. For example, at 25% speed, your Avid editing application creates three blended images between outgoing Image A and incoming Image B. The first blended image weights the pixels from Image A at 75% and Image B at 25%. The second blended image weights the pixels from Image A at 50% and Image B at 50%. The third blended image weights the pixels from Image A at 25% and Image B at 75%. Objects in motion from Image A to Image B appear to fade out of Image A and fade in to Image B.</p> <p>Timewarp effects you create using Blended Interpolated or Blended VTR render less quickly than Interpolated Field or VTR-Style.</p>
	 <i>Another Timewarp rendering option, FluidMotion™, is available only through the Motion Effect Editor. See “Creating Timewarp Effects” on page 213.</i>	
Effects Quality Render Using		<p>Sets a global override for 3D effects that have HQ (Highest Quality) rendering options. You select HQ rendering or standard rendering for individual effects by clicking the HQ button in the Effect Editor. For more information, see “Rendering 3D Effects Using the HQ (Highest Quality) Option” on page 176.</p> <p> <i>Once your Avid editing application begins rendering, it changes all affected HQ settings to the Effects Quality Render Using value in the active Render setting. If you cancel the render, HQ settings do not revert to their previous values.</i></p>
	Quality Set in Each Effect	<p>Causes effects to render at the quality determined by the HQ selection in the individual effects. This is the default.</p>

Option	Suboption	Description
	Standard Quality	Causes effects to render at Standard Quality, regardless of whether the HQ button was selected for the individual effect.
	Highest Quality	Causes effects to render at High Quality.

Using Partial Render

If you interrupt a render that is not complete, your Avid editing application lets you save the completed portion of the render. You can finish the render later by resubmitting the effect for rendering. Your Avid editing application then renders only the part of the effect that has not rendered previously and saves that part as a separate precompute.

This feature is especially useful if you have to interrupt a long render of a single effect, such as a Submaster effect.

You can also use the Render Ranges command in the Timeline Fast menu to customize the Timeline so that it indicates which parts of an effect your Avid editing application has rendered.

The playback behavior of a partially rendered effect depends on the frame at which playback begins. If playback begins at a rendered frame, your Avid editing application attempts to play the entire effect in real time. You see the rendered portion in real time but cannot see the unrendered portion. If playback begins at a non-rendered frame, your Avid editing application plays the entire effect using Render On-the-Fly.

To interrupt a render:

1. Press Ctrl+period (Windows) or Command+period (Macintosh) to interrupt the render.
A message box opens.
2. Do one of the following:
 - ▶ Click Keep to save the material already rendered.
 - ▶ Click Discard to end the render without saving the material already rendered.

To customize the display of render ranges in the Timeline:

1. Click the Timeline Fast Menu button, and select Render Ranges.
2. Select one of the following from the submenu:

Option	Description
None	Turns off the display of render ranges.
Partial Only	Displays a red line on the portion of any partially rendered effect that is currently unrendered (but does not mark completely unrendered effects). This is the default option.
All	Displays a red line on the portion of any partially rendered effect that is currently unrendered and on all completely unrendered effects. This is a simple visual indication of which effects are unrendered. It is not an indication of which effects you might need to render to achieve successful playback.

Using 16-Bit Processing Support for Rendered Effects

You can choose to render most effects using a bit depth of 16 or a bit depth of 8. 16-bit rendering provides greater precision and better color quality when working with 10-bit resolutions. For example, if you apply a color effect to a clip that contains a gradient (such as a wide, soft border), you notice a difference if you zoom in on the rendered effect. An effect rendered at 8-bit would show banding between colors at higher zoom ratios than an effect rendered at 16-bit. Also, if you use nested effects with many levels of nesting, using 16-bit precision can help preserve the overall image quality of the rendered effect.

The results of 16-bit precision rendering are more obvious with 10-bit resolutions than with 8-bit resolutions. However, 16-bit precision can be useful with 8-bit resolutions if you use color effects or use nested effects with many levels of nesting. Because it takes longer to render effects with 16-bit precision, you need to determine when the additional time is useful.

Some effects do not support 16-bit processing. The reference information for each individual effect in [“Effects Reference” on page 555](#) indicates which effects do not support 16-bit processing.



If you switch from one processing bit depth to another during the course of your workflow, you might create precomputed clips that have not rendered with the quality that you need for your final output. You might need to manually purge the precomputed clips and re-render effects. For more information, see “Ensuring the Quality Level of Precomputed Clips” on page 174.




Rendering times are slower when using 16-bit processing. Turning on HQ (highest quality render mode) for a 3D effect can also add additional rendering time. For more information on HQ, see “Rendering 3D Effects Using the HQ (Highest Quality) Option” on page 176.

To set the bit depth for rendered effects:

1. Select Tools > Media Creation.

The Media Creation dialog box opens.

2. Click the Render tab.



3. Set the Effects Processing bit depth option to one of the following:

Option	Description
8-bit	Use this option when rendering time is more important than image quality, or if you are mainly working with effects that do not support 16-bit precision.
16-bit	Use this option if you want the best overall image quality. Use this option if you use 10-bit resolutions, use many levels of nested effects, or want the best color fidelity for rendered effects.

Option	Description
Automatic	Use this option if you want the media source to determine the effects resolution. Effects render at 16-bit for 10-bit media and at 8-bit for 8-bit media. This is the default.

Ensuring the Quality Level of Precomputed Clips

Before you export or output your sequence, you must ensure that all your precomputed clips have been rendered using the desired quality settings. Your Avid editing application cannot always recognize that it needs to re-render effects when you change a quality setting. You must manually purge and re-render precomputed clips to ensure that all effects render with the desired quality.

In general, you need to purge and re-render if you have rendered effects while working in a lower quality setting and have then switched to a higher quality setting.

In contrast, if you render in a higher quality and switch to a lower quality, you do not always need to re-render. The quality of the precomputed clips is higher than that of the sequence and they are downconverted in real-time during playback. In this case, you should re-render only if you want to improve playback performance or maintain a consistent rendering quality across all clips.

You need to consider re-rendering your precomputes if you change any of the settings listed in the following table.

Location	Setting
Project Window - Format Tab	Project type
	Aspect ratio
	Color space
	Raster dimension
Media Creation Settings - Render Tab	Effects processing bit-depth
Video Quality Menu Button	Video playback quality

You can either purge precomputes from an individual sequence, or you can purge precomputes from all sequences in the project.

To purge precomputes from an individual sequence:

1. Open the sequence in Source/Record mode.
2. Select all audio and video tracks that contain prerendered effects.
3. Mark an IN point at the start of the sequence, and then mark an OUT point at the very end.
4. Select Clip > Clear Renders In/Out.
The Clear Renders dialog box opens.
5. Deselect Skip Motion Effects and Skip Unknown Effects.
6. Click OK.

To purge precomputes from all sequences:

1. Select Tools > Media Tool.
The Media Tool Display window opens.
2. Select All Drives to select all media drives.
3. Select Current Project to select the current project.



You can select multiple projects if you also want to clear pre-computes in other projects.

4. Deselect Master Clips and Media Files.
5. Select Precompute Clips.
6. Click OK.
The Media Tool window opens.
7. With the Media Tool window selected, select Edit > Select-All (or press Ctrl+A).
8. Select Edit > Delete (or press the Delete key).
9. In the Delete Media dialog, select all tracks and click OK.
10. Click Delete in the confirmation dialog.

After you purge all effects, render effects with the new settings where necessary. Avid recommends that you purge and re-render only as the last step before output. You should not need to purge pre-computed clips more than once.

Rendering 3D Effects Using the HQ (Highest Quality) Option

A small number of 3D effects have two rendering options, the standard hardware-assisted render and the HQ (Highest Quality) software-based render. HQ rendering produces a superior image but takes longer than standard rendering.

The HQ button appears in the Effect Editor for 3D effects that have an HQ rendering option. Use the HQ button to select HQ rendering for an individual effect in your sequence.

The additional quality that you achieve using the HQ rendering option depends on the effect and the footage you use to create the effect. For example, HQ rendering can often improve the quality of an effect that dynamically resizes an image or an effect on a clip with a lot of motion.



If an effect supports 16-bit processing, you can achieve additional quality by turning on HQ rendering along with 16-bit processing. See “Using 16-Bit Processing Support for Rendered Effects” on page 172.

To select HQ rendering for an individual effect:


1. In Effect mode, move the position indicator to the effect you want to select.
If HQ rendering exists for the effect, the HQ button is available in the Effect Editor.
2. Click the HQ button.
The button turns green.



To select standard rendering for an individual effect:

- Click the HQ button again.
The button turns black.

The HQ button has a global setting in the Render Setting dialog box. The Effects Quality Render Using menu lets you override the selection you made in the Effect Editor for individual effects.



You can easily change from standard rendering to HQ rendering for your entire sequence, once you are satisfied with your draft version, by using the Render Setting selection. You can also choose to set all effect rendering to standard if you want to reduce rendering time. For more information, see [“Creating and Using Render Settings” on page 167](#).



Once your Avid editing application begins rendering, it changes all affected HQ settings to the Effects Quality Render Using value in the active Render setting. If you cancel the render, HQ settings for individual effects do not revert to their previous values.

For example, suppose you apply several effects to a sequence and use the HQ button in the Effect Editor to select HQ rendering for some but not all the effects. In the active Render setting, you set Effects Quality Render Using to Highest Quality. You set an IN point and an OUT point, and select Clip > Render In/Out.

When you start the render, your Avid editing application immediately changes all the effects between the IN point and the OUT point to HQ rendering, if the HQ render is available for a given effect. If you cancel the render, the HQ settings that changed do not change back. You must reset the HQ settings individually.

Rendering Effects for the Media Station XL

When your workflow includes an Avid Media Station XL system for off-loading the rendering process, you can use the Render to Media Station command. Because Media Station cannot render all types of effects, this command determines which effects in the selected area require rendering on your Avid editing application before you send the sequence to the Media Station XL system.

For example, the Media Station XL system does not have 3D hardware, so you must render any 3D effects before you send the sequence to the Media Station XL system.

5 Playing Effects, Rendering Effects, and Managing Effect Media Files

You can choose to render the effects identified by the Render to Media Station command or to modify the selections before submitting them for rendering. For more information, see [“Modifying ExpertRender Results” on page 164](#).


You can cancel a Render to Media Station command at any point during the modification process.

For a multiple-track sequence, Render to Media Station begins analyzing the effects from the top track down. When your Avid editing application finds an effect that Media Station XL cannot render, it selects the effect for rendering. Any lower-track effects entirely covered by an upper-track clip that contains a selected effect will not be rendered. If you want to render these effects, deselect the tracks above the track with the effects that you want to render. Then use Render to Media Station again.

To use the Render to Media Station command:

1. Select all tracks in the Timeline that contain effects you want the Render to Media Station command to analyze.
2. Do one of the following:
 - ▶ To render at position, move the position indicator to the effects in the Timeline.
 - ▶ To render between IN and OUT points, mark IN and OUT points around the effects.
3. Select Clip > Render to Media Station.

The Render to Media Station dialog box opens.



4. Select one of the following options:

Option	Description
Entire Sequence	Selects any effects in the sequence that require rendering on your Avid editing application

Option	Description
In/Out	Selects any effects between the IN and OUT points that require rendering on your Avid editing application. This option is available only when IN and OUT points are marked.
Position	Selects any effects located at the position indicator that require rendering on your Avid editing application. This option is not available when IN and OUT points are marked in the sequence.

5. (Option) Select Render AVX™ Effects if you want your Avid editing application to render the AVX effects.
6. Click OK.

The Render to Media Station command analyzes the selected effects and highlights the effects that require rendering by your Avid editing application.

The Render Effects for Media Station dialog box opens and indicates how many of the effects submitted require rendering.

7. Click the Drive menu, and select a drive for the rendered media.

The *Effect Source Drive* is the location of the media for the outgoing shot of a transition.

8. Do one of the following:

- ▶ Click OK to render the selected effects that Media Station cannot render.
- ▶ Click Modify Selection if you want to modify the set of effects selected to render.
For more information, see [“Modifying ExpertRender Results” on page 164](#).
- ▶ Click Cancel to remove all Render to Media Station highlighting and to cancel the Render to Media Station process without rendering any effects.

To modify the results of a Render to Media Station analysis:

1. Perform the Render to Media Station analysis by following steps 1 to 6 in [“Rendering Effects for the Media Station XL” on page 177](#).
2. In the Render Effects for Media Station dialog box, click Modify Selection.
3. Shift+click effects in the Timeline to add them or remove them from the set of effects to render.
Selected effects are highlighted.
4. When you are satisfied with your selection, do the following:
 - a. Select Tools > Command Palette.
 - b. Click the FX tab.
 - c. If Active Palette is not selected, click the Active Palette radio button.

5 Playing Effects, Rendering Effects, and Managing Effect Media Files



- d. Click the Render Effect button.

The Render Effect dialog box opens.

5. Click the Drive menu, and select a drive for the rendered media.

The *Effect Source Drive* is the location of the media for the outgoing shot of a transition.

6. Click OK.

If there is not enough room on the drive, a message box opens.

7. (Option) Do one of the following:

- ▶ Click Stop to stop the rendering process and return to the Render Effects dialog box, and then select another drive before continuing.
- ▶ Click Continue to attempt to render the effects anyway, in case there might be enough room on the drive.

The selected effects render.



To display the estimated rendering time, press the T key on the keyboard. Press the T key again to clear the display. Press the P key to view the percent rendered.

To cancel a Render to Media Station command during the modification process, do one of the following:

- ▶ Click in the timecode (TC) track to move the position indicator.
- ▶ Double-click one of the segment tools on the Timeline palette.



Segment tools in the Timeline palette

- ▶ Select Clip > Render to Media Station, and then click Cancel in the Render to Media Station dialog box.

Your Avid editing application removes all Render to Media Station highlighting and cancels the Render to Media Station process without rendering any effects.

Managing Effect Media Files

Your Avid editing application lets you view effect media files and select them for deletion. You can quickly find or delete an effect media file from a bin, or you can use the Media tool to view all the files that relate to your project and select those you want to delete.

Understanding Effect Media Files Management

When you render an effect, your Avid editing application creates two elements: a rendered effect clip (also known as a precompute clip) and an associated media file. When you create a title or an imported matte key clip, your Avid editing application creates several elements: an effect clip, a precompute clip, and associated media files.

Your Avid editing application overwrites or automatically deletes a media file from your drive only if you:

- Render an effect two or more times with the Render Effect button.
- Close the project before either an Auto-save or a manual save occurs.

In this case, your Avid editing application automatically saves the last-rendered effect and deletes the earlier, unreferenced versions. This autodeletion applies only to effects rendered since the last save or project close.

This prevents you from deleting media that might be necessary to play other versions of the sequence. If you want to remove media files from your drive to save space, you must manually delete the files.

For complete information on the media management features and on the use of the Media tool, see “Managing Media Files” in the Help.



If you are using your Avid editing application in an Avid Interplay™ workgroup environment, you can use the asset manager to manage your media. For more information, see “Working with Media Files in an Avid Interplay Environment” in the Help.

Revealing Effect Media Files

You can reveal the media files associated with effect clips (titles and matte keys), rendered effect clips (precompute clips), and motion effects so that they are visible in their folders on the desktop. You can then verify information about the media files, delete them directly from the folder, or perform other standard file management operations.

5 Playing Effects, Rendering Effects, and Managing Effect Media Files

To reveal effect clip, rendered effect clip, or motion effect media:


1. (Option) If you want to reveal effect media for rendered effect clips (precompute clips), display those clips in the bin by doing the following:

- a. Select Bin > Set Bin Display.

The Set Bin Display dialog box opens.


- b. Select Rendered Effects and Show reference clips, and click OK.

Any rendered effect clips appear in the bin. The clips are named with the sequence name and effect type. In the following illustration, the effects are in a sequence named Rendered Effects.



2. Select an effect item in the bin.


In the following illustration, a rendered effect clip is selected.



You can reveal media files for only one item in a bin at a time.

3. Select File > Reveal File.

(Windows) Your Avid editing application searches all available drives, opens the folder in Windows Explorer, and highlights a related media file.



(Macintosh) Your Avid editing application searches all available drives, opens the folder, and highlights related media files.

4. (Option — Windows only) If more than one media file is associated with the clip, your Avid editing application displays a message box prompting you to reveal the next file. Do one of the following:

- ▶ Click OK to reveal the next file.

If the Explorer window disappears from view, bring it forward by pressing and holding the Alt key and pressing the Tab key until you select the Explorer window containing the OMFI MediaFiles folder or Avid MediaFiles folder information.

- ▶ Click Cancel to end the Reveal File operation.


Deleting Effect Media Files from a Bin

You can delete effect media files (for titles, matte key clips, and rendered effects) and motion effect media from a bin using the Delete dialog box.

To delete effect media files and motion effect media:

1. (Option) If you want to delete effect media for rendered effect clips (precompute clips), display those clips in the bin by doing the following:
 - a. Select Bin > Set Bin Display.
The Set Bin Display dialog box opens.
 - b. Select Rendered Effects and Show reference clips, and click OK.
Any rendered effect clips appear in the bin.
2. In the bin, select the clip or clips whose media you want to delete.
In this example, two items are selected: a title and a motion effect.

5 Playing Effects, Rendering Effects, and Managing Effect Media Files



3. Press the Delete key.

The Delete dialog box opens.

4. Select the appropriate check boxes for the material you want to delete, and then click OK.

For more information, see “Deleting Items from a Bin” in the Help.

6 Working with Plug-In Effects

You can use AVX plug-in effects to add new effects or to update existing effects. This chapter describes how to work with these plug-in effects.

On Windows systems only, some Avid editing applications can use Avid input/output hardware and an Avid plug-in for Adobe After Effects® to view After Effects compositions on an external (client) monitor.

- [Understanding AVX Plug-Ins](#)
- [Freeing Memory Used by AVX 1.x Plug-ins](#)
- [Installing AVX Plug-ins](#)
- [Locating the AVX 1.x Plug-Ins Folder \(Windows Only\)](#)
- [Updating and Promoting AVX Plug-ins](#)
- [Assigning Multiple Tracks in Plug-in Effects](#)
- [Using AVX Plug-In Controls](#)
- [Using the Client Monitor to Preview a Plug-In Effect](#)
- [Troubleshooting AVX Plug-Ins](#)
- [Working with the Avid After Effects EMP Plug-In \(Windows Only\)](#)

Understanding AVX Plug-Ins

Third-party plug-in effects use the Avid Visual Extensions (AVX) standard. AVX is a cross-platform software architecture that allows software effect modules to work with a host application such as an Avid editing application.

Avid also develops some AVX plug-in effects and supplies them with your Avid editing application. For example, the Illusion FX category of effects are AVX plug-in effects.



Third-party plug-in effects appear in the Effect Palette in their own category (usually the name of the plug-in vendor). Individual effects each have a plug-in icon. Plug-in effects behave in your Avid editing application in much the same way as standard Avid-supplied

effects. For example, when you apply a plug-in effect to a sequence, the plug-in effect icon appears in the Timeline. You can also save and apply effect templates based on plug-in effects.

Your Avid editing application supports both 1.x and 2.0 versions of the AVX standard. AVX 2.0 supports advanced keyframes and allows plug-in vendors to take advantage of 16-bit effects processing, while AVX 1.x does not. AVX 2.0 plug-ins automatically use advanced keyframes, so you do not need to promote them. A particular AVX 2.0 effect might or might not support 16-bit processing. For more information on 16-bit effects processing, see [“Using 16-Bit Processing Support for Rendered Effects” on page 172](#).

Some vendors let you promote AVX 1.x plug-ins to an AVX 2.0 version. For more information, see [“Updating and Promoting AVX Plug-ins” on page 189](#).

In general, AVX plug-ins are resolution-independent and automatically scale to the resolution of the clip. If an older AVX plug-in does not scale correctly with HD resolutions, please contact the plug-in vendor.



Your Avid editing application also supports AudioSuite™ plug-ins. These plug-ins apply only to audio clips and do not appear in the Effect Palette. For more information, see “Working with Audio” in the Help.



If you are transferring a project that includes sequences with AVX plug-in effects from another system, you must install matching AVX plug-ins to see the effects.

For more information on AVX, visit the [Avid AVX Developer Program page](#) at www.avid.com. For a complete list of third-party AVX plug-in vendors, see the [Partner Product Search page](#) at www.avid.com.

Freeing Memory Used by AVX 1.x Plug-ins

Each time you apply an AVX plug-in effect to a sequence, your Avid editing application keeps the effect resident in memory. When you close the bin containing the sequence, your Avid editing application closes the AVX plug-ins, which frees the memory. If you apply many plug-ins and find your Avid editing application running out of memory, you can close all AVX 1.x plug-ins and free the memory they use with a console command.

To close all AVX 1.x plug-ins:

1. Select Tools > Console.
2. Type `closeallavxplugins` and press Enter (Windows) or Return (Macintosh).

Your Avid editing application closes all open AVX 1.x plug-ins. The AVX plug-ins automatically open again as needed.

Installing AVX Plug-ins

Most AVX plug-ins have an installation program that installs the plug-ins automatically in the correct AVX Plug-In folder when you follow the installation instructions.



If an AVX plug-in has an installation program, always use the program to install the plug-ins. For more information, see the documentation for the plug-in.

Some AVX plug-ins do not have an installation program and you must install them manually.

To install AVX plug-ins manually:

1. Quit your Avid editing application.



Do not add or remove plug-ins while your Avid editing application is running.

2. Copy the plug-in files from the software vendor's folder to the corresponding AVX Plug-Ins folder located on your Avid system.

- ▶ (Windows) You must install AVX 2.0 plug-ins in the following folder:

C:\Program Files\Avid\Avid editing application\AVX2_Plug-Ins

- ▶ (Windows) The default location for AVX 1.x plug-ins is:

C:\Program Files\Avid\AVX_Plug-Ins

The AVX 1.x Plug-Ins folder might be in a different location on your system.

- ▶ (Macintosh) The AVX_Plug-Ins folder is located within the Avid file structure:

Macintosh HD:Applications:Avid editing application:SupportingFiles:
AVX_Plug-Ins

(AVX 1.x plug-ins only) You must place AVX 1.x plug-ins directly in the corresponding AVX_Plug-Ins folder for your Avid editing application to recognize them. They cannot be inside another folder within this folder or elsewhere on your system.

(Windows only) If the AVX 1.x AVX_Plug-Ins folder does not appear in the default location and you do not know where the folder is located, you can use the Registry Editor to locate the folder. For more information, see [“Locating the AVX 1.x Plug-Ins Folder \(Windows Only\)” on page 188](#).

3. Restart your Avid editing application.
4. Select Tools > Effect Palette.

For more information, see [“Understanding the Effect Palette” on page 26](#).

The AVX plug-in effects appear in the Effect Palette, usually in their own category under the name of the vendor.

(Windows only) If the plug-in effects do not appear in the Effect Palette after installation, see [“Troubleshooting AVX Plug-Ins” on page 192](#).

Locating the AVX 1.x Plug-Ins Folder (Windows Only)

This topic applies only to AVX 1.x plug-ins. The AVX2_Plug-Ins folder is always in the same location. For more information, see [“Installing AVX Plug-ins” on page 187](#).

When you first install your Avid editing application, you can select a location for the AVX_Plug-Ins folder. The default path is:

C:\Program Files\Avid\AVX_Plug-Ins

If you accept this location for the AVX_Plug-Ins folder, you install AVX 1.x plug-ins here.

If the AVX_Plug-Ins folder is not in the default location, or if the effects do not appear in the Effect Palette after you install them, you can use the Windows Registry Editor (Regedit) to locate the AVX_Plug-Ins folder.



Use the following procedure only to locate the AVX_Plug-Ins folder. Do not change any of the information in the Windows Registry. Changing values in the Windows Registry might affect the performance of your system.

To locate the AVX_Plug-Ins folder by using Regedit:

1. Click the Start button, and then click Run.

The Run dialog box opens.

2. Type **regedit** in the command line, and click OK.


The Registry Editor window opens.

3. In the left pane of the window, navigate to the following path:

HKEY_LOCAL_MACHINE\SOFTWARE\Avid Technology\AVX Plug-Ins

4. Click the AVX Plug-Ins folder in the left pane, and then check the entry for “Directory” in the right pane.

The value of this entry is the path that contains the AVX_Plug-Ins folder. For example, if the AVX_Plug-Ins folder is in its default location, the Directory entry is “C:\Program Files\Avid.” If you navigate to C:\Program Files\Avid using My Computer or Windows Explorer, you will find the AVX_Plug-Ins folder in that location.



The Directory entry for HKEY_LOCAL_MACHINE\SOFTWARE\Avid Technology\AVX Plug-ins in the Registry Editor

Updating and Promoting AVX Plug-ins

You can upgrade an AVX 1.x plug-in to a newer AVX 1.x plugin, or upgrade an AVX 2.0 plug-in to a newer AVX 2.0 plug-in.

You can promote some AVX 1.x plug-ins to an AVX 2.0 version if you have both versions of the plug-in installed on your system.

You can also promote all promotable AVX 1.x plug-ins in a sequence to AVX 2.0 in a single operation if the AVX 1.x plug-ins are missing (not installed on your system). For more information, see [“Updating and Reverting Existing Effects in Sequences” on page 44](#).



You might be able to downgrade an AVX 2.0 plug-in, depending on the vendor's implementation. See your plug-in documentation for details.

To upgrade an AVX 1.x plug-in to a newer AVX 1.x plug-in or an AVX 2.0 plug-in to a newer AVX 2.0 plug-in:

1. Uninstall the old version of the plug-in.
2. Install the new version in your AVX2_Plug-Ins or AVX_Plug-Ins folder.

Your Avid editing application upgrades existing effects in sequences to be compatible with the new version. When you select one of the effects, the existing parameter values for the effect appear in the Effect Editor or in the plug-in's own user interface.

If the new version of the plug-in has new or redesigned parameter controls, your Avid editing application sets these controls to their default settings for existing effects.

Controls that are unchanged from the older version of the plug-in retain the values you previously set.



(AVX 1.x plug-ins only) Once you upgrade a plug-in effect, do not reinstall the older version of the plug-in. Your Avid editing application cannot use an older version of a plug-in to process effects that you create with a newer version. Similarly, if you transfer projects between systems, an effect you create with a newer version of a plug-in does not work on a system that has an older version installed.

To promote an AVX 1.x plug-in effect to AVX 2.0:

1. Ensure that both the 1.x and the 2.0 versions of the plug-in are installed on your system.
2. Open the sequence containing the 1.x plug-in that you want to promote.
3. Open the AVX 1.x plug-in in the Effect Editor.

If the plug-in is promotable, the Promote to Advanced Keyframes button appears in the Effect Editor.



4. Click the Promote to Advanced Keyframes button.

The Effect Editor changes to display the advanced keyframe interface.



New parameters might not exactly match the old parameters, depending on how the vendor implements the new version of the plug-in.



Once you promote an effect to AVX 2.0 and save the effect in a bin, you cannot demote it back to AVX 1.x. This is important if you are moving sequences and effects between different Avid editing systems. If you will be moving sequences and effects between newer and older Avid editing systems, you might want to keep the plug-in effect at the 1.x version.

Assigning Multiple Tracks in Plug-in Effects

Some plug-in effects take an arbitrary number of tracks as input. Your Avid editing application lets you select the number of video inputs from the AVX Optional Inputs dialog box.



For more information on the multiple track capabilities of a plug-in, see the documentation for that plug-in.

To assign multiple tracks to a plug-in effect by using the AVX Optional Inputs dialog box:

1. Drag the plug-in icon to the Timeline.
If the plug-in supports a variable number of input tracks, the AVX Optional Inputs dialog box opens.
2. Click the Number of Tracks menu, select the number of video inputs, and then click OK.
For more information on nested effects, see [“Nesting Effects” on page 267](#).

Using AVX Plug-In Controls

AVX plug-ins use a variety of interfaces that give you control over the effects. Plug-in vendors have the following styles for controls:

- Standard buttons and parameter controls.
For AVX 2.0 plug-ins, this includes advanced keyframe buttons and parameter controls.

The Effect Editor for a specific plug-in might include only Avid standard buttons and parameter controls, or it might include additional custom controls that use an Avid-like interface.

- Custom dialog box only.



You typically access this dialog box by clicking the Other Options button or another custom button in the Effect Editor.

- Direct manipulation controls in the Effect Preview monitor.



In this case, when you click the Outline/Path button in the Effect Editor, custom controls appear over the image in the monitor.

For more information on how the plug-in vendor implements their interface, see the plug-in vendor’s documentation.

Some plug-in effects let you adjust an image by using controls that appear as overlays, such as handles and wire frames, in the Effect Preview monitor. You access these overlays by clicking the Outline/Path button at the bottom of the Effect Editor. In some cases, you can then access further controls by clicking buttons on the right side of the Effect Editor that are similar to the buttons available in standard Avid 3D effects.

The Angle control is not available in standard Avid effects but appears in some AVX plug-in effects. The Angle control lets you alter an effect’s angle or direction value by dragging within a graphic representation of a circle. Values can be positive or negative and are not limited to a single 360° rotation.



Using the Client Monitor to Preview a Plug-In Effect

Some plug-in vendors let you preview the effect in the client monitor. This lets you see how the effect will look in your Avid editing application while you are working on the effect in the plug-in interface. The effect does not play smoothly but you can view the results frame by frame.

Depending on the vendor's implementation this might apply to HD as well as SD projects. See your plug-in documentation for information on whether the option is supported and any additional information on configuring the plug-in to work with the client monitor.



The AVX Plug-ins custom interface cannot display frames on the client monitor if the Capture tool is open.

Troubleshooting AVX Plug-Ins

This topic describes problems that you might encounter with AVX plug-ins and suggests possible solutions or sources for more information.

If a plug-in does not work as expected and these suggestions do not solve the problem, contact the plug-in vendor.

Plug-In Does Not Appear in the Effect Palette

AVX plug-ins have a plug-in icon in the Effect Palette and in the Timeline. If the plug-in icon does not appear in the Effect Palette after installation, the plug-in might be in the wrong folder. For more information, see [“Locating the AVX 1.x Plug-Ins Folder \(Windows Only\)” on page 188](#) and [“Installing AVX Plug-ins” on page 187](#).

Plug-In Does Not Load

AVX plug-ins might not load correctly for a variety of reasons. In particular, even though a plug-in is located correctly in the AVX2_Plug-Ins or AVX_Plug-Ins folder, it might require supporting files such as .dll files that are missing from your system or are installed in the wrong location.

The Console window might display messages about why a plug-in did not load correctly.

If a correctly located plug-in does not load, check the plug-in documentation for information on required supporting files.

Your Avid Editing Application Cannot Render the Plug-In

If your Avid editing application cannot render the plug-in, the plug-in might have expired.

If you have problems rendering a plug-in effect, check the Console window. Some plug-ins write information about the failure to the Console window. Also, some plug-ins might report the problem as a message in the Bin or in the Edit monitor.

Blank Effect Icons in the Timeline



AVX plug-ins have a plug-in icon in the Effect Palette and in the Timeline. If the effect icon in the Timeline is blank, your Avid editing application could not find the plug-in.

To identify the plug-in that is missing or misplaced, open the Console window (select Tools > Console), and look for the message “Can’t find effect.” The message identifies the plug-in. You can then reinstall the plug-in in your AVX2_Plug-Ins or AVX_Plug-Ins folder and restart your Avid editing application.

Missing Effect Categories in the Effect Palette

If plug-in effect categories are not visible in the Effect Palette, either they are not installed correctly or you might have an incorrect version of the AVX Library. Check the Console window for a message that states that AVX was disabled.

- If AVX was not disabled, quit your Avid editing application, reinstall the plug-ins, and restart your Avid editing application.
- If AVX was disabled, contact Avid Technical Support to determine whether you need a new version of the AVXLibrary.

To obtain Technical Support, visit the online Knowledge Base at www.avid.com.

The Avid System Is Running Out of Free Memory

Each time you apply an AVX plug-in to a sequence, your Avid editing application keeps the effect resident in memory. When you close the bin containing the sequence, your Avid editing application also closes the AVX plug-ins and frees the memory. To close the AVX plug-ins manually, see “Freeing Memory Used by AVX 1.x Plug-ins” on page 186.

Working with the Avid After Effects EMP Plug-In (Windows Only)

Some Avid editing applications let you use the Avid After Effects EMP (External Monitor Preview) plug-in with your Avid input/output hardware to view an Adobe After Effects composition on an external NTSC or PAL monitor. This lets you see how the composition will look in your Avid editing application while you are working on the composition in After Effects. The Avid After Effects EMP plug-in is a Windows-only feature.

Install the plug-in on the system on which you run After Effects. Avid input/output hardware must also be connected to the system. For information on connecting and configuring the hardware, see the installation poster and instructions that shipped with the hardware.



You can run After Effects on the same system as your Avid editing application. While you run After Effects, After Effects uses the Avid input/output hardware. When you switch to your Avid editing application, it takes control of the Avid input/output hardware.

You install the Avid After Effects EMP plug-in from your Avid editing application installation disk as you would install one of the auxiliary applications such as FilmScribe or MediaLog™.

For more information, see [“Considerations for Using the Avid After Effects EMP Plug-in \(Windows Only\)” on page 195.](#)

To install the Avid After Effects EMP plug-in:

1. On the system that runs After Effects, quit all Windows applications.
2. Insert the Avid editing application CD-ROM into the CD-ROM drive.

If the installer does not automatically start after you insert the CD-ROM, do the following:

- a. Double-click the My Computer icon.
 - b. Double click the CD-ROM icon.
 - c. Double-click Launch.exe to start the Installer.
3. In the main installer window, click Install Individual Products.
 4. Click Avid After Effects EMP.
 5. Follow the instructions on the screen.

The installer automatically searches for After Effects on your system. If you have multiple versions of After Effects or if you store After Effects in an unusual location, use the Browse button to select the correct version.



*The installer creates a **Plugin/Avid** folder to store the Avid After Effects EMP plug-in. Do not change the name of this folder.*

To enable the Avid After Effects EMP plug-in:

1. Start After Effects.
2. Select **Edit > Preferences > Avid External Monitor Settings**.
3. Select one of the following options:

Option	Description
NTSC	Use if you have an external NTSC monitor connected to your system.
PAL	Use if you are using a PAL monitor.
Disable	Use if you want to want to disable the plug-in. This might be useful if you need to free up system resources when you edit a complex composition.

Considerations for Using the Avid After Effects EMP Plug-in (Windows Only)

You use the Avid After Effects EMP plug-in mainly to preview colors, objects, and anti-aliased text on an NTSC or PAL monitor without having to export the composition to your Avid editing application.

The Avid After Effect EMP plug-in accurately converts colors produced in After Effects to color values that can be displayed on an NTSC or PAL monitor. It converts RGB 4:4:4 values to the YUV 4:2:2 values used for video output.

Playback Motion

Playback motion is not as smooth on the external monitor because After Effects displays full progressive frames rather than interlaced fields. To view the interlaced video, you must render the composition with the Field Render option active and then import the composition into your Avid editing application.

Composition Settings

To view the image exactly as you will see it in your Avid editing application, select one of the following resolutions for your After Effects composition:

- NTSC D1
- NTSC DV
- PAL D1/DV

If you use another resolution, After Effects resizes the image when it displays it on the external monitor. This might cause some softening of the image. Color representation is still correct, but the display quality differs from the image you see in your Avid editing application.

7

Creating and Customizing Motion Effects

This chapter describes how to create and customize effects that alter motion in a clip either by changing a clip's speed or by creating a strobe (stuttering) effect.

- [Understanding Motion Effects](#)
- [Creating Traditional Motion Effects](#)
- [Playing and Rendering Motion Effects](#)
- [Understanding Timewarp Effects](#)
- [Creating Timewarp Effects](#)
- [Promoting a Traditional Motion Effect to Timewarp](#)
- [Using the Motion Effect Editor](#)
- [Scaling a Graph Display in the Motion Effect Editor](#)
- [Using the Source Anchor Frame](#)
- [Using Adaptive Deinterlacing](#)
- [Motion Effect Editor Reference](#)
- [Rendering Options for Timewarp Effects](#)
- [Timewarp Speed Graph Reference](#)
- [Timewarp Position Graph Reference](#)
- [Timewarp Effect Examples](#)
- [Understanding FluidMotion Timewarp Effects](#)
- [FluidMotion Workflow](#)
- [Using FluidMotion Edit](#)
- [Example of Correcting FluidMotion Artifacts](#)
- [Timewarp Preset Effects](#)
- [FluidFilm Preset Effects](#)
- [Setting Source and Output Options for Format Conversion with Timewarp Effects](#)

Understanding Motion Effects

Motion effects divide into two main categories, traditional motion effects (sometimes known as source-side motion effects) and Timewarp effects.

Traditional Motion Effects

You create a traditional Freeze Frame, Variable Speed, or Strobe Motion effect by generating a new clip with specific motion characteristics from an original clip that you open in the Source monitor. You then edit the motion effect clip into your sequence.

For example, if you begin with a 3-second clip and create a Variable Speed motion effect from that clip with the speed set to 50%, the result is a new 6-second clip in which movement takes place at half the speed of the original clip.

The advantage of traditional motion effects is that they are simple to create. The disadvantage of traditional motion effects is that they limit flexibility when you are editing and they allow only one speed for the duration of the clip. You cannot change the speed of a Variable Speed effect without creating a new motion effect clip, and you cannot achieve an effect where a clip moves slowly for part of its duration and then suddenly speeds up.

For more information, see [“Creating Traditional Motion Effects” on page 199](#).

Timewarp Effects

You create Timewarp effects by applying the Timewarp effect from the Effect Palette to a clip in a sequence. You modify the effect by using the Motion Effect Editor. You can also promote a traditional motion effect to a Timewarp effect once you edit it into a sequence.

You can use keyframes with the Timewarp effect to make multiple changes to the speed and position of any image in the effect. You can employ several different rates of speed, including reverse speed, in the same clip. You can also freely edit the effect, changing your speed settings as often as you need until you achieve the look you want.

In a Timewarp effect, the variations in speed are independent of the length of the clip in the sequence, so you can trim the clip without affecting your speed adjustments.

For more detailed information on Timewarp effects and how they differ from traditional motion effects, see [“Understanding Timewarp Effects” on page 210](#).

Creating Traditional Motion Effects

You can create the following kinds of traditional motion effects:

- Freeze Frame
For more information, see [“Creating a Traditional Freeze Frame Effect” on page 199](#) and [“Creating a Rolling Clip That Freezes” on page 201](#).
- Variable Speed
For more information, see [“Creating a Traditional Variable Speed Effect” on page 201](#) and [“Using the Fit to Fill Button to Create a Variable Speed Effect” on page 204](#).
- Strobe Motion
For more information, see [“Creating a Traditional Strobe Motion Effect” on page 204](#).

You can also combine a variable speed effect with a strobe motion effect. For more information, see [“Creating a Traditional Variable Speed Effect” on page 201](#).

Some of the options you can choose from when you create traditional motion effects, for example the rendering options, affect the quality of the finished effect or its playback capabilities. It is important to understand these choices fully. For more information, see [“Playing and Rendering Motion Effects” on page 207](#).

Creating a Traditional Freeze Frame Effect

A Freeze Frame effect is a still image, based on a selected frame from a clip, that continues to display for the duration that you select. When combined with the original clip, the footage plays and then “freezes” and holds on the frame that you specified.

As an alternative to creating a traditional freeze frame, you can use the Timewarp effect to freeze a single frame or create a rolling clip that freezes. See [“Speed Graph Example: Creating a Rolling Clip That Freezes” on page 229](#).

To create a traditional Freeze Frame effect:

1. Load a clip into the Source monitor.
For more information, see [“Creating and Editing Sequences” in the Help](#).
2. Cue the clip to the frame that you want to freeze.
3. Select Clip > Freeze Frame.
A submenu appears.

7 Creating and Customizing Motion Effects

4. (Option) If you are using two-field or uncompressed media, select Two Field Freeze Frames, and then select one of the following:

Option	Description
Using Duplicated Field	Your Avid editing application uses a single field to create the effect. This reduces the vertical resolution of the image by one-half, but is often the best option if the source footage contains rapid motion.
Using Both Fields	Your Avid editing application uses both fields to create the effect. This option is especially useful when there is little or no motion in the footage because it preserves all vertical resolution.
Using Interpolated Field	Your Avid editing application creates a second field for the effect by combining scan line pairs from the first field in the original media. This might result in a slightly softer look to the freeze frame.



For more information on these options, see “Motion Effect: Freeze Frame” on page 581.


The selected option becomes the default until you select another option.

5. (Option) If you made a Two Field Freeze Frames choice in step 4, select Clip > Freeze Frame again.
6. Select a duration:
- ▶ Select a preconfigured duration from the list.
 - ▶ Select Other, type a custom duration in the dialog box, and then click OK to enter the new duration.

A dialog box opens and prompts you to select a target drive for the freeze frame media.

7. Click the Drive menu, select a drive, and then click OK.

A new clip appears in the Source monitor and in the current bin preceded by a Motion Effect icon. The new clip has the original clip name followed by the letters FF.



Motion Effect icon and FF (Freeze Frame) clip name suffix on a Freeze Frame clip in the bin

Creating a Rolling Clip That Freezes

One common use for freeze frames is to create a segment that plays normally and then freezes, either to superimpose text information or to add emphasis to the end of a sequence before fading.

For an example that uses the Timewarp effect instead of a traditional freeze frame, see [“Speed Graph Example: Creating a Rolling Clip That Freezes” on page 229](#).

To create a rolling clip that freezes:

1. Edit the clip into the sequence.
2. Mark an IN point in the sequence at the frame where you want the freeze frame to occur.
3. Click the Match Frame button to load and cue the source clip to the matching frame.



For more information on matchframing, see “Using Match Frame” in the Help.

4. Create the Freeze Frame effect from the source footage as described in [“Creating a Traditional Freeze Frame Effect” on page 199](#).
5. Click the Extract/Splice-in button or the Lift/Overwrite button to edit the freeze frame into the sequence at the previously marked IN point.



Extract/Splice-in button (left) and Lift/Overwrite button (right)

When you play the sequence, the footage plays full-motion and then freezes at the selected frame.

Creating a Traditional Variable Speed Effect

Variable Speed effects involve changing the rate of playback to achieve fast-motion or slow-motion effects. Your Avid editing application creates slow-motion effects by duplicating frames in the original media. It creates fast-motion effects by eliminating frames from the original media.

For information on using the Timewarp effect to create a Variable Speed effect, see [“Timewarp Speed Graph Reference” on page 226](#) and [“Position Graph Example: Reverse Motion” on page 235](#).

To create a Variable Speed effect:

1. (Option) If you require a fixed duration for the clip based on a segment in the sequence, mark the segment in the Timeline with IN and OUT points.



You can use the Fit to Fill button to create a motion effect of fixed duration. See “Using the Fit to Fill Button to Create a Variable Speed Effect” on page 204.

2. (Option) If you want to use only part of the source clip for the motion effect, mark IN and OUT points in the Source monitor.
3. Click in the Source monitor to activate it.



If you do not activate the Source monitor, clicking the Motion Effect button does not open the Motion Effect dialog box. If the Record monitor is active, clicking the Motion Effect button opens the Motion Effect Editor for Timewarp effects.

4. Do the following:
 - a. Select Tools > Command Palette.
 - b. Click the FX tab.
 - c. Select Active Palette.
 - d. Click the Motion Effect button.



The Motion Effect dialog box opens.



If you map the Motion Effect button from the Command palette to the button palettes on the interface or to the keyboard, it opens the Motion Effect Editor for Timewarp effects. You must use the Motion Effect button in the Command palette (with Active Palette selected) to create traditional Variable Speed or Strobe Motion effects. For information on using the Command palette, see “The Command Palette” in the Help.

5. Select the Variable Speed option.
6. Specify the play speed for the Variable Speed motion effect by doing one of the following:
 - ▶ Type a number of frames in the Frames text box.
 - ▶ Type a frame rate in the FPS text box. To indicate reverse motion, enter a negative number for the play rate.
 - ▶ Type a percentage of the current play rate in the % Speed text box. To indicate reverse motion, enter a negative number for the percentage.
 - ▶ Select the Fit To Fill option to automatically set the variable speed parameters so that the duration of the motion effect will match the IN to OUT duration marked in the sequence.

All of the values change to reflect the rate you specify.

7. (Option) If you are using two-field or uncompressed media, select Two Field Freeze Frames, and then select one of the following:

Option	Description
Duplicated Field	Your Avid editing application creates the effect using one field.
Both Fields	Your Avid editing application creates the effect using both fields.
Interpolated Field	Your Avid editing application creates a second field for the effect by combining scan line pairs from the first field in the original media.
VTR-Style	Your Avid editing application creates a second field for the effect by shifting selected video fields of the original media by a full scan line. This technique is similar to that used by high-quality professional video decks when playing footage at less than normal speed.



For more information on these options, see “Motion Effect: Variable Speed and Strobe Motion” on page 581.


8. (Option) If you are using two-field media, and a specific motion effect type is set as the Motion Effects Render Using option in the active Render setting (in the Settings list), your Avid editing application automatically selects that type in the Motion Effect dialog box, makes all other types unavailable, and displays the Ignore Render Setting check box. If you want to override the Render setting, select the Ignore Render Setting check box, and then select one of the four options described in step 7.
9. Do one of the following:
 - ▶ Click Create to create the new clip and close the dialog box.
Another dialog box asks you to select the target bin for the effect.
 - ▶ Click Create and Render to render the clip (creating new media files) and close the dialog box.
Another dialog box asks you to select the target bin for the effect.



You must render a reverse motion Variable Speed effect in order to play it back in real time. If you do not render the effect at the time you create it, the effect plays back as filler (black image) until it is rendered.

A new clip appears in the Source monitor and in the current bin. The clip has the original clip name followed by the frame rate in parentheses. You can then edit this clip into your sequence as you would any other clip.

7 Creating and Customizing Motion Effects



Motion Effect icon and Variable Speed clip name suffix on a Variable Speed clip in the bin

Using the Fit to Fill Button to Create a Variable Speed Effect



You can create a Variable Speed effect that is automatically sized to fit a marked IN to OUT duration in a sequence by clicking the Fit to Fill button.

The Fit to Fill button, in the Edit tab of the Command palette, performs an overwrite edit and uses a Variable Speed motion effect to fill the marked duration. When you click the Fit to Fill button, your Avid editing application automatically selects variable speed parameters so that the duration of the motion effect matches the IN to OUT duration marked in the Timeline. Your Avid editing application then overwrites the motion effect into the sequence.

The motion effect you create with the Fit to Fill button uses the parameters you set in the Render Setting and Media Creation dialog boxes. If the Render preference is set to Original Preference, the new motion effect is rendered with duplicated fields.



To create an unrendered motion effect, press the Alt key (Windows) or the Option key (Macintosh) when you click the Fit to Fill button.

For more information, see “The Command Palette,” “Performing an Overwrite Edit,” and “Media Creation Settings” in the Help.

For information about Render settings, see [“Creating and Using Render Settings” on page 167.](#)

Creating a Traditional Strobe Motion Effect

Strobe motion results in a stuttering effect during playback of a clip. You determine the degree of the stutter or strobe when you create the effect.

You can also combine the Strobe Motion effect with the Variable Speed effect. For more information on the Variable Speed effect, see [“Creating a Traditional Variable Speed Effect” on page 201.](#)

For a procedure using the Timewarp effect, see [“Strobe Motion Using the Timewarp Effect” on page 234.](#)

To create a Strobe Motion effect:

1. (Option) If you want to use only part of the source clip for the effect, mark IN and OUT points in the Source monitor.
2. Click in the Source monitor to activate it.



If you do not activate the Source monitor, clicking the Motion Effect button does not open the Motion Effect dialog box. If the Record monitor is active, clicking the Motion Effect button opens the Motion Effect Editor for Timewarp effects.

3. Do the following:
 - a. Select Tools > Command Palette.
 - b. Click the FX tab.
 - c. Select Active Palette.
 - d. Click the Motion Effect button.



The Motion Effect dialog box opens.



The Motion Effect button on the Tool palette and in the Timeline top toolbar opens the Motion Effect Editor for Timewarp effects. If you map the Motion Effect button from the Command palette to another button, it opens the Motion Effect Editor. You must use the Motion Effect button in the Command palette to create traditional Variable Speed or Strobe Motion effects.


4. Select the Strobe Motion option.
5. Specify the update rate in frames for the Strobe Motion effect.

For example, a rate of 5 causes every fifth frame to be held for five frames before updating in the Strobe Motion effect.


6. (Option) If you are using two-field or uncompressed media, select Two Field Freeze Frames, and then select one of the following:

Option	Description
Duplicated Field	Your Avid editing application creates the effect using one field.
Both Fields	Your Avid editing application creates the effect using both fields.
Interpolated Field	Your Avid editing application creates a second field for the effect by combining scan line pairs from the first field in the original media.


Option	Description
VTR-Style	Your Avid editing application creates a second field for the effect by shifting selected video fields of the original media by a full scan line. This technique is similar to that used by high-quality professional video decks when playing footage at less than normal speed.

 For more information on these options, see *“Motion Effect: Variable Speed and Strobe Motion”* on page 581.

7. (Option) If you are using two-field media, and a specific motion effect type is set as the Motion Effects Render Using option in the active Render setting (in the Settings list), your Avid editing application automatically selects that type in the Motion Effect dialog box, makes all other types unavailable, and displays the Ignore Render Setting check box.
8. Do one of the following:
 - ▶ Click Create to create the new clip and close the dialog box.
Another dialog box asks you to select the target bin for the effect.
 - ▶ Click Create and Render to render the clip (creating new media files) and close the dialog box.
Another dialog box asks you to select the target bin for the effect.

 You must render a Strobe Motion effect in order to play it back in real time. If you do not render the effect at the time you create it, the effect plays back as filler (black image) until it is rendered.

A new clip appears in the Source monitor and in the current bin preceded by a Motion Effect icon. The new clip has the original clip name followed by the word Strobe and the number of update frames in parentheses.



Motion Effect icon and Strobe Motion clip name suffix on a Strobe Motion clip in the bin

Playing and Rendering Motion Effects

This section provides information on playback capabilities for traditional motion effects, and on your options for rendering and rerendering motion effects.

Playback Capabilities for Traditional Motion Effects

Some motion effect clips play in real time when edited into a sequence. You must render others before they can play. The following table describes the normal playback capabilities for traditional motion effects:

Effect Type	Description
Freeze Frame	Clips play in real time regardless of their type or duration. No icon appears on a Freeze Frame clip in the Timeline.
Variable Speed, forward motion	Clips play in real time and appear with a motion effect icon and a green dot in the Timeline. The motion effect icon indicates the type of the effect.
Variable Speed, reverse motion	Clips cannot play in real time and play as filler (black image) until you render them. Clips of this type appear with a motion effect icon and a blue dot in the Timeline.
Strobe Motion or Strobe Motion combined with Variable Speed	Clips cannot play in real time and play as filler (black image) until you render them. Clips of this type appear with a motion effect icon and a blue dot in the Timeline.

Understanding When to Render or Rerender Motion Effects

You sometimes need to render or rerender existing traditional motion effects. To do this, follow one of the procedures described in [“Basics of Effects Rendering” on page 53](#).

You might need to render or rerender motion effects in the following circumstances:

- You need to render any motion effect that requires rendering for successful playback if you did not render the effect when you created it.
This kind of effect appears with a blue dot in the Timeline until you render it.
- You might need to render a motion effect so that it plays successfully in a complex sequence even if that effect does not normally require rendering.
This kind of effect appears with a green dot in the Timeline, but might not play back in real time under some circumstances.

For more information on overall real-time playback capabilities, see [“Real-Time Playback of Video Effects” on page 151](#).

- You might need to render or rerender motion effects when you edit them into a sequence and perform trims or apply transition effects.

This kind of effect appears with a blue dot in the Timeline after the changes that cause it to require rendering. (Previously, it appeared with no colored dot in the Timeline (if it had been rendered) or with a green dot in the Timeline (if it previously played in real time).

The Partial Render feature lets you render only those parts of the Motion Effect clip that have been changed by your editing. The Render Ranges command in the Timeline Fast menu lets you see which parts of the motion effect require rendering. For more information, see [“Using Partial Render” on page 171](#).

- You need to rerender motion effects when you recapture media at a different resolution.

For example, if you offline a sequence using a single-field resolution and then recapture at a two-field resolution, you need to rerender all motion effects before they can play back correctly. In this circumstance, it is important to manage the quality of the finished effects using the most appropriate Render settings. For more information, see [“Controlling Motion Effect Type When Rendering or Rerendering Motion Effects” on page 208](#) and [“Creating and Using Render Settings” on page 167](#).

Controlling Motion Effect Type When Rendering or Rerendering Motion Effects

Each motion effect type has a distinct effect icon in the Timeline:

Icon	Description	Icon	Description
	Duplicated Field Motion Effect		Interpolated Field Motion Effect
	Both Fields Motion Effect		VTR-Style Motion Effect

Color-coded dots appear on Motion Effect icons to indicate whether they require rendering. For more information, see [“Color Coding on Effect Icons” on page 25](#).

The following illustration shows several examples of Motion Effect icons in the Timeline.



Left to right, examples of Motion Effect icons in the Timeline: rendered VTR-style motion effect (no dot); unrendered Interpolated Field motion effect (green dot — plays in real time); unrendered Interpolated Field motion effect (blue dot — plays as black until rendered)

ExpertRender correctly identifies motion effects that require rendering.

The motion effect type that your Avid editing application uses when it renders a motion effect depends on the setting for the Motion Effects Render Using option or the Timewarp Effects Render Using option in the active Render setting. If the option is set to Original Preference (the default setting), your Avid editing application makes no change to the type of motion effects when it renders them. If the option is set to a specific motion effect type, your Avid editing application changes all motion effects to that type when it renders them.

If you render motion effects after recapturing at a new resolution, or if you have another reason for wanting to change the type of all motion effects, ensure you have set the type you want in the active Render setting. Changes to motion effect types are permanent changes to both the Motion Effect clip and its associated media. You can return to the old motion effect type only by rerendering.

Using the same type for all motion effects is particularly important for controlling the look of motion effects when you are working with two-field media. For example, you might offline a project using single-field media and the Duplicated Field type for motion effects. Later, you might recapture the media at a two-field resolution, set the Motion Effects Render Using option in the active Render setting to VTR-Style, and submit the whole sequence for rendering. This creates new motion effects that are higher quality and that can play with the two-field media.

If you want to ignore the motion effect type set in the active Render setting for an individual motion effect or for a group of motion effects selected for rendering, you can do so using the Ignore Render Setting check box in the Motion Effect Editor. For more information, see [“Motion Effect Editor Reference” on page 219](#).

Considerations for Motion Effects in Progressive Projects

Motion effects in progressive projects behave somewhat differently from the same effects in interlaced projects. You should be aware of the following issues when you are working with motion effects in progressive projects.

- Your Avid editing application always uses complete progressive frames to create motion effects since there are no fields in progressive material. There are no two-field rendering options available in the Motion Effect dialog box in a progressive project.
- Your Avid editing application creates motion effects by duplicating or eliminating frames to speed up or slow down the motion. Because progressive motion effects use a relatively small number of full frames per second (for example, 24 or 25), if you use speed ratios that are not integer values, you might notice minor stuttering due to unusual patterns of duplication. Select simple ratios such as 2:1 (50%), 3:1 (33%), or 4:1 (25%).
- Progressive motion effects might look slightly different from interlaced motion effects because of the way your Avid editing application handles progressive material. For more information, see [“Working with Effects in HD and in Progressive Frame Projects” on page 27](#).

Understanding Timewarp Effects

Timewarp effects provides a powerful and flexible alternative to traditional motion effects. You apply Timewarp effects to segments in a sequence, and then use keyframes and other controls in the Motion Effect Editor to control the speed and the position of any image in the effect. For example, you can create a sequence that begins and ends with specific images, and in which the speed of motion changes an arbitrary number of times between the first image and the last.

For information on creating and modifying Timewarp effects, see [“Creating Timewarp Effects” on page 213](#), [“Promoting a Traditional Motion Effect to Timewarp” on page 213](#), and [“Using the Motion Effect Editor” on page 215](#).

FluidMotion is a method of interpolating motion in a Timewarp effect that results in extremely smooth motion. The tools available in FluidMotion Edit lets you refine the results of rendering effects with FluidMotion. For more information, see [“Understanding FluidMotion Timewarp Effects” on page 238](#).

Differences Between Timewarp Effects and Traditional Motion Effects

Timewarp effects differ from traditional motion effects in the following ways:

Difference	Description
Method of application	<p>You apply a Timewarp effect to a segment in a sequence, in just the same way that you apply any other effect from the Effect Palette. To switch to a different Timewarp effect, just replace the effect.</p> <p>With traditional effects, you must load a source clip, create a motion effect clip from that source clip, and then edit the motion effect into the sequence. If you want to change the speed, you must go back to the original clip, make a new motion effect clip, and then cut the new effect clip into the sequence.</p>
Clip duration	<p>With traditional motion effects, if you create an effect at 50-percent speed, the clip becomes twice as long.</p> <p>With the Timewarp effect, the duration of the segment in the sequence does not change. You can enter Trim mode directly from the Motion Effect Editor to make the segment longer or shorter.</p>
Speed display in the Timeline	<p>Traditional motion effects display the effect speed in parentheses beside the effect icon in the Timeline.</p> <p>Because the speed in a Timewarp effect is not fixed, a clip with a Timewarp effect does not display the speed.</p>

Understanding Speed and Position Controls for Timewarp Effects

The Timewarp effect provides two ways to control motion: speed and position. You display the Speed graph and the Position graph in the Motion Effect Editor.

The Speed control resembles traditional motion effects because you determine how fast you want the clip to play and change the speed accordingly. The Motion Effect Editor displays the speed of the source (input speed) at output time in the Speed graph. You customize the effect by using the Speed graph to add keyframes at specific times and then setting the speed of the effect at that time. For more information, see [“Timewarp Speed Graph Reference” on page 226](#).

Position maps input (source) time to output (effect) time. The Motion Effect Editor displays input time (vertical axis) over output time (horizontal axis) in the Position graph. You use the Position graph if you need a specific frame in the source to be at a specific frame in the effect. For example, you might want the clip to begin with a soccer player kicking the ball and end with the goalie catching the ball. You can position everything in between for effect, but you keep these two keyframes fixed. For more information, see [“Timewarp Position Graph Reference” on page 228](#).

You can work with either the Speed graph or the Position graph but not both at once. The adjustments you make with one control graph do not alter adjustments made on the other control graph. You activate the graph with which you want to work by selecting it from the Edit Graph menu. See [“Using the Motion Effect Editor” on page 215](#).



When you render a Timewarp effect, your Avid editing application applies only the information from the active graph.

Your Avid editing application stores keyframe information for both control graphs and maintains the two sets of keyframe information separately. For example, you might make adjustments using the Speed graph, switch to working with the Position graph, and then change back to the Speed graph. Your Avid editing application displays and applies all the keyframe information you initially created using the Speed graph. It does not show your adjustments with the Position graph, but does save the Position graph information so you can return to it if you choose.

While you adjust the active graph, the Motion Effect Editor represents changes in the inactive graph as well. This gives you a visual check in the inactive graph of your modifications to the active graph. You might find this useful, especially when working with the Position graph, to give you an idea of how your position alterations affect the speed of the effect.

Understanding Keyframe Interpolation Options for Timewarp Effects

You select a keyframe interpolation option to define the way the Timewarp effect changes speed or position in a clip. This selection determines the rate of change and the relative smoothness of change at keyframes. For example, you can create an effect in which all changes occur abruptly, or you can choose to smooth out all changes. For a full explanation of interpolation options, see [“Controlling Parameter Changes at Keyframes” on page 133](#).

You select an interpolation option from the Motion Effect Editor Fast menu.

Rendering Timewarp Effects

In addition to the rendering options familiar from other Avid effects (Duplicated Field, Both Fields, Interpolated Field, and VTR-Style), the Timewarp effect offers the following rendering options:

- Blended Interpolated takes the quality of the Interpolated Field option and combines it with frame blending.
- Blended VTR first applies the VTR-Style rendering option and then applies frame blending
- FluidMotion uses an interpolation algorithm that creates intermediate images by morphing the motion across the bracketing images

This results in extremely smooth motion. However, it can also cause artifacts (distorted areas) to appear when objects move in front of or behind other objects, move significantly from one frame to the next, or move into the image from outside the frame. FluidMotion Edit provides tools for correcting artifacts. See [“Understanding FluidMotion Timewarp Effects” on page 238](#).

For more information, see [“Rendering Options for Timewarp Effects” on page 223](#).

Rendering time for a Timewarp effect varies considerably. The following list ranks the rendering options by length of rendering time, from shortest to longest:

- Duplicated Field
- Both Fields
- Interpolated Field and VTR-Style (approximately the same)
- Blended Interpolated and Blended VTR (approximately the same)
- FluidMotion Draft
- FluidMotion



To save time while rendering the Timewarp effect, select a faster rendering option to rough out your sequence, and use FluidMotion only when you are satisfied with the overall sequence.

Creating Timewarp Effects

You create a Timewarp effect by dragging the Timewarp effect icon from the Effect Palette.

You can also promote a traditional motion effect to a Timewarp effect. For more information, see [“Promoting a Traditional Motion Effect to Timewarp” on page 213](#).

To apply a Timewarp effect from the Effect Palette:

1. Create a sequence in the Record monitor.
For information about creating a sequence, see “Creating and Editing Sequences” in the Help.
2. Enter Effect mode, for example, by selecting Toolset > Effects Editing.
For more information, see [“Entering Effect Mode” on page 41](#).
3. In the Effect Palette, click the Timewarp Effect category.
4. Click the Timewarp Effect icon, and drag it to the clip in the Timeline.
The Timewarp Effect icon appears in the Timeline.



If you apply the Timewarp effect as part of a nested effect, it must be the outermost effect.

Promoting a Traditional Motion Effect to Timewarp

You can promote a traditional motion effect to the Timewarp effect by using the Promote button in the Motion Effect Editor. The Promote button appears in the Motion Effect Editor only when you have the position indicator on a traditional motion effect in the Timeline.

You can also promote all traditional motion effects in a sequence to Timewarp effects with a single operation. For more information, see [“Updating and Reverting Existing Effects in Sequences” on page 44](#).



Once you promote the effect, you might not be able to load or use the sequence in an older version of an Avid editing application. Before promoting any effect, create a copy of the original sequence.

To promote a traditional motion effect to a Timewarp effect:

1. Move the position indicator to the traditional motion effect in the Timeline.
2. Click the Effect Mode button or the Motion Effect button.




Effect Mode button (left) and Motion Effect button (right)

7 Creating and Customizing Motion Effects

For more information, see [“Using the Motion Effect Editor” on page 215](#).

The Motion Effect Editor opens.

The Promote button appears in the Motion Effect Editor. The Speed, Strobe and Duration values for the motion effect appear in the appropriate text boxes in the Motion Effect Editor.



Promote button, Speed value text box, and Strobe and Duration value text boxes in the Motion Effect Editor

3. In the Motion Effect Editor, click the Promote button.

The Timewarp icon appears in the Timeline. The Motion Effect Editor uses the duration and speed information from the traditional motion effect to create a Timewarp effect.



Strobe motion information does not carry over to the Timewarp effect.

The name of the clip in the Timeline does not change. Your Avid editing application creates traditional motion effect clips with speed and strobe information in parentheses following the name. For example, a traditional motion effect clip named Turbocharge (15FPS) (Strobe: 5) is a half-speed effect with a strobe every five frames. After you promote the effect to a Timewarp effect, the name remains the same. This can be confusing if you rely on the information in parentheses to accurately reflect the effect's parameters.

Using the Motion Effect Editor

You customize Timewarp effects by using the Motion Effect Editor.

You do not have to be in Effect mode to use the Motion Effect Editor, and you do not have to close the Motion Effect Editor to use other modes. You can, for example, use the Motion Effect Editor while in Trim mode.




You cannot create a traditional motion effect with the Motion Effect Editor open. To create a traditional motion effect, close the Motion Effect Editor and follow the procedure in “Creating Traditional Motion Effects” on page 199.

You can expand the Motion Effect Editor to display the Speed graph, the Position graph, or both. Displaying a graph does not activate the graph.

You use the Edit Graph menu to activate a graph. Although both graphs might be visible, only one graph can be active at a time. However, you can switch between the Speed graph and the Position graph while you are working.

The following illustration shows the fully expanded Motion Effect Editor.



To set up the Motion Effect Editor for customizing a Timewarp effect:

1. Do one of the following:



- ▶ Click the Timewarp Effect icon in the Effect Palette and drag it to the segment in the Timeline where you want to create a Timewarp effect.
- ▶ Move the position indicator to an existing Timewarp effect in the sequence.



2. If the Motion Effect Editor is not already open, click the Motion Effect button.

For more information, see “Using the Motion Effect Editor” on page 215.

7 Creating and Customizing Motion Effects

The Motion Effect Editor opens.



The Motion Effect button appears in the Tool palette and in the Timeline top toolbar. You can also map the Motion Effect button from the Command palette to another button or to the keyboard. For more information, see the following topics in the Help: “Using the Tool Palette,” “Displaying the Timeline Top Toolbar,” and “The Command Palette.”

3. Click either the Speed Graph Display button or the Position Graph Display button.



Speed Graph Display button (left) and Position Graph Display button (right)

The appropriate graph opens, and the button you clicked changes its appearance.

4. Click the Edit Graph menu, and select one of the following:

- ▶ Speed to activate the Speed graph
- ▶ Position to activate the Position graph

The graph you selected becomes the active graph. The Fast Menu, Rewind, Fast Forward, and Add Keyframe buttons appear under the active graph. For more information, see [“Motion Effect Editor Reference” on page 219](#).

5. Make input and output format selections appropriate for your project in the Formats dialog box.

For more information, see [“Motion Effect Editor Reference” on page 219](#).



6. Click the Motion Effect Editor Fast Menu button, and select an interpolation option.

For more information, see [“Controlling Parameter Changes at Keyframes” on page 133](#).

7. (Option) If you are using two-field media, and a specific motion effect type is set as the Timewarp Effects Render Using option in the active Render setting, your Avid editing application automatically selects that type in the Type menu, makes all other types unavailable, and displays the Ignore Render Setting option.

If you want to override the Render setting, select the Ignore Render Setting option, and then select a new rendering option. For a complete description of rendering options, see [“Rendering Options for Timewarp Effects” on page 223](#).

8. Customize your effect.

For more information, see [“Timewarp Speed Graph Reference” on page 226](#) and [“Timewarp Position Graph Reference” on page 228](#).


For examples using the Speed graph and the Position graph to create various effects, see [“Timewarp Effect Examples” on page 229](#).

Scaling a Graph Display in the Motion Effect Editor

Each graph in the Motion Effect Editor has a Value scale slider and a Position scale slider. You use these sliders to scale the graph view up or down to see more or less detail.

For the Speed graph, the Value scale slider controls the Percent Speed (vertical) axis, and the Position scale slider controls the Output Position (horizontal) axis.

For the Position graph, the Value scale slider controls the Input Position (vertical) axis, and the Position scale slider controls the Output Position (horizontal) axis.



Speed graph (left) and Position graph (right) in the Motion Effect Editor. Below each graph are the Value scale slider (on the left), which controls the scaling of the vertical axis, and the Position scale slider (on the right), which controls the scaling of the horizontal axis.

To change the amount of detail in the Percent Speed axis (Speed graph) or the Input Position axis (Position graph):

- ▶ Drag the Value scale slider for either the Speed graph or the Position graph to the right (to show more detail) or to the left (to show less detail).

To change the amount of detail in the Output Position axis for either graph:

- ▶ Drag the Position scale slider for either the Speed graph or the Position graph to the right (to show more detail) or to the left (to show less detail).



The darker gray area of a graph represents the valid working area (the amount of source material you have available). The lighter gray area represents handles before and after the source material.

To move the view in the graph display without scaling:

1. Click within the boundaries of the graph display you want to move.
2. Press and hold Ctrl+Alt (Windows) or Command+Option (Macintosh).
The pointer changes to a hand.
3. Drag the hand in any direction to reposition the view within the graph display.

Using the Source Anchor Frame

Your Avid editing application needs to know the Source Anchor Frame to completely determine the results of Speed graph settings. One point in the source material — the input material for the effect — must map to one point in the effect — the output material. This allows your Avid editing application to use your Speed graph keyframe information to create the Timewarp effect.

The default Source Anchor Frame is the first frame or field of the source, and the default point for anchoring the Source Anchor Frame is timecode 0 — the first frame or field of the effect's output.

When you select elastic keyframes, the Source Anchor Frame determines which frame remains anchored (stays the same) while the other keyframes stretch or compress. See [“Controlling Advanced Keyframe Behavior with Trimmed Effects” on page 138](#).

To change the Source Anchor Frame:

- ▶ Enter the source timecode of the frame or field you selected in the Anchor text box.

To anchor the Source Anchor Frame at the active keyframe:



- ▶ Click the Source Anchor Frame button.

The Source Anchor Frame indicator moves to the active keyframe. The output timecode shows above the Record monitor.

To anchor the Source Anchor Frame manually:



- ▶ Click the Source Anchor Frame indicator, and drag it in the Output Position axis of the Speed graph.

The output timecode shows above the Record monitor.

Using Adaptive Deinterlacing

Adaptive deinterlacing is an additional processing option for Timewarp and Motion Adapter effects. The Adaptive Deinterlace Source check box is available in the Motion Effect Editor when all of the following are true:

- The Source parameter value is Interlaced.
- The Output parameter value is Progressive.
- The Type parameter value is one of the following: Both Fields, Blended Interpolated, Blended VTR.


Adaptive deinterlacing uses an algorithm for producing progressive frames from interlaced fields that analyzes adjacent frames as well as the current frame. Adaptive deinterlacing results in higher image quality for some kinds of clips, particularly where there is fast motion in the clip and when the clip is being slowed down significantly. For example, it can help to eliminate interlacing line artifacts, or jagged edges between a moving object and a background, without losing information from an entire field.

However, the complex calculations required by adaptive deinterlacing reduce processing performance, so you need to balance this against any improvement in image quality. You can experiment with the option to see whether it provides a valuable gain in image quality with your footage at an acceptable performance cost.

Motion Effect Editor Reference








The initial appearance of the Motion Effect Editor depends on whether there is no motion effect, a Timewarp effect, or a traditional motion effect in the segment at the position indicator. The following illustration shows the three possibilities.

7 Creating and Customizing Motion Effects





Initial appearance of the Motion Effect Editor when no effect (left), a Timewarp effect (center), or a traditional motion effect (right) is in the segment at the location of the position indicator.


Motion Effect Editor Components

Component	Description
Timewarp Effect icon 	Drag the icon to a bin to create a Timewarp Effect template from the current settings in the Speed graph and Position graph.
Speed Graph display button  	Click to open or close the Speed graph. See “Using the Motion Effect Editor” on page 215 .
Graph closed (left) and open (right)	
Position Graph display button  	Click to open the Position graph. Click again to close the Position graph. See “Using the Motion Effect Editor” on page 215 .
Graph closed (left) and open (right)	
 Clicking a graph display button does not activate the graph. Use the Edit Graph menu (described below) to select the Speed graph or Position graph.	
Promote to Timewarp button 	Click to promote a traditional motion effect to a Timewarp effect. See “Creating Timewarp Effects” on page 213 .

Motion Effect Editor Components (Continued)




Component	Description
Edit Graph menu <ul style="list-style-type: none"> Speed Position 	<p>Click to activate a control graph with which to customize the Timewarp effect. You can work with either the Speed graph or the Position graph but not both at once.</p> <p> <i>The Motion Effect Editor applies information only from the active control graph.</i></p> <p>For more information, see “Timewarp Speed Graph Reference” on page 226 and “Timewarp Position Graph Reference” on page 228.</p>
Type menu	<p>Click to select a rendering option. For more information, see “Playing and Rendering Motion Effects” on page 207 and “Rendering Options for Timewarp Effects” on page 223.</p>
Ignore Render Setting check box	<p>The Ignore Render Setting check box appears below the Type menu when you have made a rendering selection other than Original Preference in either the Motion Effects Render Using or the Timewarp Effects Render Using menu in the Render Setting dialog box. In this situation, the Type menu is dimmed.</p> <p>If you want to override the motion effect render settings in the Render Setting dialog box, click the Ignore Render Setting check box, and then select an option from the Type menu. For information about the Render Setting dialog box, see “Creating and Using Render Settings” on page 167.</p>
Speed display	Displays the percent speed of the traditional motion effect.
Anchor text box	Displays the source timecode of the Source Anchor Frame. Use the Anchor text box to set the timecode of the Source Anchor Frame for the Timewarp effect. For more information, see “Using the Source Anchor Frame” on page 218 .
Source Anchor Frame button 	Click to set the Source Anchor Frame at the active keyframe. The default Source Anchor Frame is the first frame of the source clip. For more information, see “Using the Source Anchor Frame” on page 218 .
Source menu	Click to select the Source format for a rendered Timewarp effect. Your selection should match the format of the original source material. For example, if you shot the material on a 30i camera, select Interlaced.

Motion Effect Editor Components (Continued)




Component	Description
Output menu	<p>Click to select the Output format for a rendered Timewarp effect. If you are creating a regular motion effect, you can use the same value as for the Source format. You also have the option of performing a format conversion on the effect. This lets you create a film look from interlaced video sources. For more information, see “FluidFilm Preset Effects” on page 247.</p> <p>You might also use a Timewarp effect to help in the processing of an effect on an interlaced clip within a progressive project. In this situation, you set the Source menu to Interlaced and the Output menu to Progressive.</p>
 <i>The Source and Output menus are not available in Film projects.</i>	
Adaptive Deinterlace Source option	Adaptive Deinterlacing is an additional processing option that might improve output image quality in some circumstances. This option is only available when certain combinations of options are set in the Type, Source, and Output menus. For more information, see “Using Adaptive Deinterlacing” on page 219 .
Strobe <i>n</i> frames text box	Displays the number of frames the Strobe Motion effect holds the image before updating. To change the strobe rate of the effect, type a new strobe rate in the text box and then press Enter (Windows) or Return (Macintosh).
Duration display	Displays the duration of the effect. If you change the output duration by manipulating the Speed graph or Position graph, or by trimming the clip in the Timeline, your Avid editing application reflects the new duration in this display.

The following table describes the buttons that always appear in the Motion Effect Editor toolbar.

Motion Effect Editor Toolbar Buttons





Button	Description
Render Effect	 Renders the Timewarp effect with the selected rendering option.
Remove Effect	 Removes the Timewarp effect.
Match Frame	 Finds and displays the frame in the source material that matches the frame in the Timewarp effect. In the case of an intermediate (interpolated) frame, the frame that displays is the frame closest to the intermediate frame.

Motion Effect Editor Toolbar Buttons (Continued)

Button		Description
Play Loop		Plays the Timewarp effect in a loop.
Play		Plays the Timewarp effect from the current position in the effect's position bar.
Trim Mode		You can trim out or trim in material while the Motion Effect Editor is active. For more information, see “Working in Trim Mode” in the Help.

The following table describes the buttons that appear in the Motion Effect Editor toolbar below the active control graph.


Active Control Graph Buttons



Button		Description
Fast Menu		Displays the Fast menu. The same menu appears as the shortcut menu when you right-click the active control graph. Because the Motion Effect Editor uses advanced keyframes, its Fast menu is similar to the Effect Editor shortcut menu for keyframe graphs. The components of these menus are described in “Shortcut Menus for Keyframe Tracks and the Motion Effect Editor” on page 144 .
Rewind		Moves the position indicator one keyframe to the left and activates the keyframe. If there is no keyframe to the left, nothing happens.
Fast Forward		Moves the position indicator one keyframe to the right and activates the keyframe. If there is no keyframe to the right, nothing happens.
Add Keyframe		Creates a keyframe at the current position. Alt+click (Windows) or Option+click (Macintosh) this button to delete a keyframe.



Rendering Options for Timewarp Effects

For information on selecting a rendering option, see [“Using the Motion Effect Editor” on page 215](#).

7 Creating and Customizing Motion Effects

Option	Description
Duplicated Field	<p>Displays a single field in the effect. For two-field media, this reduces the information stored by half because it drops one field of the image, resulting in a lower quality image. For single-field media, this is usually the best choice because of its speed. (The other options do not improve effect quality for single-field media.)</p> <p>Timewarp effects that you create using Duplicated Field render in the shortest amount of time.</p> <p>You can use this option to remove unwanted field motion in interlaced material brought into a progressive project.</p>
Both Fields	<p>Displays both fields in the effect. For example, the first two frames of a half-speed (50%) slow-motion effect repeat the original Frame 1 (both fields) twice. This option is good for clips without inter-field motion, for NTSC or PAL film-to-tape transfers, and for stills. With footage that includes inter-field motion, this method might result in minor shifting or bumping of the image because it disturbs the original order of fields: a Field 1 appears both before and after the corresponding Field 2.</p> <p>Timewarp effects that you create using Both Fields render relatively quickly. For best results, use evenly divisible frame rates with this option.</p> <p> <i>In some circumstances, Adaptive Deinterlace Source is available as a further processing option. For more information, see “Using Adaptive Deinterlacing” on page 219.</i></p>
VTR-Style	<p>Creates a second field for the effect by shifting selected video fields of the original media by a full scan line. This option also creates the motion effect at the field level rather than the frame level, but because pixels are not filtered, the final image is sharper than that created by the Interpolated Field option. The image might display slight jittering at certain speeds. This technique is similar to that used by high-quality professional video decks when playing footage at less than normal speed.</p> <p>Timewarp effects that you create using Interpolated Field or VTR-Style render less quickly than Both Fields but more quickly than Blended Interpolated, Blended VTR, or FluidMotion.</p>
Interpolated Field	<p>Creates a second field for the effect by combining scan line pairs from the first field in the original media. This option calculates the motion effect at the field level rather than the frame level. Because your Avid editing application considers all fields and does not disturb the original order of fields, the smoothness of the rendered effect is second only to FluidMotion. This method is best for video-originated material or film-originated material transferred at 24 fps.</p> <p>Timewarp effects that you create using Interpolated Field or VTR-Style render less quickly than Both Fields but more quickly than Blended Interpolated, Blended VTR, or FluidMotion.</p>


Option	Description
Blended Interpolated	<p>Blends, or averages, pixels from the original frames or fields to create intermediate frames or fields. For example, at 25% speed, your Avid editing application creates three blended images between outgoing Image A and incoming Image B. The first blended image weights the pixels from Image A at 75% and Image B at 25%. The second blended image weights the pixels from Image A at 50% and Image B at 50%. The third blended image weights the pixels from Image A at 25% and Image B at 75%. Objects in motion from Image A to Image B appear to fade out of Image A and fade in to Image B.</p> <p>Timewarp effects that you create using Blended Interpolated or Blended VTR render less quickly than Interpolated Field or VTR-Style but more quickly than FluidMotion.</p> <p> <i>In some circumstances, Adaptive Deinterlace Source is available as a further processing option. For more information, see “Using Adaptive Deinterlacing” on page 219.</i></p>
Blended VTR	<p>First creates a second field for the effect by shifting selected video fields of the original media by a full scan line, then blends, or averages, pixels from the original frames or fields to create intermediate frames or fields. For example, at 25% speed, your Avid editing application creates three blended images between outgoing Image A and incoming Image B. The first blended image weights the pixels from Image A at 75% and Image B at 25%. The second blended image weights the pixels from Image A at 50% and Image B at 50%. The third blended image weights the pixels from Image A at 25% and Image B at 75%. Objects in motion from Image A to Image B appear to fade out of Image A and fade in to Image B.</p> <p>Timewarp effects that you create using Blended Interpolated or Blended VTR render less quickly than Interpolated Field or VTR-Style but more quickly than FluidMotion.</p> <p> <i>In some circumstances, Adaptive Deinterlace Source is available as a further processing option. For more information, see “Using Adaptive Deinterlacing” on page 219.</i></p>
FluidMotion Draft	<p>Lets you view the motion that would be created by the FluidMotion setting, but at a lower quality. Use this setting if you are working in vector edit mode and performance is too slow. Use the FluidMotion setting for final output.</p>

Option	Description
FluidMotion	<p>Analyzes the motion between outgoing Image A and incoming Image B, and interpolates intermediate frames pixel-by-pixel. The motion generated by FluidMotion is the smoothest of all the rendering options.</p> <p>Timewarp effects that you create using FluidMotion are the slowest to render.</p> <p> <i>When you step through a sequence with a Timewarp effect, your Avid editing application can take a noticeable amount of time to update the Effect Preview monitor. For better performance, use FluidMotion Draft while you work on your sequence.</i></p> <p>To save time, select one of the other rendering options to rough out your sequence and use FluidMotion only when you are satisfied with the overall sequence.</p> <p> <i>This option is not available in the Render Setting dialog box in the Settings list because it is best used while you are working with a Timewarp effect.</i></p>


 **You must render FluidMotion effects before combining with any other effects, especially any other time-based effects such as FluidColorMap.**

Timewarp Speed Graph Reference

The following illustration shows the activated Speed graph.



Motion Effect Editor Speed Graph Components

Component	Description
1 Anchor text box	Displays the timecode of the Source Anchor Frame. For more information, see “Using the Source Anchor Frame” on page 218 .
2 Source Anchor Frame button	Click to anchor the Source Anchor Frame at the current keyframe. For more information, see “Using the Source Anchor Frame” on page 218 .
3 Active keyframes	The keyframes to which your Avid editing application applies any changes you specify. Active keyframes are pink.
4, 11 Percent Speed axis Output Position axis	The Percent Speed (vertical) axis represents the speed of the resulting effect as a percentage of the speed of the source material. The Output Position (horizontal) axis represents the timecode for the resulting effect. For example, if Percent Speed is 200 at an Output Position of 00:00:02:15, then at 2:15 after the start of the effect, the speed of the effect is twice the speed (200%) of the source material.
5 Position indicator (blue)	The image that appears in the monitor is the image at this position in the effect. You move the Speed graph position indicator as you would any other position indicator. When you add a keyframe, it appears at the position indicator.
6 Source Anchor Frame indicator 	Indicates the point (timecode) in the effect where you have anchored the source. The default Source Anchor Frame is the first frame or field of the source, and the default point for anchoring the Source Anchor Frame is timecode 0 — the first frame or field of the effect. For more information, see “Using the Source Anchor Frame” on page 218 .
7 Percent Speed text box	Displays the percent speed at the active keyframe. You change the percent speed by moving keyframes vertically or by typing a number in the Percent Speed text box.
8 Output Position text box	Displays the timecode for the resulting effect at the active keyframe. You can change the output position by Alt+dragging (Windows) or Option+dragging (Macintosh) keyframes horizontally or by typing a timecode in the Output Position text box.
9 Value scale slider and Position scale slider	Scale sliders scale the Speed graph view up or down so you can see more or less detail. The Value scale slider controls the Percent Speed axis. The Position scale slider controls the Output Position axis. For more information, see “Scaling a Graph Display in the Motion Effect Editor” on page 217 .
10 Green line	Indicates output speed in the effect as a percentage of input speed. The slope of the line tells you how fast and in which direction the speed changes over the course of the effect. You add keyframes to further refine the effect.
12 Active control graph toolbar	Appears under the active control graph. See “Motion Effect Editor Reference” on page 219 .


7 Creating and Customizing Motion Effects



The Fast menu that appears when you click the Fast Menu button in the Speed graph toolbar is the same as the shortcut menu that appears when you right-click the Speed graph. The menu is described in “Shortcut Menus for Keyframe Tracks and the Motion Effect Editor” on page 144.

Timewarp Position Graph Reference

The following illustration shows the activated Position graph.



Motion Effect Editor Position Graph Components

Components	Description
1, Input Position axis	The Input Position (vertical) axis represents the timecode for the source clip. The Output Position (horizontal) axis represents the relative timecode for the resulting effect. The exact timecode displays above the Record monitor.
8 Output Position axis	
2 Position indicator (blue)	The image that appears in the monitor is the image at this position in the effect. You move the Position graph position indicator as you would any other position indicator. When you add a keyframe, it appears at the position indicator.

Motion Effect Editor Position Graph Components (Continued)

	Components	Description
3	Active keyframes	The keyframes to which your Avid editing application applies any changes you specify. Active keyframes are pink.
4	Input Position text box	Indicates the input position (timecode in the source clip) at the active keyframe. You can change the input position by moving keyframes vertically or by typing a number in the Input Position text box.
5	Output Position text box	Indicates the relative timecode for the resulting effect at the active keyframe. You can change the output position by Alt+dragging (Windows) or Option+dragging (Macintosh) keyframes horizontally or by typing a timecode in the Output Position text box.
6	Value scale slider Position scale slider	Use the scale sliders to scale the Position graph view up or down to see more or less detail. The Value scale slider controls the Input Position axis. The Position scale slider controls the Output Position axis. For more information, see “Scaling a Graph Display in the Motion Effect Editor” on page 217 .
7	Green line	A point on the green line indicates the timecode in the source clip relative to the timecode in the resulting effect. The line shows the mapping of source material to the effect. You add keyframes to further refine the effect.
9	Active control graph toolbar	Appears under the active control graph. See “Motion Effect Editor Reference” on page 219 .



The Fast menu that appears when you click the Fast Menu button in the Position graph toolbar is the same as the shortcut menu that appears when you right-click the Position graph. The menu is described in [“Shortcut Menus for Keyframe Tracks and the Motion Effect Editor” on page 144](#).

Timewarp Effect Examples

The examples in this section demonstrate several basic effects you can achieve with the Timewarp effect. You can also use the Timewarp templates that appear in the Motion Effect category as a starting place for familiarizing yourself with the capabilities of the Timewarp effect. For more information, see [“Timewarp Effects” on page 592](#).

Speed Graph Example: Creating a Rolling Clip That Freezes

When you create a traditional Freeze Frame effect, you create a clip of a single frozen image in the Source monitor and edit it into your sequence at the right place. To change the location of the frozen image, you must create a new Freeze Frame clip.

7 Creating and Customizing Motion Effects

You create a freeze frame with a Timewarp effect by cueing to the image in your sequence that you want to freeze and adding a keyframe to set the speed of the clip to 0% at that point. When you want motion to resume, add a keyframe at that timecode and set the speed of the clip to 100%.

You can easily add multiple freeze frames to a single clip by creating additional pairs of keyframes: one at the beginning of each freeze frame to set the speed to 0%, and one at the end of each freeze frame to return the speed to 100%.

To create a rolling clip that freezes by using the Timewarp effect Speed graph:

1. Apply a Timewarp effect, and set up the Motion Effect Editor as described in [“Using the Motion Effect Editor” on page 215](#), with the following specifics:



- a. Click the Edit Graph menu, select Speed, and click the Speed Graph Display button to open the Speed graph.



- b. Click the Motion Effect Editor Fast Menu button, and select Shelf as the interpolation option. See [“Controlling Parameter Changes at Keyframes” on page 133](#).



2. (Option) Click the Position Graph Display button to open the Position graph.

Changes you make to the Speed graph are reflected in the Position graph. Having the Position graph open lets you see how you could achieve the same changes by using the Position graph.


The Position graph opens, and the Position Graph Display button changes.

3. Cue to the image in your sequence where you want the image to freeze.



4. In the toolbar below the Speed graph, click the Add Keyframe button.

A keyframe indicator appears at the position indicator in the Speed graph.




5. Move the position indicator to the timecode at which you want action to resume.

As you drag the position indicator in the Position graph, the output timecode shows in the upper left corner of the Position graph.


6. In the toolbar below the Speed graph, click the Add Keyframe button.

A keyframe indicator appears at the position indicator in the Speed graph.



7. Click the middle keyframe indicator to activate it, and set the speed at 0% for this keyframe by doing one of the following:

- ▶ Type 0 in the Percent Speed text box, and press Enter (Windows) or Return (Macintosh).
- ▶ Click the keyframe indicator, and drag it down until it reaches the zero (0) marking on the Percent Speed axis.



7 Creating and Customizing Motion Effects



You move Timewarp keyframes directly in the same way you move keyframes in keyframe graphs. See “Moving Advanced Keyframes” on page 123.

Notice the line in the Position graph. At the beginning of the effect, the line shows that input position (timecode in the source) and output position (timecode in the effect) are changing at the same rate.

The effect plays at 100% speed until the freeze frame. At that point, the line becomes flat. It remains flat for the length of the freeze frame because the timecode in the source does not change.

From the end of the freeze frame to the end of the effect, the line again slopes upwards at 45 degrees, showing that input position and output position are changing at the same rate.

You can become familiar with using the Position graph by experimenting with duplicating the Speed graph freeze frame results with the Position graph as the active control graph.



8. In the Motion Effect Editor toolbar, click the Render Effect button.



9. (Option) In the Motion Effect Editor toolbar, click the Trim Mode button, and trim the effect to achieve the duration you want.

For more information, see “Working with Trim Edits” in the Help.



10. (Option) Click the Timewarp Effect icon in the Motion Effect Editor, and drag it to a bin to create an effect template with the current parameters.

Speed Graph Variations: Moving Keyframes


You can change the time in the clip at which a freeze frame starts or ends, or change the length of the freeze, by moving the keyframes that control the starting and ending times of the freeze frame.



You move Timewarp keyframes directly in the same way you move keyframes in keyframe graphs. See “Moving Advanced Keyframes” on page 123.

To change the time at which the freeze frame starts:


1. Click the keyframe indicator at which the freeze frame ends.
2. Shift+click the keyframe indicator at which the freeze frame starts.



3. Do one of the following:

- ▶ Alt+Shift+click (Windows) or Option+Shift+click (Macintosh) the first keyframe indicator, and drag it to its new position.
- ▶ Type a new start timecode in the Output Position text box.

The keyframes move together to the new position.



The freeze frame now starts and ends at the new keyframe positions.

To change the length of the freeze frame, without changing the starting time, do one of the following:

- ▶ Alt+Shift+click (Windows) or Option+Shift+click (Macintosh) the second keyframe indicator, and drag it to its new position.

Dragging to the left shortens the freeze frame, while dragging to the right lengthens it.

- ▶ Type a new ending timecode in the Output Position text box.

Strobe Motion Using the Timewarp Effect

Strobe motion is essentially the same for the Timewarp effect as for a traditional motion effect.

To create a Strobe Motion effect by using the Timewarp effect:

1. Apply a Timewarp effect, and set up the Motion Effect Editor as described in [“Using the Motion Effect Editor” on page 215](#).

2. Type the strobe motion rate in frames in the Strobe text box.

For example, a rate of 5 causes every fifth frame to be held for five frames before updating.



3. In the Motion Effect Editor toolbar, click the Render Effect button.

4. View the result. If you want to change the strobe motion rate, repeat steps 3 and 4

5. (Option) You can combine strobe motion and variable speed in the same Timewarp effect. Set and customize keyframes in either the Speed graph or the Position graph to achieve the result you want.



6. (Option) In the Motion Effect Editor toolbar, click the Trim Mode button, and then trim the effect to achieve the duration you want.

For more information, see [“Working with Trim Edits”](#) in the Help.



7. (Option) In the Motion Effect Editor, click the Timewarp Effect icon, and drag it to a bin to create an effect template with the current parameters.

Customizing an Effect with the Position Graph

When you use the Position graph to customize a Timewarp effect, you map source material position to output position. Any timecode of the source material is mapped to any timecode of the result, within the constraints of the Position graph. The results of the Position graph are reflected in the Speed graph.

To customize an effect with the Position graph:

1. Apply a Timewarp effect, and set up the Motion Effect Editor as described in [“Using the Motion Effect Editor” on page 215](#), with the following specifics:



- a. Click the Edit Graph menu, select Position, and then click the Position Graph Display button to open the Position graph.



- b. Click the Motion Effect Editor Fast Menu button, and select an interpolation option.

For more information, see [“Controlling Parameter Changes at Keyframes” on page 133](#).



2. (Option) Click the Speed Graph Display button to open the Speed graph.

Changes you make to the Position graph are reflected in the Speed graph. Having the Speed graph open gives you a visual check on how your changes affect the speed of the result.

The Speed graph opens, and the Speed Graph Display button changes.

3. Where you want to have a particular part of the source appear at a fixed time in the effect, move the position indicator to that timecode in the Output Position axis, and add a keyframe. For more information, see [“Adding Advanced Keyframes” on page 113](#).

A keyframe indicator appears on the green line at the position indicator.

4. Map the source timecode to the output by doing one of the following:
 - ▶ Move the keyframe indicator to the point where the input timecode (shown in the Input Position text box) maps to the output timecode (shown in the Record monitor) to achieve the effect you want.



You move Timewarp keyframes directly in the same way you move keyframes in keyframe graphs. See [“Moving Advanced Keyframes” on page 123](#).

As you drag the keyframe over major position markings, you will notice a resistance. This helps you place keyframes more accurately.

- ▶ Type the input timecode in the Input Position text box.
5. Add and customize more keyframes to achieve the effect you want.

For more detailed information, see [“Position Graph Example: Reverse Motion” on page 235](#).

6. Render and review the effect.



7. (Option) Click the Timewarp Effect icon in the Motion Effect Editor, and drag it to a bin to create an effect template with the current parameters.

Position Graph Example: Reverse Motion

While the Motion Effect category contains a Reverse Motion template for the Timewarp effect, setting up reverse motion directly in a clip demonstrates how the Position graph works in this basic effect. You can use the same technique to create reverse motion in part of a clip instead of across the entire clip.

To create reverse motion, you map the end of the source to the beginning of the effect, and the beginning of the source to the end of the effect. You do this by setting new input positions for the first and last keyframes, either by dragging the keyframe indicators to their new locations or by typing the input position timecodes for each keyframe.



You move Timewarp keyframes directly in the same way you move keyframes in keyframe graphs. See [“Moving Advanced Keyframes” on page 123](#).

To create reverse motion in a clip:

1. Apply a Timewarp effect, and set up the Motion Effect Editor as described in [“Using the Motion Effect Editor” on page 215](#) with the following specifics:




- a. Click the Motion Effect Editor Fast Menu button, and select Linear or Bézier as the interpolation option.

The Bézier interpolation option eases the parameter change in and out at each keyframe. By manipulating the Bézier direction handles, you control the characteristics of the speed change. For more information, see [“Controlling Parameter Changes at Keyframes” on page 133](#).

- b. Click the Edit Graph menu, and select Position to make the Position graph the active control graph.

The Motion Effect Editor displays the graphs for the unaltered clip. In the Position graph, a straight diagonal line stretches from the first keyframe to the last keyframe. Each frame of the input is the same as each output frame, with no variations in speed. The Input Position timecode is the same as the Output Position timecode at each keyframe.

In the Speed graph, a straight line crosses the graph at 100% speed.



2. Click the first keyframe indicator, and note the starting timecode in the Input Position text box.
3. Click the last keyframe indicator, and note the ending timecode in the Input Position text box.


4. Reverse the starting timecode and ending timecode by doing the following:
 - a. Click the first keyframe indicator, and either drag the indicator up the Input Position axis until it is even with the last keyframe indicator, or type the original ending timecode in the Input Position text box.

If you drag, the Input Position text box changes until it reaches the timecode for the last frame of the source. In the Speed graph, the Percent Speed at the left changes until it reaches 0% — with starting and ending timecodes the same, if you played the effect it would be a freeze frame of the last frame.

- b. Click the last keyframe indicator, and either drag it vertically down the graph until the line in the Speed graph reaches -100%, or type the original starting timecode in the Input Position text box.

If you drag, the value in the Input Position text box changes until it reaches the timecode for the first frame of the source.

In the Position graph, a straight line descends across the graph, mapping the effect's starting time to the clip's ending time, and the effect's ending time to the clip's starting time, effectively reversing the clip.



The effect plays back in reverse motion.



5. (Option) Click the Timewarp Effect icon in the Motion Effect Editor, and drag it to a bin to create an effect template with the current parameters.

Understanding FluidMotion Timewarp Effects

The FluidMotion rendering option for Timewarp effect creates very smooth rendered effects. FluidMotion uses an interpolation algorithm that creates intermediate images by morphing the motion across the bracketing images. FluidMotion examines each pixel in the outgoing image, finds the corresponding pixel in the incoming image, and creates a motion path between the two that it uses to build the intermediate images necessary to fill out the effect.



On a Macintosh system, FluidMotion requires significant system resources and rendering times can be very long. In addition, when you step through a sequence with a Timewarp effect, your Avid editing application can take a noticeable amount of time to update the Effect Preview monitor.

FluidMotion can introduce artifacts into the effect, particularly when objects move in front of or behind other objects, move significantly between one frame and the next, or move into the image from outside the frame. FluidMotion Edit provides tools to correct artifacts in a Timewarp effect.

By definition, artifacts appear only in intermediate images that FluidMotion creates. The bracketing images, whether frames or fields of original material, do not have artifacts. You use FluidMotion Edit to make corrections either by incorporating motion information from other parts of the image or clip or by directly manipulating the artifact's motion vectors.

FluidMotion performs motion estimation based on the original source frames. When you use the Effect Editor to edit the motion vectors in a FluidMotion effect, the Timeline changes to a source-frame Timeline. The position indicator under the Record monitor appears green when you are working in a source-frame Timeline.

FluidMotion Workflow

The typical workflow for using FluidMotion effects is as follows:

1. Use the Blended Interpolated rendering option to set up the initial motion effect.

This lets you quickly set up the ramp rates and time curves you want. Blended Interpolated is the closest in quality to FluidMotion but takes less time to render.

For more information, see [“Understanding Timewarp Effects” on page 210](#).

2. Render and play the effect.

For more information, see [“Basics of Effects Rendering” on page 53](#).

3. If you want smoother motion, use the Motion Effect Editor to change the effect to FluidMotion.
4. Render the effect, and look for artifacts in the rendered media.

5. Use the Effect Editor and the Effect Preview monitor to step through the effect to the first frame that contains artifacts.

6. Fix the artifacts on that frame, and render the effect again.

Your Avid editing application renders only the part of the effect that has changed.

7. Determine whether you need to continue to work on the current frame or move on to the next frame.

8. Each time you fix an artifact, render the effect again.

This is often the fastest way to remove all the artifacts.



By fixing the intermediate frame represented by Warp 50% or Color Warp 50%, you are fixing all the intermediate frames in the final result between Image A and Image B.

Using FluidMotion Edit

An artifact occurs when your Avid editing application makes an incorrect estimation about the motion for a region of pixels. FluidMotion Edit provides a variety of methods for dealing with artifacts. In general, you define a region around an artifact and then modify the way FluidMotion creates new material from the source material *within that region*. FluidMotion does not alter the way it creates new material outside defined regions.

FluidMotion Edit uses motion vectors to show the relative speed and direction of a pixel from the outgoing Image A to the incoming Image B. FluidMotion Edit represents motion vectors as arrows and as colors.

Correcting an artifact involves changing the motion vectors that FluidMotion calculates to motion vectors that produce little or no distortion. You can use the following approaches to make corrections:

- Copy the motion vectors from an area of the image that behaves correctly to the defined region, replacing the original motion vectors with the copied motion vectors.
- Copy a correction from one image, and paste it into another to correct multiple artifacts.
- Clear the motion vectors that FluidMotion creates inside a defined region. You can do this by drawing a region and setting the vectors within the region to zero with the Vector X and Vector Y sliders.
- Use the Mask parameter to prevent black borders around the image from affecting the result. Mask defines a border around the edge of the image, shown by a blue wire frame on the Effect Preview monitor.

7 Creating and Customizing Motion Effects

To open FluidMotion Edit:

1. In the Motion Effect Editor, click the Type menu, and then select FluidMotion.


The Edit FluidMotion Vectors button appears in the Motion Effect Editor next to the Type menu.



2. Click the Edit FluidMotion Vectors button.

If your Avid editing application was not in Effect mode, it enters Effect mode and the Effect Editor opens.


FluidMotion Edit appears in the Effect Editor.



For general information on working with the Effect Editor, see [“Using the Effect Editor” on page 89](#).

To view vectors as arrows:

- ▶ In the Display parameter category, select Show Vectors.



Notice the motion vectors around the rope and the child's hand. The length of a vector arrow represents the speed at which a pixel moves between Image A and Image B, and the arrow's orientation shows the direction of motion.

To view vectors as colors:



1. In the Display parameter category, click the Fast Menu button, and select Color Warp 50%.
2. (Option) Deselect Show Vectors to see the color vectors and the underlying image more clearly.



The saturation of a vector color corresponds to speed, and hue corresponds to direction.

To define a region for FluidMotion Edit:



1. In the Display parameter category, click the Fast Menu button, and then select Warp 50% or Color Warp 50%.

Warp 50% shows the image generated by FluidMotion that is halfway between source material Image A and Image B. Color Warp 50% shows the same image, with an overlay of motion vector colors.

2. (Option) Select Show Vectors to display the motion vector arrows.
3. Step through your clip until you reach an image in which you want to make a correction.
4. Select a shape from the drawing tools in the Effect Editor, and draw around the region that has the artifact.

You use the drawing tools in the same way as you would for Intraframe editing. You can copy, move, and modify any shape. For more information, see [“Intraframe Editing” on page 467](#).



Use the Feathering and Brush parameters at any point during the correction process to help define and modify the selected area.

Example of Correcting FluidMotion Artifacts


In this example, a table tennis ball crosses a net. FluidMotion creates one artifact where the ball crosses the net and a second artifact directly above the first at the edge of the table.



Example of FluidMotion artifacts: details of the bracketing images (left and right) and the intermediate image (center) with artifacts created by FluidMotion.

The following illustrations show the vector information in the image as vector arrows and vector colors. The vector displays indicate that there is motion across a large portion of the image.

This example uses vector colors to fix the artifacts.



The artifacts in this example: without vector display (left), with vector arrow display (center), and with vector color display (right).

You can view artifacts by stepping through the effect while keeping the Display Fast menu in the Effect editor set to Warp 50% or Color Warp 50%. This shows the images created at the halfway point between the source images. To view the corresponding source images, change the Display Fast menu to Image A or Image B.

In this example, we fix the artifacts by reducing the amount of motion within the areas where the artifacts occur.


To fix the artifacts:



1. In the Effect Editor, click the Fast Menu button in the Mode parameter category, and select Set Vector.




2. Select the Oval tool, and draw ovals around the areas containing the artifacts.



Your Avid editing application automatically sets the Vector X and Vector Y values to 0 within the new objects. This removes all motion information from within the regions. The artifacts disappear but the image is now a blend of the two bracketing images, so the ball appears extended and dimmer than before.

7 Creating and Customizing Motion Effects




Bracketing images (left and right) with blended intermediate frame (center) after use of the Oval tool.

If you play the effect now, the image of the ball over the net fades out as the image of the ball under the net fades in. We need to add motion information back into the image so we can view the moving ball.

3. Turn on color vector information in the image by doing the following:



- Click the Fast Menu button in the Display parameter category, and select Color Warp 50%.



Color Warp 50% shows movement as chroma (color) and direction and hue (color intensity). The image shows that there is no motion information within the oval.

Some motion along the top of the net shows as yellow in the image. We can use the eyedropper in the Mode parameter category to copy this motion information into the oval.

4. Do the following:

- a. Select the oval shape that you created to make it active.
- b. Press and hold the mouse pointer over the Color Preview window of the Mode parameter category in the Effect Editor.
The pointer changes to an eyedropper.
- c. Drag the eyedropper over the top of the net, and view the changes in the Vector X and Vector Y parameter values. The values change as you drag over an area that contains motion information.




Color Preview window and Vector thumbwheels in the Effect Editor



You can use the eyedropper to view Vector X and Vector Y information in the image even if Color Warp 50% is not enabled.

- d. Release the mouse button over the yellow portion of the top of the net (to the left of the oval).

Your Avid editing application applies the motion information to the oval and the yellow vector color display appears inside the oval.





5. Render the effect, and click the Play Loop button to review the rendered effect.

We need to put some of the motion information back into the image of the ball. One way to do this is to draw an object around the ball that cuts a hole through the oval that we just created and reveals the original motion of the ball.



6. Select the Polygon tool, and draw an object around the blurred image of the ball.

The following illustrations show the result displayed with Color Warp 50% and Warp 50%.




7 Creating and Customizing Motion Effects



7. In the Mode parameter category, click the Fast Menu button, and select Erase.
8. Add some feathering to create a smooth transition between the motion within the polygon and the motion in the oval.

The illustration below shows the result of setting Bias to 92, and both Feathering X and Feathering Y to 5.

For more information, see [“Intraframe Editing” on page 467](#).



9. Render the effect, and play the result.

After you remove the artifact at the Warp 50% position, all intermediate frames between Image A and Image B reflect the change.

Timewarp Preset Effects

The Timewarp effect category contains several preset effects that you apply directly to clips in a sequence. The effects are set up as templates but you can modify them using the Motion Effect editor. The following table describes these effects.

For information on using the FluidFilm templates, see [“FluidFilm Preset Effects” on page 247](#). For details on using the other templates, see [“Timewarp Effects” on page 592](#).

Effect	Description
0% To 100%	Ramps motion in a sequence from 0% (freeze frame) to 100% (full speed).
100% To 0%	Ramps motion in a sequence from 100% (full speed) down to 0% (freeze frame). The last frame of the clip is the last frame of the motion effect.
FluidFilm 2:3 Cadence and FluidFilm Progressive	Let you create a film look from interlaced video sources or a video look from sources originally shot on film.

Effect	Description
Pulldown Insertion and Pulldown Removal	Inserts or removes pulldown in a sequence.
Reverse Motion	Creates a reverse motion effect at 100% speed.
Speed Boost	Creates an effect that starts out at half speed, reaches approximately double speed at the midpoint, and returns to half speed at the end.
Speed Bump	Creates an effect that starts out at full speed, slows to approximately half speed at the midpoint, and returns to full speed at the end.
Trim to Fill	Plays at a constant speed. You can adjust the speed by entering Trim mode and trimming the effect.

FluidFilm Preset Effects

Film footage has specific timing characteristics that you might want to duplicate with video footage. Film timing is different because a film camera records images as full frames while a video camera records individual fields, a fraction of a second apart. The resulting video playback has a very different look from film.

The FluidFilm templates (FluidFilm 2:3 Cadence and FluidFilm Progressive) use the FluidMotion rendering option to create intermediate progressive frames. The result is a motion effect that plays as though it were shot on film. The default speed is 100%.



You can also use the templates as a starting point to create a video look from sources originally shot on film by switching the input and output format values.

Applying a Film Look to a Video Clip

A common scenario involves a show that is shot on film and edited at 30i where you want to incorporate some video clips into the Timeline. You can process the video clips with the FluidFilm template to generate a look similar to the film footage.

Applying a Film Look to an Entire Sequence

You can use the FluidFilm templates to apply a film look to an entire interlaced sequence by doing one of the following:

- Mix down the entire sequence and apply a FluidMotion effect to the resulting master clip.

Your Avid editing application might produce artifacts between the original cuts. If this happens, you can use FluidMotion Edit to set the motion vectors for the entire frame to zero at the cut points. For more information, see [“Understanding FluidMotion Timewarp Effects” on page 238](#).
- Apply the FluidMotion effect to each clip in the sequence.

The 2:3 cadence might be off between adjacent clips depending on whether the clip starts on an A, B, C, or D frame. If this is a problem, use the mixdown method instead.



The FluidMotion rendering option can take a long time to process an entire sequence.

Default Values for the FluidFilm Preset Effects

The FluidFilm Timewarp effect options use the following default values:

Option	Default Value
Source format	Interlaced
Output format	Film with 2:3 Pulldown (for FluidFilm 2:3 Cadence effect) Progressive (for FluidFilm Progressive effect)
Rendering option	FluidMotion

By default, these templates create 100% Timewarp effects (the effect plays at the same speed as the original clip). You can use the Speed and Position controls to change the speed.

Setting Source and Output Options for Format Conversion with Timewarp Effects

You can use the Motion Effect editor to convert formats when creating a Timewarp effect.

You need to match the Source format option to the format of the original source material. For example, if the material was shot on a 30i camera, select Interlaced as the Source format.

If your source material includes repeated progressive frames, such as animation or video from a consumer digital photo camera, select Progressive Repeated as the Source format

In some circumstances, adaptive deinterlacing might improve the image quality of the output.

To set source format and output format options:

1. In the Motion Effect Editor, click the Source menu, and select your source format.

The following table lists the source format and the output format options to use for format conversions. Progressive projects do not allow format conversions.

Project Type	Source media type	Corresponding Source Option	Possible Output Options
30 fps interlaced	30 fps interlaced	Interlaced	Progressive, Film with pulldown
	30 fps progressive	Progressive	Interlaced, Film with pulldown
	30 fps interlaced with 2:3 pulldown	Film with pulldown	Interlaced, Progressive
	Repeated progressive frames	Progressive Repeated	Interlaced, Progressive, Film with pulldown
25 fps interlaced	25 fps interlaced	Interlaced	Progressive
	25 fps progressive	Progressive	Interlaced
	Repeated progressive frames	Progressive Repeated	Interlaced, Progressive

If you select Film with Pulldown as the source format, additional options display that lets you either manually or automatically set the pulldown pattern.

If you select Progressive Repeated as the source format, additional options display that lets you either manually or automatically set the repeated frame count.

2. Click the Output menu, and select an output format.

See the table in step 1 above.

3. (Option) Select Adaptive Deinterlace Source.

For more information, see [“Using Adaptive Deinterlacing” on page 219](#).

4. Click OK.



For best results when performing a format conversion, use the FluidMotion render option and view the resulting footage on a client monitor.

8 Layered and Nested Effects

This chapter describes how to apply multilayer effects to your sequence. Layered effects consist of two or more layers of video that play back simultaneously with effects such as Picture-in-Picture, Superimpose, or Submaster applied to the tracks. Nested effects consist of one or more effect layers that are contained within another effect on the *same* video layer.

The methods for creating multilayer effects that this chapter describes build on the procedures for creating single-layer effects in [“Applying Effects” on page 35](#).

- [Key Effects](#)
- [Working with Imported Graphics and Animation](#)
- [Nesting Effects](#)
- [Submaster Editing](#)
- [Collapsing Layers into a Submaster Effect](#)
- [Performing a Video Mixdown](#)

Key Effects

Your Avid editing application supports the following key effects:

Key Effect Type	Description
Chroma	<p>Replaces one part of the video image with another video image based on color. You have the following options for chroma key effects:</p> <p>The SpectraMatte™ chroma key effect creates a superior quality key and makes it easy to correct common keying problems such as controlling shadows and removing color spill.</p> <p>The Chroma Key and RGB Keyer effects are more basic effects that are supported for backwards compatibility with older versions of Avid editing applications.</p>
Luma	<p>Replaces one part of the video image with another video image based on luminance (brightness). You create a luma key using the Luma Key effect.</p>

Key Effect Type	Description
Matte	Replaces one part of the video image with another video image or graphic based on the location of a high-contrast image known as a matte. You create a matte key using the Matte Key effect or an imported Matte Key clip.

For reference information on all key effects, see [“Key Effects” on page 575](#).

Understanding the SpectraMatte Chroma Key Effect

The SpectraMatte effect provides superior quality keying and makes it easy to fine-tune your keys to solve problems such as controlling shadows and removing color spill. The SpectraMatte effect is available in the Key category of the Effect Palette.

The SpectraMatte effect includes the following main features:

- Analysis displays that provide visual feedback and aid in fine-tuning the key.
- Chrominance controls for precise adjustment of the range of hue and saturation values that the effect keys out.
- Additional luminance-based controls that let you fine-tune alpha values in the key and remove unwanted shadows.
- Matte processing controls that let you blur, erode, or dilate the edges of the alpha matte generated by the effect.
- Spill suppression controls that let you remove reflected key color from a foreground subject.
- Scale, position, and crop controls.
- Advanced keyframes that let you keyframe each effect parameter individually, enabling you to adjust for changes over the duration of a clip.

You apply the SpectraMatte effect to the foreground track of a multilayer segment in the Timeline in the same way that you apply other chroma key effects. For more information, see [“Creating a SpectraMatte Effect” on page 257](#).



The keying capabilities of SpectraMatte are also available in the 3D Warp effect. A SpectraMatte Key option in the Foreground parameter category provides access to the full set of SpectraMatte parameter controls. You might prefer to use SpectraMatte from the 3D Warp effect because 3D Warp uses Hue, Saturation, and Luminance controls to define the key color rather than Red, Green, and Blue controls. For more information, see [“Foreground \(3D\)” on page 710](#).

Understanding SpectraMatte Analysis Displays

The SpectraGraph™ display for the SpectraMatte effect shows how the effect operates on the entire CbCr color space. This helps you see how the effect is working and what further adjustments you might need to make.

You can also display the alpha matte that the effect is generating. This lets you see clearly which pixels from the foreground image are being keyed in or out, and how pixels on the edge of the matte are being blended.

You can display these analysis views in either the Effect Preview monitor or in the Source monitor. If you display them in the Effect Preview monitor, they replace your view of the composite image created by the effect itself until you turn the analysis display off. If you display them in the Source monitor, you can see the analysis and the composite image at the same time.

The SpectraGraph Display

The SpectraGraph display shows a color swatch that represents the entire CbCr color space with which the SpectraMatte effect works. You activate the SpectraGraph display using controls in the Matte Analysis category in the Effect Editor. For more information, see [“Key: SpectraMatte Effect” on page 578](#).

The center point of the swatch is neutral gray while the outer areas show highly saturated color. This representation of color is similar to that in the ChromaWheel color wheels in the Color Correction tool. Hue changes as you move around the swatch and saturation increases as you move away from the center. The following illustration shows this swatch.




The range of colors that the SpectraMatte effect is currently keying out from your foreground image is also keyed out from this swatch, revealing a black background in its place. The range of colors that the effect is currently retaining from the foreground image

8 Layered and Nested Effects

appears as fully opaque color. The range of colors that the effect is currently blending between foreground and background appears as partially transparent color. For more information on how the effect calculates these color ranges based on your input, see [“How the SpectraMatte Effect Calculates Key Color Values”](#) on page 255.

Superimposed on the color swatch is a vectorscope-style display that shows the distribution of color values in the foreground image. This typically shows a concentration of either green or blue color values that represent the background screen colors you want to key out, along with the distribution of other color values from the foreground subject that you want to retain.



Example of a SpectraGraph display for an image where the key color is green. The area outlined in white shows the range of colors that are currently keyed out and replaced by background pixels. The area outlined in black shows the range of colors that are being retained from the foreground image. The gradient between the two outlined areas shows the range of values that are currently a blend of foreground and background pixels. The superimposed color data shows the distribution of color in the foreground image (a subject shot in front of a green screen).

The SpectraGraph display lets you clearly see the relationship between the current result of the key and the color values in your image. In the preceding illustration, you can see that many of the green color values in the superimposed color display are still at least partially included in the key. Knowing this, you can make further parameter adjustments that remove these values more completely from the key. By viewing both the SpectraGraph display and the standard view of the composited images, you get all the information you need to produce a high-quality key.


The Alpha Matte Display

The alpha matte display shows the alpha matte that the SpectraMatte effect is currently generating. This matte is used to create the final composite of foreground and background images. You activate the alpha matte display using controls in the Matte Analysis category in the Effect Editor. For more information, see [“Key: SpectraMatte Effect”](#) on page 578.

The alpha matte display is particularly useful for checking and adjusting how foreground and background pixels are being blended at the edges of the matte. Refining this blend is often important to create a natural-looking composite of foreground and background.

As you adjust parameter controls that affect the position and extent of the blend, the alpha matte display updates to show the result of your adjustments.

The following illustration shows a typical alpha matte display.



How the SpectraMatte Effect Calculates Key Color Values

The SpectraMatte effect calculates a range of color values that are either completely or partially keyed out from the foreground image. In the SpectraGraph display, this range of color appears as a wedge with blended edges in the CbCr color swatch. The effect generates an alpha matte based on these values, then uses this matte to create the final composite.


The shape and design of the wedge is a good model for calculating key color values because it automatically keys out a relatively wide range of high-saturation color values in the region of the key color. These are the kinds of color values that should always require keying out of well-shot key footage and that you should not normally need to blend or adjust. The wedge also provides very precise control over lower saturation color values and hue color values that fall on the borderline between those you want to key out and those you want to retain. These are the kinds of color values that you often need to blend or fine-tune, for example, to improve the edges of the foreground subject in a key shot.

This topic explains how the SpectraMatte effect calculates the key color wedge from some of the main parameter values you set. For detailed information about all of the SpectraMatte effect's parameters, see [“Key: SpectraMatte Effect” on page 578](#).

8 Layered and Nested Effects

The basic size and position of the wedge is defined by the following parameters:

- The hue set by the Key Color parameters defines the position of the wedge around the swatch. In the following illustration, the key color is green, so the wedge falls in the green part of the swatch.
- The saturation value set by the Chroma Control Key Saturation parameter defines the location of the center point of the wedge. The illustration shows the effect of the default Key Saturation value (0), so the point of the wedge is at the exact center of the swatch. You can move the wedge out from the center of the swatch by increasing the Key Saturation value.
- The angle set by the Chroma Control Tolerance parameter defines the width or spread of the wedge. The illustration shows the effect of the default Tolerance value (90 degrees), so the wedge is 90 degrees wide, 45 degrees on either side of the line between the Key Saturation value and the Key Color value.



The Key Color wedge in the SpectraGraph display. The white point at the center is the point defined by the Key Saturation parameter. The white point within the wedge is the point defined by the Key Color parameter. The marked angle is the angle defined by the Tolerance parameter.

Many of the other parameters modify how this basic key color wedge is calculated. For example, the Key Saturation Line parameter reshapes the wedge near the center of the swatch so that it retains a wider range of low-saturation color values from the foreground image. Several parameters affect how the blend gradient is calculated (its position and its width on the wedge), which results in changes to how foreground and background pixels blend in the final composite.

Creating a SpectraMatte Effect

To create a SpectraMatte Key effect:

1. Create a sequence with two video layers.

For information about editing a sequence, see “Creating and Editing Sequences” in the Help.

2. Edit the background image onto track V1 and the foreground image onto track V2.
3. Enter Effect mode, for example, by selecting Toolset > Effects Editing.

For more information, see [“Entering Effect Mode” on page 41](#).

4. In the Effect Palette, click the Key category.




5. Drag the SpectraMatte icon from the Effect Palette to the clip on track V2.

Your Avid editing application adds the SpectraMatte Key effect.


6. Move the position indicator to the segment containing the effect in the Timeline.

The Effect Editor displays parameters for adjusting the SpectraMatte effect. The effect uses advanced keyframes.



8 Layered and Nested Effects

- Click the Color Preview window in the Key Color parameter category to display the Eyedropper icon, and then drag the eyedropper to a representative region of the blue or green background screen in the Record monitor.



Your Avid editing application selects the primary key color, and the key takes effect.



- Fine-tune the key by enabling and adjusting additional parameter categories as necessary.

This example uses the following adjustments to improve the edges of the key:

- Increase the Spill Angle Offset value
- In the Matte Processing parameter category, use the Erode matte Blur type and add a small amount of Matte Blur
- In the Chroma Control parameter category, increase the Inner Softness value

You can achieve similar results using different parameter combinations. For more information, see [“Understanding the SpectraMatte Chroma Key Effect” on page 252](#).

While adjusting the colors and matte, use the analysis displays as described in [“Understanding SpectraMatte Analysis Displays” on page 253](#). For more information on specific parameters, see [“Key: SpectraMatte Effect” on page 578](#).

Understanding the Chroma Key Effect and the RGB Keyer Effect

The Chroma Key and RGB Keyer effects do not create as high a quality key as the SpectraMatte effect. However, they provide backwards compatibility with older Avid editing applications.

If you are moving sequences between different versions of Avid editing applications, use the Chroma Key or RGB Keyer effect. Otherwise, try the higher quality SpectraMatte effect.



You can promote a Chroma Key effect to the SpectraMatte effect. For more information, see “Promoting a Chroma Key Effect to the SpectraMatte Effect” on page 262.


The Chroma Key effect and the RGB Keyer effect are typically used with a foreground image shot in front of a highly saturated color screen that is keyed against a background image.

This topic explains the basic differences between these color-based key effect options. For information on creating color-based key effects, see “Creating a Chroma Key Effect or RGB Keyer Effect” on page 260.

Chroma Key Effect

The Chroma Key effect includes several standard effect parameters such as scaling, position, and crop in addition to key control parameters. You can also promote the Chroma Key effect to 3D for additional adjustments to various 3D parameters such as skew, perspective, and spline-based motion.

Use the Chroma Key effect when you want to work in real time, or when you need to adjust various parameters of the foreground chroma key footage.



Chroma Key effect example: the original key (left), and the key after promoting to 3D, repositioning, and applying defocus to enhance the effect of perspective between foreground and background

RGB Keyer Effect

The RGB Keyer effect is a non-real-time plug-in effect that includes additional parameters for fine-tuning the edges of the key and for applying *post-key color correction* (correction applied to the foreground image without affecting the key itself). You cannot promote the RGB Keyer effect to 3D.

Because the foreground and background elements of a chroma key are often shot at different times and locations, post-key color correction is especially useful for maintaining the key while matching the visual characteristics of the foreground elements to the background footage.

Use the RGB Keyer when working with full-screen chroma key footage that does not require parameter adjustments such as repositioning or scaling, or when you need the RGB Keyer's post-key color correction capabilities to better match the foreground to the background.

Creating a Chroma Key Effect or RGB Keyer Effect

To create a Chroma Key effect:

1. Create a sequence with two video layers.


For information about editing a sequence, see “Creating and Editing Sequences” in the Help.

2. Edit the background image onto track V1 and the foreground image onto track V2.
3. In the Effect Palette, click the Key category.



4. Drag either the Chroma Key Effect icon or the RGB Keyer icon from the Effect Palette to the clip on track V2.

The following example shows the Chroma Key effect applied to V2.



Your Avid editing application adds the Chroma Key effect. Ultimatte® blue is the default key color.

5. Move the position indicator to the segment containing the effect in the Timeline.
6. Enter Effect mode, for example, by selecting Toolset > Effects Editing.

For more information, see [“Entering Effect Mode” on page 41](#).

The Effect Editor displays parameters for adjusting the effect.


7. Open the Key parameter category (Chroma Key effect) or the Key Color parameter category (RGB Keyer).

Ultimatte blue is selected by default. To match the key color more closely to the color of the background screen used in the footage, proceed with the following step.

8. (Option) Click the Color Preview window in the Key or Key Color parameter category to display the Eyedropper icon, and then drag the eyedropper to a representative region of the blue or green background screen in the Record monitor.



Your Avid editing application selects the primary key color, and the key takes effect.



9. Fine-tune the key by enabling additional parameter categories and then adjusting parameters as necessary.

For more information on specific parameters, see the reference information in [“Key Effects” on page 575](#).

10. (Option) Perform post-key color correction by adjusting the hue, saturation, and value of the foreground elements using the Color Correction parameters in the Effect Editor.

For more information on the specific parameters, see the reference information in [“Key: RGB Keyer” on page 578](#).

Promoting a Chroma Key Effect to the SpectraMatte Effect

You can promote a Chroma Key effect to the SpectraMatte effect. Because of the differences in the way the two effects work, existing parameter adjustments in the Chroma Key effect might not all move forward to the SpectraMatte effect. The primary key color does always move forward correctly to the SpectraMatte effect.

To promote a Chroma Key effect to the SpectraMatte effect:



- ▶ Click the Promote to SpectraMatte button in the bottom right of the Effect Editor for the Chroma Key effect.

Creating a Luma Key Effect

Use a Luma Key effect to replace portions of the foreground video with the background video based on brightness or luminance.

To create a Luma Key effect:

1. Create a sequence with two video layers.

For information about editing a sequence, see “Creating and Editing Sequences” in the Help.

2. Edit the background image onto track V1 and the foreground image onto track V2.
3. In the Effect Palette, click the Key category.



4. Drag the Luma Key Effect icon from the Effect Palette to the segment on track V2.
5. In the Timeline, move the position indicator to the segment with the Luma Key effect.
6. Enter Effect mode, for example, by selecting Toolset > Effects Editing.

For more information, see [“Entering Effect Mode” on page 41](#).

The Luma Key parameters appear in the Effect Editor.

7. Use the eyedropper or the Luma Key sliders to select a brightness value in the foreground video.

Your Avid editing application replaces the corresponding portions of the foreground video with background video.

For information on all Luma Key parameters, see [“Key: Luma Key” on page 577](#).

Creating a Matte Key Effect

A Matte Key effect replaces one part of the video image with another video image or graphic based on the location of a high-contrast image known as a matte.

The Matte Key effect uses three layers of video to create the effect. The bottom layer is the background image, the middle layer is the foreground image, and the top layer contains the matte or alpha channel.

To create a Matte Key effect:

1. Create a sequence with three video layers.

For information about editing a sequence, see “Creating and Editing Sequences” in the Help.

2. Edit the background image onto track V1 and the foreground image onto track V3.
3. Load a high-contrast image into the Source monitor, and edit it onto track V3.

The high-contrast image can be an imported graphic or a clip that you adjust within your Avid editing application.



If the image is not high enough in contrast, you can adjust the contrast by applying the Color Effect, and then adjusting its parameters in Effect mode. For more information, see “Using the Color Effect to Prepare a High-Contrast Image” on page 265.

4. In the Effect Palette, click the Key category.

5. Apply the Matte Key effect as follows:



- ▶ If your high-contrast image was created with the Color Effect, press and hold the Alt key (Windows) or Option key (Macintosh) and drag the Matte Key Effect icon from the Effect Palette onto the segment on track V3 to nest the Color Effect within the Matte Key effect.
- ▶ If your high-contrast image on track V3 does not include a Color Effect, drag the Matte Key Effect icon from the Effect Palette onto the segment on track V3.

6. Click the Record Track Monitor button for track V3 in the Track Selector panel.



Tracks V2 and V1 become visible through the high-contrast image on track V3.

7. Move the position indicator to the Matte Key effect, and render the effect.

For more information, see “Basics of Effects Rendering” on page 53.



For information on Matte keys and Matte Key parameters, see “Using Matte Keys with 3D Effects” on page 364 and “Key: Matte Key” on page 577.

Working with Real-Time Moving Mattes

If you import a moving matte as a 32-bit QuickTime file or a graphic sequence, your Avid editing application handles the effect in real time. Your Avid editing application treats a QuickTime file with embedded alpha as a moving matte if it has more than one frame.

The basic procedure for importing a moving matte is described in “Importing Files” in the Help.

You should be aware of the following when editing with real-time moving mattes:

- You can promote a real-time Matte Key effect to a 3D Warp effect, and use the 3D manipulation parameters.
- If the Matte Key effect is not on the top video track of a multilayered composite, you must render it before it can play in real time.
- If you add a motion effect to the matte and foreground, the effect does not play in real time until you render the motion effect.
- Real-time moving mattes cannot be combined with real-time titles without rendering the effect.
- Moving mattes in a 24p or 25p project play in real time in their native format only. You must render moving mattes in order to output the sequence in alternate formats when using the Digital Cut tool. For example, a moving matte imported into a 24p NTSC project does not play back to the PAL format on output unless you render it first.

To import a QuickTime file as a moving matte:

1. Click the Image tab of the Import Settings dialog box.
2. In the Alpha parameter category, select either Use Existing or Invert Existing.

To import a graphics sequence as a moving matte:

1. Select the first file in the sequence as the file to import.
2. In the Image tab of the Import Settings dialog box, select Autodetect Sequential Files.

Your Avid editing application uses all the files in the sequence to make the moving matte. If you import only one graphic file with alpha, it becomes a static matte.

Your Avid editing application creates a real-time Matte Key effect with nested alpha and video fill. To preserve real-time performance, your Avid editing application locks the alpha track so that you cannot replace it.

Using the Color Effect to Prepare a High-Contrast Image

This topic describes how to enhance high-contrast images for use in creating Matte Key effects. You can also import a graphic image with an alpha channel and use it as a Matte Key effect. For more information, see [“Working with Imported Graphics and Animation” on page 265](#).

To create a high-contrast image from available footage:

1. Apply the Color Effect to the clip.
For more information, see [“Applying Effects” on page 35](#).
2. Enter Effect mode, for example, by selecting Toolset > Effects Editing.
For more information, see [“Entering Effect Mode” on page 41](#).
3. Change the Luma Range to 0 to 255.
4. Drag the Sat (saturation) slider under Chroma Adjust all the way down to remove all color saturation from the image.
5. Adjust the Gamma to change the color of the midtones.
You can now use the high-contrast image as a matte for the key effect, as described in [“Creating a Matte Key Effect” on page 262](#).
6. (Option) Black portions of the high-contrast image are transparent and white portions are opaque. To switch the order, use the Reverse option in the Foreground parameter category of the Matte Key effect.

Working with Imported Graphics and Animation

This topic describes two different methods for editing with imported graphic images, depending upon whether:


- The image was imported as a master clip with no alpha channel (an opaque graphic element).
- The image was imported as a Matte Key clip with an alpha channel (a keyable graphic element for video overlay).

Both single-frame graphic images (such as a single JPEG file) and multiple-frame animation sequences (such as a JPEG file sequence) appear in the bin in the same form after import, and you use the same editing techniques for both. You can edit this type of clip into a sequence as a standard matte key overlay.



Only single-frame files can be used as real-time keyed graphics. PICT sequences, QuickTime files, PICS animation files, and ERIMovie files cannot be used as real-time keyed graphics.

8 Layered and Nested Effects



Imported graphics in a bin: graphic master clip with no alpha channel (top), and Matte Key Effect clip with alpha channel (bottom)

These alternatives apply to both single-frame graphic images and animation. You can also edit imported images into sequences by using standard Avid editing application effects.



(Windows only) AVI files cannot be imported with an alpha channel. To import animation with an alpha channel, you must use another supported format. For more information on importing graphic and animation clips, see “Importing Files” in the Help.

To edit an imported master clip into the sequence:

1. Create the sequence, and then load a graphic clip into the Source monitor.
For information about editing a sequence, see “Creating and Editing Sequences” in the Help.
2. In the Source monitor, mark an IN point at the start of the clip and an OUT point to specify the duration of the graphic.
3. In the sequence, mark an IN point where you want the graphic clip to begin.
4. Click the Source Track and Record Track buttons.
5. Click the Splice-in button or the Overwrite button to add the opaque graphic to the sequence.



Splice-in button (left) and Overwrite button (right)

The opaque image appears in the sequence. In the Timeline, the graphic looks like a standard video clip edited into the sequence.

6. Play the clip by using the standard playback procedures.

To edit a Matte Key clip into the sequence:

1. Edit the main video sequence.
2. Add a new track above the tracks in the sequence by selecting Clip > New Video Track.



You must edit Matte Key clips onto an upper track to achieve the keying effect. If you edit a Matte Key clip onto track V1, for example, the image is keyed over black unless track V1 contains nested tracks.

3. Play the sequence, and mark an IN point and an OUT point where you want to overlay the graphic.
4. Load a Matte Key clip into the Source monitor. Mark an IN point toward the center of the clip if it is a still.

For information about editing a sequence, see “Creating and Editing Sequences” in the Help.

5. In the Track Selector panel, click the V1 Source Track button and drag it to the Record Track button for the new track to patch the video from track V1 of the Source monitor to the track in the sequence that will receive the Matte Key clip.



Track Selector panel before (left) and after (right) patching Source V1 to Record V2



6. Click the Overwrite button to edit the matte key into the sequence.

Your Avid editing application keys the graphic over the video on the lower tracks.

7. Adjust effect parameters in the Effect Editor, if necessary, using procedures described in [“Using the Effect Editor” on page 89](#).
8. (Option) If the keyed portions of the images are the reverse of the intended effect, open the Foreground parameter category and click the Invert Key button.

For more information, see the reference information in [“Foreground” on page 609](#).


9. Use standard effect editing procedures to preview, render, or play the Matte Key clip.

To see the complete effect, make sure the Record Track Monitor button for the topmost track is selected in the Track Selector panel.

Nesting Effects

You can place effect tracks inside one another to better combine multiple images and effects. This involves a process known as *nesting*, which lets you use the Timeline to *step into* a track, perform a series of editing operations, and then *step out* to view and render the effect as one segment on the track.

8 Layered and Nested Effects



Example of nested layers in a Timeline. Tracks 1.1, 1.2, and 1.3 hold effects nested inside the Submaster effect on track V1. Tracks 2.1 and 2.2 are additional nested layers inside the first nest.

Depending on the model of your Avid editing application, you can edit up to 24 video track layers, and you can additionally nest (stack inside) up to 24 more video tracks within each layer. You can step into each video track indefinitely, constrained only by your Avid system's memory.

You can use nesting when you want to create layered effects. The nested layers are treated as one element during the transition.

Transition effects themselves, such as dissolves, fades, and wipes, are not multilayered, so nesting is not applicable to transition effects. Nesting is also not applicable to audio tracks.

Nested effects have the same playback capabilities and constraints as any other effects that you apply to a sequence. However, because of the complexity you create when you layer effects in nests, nested effects are a good example of a situation where you might need to render or change video display settings to achieve acceptable playback.



Some effects do not work well together when nested. For example, you cannot use the Box Wipe effect and Edge Wipe effect together in a nested segment because the two effects are competing to establish the shape of the wipe.

Another use of nesting is to constrain one effect using another effect. For example, you can use the Circle Shape Wipe effect to constrain an image posterization inside a region.

All nested effects on a segment are fully available when they use advanced keyframes. You can open and manipulate the available parameter and keyframe graphs for any nested effect at any time.



Nested effects do not appear in edit decision lists (EDLs) because they are not supported by linear tape-based edit controllers.

Stepping Into and Out of Nested Effects

You can step into an existing nested effect for editing. When you step into the effect, your Avid editing application replaces the full sequence in the Timeline with just the tracks that make up the nested effect. You can then add new tracks, monitor individual tracks, edit source material into the tracks, and apply and adjust effects on the nested tracks. You can step into any segment effect in this way.



You can also expand nested effects while leaving the rest of the sequence visible in the Timeline. See “Expanding Nested Effects in the Timeline” on page 269.



When you step into a nested effect, a number appears with the letter N in the Timecode button. This number represents the level of nesting that you are currently in. For example, N2 indicates that you are two levels in from the outermost track level.

To step into a nested effect:



- ▶ Click the Step In button.

To step out of a nested effect:



- ▶ Click the Step Out button.



The Step In and Step Out buttons appear by default in the Timeline top toolbar, and are also available in the Command palette.

Expanding Nested Effects in the Timeline

You can expand an existing nested effect for editing within the Timeline. You can then add new tracks, edit source material into the tracks, and apply and adjust effects on the nested tracks. You can expand any segment effect in this way.



You cannot monitor individual tracks when you expand nested tracks in the Timeline. To monitor individual tracks within a nested effect, see “Stepping Into and Out of Nested Effects” on page 269.

To expand a nested effect, do one of the following:

- ▶ In Effect mode, double-click the nested effect.
- ▶ In Source/Record mode (editing mode in NewsCutter), click one of the segment tools on the Timeline palette, and then double-click the nested effect.

8 Layered and Nested Effects



Segment tools in the Timeline palette

The nested tracks appear in the Timeline above the track you double-clicked. Editing and patching features are available for changing the content of the track's effect.

To step out of the nested effect

- ▶ Double-click the effect's icon in the Timeline.

Creating a Simple Nested Effect

This example involves nesting a sequence of clips with dissolves inside another segment effect.

To create the nest:

1. Create a sequence and add a segment effect.

For information about editing a sequence, see “Creating and Editing Sequences” in the Help.




2. Click one of the segment tools on the Timeline palette, and then double-click the segment.




Segment tools in the Timeline palette

The segment opens to reveal the nested tracks.



3. Edit new footage into the nested tracks, and apply additional effects as necessary.

In this example, a series of clips is edited onto nested track 1.2, with dissolves applied between the shots. The 3D Picture-in-Picture effect applies to the entire nested dissolve sequence.




4. Double-click the main track for the nested effect (V2 in this example) to close the nested tracks again.



Nested Effects in the Effect Editor

Nested effects on a segment are fully available in the Effect Editor if the effects use advanced keyframes. You can open and manipulate the available parameters and keyframe graphs for any nested effect at any time. For example, if you have a Picture-in-Picture effect with a Color Correction effect nested inside it, you can see both effects and their parameters in the Effect Editor, as shown in the following illustration.

8 Layered and Nested Effects



Foreground and nested effect in the Timeline (top) and in the Effect Editor (bottom)


If you have nested standard keyframe effects in a sequence, the Effect Editor shows only one effect at a time. If you have a mix of standard keyframe and advanced keyframe effects in a nest, effects below the standard keyframe do not show in the Effect Editor unless you step into the nest.

Changing the Order of Nested Effects

You can change the order of most nested effects in the Effect Editor.

To change the order of nested effects:


- ▶ Drag the effect icon for the effect you want to move to the position you want it to occupy in the nest.



Before (left), during (center), and after changing the order of nested effects. In this example, the SubCap effect is moved above the Color Effect and Flop effects.

If you attempt a change in order that is not possible, a message box opens that explains why you cannot make the change. For example, you cannot change the order of nested effects if the result would not provide enough video inputs for the effect.

When you release the mouse button, the order of the effects changes in the Effect Editor and in the Timeline. Changes to the appearance of the image appear in the Effect Preview monitor. For example, the following illustration shows the results of changing the order of a Flip effect and a Subcap effect.



A simple example of changing the order of nested effects. In the original order, the SubCap effect is nested inside the Flip, so the text in the image is reversed. Changing the order of the two effects in the Effect Editor corrects the problem.

Nesting a Matte Key Effect

A Matte Key effect uses three layers of video to create the effect.

To nest a Matte Key effect:

1. Create a sequence with the background video on track V1.
For information about editing a sequence, see “Creating and Editing Sequences” in the Help.
2. Load a high-contrast image into the Source monitor, and edit it onto track V2.
For an example of a high-contrast image, see “Key: Matte Key” on page 577.

8 Layered and Nested Effects



3. In the Effect Palette, click the Key category.



4. Drag the Matte Key Effect icon from the Effect Palette to the segment on track V2.


5. Click one of the segment tools on the Timeline palette.



Segment tools in the Timeline palette

6. Double-click the Matte Key Effect icon in the segment.

The Timeline expands to display three nested tracks (1.1, 1.2, and 1.3).



By default, nested track 1.3 contains the same image segment as track V2. Nested track 1.2 is empty (foreground filler track). Nested track 1.1 (background video) is also empty.

7. Click one of the segment tools again to stop segment editing so you can edit the tracks.

8. Edit the foreground image onto nested track 1.1.



9. Click one of the segment tools on the Timeline palette, and double-click track V2 to collapse the nested tracks.
10. Click the Record Track Monitor button for track V2 in the Track Selector panel.



Tracks V1 and nested track 1.1 become visible through the high-contrast image on track 1.3.

For information on Matte Key parameters, see [“Key: Matte Key” on page 577](#).

Submaster Editing

The Submaster effect is a single-track segment effect, available in the Image category of the Effect Palette. You can apply the Submaster effect to a track above layered or nested effects and then render only the Submaster. Your Avid editing application renders the composite result of all tracks into the top track. Rendering a Submaster effect saves the new Submaster clip to the drive as a single media file. However, your Avid editing application leaves each element that makes up the composite untouched, so you can still manipulate any element.

The Submaster effect is useful when you want to play back bandwidth-limited sequences, such as sequences composed of several seconds of single-frame clips. It is much faster to use the Submaster effect than to use methods such as applying a graphic, or using a Picture-in-Picture, Mask, or Resize effect. Normally, Submaster effects render at about the same rate as motion effects.

The Submaster effect maintains links to the original media files, so you should not delete the original media files. If you want to combine tracks to create a sequence that is independent from the original media files, perform a video mixdown. For more information, see [“Performing a Video Mixdown” on page 278](#).

8 Layered and Nested Effects

The Submaster effect does not render each track separately, so you cannot play each track individually, and the blue dot remains in the effect icon. If you delete or modify a track below a Submaster effect, the Submaster effect becomes unrendered.




You can nest up to 24 tracks inside a Submaster effect depending on the model of your Avid editing application.

An edit decision list (EDL) for a sequence that contains a Submaster effect represents the contents of the Submaster effect as a single cut. To work around this, you can create a new sequence with the contents of the Submaster effect and generate a separate EDL for that sequence.

To apply the Submaster effect to a multilayered sequence:


1. Select Clip > New Video Track.
2. On the new video track, create one add edit before and another after the group of clips to be submastered.



Add edits on track V5 bracket a group of clips on V4

For more information on add edits, see “Working with Add Edits (Match Frames)” in the Help.

3. In the Effect Palette, click the Image category.
 4. Drag the Submaster Effect icon to the space between the add edits you created in step 2.
- Your Avid editing application applies the effect above the layers.



Submaster effect on track V5

5. Render the Submaster effect, as described in “Basics of Effects Rendering” on page 53.

To apply the Submaster effect to multiple short clips:

1. Select Clip > New Video Track.
2. On the new video track, create one add edit before and another after the group of clips.
For more information on add edits, see “Working with Add Edits (Match Frames)” in the Help.
3. In the Effect Palette, click the Image category.
4. Drag the Submaster Effect icon to the space between the add edits you created in step 2.



5. Render the Submaster effect, as described in “Basics of Effects Rendering” on page 53.

Collapsing Layers into a Submaster Effect

The Collapse feature lets you build your effect at the topmost level. When you are finished, you collapse the layers automatically into one Submaster effect. This is useful for simplifying a sequence with complex compositing. After you collapse a complex composite, you can easily add transition effects to the start and end of the resulting Submaster effect.



You can also use the Collapse feature to simplify the deletion of multilayer segment effects. After collapsing the effects, you can select the resulting segment and press the Delete key twice to delete the effect and all the layers.

After your Avid editing application collapses tracks into a Submaster effect, it recognizes a Submaster effect as a multilayer effect instead of a single-layer effect. This lets you add chroma keys and other multilayer effects to the nested tracks within a Submaster effect.



You can drag “two-channel” effects (such as chroma keys) onto Submaster effects if the Submaster segment contains two or more nested tracks. This is useful after performing a Collapse operation to composite the new Submaster effect over another background.

To collapse layers into a submaster effect:

1. Select all the tracks you want to collapse.
The tracks must be adjacent.
2. Mark an IN point and an OUT point around the area you want to collapse.
3. Click the Collapse button.



8 Layered and Nested Effects

Depending on the model of your Avid editing application, the Collapse button might appear by default in the Timeline top toolbar or in the Tool palette. It is also available from the Command palette.

Your Avid editing application collapses the tracks into a Submaster effect on a single track.

To open the nested tracks again:

1. Click one of the segment tools on the Timeline palette.



Segment tools in the Timeline palette

2. Double-click the Submaster effect.

To collapse a sequence (alternative procedure):

1. Click one of the segment tools on the Timeline palette.



Segment tools in the Timeline palette

2. Select the segments you want to collapse.



3. Click the Collapse button.

Performing a Video Mixdown

Video mixdown lets you combine several tracks into a new master clip. You can use video mixdown after you finish building your sequence and want to make it into one piece (for example, a standard opening to a program).

Video mixdown is useful when you want to:

- Create a complex sequence you need to use repeatedly.
- Add a motion effect to an entire sequence.
- Finalize a complex sequence before consolidating, exporting, or transferring.



For information to prepare a RED clip for a video mixdown, see “Preparing your Red Clip for Transcode, Mixdown or Render” in the Help.

Video mixdown is similar to the Collapse feature, but the end result is different:

- With the Collapse feature, you collapse the tracks into a Submaster effect. After you collapse the tracks, you are still able to step in to the Submaster effect and work on the individual elements.
- With video mixdown, your end result is a new master clip made up of all the tracks you built on different layers. Those tracks become one clip. You cannot separate the tracks to work on them or step in to the sequence.


For more information on the Collapse feature, see [“Collapsing Layers into a Submaster Effect” on page 277](#).



You cannot generate an edit decision list (EDL) for a sequence that contains a video mixdown. To work around this, you can either remove the video mixdown or maintain a version of the sequence that does not contain a video mixdown.

To perform a video mixdown:

1. Select the Record Track Monitor button in the Track Selector panel for the highest track you want to include in the video mixdown.



Video Mixdown collapses the selected track and all tracks under it. If you want to perform a video mixdown of only one track, select the track for solo monitoring by Ctrl+clicking (Windows) or Shift+clicking (Macintosh) the Record Track Monitor button. For more information, see “Patching Tracks” in the Help.

2. Mark an IN point and an OUT point around the area to mix down.
3. Select Special > Video Mixdown (or Clip > Video Mixdown on NewsCutter systems).
The Video Mixdown dialog box opens.

8 Layered and Nested Effects

4. Select a target bin, target drive, and resolution for storing the new master clip, and then click OK.

A progress indicator appears. When the video mixdown finishes, a new clip appears in the bin along with the sequence, and a new media file is created on the target drive.



If your sequence includes a data track, the data track will not mixdown with the video tracks.

9 Working with Camera Effects

This chapter describes effects that control aspect ratio, format, or apparent camera motion in a clip.

- [Using the Reformat Effects](#)
- [Working with the Pan and Scan Effect](#)
- [Using Avid Pan & Zoom](#)



You can also use the Stabilize and Region Stabilize effects to alter the apparent camera motion in a clip in order to eliminate unwanted camera motion. For more information, see “[Motion Tracking and Stabilization](#)” on page 307.

Using the Reformat Effects

You use Reformat effects to reformat media to different aspect ratios, such as when you need to reformat a film aspect ratio for television programming or combine 4:3 legacy media into a 16:9 master.

One of these effects, Pan and Scan, usually works as a vertical effect that you apply to a layer above the rest of your video material and that affects all the video material beneath it. For more information, see “[Working with the Pan and Scan Effect](#)” on page 282.



Reformat effect example: original footage (left) and image after applying the 16:9 Letterbox effect (right)



A Reformat effect works on all tracks below the track to which you apply it. For example, if you apply the effect above a title track, the titles become reformatted as well. If you do not want to reformat the titles, apply the effect below the title track.

The following table describes the three Reformat effects, other than Pan and Scan, that reformat media to new aspect ratios. For reference information on these effects, see [“Reformat Effects” on page 586](#).

Effect	Description
16:9 Letterbox	Scales the image vertically to the 16:9 aspect ratio within a 4:3 frame. Works on 16:9 Anamorphic media.
14:9 Letterbox	Reformats media to the 14:9 Letterbox aspect ratio with a black band at the top and bottom. The effect expands the media horizontally by a fixed amount before scaling it down vertically, resulting in a slight horizontal cropping of the image. You control what part of the image is cropped with the Position slider.
4:3 Sidebar	Reformats 4:3 source media to the 16:9 Anamorphic aspect ratio by scaling down the media horizontally and applying a black band to the left and right sides of the image.

Working with the Pan and Scan Effect

Pan and Scan lets you select a portion of the media to reformat and provides other parameters.

Pan and Scan also supports conversion of 15:9 Anamorphic source media to 16:9 Anamorphic. For more information, see [“Selecting the Source and Target Aspect Ratios for the Pan and Scan Effect” on page 284](#).



If you use the Pan and Scan effect and another Reformat effect on the same sequence, you must render one of the effects before the sequence can play in real time. For more information on other Reformat effects, see [“Using the Reformat Effects” on page 281](#).

Understanding the Pan and Scan Effect

Pan and Scan is a technique for reformatting media to different aspect ratios. The most widespread use of this technique is for reformatting television programming, for example, when you need to convert 16:9 Anamorphic material to the 4:3 aspect ratio. By selecting a portion of each frame in your media for output, you reformat without distorting the media. Traditionally, this selection process, known as Pan and Scan, is done in a telecine room during film-to-tape transfer.

The Pan and Scan effect lets you pan across your media and select what portion of the media you want to retain for output. If necessary, you can use keyframes to adjust the effect.

You can use Pan and Scan on any type of project.



Pan and Scan example: original media with the Pan and Scan wireframe in 16:9 mode (left), and results of the Pan and Scan effect in 4:3 mode (right)

Outputting Media with the Pan and Scan Effect

You can output media with the Pan and Scan effect in two video formats: 4:3 or 16:9 Anamorphic. The Pan and Scan effect does not generate data for inclusion in cut lists created with Avid FilmScribe. If your target is not video, or if your source requires excessive scaling, you can preview the reformatting operation, but the Pan and Scan effect does not automate a film-to-film or a film-to-tape transfer.

Positioning the Pan and Scan Track

When your sequence does not contain titles, the Pan and Scan track is typically the top track. When you have titles, you can place the Pan and Scan track above a title track to scale the title along with the video tracks beneath it. If you need to pan, however, the pan applies to the title as well as the other video tracks. Since this technique results in the title being panned, the results might not be what you want.

If you need to pan your footage and the title aspect ratio is not critical, you can move the titles above the Pan and Scan track. If the title aspect ratio is important, you might need to create a new title in your target aspect ratio.




When you place the Pan and Scan effect below multiformat titles, you might not see the titles with the correct Target aspect ratio as you work. For example, if you are reformatting from 4:3 to 16:9, titles appear distorted in the Client monitor. When you output the sequence at 16:9 by using the Digital Cut tool, select the 16:9 aspect ratio and the titles are sized correctly during the digital cut.

Applying the Pan and Scan Effect

Because the Pan and Scan effect controls the aspect ratio of your final output, you must apply the effect to your entire sequence. Apply the Pan and Scan effect to its own video track after you finish editing the sequence.

 You might want to place a Pan and Scan effect directly on a video segment. For more information, see [“Combining the Pan and Scan Effect with Transition Effects” on page 292.](#)

 If you apply the Pan and Scan effect and then add a segment to or remove a segment from your sequence, the Pan and Scan effect does not automatically adjust to cover the entire segment. You can either trim the Pan and Scan effect manually, or remove the Pan and Scan effect and insert a fresh effect.

To apply the Pan and Scan effect:

1. After you finish editing your sequence, press Ctrl+Y (Windows) or Command+Y (Macintosh) to create a new video track on the topmost track.

V2								
V1		Outside	Two nuns	English les	Jumprop	Official whispers	Nuns with bells	Nun playing cymbals

2. Enter Effect mode, for example, by selecting Toolset > Effects Editing.
For more information, see [“Entering Effect Mode” on page 41.](#)
3. In the Effect Palette, click the Reformat category.
4. Drag the Pan and Scan Effect icon from the Effect Palette to the new track.

V2								Filler
V1		Outside	Two nuns	English les	Jumprop	Official whispers	Nuns with bells	Nun playing cymbals

Selecting the Source and Target Aspect Ratios for the Pan and Scan Effect

In Effect mode, the Pan and Scan effect displays a white wire frame in the Effect Preview monitor. This wire frame lets you select the portion of the media that appears in your output. The Pan and Scan aspect ratios determine the size and shape of the wire frame. Setting these ratios correctly is the most important part of using Pan and Scan.



Whenever you change aspect ratios, you must decide which part of an image to retain for the final output and which part to discard. The Pan and Scan aspect ratios specify the size of the incoming image and determine how much of that image you retain for your final output.

You must set two ratios:

- Source ratio specifies the aspect ratio of your incoming media.
- Target ratio specifies the aspect ratio of the final output.


To set the Source and Target aspect ratios for a Pan and Scan effect:

1. Apply the Pan and Scan effect to the new video track, as described in [“Applying the Pan and Scan Effect” on page 284](#).
2. Enter Effect mode, for example, by selecting Toolset > Effects Editing.


For more information, see [“Entering Effect Mode” on page 41](#).

The Effect Editor opens.


9 Working with Camera Effects



3. Move the position indicator to the Pan and Scan effect.
4. In the Effect Editor, click the triangular opener for the Aspect Ratios parameter category.
5. Set the Source aspect ratio to the ratio of your source material.



6. Set the Target aspect ratio to the ratio of the final output.



Viewing Pan and Scan Media

In Effect mode, the Effect Preview monitor displays your original media and the Pan and Scan wire frame. The Client monitor displays the original media.

In Source/Record mode (editing mode on NewsCutter systems), the Client monitor displays the media inside the Pan and Scan wire frame. The portion of the image inside the wire frame expands to fill the entire monitor. The Record monitor also shows the media inside the wire frame. The media is distorted if either the Source or Target aspect ratio is 16:9 Anamorphic.




In Effect mode (left) the original media displays in the Effect Preview monitor with the Pan and Scan wire frame. In Source/Record mode (right) the Record monitor shows a distorted view of the results of the Pan and Scan effect (the Client monitor shows an accurate view of the results).

Other effects let you view results on a frame-by-frame basis in Effect mode but the Pan and Scan effect does not. You see the entire source image so that you can select a portion of it. To see the results of the Pan and Scan effect while in Effect mode, click the Play button. In Source/Record mode (editing mode on NewsCutter systems), you can see the results of the Pan and Scan effect on a frame-by-frame basis or by playing the media.

Using the Effect Grid

The Effect Grid displays positioning guides that help you move and position the Pan and Scan wire frame. Displaying the Safe Action grid and Thirds grid can be particularly useful when adjusting Pan and Scan compositions.

The following illustration shows the Effect Grid with Show Safe Action, Show Thirds, and Show Axes selected.



Safe Title/Safe Action and Thirds grid marks are based on the Target aspect ratio and are displayed inside the wire frame. Other grid markings are displayed as normal across the entire monitor.

You can open the Grid Settings dialog box by clicking the Other Options button in the Grid parameter category of the Effect Editor. The Grid Settings dialog box controls the size, position, and display of a variety of grids. For more information on Grid settings, see [“Understanding the Effect Grid” on page 83](#).

In addition to using the options in the Grid Settings dialog box, you can use the controls in the Grid parameter category of the Effect Editor to change some Grid settings. For more information on these parameters, see [“Grid” on page 610](#).

Setting an Origin in the Pan and Scan Effect

Each Target aspect ratio has default position and scaling settings. You can return to these default settings at any time by selecting the aspect ratio again.

You can also use the Establish Origin parameter to create customized default values for each instance of the Pan and Scan effect.



Establish an origin before subdividing or adjusting individual keyframes in your Pan and Scan effect.

After you insert the Pan and Scan effect, you might want to adjust the size and position of the wire frame and save the wire frame’s new settings as base settings for the effect.

To save wire-frame settings for the Pan and Scan effect:

- ▶ In the Effect Editor, open the Actions parameter category and click Establish Origin.


To reset the wire frame for the Pan and Scan effect:

- ▶ In the Effect Editor, open the Actions parameter category and click Reset to Origin.
Reset to Origin is useful for quickly centering the wire frame after you move it.

 *If you have not set a custom origin, clicking Reset to Origin returns to the default values for the Target aspect ratio.*

Subdividing the Pan and Scan Effect

When your sequence contains a variety of segments with different panning requirements, you might need to adjust the position of the Pan and Scan effect on a segment-by-segment basis. The Subdivide Effect parameter makes it easier to adjust Pan and Scan for individual segments. Subdivide Effect splits the Pan and Scan effect based on the segment boundaries of the selected video tracks underneath the Pan and Scan track.


 *You can also use add edits to subdivide a Pan and Scan effect manually.*

The following illustrations show the Timeline before and after using the Subdivide Effect command.

V2		Filler 						
V1		Outside	Two nuns	English les	Jumprop	Official whispers	Nuns with bells	Nun playing cymbals

V2		Fi 	Fill 	Fill 	Fi 	Filler 	Filler 	Filler 
V1		Outside	Two nuns	English les	Jumprop	Official whispers	Nuns with bells	Nun playing cymbals

Subdividing minimizes the number of keyframes you need to add and manipulate because, by default, each effect has a keyframe at the start and end of the effect. If you want to reposition Pan and Scan for an entire segment, you can select the segment and drag the Pan and Scan wire frame to a new position. If you need to adjust Pan and Scan within the segment, add keyframes to the effect.

 *Subdivide the Pan and Scan effect only after you have finished editing your sequence and have selected your Pan and Scan aspect ratios and origin. For more information, see “Selecting the Source and Target Aspect Ratios for the Pan and Scan Effect” on page 284 and “Setting an Origin in the Pan and Scan Effect” on page 288.*

To subdivide a Pan and Scan effect:

1. If your Avid editing application is not in Effect mode, enter Effect mode, for example, by selecting Toolset > Effects Editing.
For more information, see “Entering Effect Mode” on page 41.
2. Move the position indicator to the Pan and Scan effect.

3. Click the Record Track buttons in the Track Selector panel for the video tracks to use as the subdivision guide.

Subdivide Effect divides Pan and Scan based on the segment boundaries of the selected tracks underneath the Pan and Scan track.

4. In the Actions parameter category, click Subdivide Effect.

Your Avid editing application divides the Pan and Scan effect into multiple effects.



Subdivide Effect works on the selected Pan and Scan effect, not on the entire track.



Subdivide Effect does not subdivide segments connected by transition effects. For information on using Pan and Scan with transition effects, see “Combining the Pan and Scan Effect with Transition Effects” on page 292.

Using the Wire Frame in the Pan and Scan Effect

The Pan and Scan wire frame in the Record monitor outlines the portion of media selected for output.

The wire frame functions similarly to the Picture-in-Picture wire frame. You can move the wire frame and define a motion path, and you can manipulate the wire frame in the following ways:

- Resize (scale) the wire frame by dragging its handles or by using the Scaling sliders.

Scaling lets you zoom in on your media. When you make the wire frame smaller, the image inside the wire frame is enlarged to fit the output monitor. Because making the wire frame very small results in a pixelated (grainy) image, you might not want to zoom in closely on an image that you plan to output directly to video.

- Reposition the wire frame by dragging it or by using the Position sliders.

You cannot drag the wire frame off the screen because in most circumstances you do not need to select empty space outside the boundaries of the source image. If you do need to position the edges of the wire frame beyond the screen's limits, use the Position sliders in the Effect Editor.

You cannot change the shape of the wire frame, which is determined by the Target aspect ratio. Your Avid editing application maintains the shape during scaling.


To scale the wire frame, do one of the following:

- ▶ Click one of the wire frame's handles, and drag it to the position you want.
- ▶ Click the triangular opener for the Scaling parameter category in the Effect Editor, and use the slider controls to adjust the wire frame's height and width.

To position the wire frame, do one of the following:

- ▶ Click inside the wire frame, and drag it to a new position.

Movement is restricted to the most important axis. For example, if you go from a wide aspect ratio (16:9) to a narrow aspect ratio (4:3), you can drag the wire frame from side to side. If you go from 4:3 to 16:9, you can drag the wire frame up and down.



- ▶ Shift-click inside the wire frame, and drag it to a new position.
You can move the wireframe in all directions.
- ▶ In the Position parameter category, adjust the wire frame's horizontal and vertical Position sliders.

Adjusting the Pan and Scan Effect

You might need to adjust Pan and Scan at different points throughout your sequence. The following are some suggestions for adjusting Pan and Scan.

If your sequence needs few adjustments:

1. Click the Play button or the Play Loop button.



Play (left) and Play Loop (right) buttons

2. If you see a problem with the panning, stop playback by doing one of the following:
 - ▶ Click the Play button or the Play Loop button.
 - ▶ Press the space bar.
3. Enter Effect mode, for example, by selecting Toolset > Effects Editing.
For more information, see [“Entering Effect Mode” on page 41](#).
4. Adjust the Pan and Scan effect.

To place Pan and Scan effects in the segments:

1. After subdividing the Pan and Scan effect, select the Pan and Scan effect above the segment string.
For more information, see [“Subdividing the Pan and Scan Effect” on page 289](#).
2. Press the Delete key to remove the Pan and Scan effect.

V2		Fi				Filler	Filler	Filler
V1		Outside	Two nuns	English Id	Jump	Official whispers	Nuns with bells	Nun playing cymbals

3. Enter Effect mode, for example, by selecting Toolset > Effects Editing.
For more information, see [“Entering Effect Mode” on page 41](#).
4. In the Effect Palette, click the Reformat category.
5. Drag the Pan and Scan Effect icon from the Effect Palette to the first segment in the segment string in the Timeline.
6. Repeat step 5 for each segment in the segment string.

V2		Fi				Filler	Filler	Filler
V1		Outside	Two nuns	English Id	Jump	Official whispers	Nuns with bells	Nun playing cymbals

7. Adjust each Pan and Scan effect as needed.

Using Avid Pan & Zoom

The Avid Pan & Zoom effect provides capabilities similar to a motion control camera using high-quality digital processing. You can move around a still image, with extensive keyframe control over the location and magnification of the field of view.

The Avid Pan & Zoom effect uses a downsized proxy image as its source while you are manipulating and previewing the effect, which provides excellent speed and response to your parameter and keyframe changes. When you render the effect, you can choose from a range of filtering options that provide exceptional finished image quality.

The Avid Pan & Zoom effect parameters let you control many aspects of your effect, such as how you view the image while you are working on it, what parts of the image the camera views, and how the camera moves over time.

The Avid Pan & Zoom effect supports any image file format for which your system has the appropriate QuickTime codec. You can download the latest version of QuickTime from the [Apple® Web site](#).

Most images you use with Avid Pan & Zoom come from digital cameras, scanners, or third-party graphics applications such as Adobe Photoshop®. If the image comes from a video source, you might need to set parameters in the Advanced parameter category to enable the effect to compensate appropriately. For more information, see [“Adjusting for Source Image Pixel Aspect Ratio and Color Levels in an Avid Pan & Zoom Effect”](#) on page 304.

If you move an image file after you associate it with the effect, the image is no longer accessible to the effect. The next time you open the effect a dialog box opens asking you to locate the file.

Applying the Avid Pan & Zoom Effect

To apply the Avid Pan & Zoom effect:

1. Load a sequence and create a placeholder segment of the duration you want for your image.

For information about editing a sequence, see “Creating and Editing Sequences” in the Help.

The footage you use in the placeholder segment is the footage the effect uses if you set the Background parameter to Video. For more information, see [“Selecting the Background for an Avid Pan & Zoom Effect”](#) on page 303.



You cannot use filler in the placeholder segment.


2. Enter Effect mode, for example, by selecting Toolset > Effects Editing.

For more information, see [“Entering Effect Mode”](#) on page 41.


The Effects Editing toolset appears.

3. In the Effect Palette, click the Image category.
4. Click the Avid Pan & Zoom icon, and drag it to the placeholder segment you created in step 1.

The Avid Pan & Zoom parameters appear in the Effect Editor.



5. In the Effect Editor, click the Other Options button.



A file selection dialog box opens.

6. Navigate to the file containing your image, and click OK.

Your Avid editing application associates the image file with the effect, and superimposes the image on the placeholder segment. The image appears in the Effect Preview monitor.



If you select a file that your Avid editing application does not recognize as an image file, your Avid editing application takes no action and no error message appears. For more information, see “Using Avid Pan & Zoom” on page 293.

The placeholder segment name does not change (the name of the image file does not appear in the segment).

7. Customize the Avid Pan & Zoom effect using the procedures described in the following topics.

Controlling Your View of an Avid Pan & Zoom Image

The Display parameter lets you select how you view the image while you work. You can view a scaled representation of the entire Source image while you draft the effect, or the result (Target) of your pan and zoom settings to preview the final look of the effect.

You can use the Show Action Safe option in the Display Options parameter category to provide a visual guideline for the viewable area on a standard television screen.

To set the Display parameter:



- ▶ Click the Display Fast Menu button, and select Source or Target.

Option	Description
Source	Shows you the entire image scaled to fit inside the Effect Preview monitor. Use this mode as you draft the effect. The pan and zoom settings appear as a rectangle superimposed over the image. The closer in you zoom, the smaller the rectangle appears.
Target	Shows you the results of your pan and zoom settings. Use this mode for previewing your moves. A crosshair appears at the center of the image. If you use Target Display mode and one of the real-time filtering options, the image appears pixelated in the Effect Preview monitor. This does not affect the quality of the rendered image. For more information, see “Setting a Rendering Option for an Avid Pan & Zoom Effect” on page 302.

To set the Safe Action display in the Display Options parameter:

- ▶ Click the Show Action Safe button to turn the Safe Action area display on or off.
When Show Action Safe is on, the Safe Action area displays. When Show Action Safe is off, the Safe Action area does not display.

Adjusting the Field of View for an Avid Pan & Zoom Image

The field of view is the part of the source image that you select to create the final image. It is represented in the Effect Preview monitor by a gray rectangle superimposed on the source image. You can zoom in or out on the source image, and pan over it.



Field of view display for Avid Pan & Zoom effect: field of view rectangle (outer rectangle), Safe Action area (inner rectangle), and crosshair (center)



If your final image will display on screens with limited viewing areas, you should turn on the Safe Action area display as a guideline while you work. For information on the Safe Action area, see “Controlling Your View of an Avid Pan & Zoom Image” on page 296.

To zoom in or out on the Source image:

- Use the Zoom Factor slider in the Size parameter category.

Zoom Factor ranges from 0.1 to 20. At 0.1, the effect scales the image down to one-tenth the original. At 1, the effect applies no magnification to the image. At 20, the effect scales the image up 20 times the original size. The larger the Zoom Factor, the smaller the field of view rectangle appears when you use Source Display mode.



Example of zooming and panning in the Avid Pan & Zoom effect. In Source Display Mode (left) the field of view rectangle is reduced in size and isolates one part of the image. In Target Display Mode (right) you see the resulting magnified image.



The Avid Pan & Zoom effect automatically preserves the clip's aspect ratio. The Avid Pan & Zoom effect also uses any aspect ratio you select from the Clip menu.

To pan over the source image, do one of the following:

- ▶ Using either Source Display mode or Target Display mode, click the crosshair, and drag it to a new location.
- ▶ Use the X and Y Position parameters.


The Position parameters refer to the center of the field of view. A Position of 0, 0 centers the field of view over the center of the image.

You can use the click-and-drag method to easily create a rough path, and then refine it with the X and Y Position parameters.

Modifying Apparent Camera Speed for an Avid Pan & Zoom Effect

The Avid Pan & Zoom effect uses Velocity In and Velocity Out at each keyframe to modify apparent camera speed as it pans across the image between keyframes. It modifies changes in the Zoom Factor setting in the same way.

The Velocity parameters divide the time between keyframes in half. Velocity In controls the rate of movement in the first half. Velocity Out controls the rate of movement in the second half.



How the Velocity parameters control the rate of movement between keyframes. The first half of the time between the two middle keyframes is controlled by the Velocity In parameter, and the second half of the time is controlled by the Velocity Out parameter.

The following procedures describe:

- The general method for setting the Velocity parameter.
- A method for setting a simple ease in and ease out.

Ease in is the gradual acceleration at the beginning of movement. Ease out is the gradual deceleration at the end of movement. With the Avid Pan & Zoom effect, you typically want to create a simple ease in only on the first keyframe and an ease out only on the last keyframe. If you use Ease In and Ease Out for each keyframe, the pan and zoom movements bounce at each keyframe like a car repeatedly speeding up and slowing down.

- A method for setting a constant speed for an effect.

When you change the position of a keyframe, the time it takes the effect to move from that position to the position of the next keyframe also changes. This is usually the result you want, but if you want a constant speed across a number of key frames you can use this method. Alternatively, you can make the calculations manually and place the keyframes accordingly.

To set the Velocity parameter:

1. Click the keyframe indicator for the keyframe you want to adjust.
2. Click the In Fast Menu button, and then select a Velocity In option from the Fast menu.
For a description of all the Velocity options, see [“Image: Avid Pan & Zoom” on page 570](#).
3. Click the Out Fast Menu button, and then select a Velocity Out option from the Fast menu.
4. Repeat steps 1 to 3 for any other keyframes you want to adjust.

To set up a simple ease in and ease out for an effect with multiple keyframes:

1. Click the first keyframe indicator to select it.
2. Set Velocity In to Ease In.
3. Set Velocity Out to Linear.
4. Click the next keyframe indicator to select it.



For a quick way to jump to the next or previous keyframe indicator, use the Fast Forward and Rewind buttons in the Effect Preview Monitor toolbar.

5. Set Velocity In and Velocity Out to Linear.
6. Repeat steps 4 and 5 for all keyframes except the last keyframe.
7. Click the last keyframe indicator to select it.
8. Set Velocity In to Linear.
9. Set Velocity Out to Ease Out.

To create a path with constant velocity:

1. Create an Avid Pan & Zoom effect.
For more information, see [“Applying the Avid Pan & Zoom Effect” on page 294](#).
2. Add keyframes to define the path you want the effect to take.
3. At each keyframe, set the Velocity In and Velocity Out parameters to Constant.

When you use Constant for Velocity In and Velocity Out, the position at which you placed a keyframe in the Timeline is not necessarily the time at which the Avid Pan & Zoom effect applies the keyframe's parameters. The effect applies the parameters at the time calculated by the effect to achieve a constant velocity for the path you created.

When you use the Constant option, your Path parameter selection can affect the result of changes you might make to the effect.

- If you select Linear for the Path parameter, moving keyframes or changing the Position parameters *does not* affect the velocity of the effect's path.
- If you select Spline for the Path parameter, moving keyframes or changing the Position parameters *might* affect the velocity of the effect's path.

For more information, see [“Controlling Path Changes at Keyframes for an Avid Pan & Zoom Effect” on page 300](#).

4. Press the Play button or the Play Loop button to preview the effect.



Play (left) and Play Loop (right) buttons


The velocity of the path is constant.

Controlling Path Changes at Keyframes for an Avid Pan & Zoom Effect

The Path parameter controls how the Avid Pan & Zoom effect interpolates Position parameter changes at keyframes.


To set the Path parameter:

- Click the Path Fast Menu button, and select one of the following options from the Fast menu.
 - Linear interpolation creates straight-line changes from one keyframe to the next.



Linear interpolation (abrupt changes of direction at each keyframe). The line represents the path of the effect over time while the numbers represent keyframes and indicate where the direction of the path changes.

- Spline interpolation smooths out changes at keyframes to create a more natural movement.



Spline interpolation (gradual changes of direction at each keyframe). The line represents the path of the effect over time while the numbers represent keyframes and indicate where the direction of the path changes.

The Avid Pan & Zoom effect calculates a Spline path so that it is smooth through all points. If you move a point, the effect recalculates the entire path.



If you combine a Spline path with Constant velocity, when you move a keyframe, the path recalculation might result in a change to the velocity of the effect.

Setting a Rendering Option for an Avid Pan & Zoom Effect

The rendering option you select for the Avid Pan & Zoom effect determines the quality of the rendered result. The various filtering options let you trade off the clarity or sharpness of the resized image and the speed at which the effect renders.



The image quality of the effect in the final output depends in part on the output resolution for the sequence. You might lose some sharpness due to compression during the final output.

To select a rendering method:

- Click the Filtering Fast Menu button, and select a rendering option from the Fast menu.
For information on the available options, see [“Rendering \(Filtering\) Options for Avid Pan & Zoom” on page 302](#).


To adjust animation smoothness in progressive projects:

- Click the Progressive button in the Render Mode parameter category.
When Progressive is on, progressive frames render more smoothly. When Progressive is off, progressive frames render less smoothly.

Rendering (Filtering) Options for Avid Pan & Zoom

The following table describes the options available in the Filtering parameter category for the Avid Pan & Zoom effect. The options are ranked from fastest render and lowest quality image to slowest render and highest quality image.

You might not always want the sharpest possible result. Images with many sharp edges might look better with a softer rendering. Many users find that B-Spline Catmull is the best compromise between image quality and rendering time.

Option	Description
Real Time	Renders most quickly but results in a draft-quality image.  <i>Your Avid editing application uses Real Time filtering during uncompressed play.</i>
Triangle	Results in fairly soft images.
Quadratic	Results in slightly sharper images than Triangle filtering.

Option	Description
Cubic	Results in sharper images than Quadratic filtering although they are still fairly soft.
B-Spline Catmull	Lets you shrink an image (zoom out) by a large amount. B-Spline Catmull produces a sharper image than Cubic filtering when you stay close to the original size of the image (very little zooming in or zooming out) or when you enlarge the image (zoom in) past the source image resolution.
Gaussian	Results in an image that is relatively soft but sharper than B-Spline Catmull.
Avid Hi Qual	Creates sharp images when you shrink the original (zoom out).
Avid Ultra Qual	Creates extremely sharp images when you shrink the original (zoom out).

Selecting the Background for an Avid Pan & Zoom Effect

You can select a field of view from the original image that does not fill the entire screen. The Background parameter determines what appears outside the field of view.

 *The Background parameter is not keyframeable.*

To select the background:



1. Click the Background Fast Menu button, and select Color or Video.

Option	Description
Color	Lets you select a background color.
Video	Uses the video from the segment upon which you placed the Avid Pan & Zoom effect.

2. (Option) If you select Color, use one of the following methods to set the background color:



- ▶ Manipulate the RGB sliders directly, or use the numeric keypad to enter values.
- ▶ Click the Other Options button to use the Windows Color dialog box or the Macintosh Colors panel.
- ▶ Click the Color Preview window, and use the eyedropper.

For more information, see [“Adjusting a Color Parameter for an Effect” on page 96.](#)

Adjusting for Source Image Pixel Aspect Ratio and Color Levels in an Avid Pan & Zoom Effect

The Advanced parameter category provides controls to compensate for differences in pixel aspect ratio and in color levels between the source image and the video output.

Digital cameras and scanners, common sources for the Avid Pan & Zoom effect, use square pixels. Computer monitors and HD video formats also use square pixels. SD video formats, however, use non-square pixels.

Most images you use with the Avid Pan & Zoom effect use RGB color levels that range from 0 to 255. In rare cases, you might use images from a video source with 601 color levels.

To compensate for pixel aspect ratio differences:

- ▶ Click the Source Has Square Pixels button in the Advanced parameter category.
When Source Has Square Pixels is on, the Avid Pan & Zoom effect makes the calculations necessary to produce results compatible with rectangular pixels. This is the default setting.
When Source Has Square Pixels is off, the Avid Pan & Zoom effect does not change the pixel shape but does apply the aspect ratio in effect for the project. This might be a good setting if your source image does not have square pixels, for example, if it comes from an SD video source.

To adjust for source image color levels:

- ▶ Click the Level Fast Menu button, and select an option from the Fast menu.

Option	Description
Source has RGB Level	For images with a black level of 0 and a white level of 255. The effect maps colors to video black and white levels, which are 16 and 235 respectively. This is the default setting.
Source has 601 Levels	Refers to the ITU-R-601 standard for video black and white levels. Select 601 if you use images from an SD video source. When you select 601 for the Level setting, the effect makes no adjustment to color levels.

Managing Memory with the Avid Pan & Zoom Effect

The images you work with in Avid Pan & Zoom are often extremely large. The amount of memory used to store a large image can impact the performance of your Avid editing application. The Cache parameter gives you control over the amount of memory used to store your images for playback. A full resolution image is always used for rendering.

To control the amount of memory used to store images:

- ▶ Click the Cache Fast Menu button, and select an option from the Fast menu.

Option	Description
Video Resolution	The effect stores a source image at a reduced pixel resolution that uses about 1 MB per image. Use Video Resolution if you have many images in your sequence and you need to limit how much memory they occupy.
Image Resolution	The effect stores a source image at its original resolution. The amount of memory used varies with the size of the image.
Multi-Resolution	The effect stores several versions of the image: original image resolution, half resolution, quarter resolution, and so on, for eight versions of the image. The result is higher quality real-time preview and faster rendering. Multi-Resolution uses about twice the memory of Image Resolution.
Free Current Cache	The effect frees all memory used for image storage and then reverts to Image Resolution. Use this setting to free up memory after you have rendered the clip.
Cache All	Your Avid editing application sets the same Cache parameter for all instances of the effect in a sequence.
Free All Caches	Your Avid editing application frees the caches for all instances of the plug-in in that sequence.

10 Motion Tracking and Stabilization

You can track the motion of a selected area in an image over time. You can then use the tracking data to control the motion of an effect such as a Picture-in-Picture or to stabilize an image to compensate for camera motion.

- [Understanding Motion Tracking](#)
- [Workflow for Motion Tracking](#)
- [Effects and Effect Parameters That Use Tracking Data](#)
- [Understanding the Tracking Interface](#)
- [Opening The Tracking Window](#)
- [Tracking Window Components](#)
- [Setting Up an Effect for Tracking](#)
- [Preparing to Generate Tracking Data](#)
- [Generating Tracking Data](#)
- [Offset Tracking](#)
- [Understanding Tracking Data](#)
- [Customizing the Display of Tracking Data](#)
- [Setting the Reference Frame for a Tracker](#)
- [Understanding the SteadyGlide and Smoothing Options for Tracking](#)
- [Using SteadyGlide or Smoothing to Process Tracking Data](#)
- [Selecting, Deleting, and Moving Tracking Data Points](#)
- [Moving Tracker Data Points Outside the Frame Boundary](#)
- [Stretching a Range of Tracker Data Points](#)
- [Limiting the Effect of Position Tracking Data to a Single Axis](#)
- [Playing Effects That Use Tracking Data](#)
- [Understanding Stabilizing](#)
- [Stabilizing an Image](#)
- [Reviewing and Adjusting a Stabilized Image](#)

- [Guidelines for Using Multiple Trackers When Stabilizing](#)
- [Using the Region Stabilize Effect](#)
- [Making Adjustments to the Region Stabilize Region of Interest](#)
- [Editing Segments That Use Tracking Data](#)
- [Reusing Existing Tracking Data](#)
- [Copying and Pasting Tracking Data](#)
- [Conforming Symphony Meridien Sequences with Tracking Data](#)
- [Examples of Effects Using Motion Tracking](#)

Understanding Motion Tracking

This topic includes conceptual information that helps you to understand how tracking works and when you might want to use it.

Understanding the Tracking Process

Motion tracking searches for a distinctive pattern of pixels in each frame of a video segment. As the pattern moves over time, your Avid editing application records the movement as a series of points, one for each frame or field in the segment. For example, if a car is moving across a segment, you can track a distinctive pattern on the side of the car, such as the shape of its side mirror. The result is a set of tracking data points that represent the movement of the car over time.

Once you have a set of data points, you can associate them with an effect parameter to control how an effect moves. For example, if you need to hide the identity of the person driving the car in your segment, you can associate the tracking data with the Position parameter of a Blur effect. The tracking data then controls the movement of the Blur effect so that the blurred area remains over the person's head throughout the segment.

Each set of data points is contained within a structure called a tracker. Depending on the kind of motion you need to track, you might need one, two, or more trackers. For simple two-dimensional movement, a single tracker is sufficient. If you need to track rotational movement or scaling information, you need two trackers so that your Avid editing application can calculate the position of one point in the image relative to a second point. For even more complex motion, such as that involved in corner pinning an image, you might need three or four distinct points to correctly track perspective or the angle at which the image is tilted.

Uses of Motion Tracking

One common use for motion tracking is to replace a moving area in one image with new material. For example, you can track the motion of a distinctive area on a vehicle and then use that data to replace an advertising sign on the vehicle or to replace or blur the license plate. In many cases, especially when the motion of the vehicle is complex, using tracking data to control the movement of the foreground replacement is much quicker than using keyframes to define the movement by hand. For an example of this use of motion tracking, see [“Examples of Effects Using Motion Tracking” on page 356](#).

Sometimes a shot is designed from the outset with motion tracking in mind. A director might attach a target to the moving vehicle so that you can track it easily. You can create a replacement sign as a graphic and import it or shoot a replacement sign against a keying background. During editing, you use tracking data to control the movement of the replacement material in a Picture-in-Picture or a chroma key effect promoted to 3D Warp.

Another use for motion tracking is to create an effect in which a foreground object follows a background object but remains offset from it. For example, you might track the movement of a hand in a background clip and then use that tracking data to control the movement of a foreground object so that the object’s movement appears to be controlled by the moving hand.

When you stabilize an image, you use tracking information somewhat differently. By tracking an object that should be motionless — for example, part of a building — you collect information about the movement of the camera from one frame to the next. The Stabilize effect then applies the inverse of that movement to each frame in order to eliminate the camera motion.

Motion Tracking and Footage Characteristics

The motion tracking tools in your Avid editing application let you track movement in many kinds of footage successfully.

However, some footage will always be difficult or even impossible to track successfully. There might be no consistent pattern to track across multiple frames, or insufficient distinction between the pattern you want to track and the surrounding material. Typically, tracking requires a distinct edge in the target area, for example the edge of a moving vehicle against a background, or the edge of an advertising sign against the body of a vehicle.



In some cases, you can temporarily apply a color correction or a Color Effect that you can use to make a pattern more distinct. For example, if a blue vehicle does not track well against a sky background that is a similar shade of blue, you could use a secondary color correction on the vehicle to change its color temporarily.

Workflow for Motion Tracking

The following workflow outlines the main stages of the motion tracking process and indicates where to find more detailed information and procedures for each stage.

Motion tracking provides considerable workflow flexibility. As you become a more experienced user of motion tracking, you can modify the order of these stages or merge them together to suit your editing style and the requirements of a particular project.

1. (Option) Before you begin working with the motion tracking tools, develop a general concept and design for the effect you want to create.

In some cases, you can design your shoot itself with tracking in mind, for example, by attaching a distinctive target to a moving object that you can later track and replace with an effect.

2. Set up the effect that you want to control using tracking information.

You access motion tracking from within an effect parameter for a specific effect, so you must set up the effect first. For more information, see [“Setting Up an Effect for Tracking” on page 317](#).

3. Prepare to generate tracking data by creating trackers and customizing how your Avid editing application will conduct the tracking operation.

For more information, see [“Preparing to Generate Tracking Data” on page 318](#).

4. Generate tracking data.

Depending on the complexity of the movement you want to track, you might need to track one, two, or more distinct points in the image. If you are not able to track one target area successfully throughout your segment, you might need to add and track one or more additional tracker regions.

For more information, see [“Generating Tracking Data” on page 328](#) and [“Performing Offset Tracking” on page 332](#).

5. If necessary, process or modify the tracking data.

For example, you might want to smooth the path of the tracking points, or adjust some of the points by hand. For more information, see [“Using SteadyGlide or Smoothing to Process Tracking Data” on page 337](#) and [“Selecting, Deleting, and Moving Tracking Data Points” on page 338](#).

6. Play back the effect.

Your Avid editing application calculates the motion of the effect by incorporating the tracking data and displays the result. For more information, see [“Playing Effects That Use Tracking Data” on page 344](#).

7. If necessary, continue to adjust the tracking information or other effect parameters until you are satisfied with the look of the effect.

Effects and Effect Parameters That Use Tracking Data

You can enable tracking and use tracking data for most segment effects that can move over time, including Picture-in-Picture, keys, Intraframe™ effects, titles, and all 3D effects. In some cases, you must promote an effect to 3D to access tracking for the effect or to access the full range of tracking options.

Effect parameters that can use tracking data divide into two groups:

- The Position, Scaling, and Rotation parameters let you use tracking data to control the specific kinds of motion associated with each parameter. You can work with tracking enabled in any combination of these parameters at the same time. For example, you can work with tracking enabled in both the Position and the Scaling parameters to control both the position of an effect on the X and Y axes and the size of the effect.
- The Tracking parameter category provides a more flexible way to define and use tracking data by allowing you to enable up to four trackers. The Tracking parameter is the only parameter that lets you work with more than two trackers at one time and is therefore the only option for controlling complex motions that involve perspective changes or tilting of the effect.

You can also use the Tracking parameter with only one or two trackers enabled to control simpler motions such as position and scaling. This is the only option for such control in effects that do not have Position, Scaling, and Rotation parameters, such as Intraframe effects. This is also an alternative method for controlling simpler motions in effects that do have Position, Scaling, and Rotation parameters.

The two groups of parameters that use tracking data are mutually exclusive. When you enable the Tracking parameter, tracking is automatically disabled in the Position, Scaling, and Rotation parameters. When you enable tracking in the Position, Scaling, or Rotation parameters, the Tracking parameter is automatically disabled.

The following table provides a complete list of the effects and effect parameters that can use tracking data. For reference information on these effects and their parameters, see [“Effects Reference” on page 555](#) and [“Effects Parameter Reference” on page 603](#).

Effect	Available Parameters
Picture-in-Picture (2D)	Position, Scaling
Paint	Tracking
AniMatte	
Blur Effect	
Mosaic Effect	
Scratch Removal	
Spot Color Correction (Symphony only)	
Stabilize	Position, Scaling, Tracking
Matte Key effect (applied from Key category in the Effect Palette)	Position, Scaling
Imported Matte Key clip (2D)	Position, Scaling
Titles (2D)	Position, Scaling
3D Warp (including promoted Picture-in-Picture effects, keys, 3D Xpress shape effects, and titles)	Position, Rotation, Scaling, Tracking

Understanding the Tracking Interface

Tracking controls appear in three locations: the Effect Editor, the Effect Preview monitor, and the Tracking window.

Tracking Controls in the Effect Editor

The Effect Editor includes tracking controls within those effect parameter categories that can use tracking information. These controls let you enable tracking for the parameter and to define which trackers apply to that parameter.

The appearance of tracking controls in the Effect Editor varies depending on whether or not the effect uses advanced keyframes.

The following illustration shows the tracking controls for the Position parameter category in both standard keyframes and advanced keyframes.



Examples of tracker controls in an effect with standard keyframes (left), and in an effect with advanced keyframes (right)

For more information, see:

- [“Effects and Effect Parameters That Use Tracking Data” on page 311](#)
- [“Enabling Tracking in the Effect Editor” on page 319](#)
- [“Creating and Mapping Trackers” on page 322](#)


Tracking Controls in the Effect Preview Monitor

The Effect Preview monitor displays tracking controls that you can manipulate directly. The monitor displays the tracking boxes that you use to define the target area and the search area on the first frame or field of the region that you want to track. As tracking takes place, the monitor displays the generated data points for each frame or field. Once tracking data has been generated, you can display tracking data points and manipulate them in the monitor.

For more information, see:

- [“Setting Up Tracking in the Effect Preview Monitor” on page 324](#)
- [“Understanding Tracking Data” on page 332](#)
- [“Customizing the Display of Tracking Data” on page 334](#)
- [“Selecting, Deleting, and Moving Tracking Data Points” on page 338](#)

The following illustration shows a typical display of tracking boxes and data points.



Tracking Controls in the Tracking Window


The Tracking window has the following main features:

- An area containing controls for setting up and performing tracking, controlling the display of tracking data, and modifying tracking data
- A timeline representation of each tracker for the current effect

For more information, see:

- [“Opening The Tracking Window” on page 314](#)
- [“Tracking Window Components” on page 315](#)

The following illustration shows the Tracking window.



Opening The Tracking Window

For more information on the features of the Tracking window, see [“Tracking Window Components” on page 315](#).

To open the Tracking window, do one of the following in the Effect Editor:

- ▶ Enable tracking in an effect parameter for a tracker that is not currently mapped.

For more information, see [“Creating and Mapping Trackers” on page 322](#).












- ▶ Click the Tracking Tool button.

You might need to resize the Effect Editor to see the Tracking Tool button in the column of buttons on the right side.








Tracking Window Components

The following table describes the components of the Tracking window and indicates where to find more detailed information.




Tracking Window Components

Control		Description
Start Tracking		Starts a tracking operation from the current location of the position indicator. For more information, see “Generating Tracking Data” on page 328 .
New Tracker		Creates a new tracker. For more information, see “Creating and Mapping Trackers” on page 322 .
Go to Previous Region and Go to Next Region	 	Click one of these buttons to move to the previous or next region boundary in the tracker timelines. For more information, see “Using Tracker Regions” on page 331 .
Tracking Engine		Lets you choose the tracking engine that calculates the tracking data. For more information, see “Understanding Tracking Engines” on page 327 .
Track Background/Foreground		Lets you choose between tracking the background shot and tracking the foreground shot, (In the great majority of cases, you track the background shot.) For more information, see “Setting Up Tracking in the Tracking Window” on page 326 .
Point Range		Controls how many of the tracking data points appear in the Effect Preview monitor. For more information, see “Customizing the Display of Tracking Data” on page 334 .
Display		Controls the display in the Effect Preview monitor, allowing you to view either the tracking data or the results of the effect. For more information, see “Customizing the Display of Tracking Data” on page 334 .
Stretch Points Mode		Lets you stretch data points. For more information, see “Stretching a Range of Tracker Data Points” on page 341 .

Tracking Window Components (Continued)

Control		Description
Enable Tracker button (Tracker timeline displays)	 	When this button is active for a tracker, tracking boxes and tracking data points display in the Effect Preview monitor, and your Avid editing application generates tracking data for that tracker during a tracking operation. The button is purple when active and gray when inactive. For more information, see “Enabling, Disabling, and Deleting Trackers” on page 323.
Offset Tracking (Tracker timeline displays)		When this option is selected, the tracker uses offset tracking to calculate a continuous motion for the effect from multiple regions of tracking data. For more information, see “Offset Tracking” on page 330.
SteadyGlide (Tracker timeline displays)		When this option is selected, your Avid editing application processes the tracking data for the tracker to remove unwanted jittery motion while preserving underlying smooth movement such as a camera pan or zoom. The value in the Smoothing Value text box controls the extent of the processing. For more information, see “Using SteadyGlide or Smoothing to Process Tracking Data” on page 337.
Smoothing (Tracker timeline displays)		When this option is selected, your Avid editing application processes the tracking data for the tracker to smooth the path between selected points. The value in the Smoothing Value text box controls the amount of smoothing. For more information, see “Using SteadyGlide or Smoothing to Process Tracking Data” on page 337.
Smoothing Value (Tracker timeline displays)		Enter a value between 1 and 100 to control the amount of smoothing the SteadyGlide or Smoothing processes provide. The larger the value, the more smoothing occurs. For more information, see “Using SteadyGlide or Smoothing to Process Tracking Data” on page 337.
Tracker Color box (Tracker timeline displays, Effect Editor)		Shows the color the Effect Preview monitor uses to display information for this tracker and lets you change the tracker’s display color. For more information, see “Customizing the Display of Tracking Data” on page 334.

Tracking Window Components (Continued)

Control		Description
Tracker Name text box (Tracker timeline displays, Effect Editor)		Shows the name of the tracker and lets you change the name. For more information, see “Creating and Mapping Trackers” on page 322.
Tracker timeline (Tracker timeline displays)		Shows information about the tracking data in the tracker. Color coding indicates the status of the data. For more information, see “Setting Up Tracking in the Effect Preview Monitor” on page 324 and “Understanding Tracking Data” on page 332.
Tracker Close button (Tracker timeline displays)		Closes the tracker and permanently deletes any information within it. For more information, see “Enabling, Disabling, and Deleting Trackers” on page 323.

Setting Up an Effect for Tracking

The first stage of the motion tracking workflow is to set up the effect to which you want to apply tracking data. To do this, you edit the necessary footage into a sequence, apply the effect, and, in most cases, make initial parameter adjustments to the effect.

Understanding Video Layers and Motion Tracking

Because motion tracking either controls an effect in relation to a moving area in a clip or controls the stabilization of a clip, you need one of the following situations for motion tracking to be useful:

- Two (or more) layers in the Timeline, where one contains the video you track and another contains the material to which you apply the effect (that material might be video, an imported graphic, or a title clip).
- A single video layer on which you draw one or more Intraframe objects. When you track movement in the video, you can use that tracking data to control the movement of the Intraframe objects.
- For stabilizing only, a single video layer that you intend to stabilize.

When you are working with two video layers, the material you intend to track typically is on the background layer and the effect is on the foreground layer. However, your Avid editing application can track either the foreground or the background layer, so you can place the material you want to track on top of the material that receives the effect if necessary.

Applying an Effect for Motion Tracking

You apply an effect for motion tracking in the same way that you apply any effect that either operates on a multilayer sequence or lets you draw a foreground object on top of a video layer. For more information, see [“Applying Effects” on page 35](#).

Making Non-Tracking Parameter Adjustments to an Effect

The final look of an effect that uses tracking is typically the result of combining the tracking data with standard effect parameter adjustments. You usually need to define the appearance of the effect in the first frame or field of the segment, and you might also need keyframe adjustments at other points in the segment.

In most cases, you can choose whether to make these adjustments before or after you generate the tracking data. As long as the standard adjustments as well as the tracking data are in place when you play the effect, you see the final result of all the adjustment data.

For example, if you are replacing a sign on a moving vehicle, you use standard effect parameter adjustments to set the initial size, shape, and position of the sign. Depending on the complexity of the material, you might make these adjustments using basic parameters such as Position and Scaling, or you might place each corner independently using the Corner Pin parameter.

If you want the effect to be offset from the moving area that you plan to track, you establish the offset by adjusting the Position parameters. The final motion of the effect maintains that offset from the tracking data points as it moves. If you want the size of the effect to change in a manner that is not dependent on changes in the moving area, you can set up that change in size by using keyframes and the Scaling parameters.

When you work with Intraframe effects, you must draw the foreground object that you want to control with tracking information and select it with the Selection tool before you can generate tracking data. As with other effects, however, you can establish the precise size, shape, and position of the object either before or after generating tracking data.



You can choose which frame in a tracked segment is the reference frame (the frame at which the tracking data makes no change to the look of the effect). For more information, see [“Setting the Reference Frame for a Tracker” on page 335](#).

Preparing to Generate Tracking Data

The topics in this section cover procedures that you need to follow before you can generate tracking data. These procedures control how the system operates as it creates the tracking data.

Enabling Tracking in the Effect Editor

The first step in creating tracking data is to enable tracking for an effect parameter in the Effect Editor. Once you do this, other tracking controls become available.

The basic procedure for enabling tracking in an effect parameter is simple, but there are slight variations depending on:


- The parameter type
- Whether the effect is 2D or 3D
- Whether the effect uses standard keyframes or advanced keyframes



For Intraframe effects, you can only enable trackers when an Intraframe object is selected.

To enable tracking for the Position, Rotation, or Scaling parameters in effects that use standard keyframes:


- ▶ Click the Use Tracking button.



Your Avid editing application creates an appropriate number of trackers (one for Position, two for Rotation or Scaling) and maps them to the parameter.

To enable tracking for the Position or Scaling parameters in 2D effects that use advanced keyframes:


- ▶ Open the Position or Scaling category, and then click the enable button for the Tracking subcategory.



Your Avid editing application creates an appropriate number of trackers (one for Position, two for Scaling) and maps them to the parameter. You must open the Tracking subcategory to see the list of mapped trackers and any additional controls.

To enable tracking for the Position, Rotation, or Scaling parameters in 3D Warp effects:


- ▶ Open the Position, Rotation, or Scaling category, and then click the enable button for the Position Tracking, Rotation Tracking, or Scale Tracking subcategory.



Your Avid editing application creates an appropriate number of trackers (one for Position, two for Rotation or Scaling) and maps them to the parameter. You must open the Position Tracking, Rotation Tracking, or Scale Tracking subcategory to see the list of mapped trackers and any additional controls.

To enable tracking for the Tracking parameter in effects that use standard keyframes:

- ▶ Click one or more of the individual tracker enable buttons.



Your Avid editing application creates and maps a tracker for each tracker enable button you click, and also enables the Tracking parameter category.

To enable tracking for the Tracking parameter in 2D effects that use advanced keyframes:


- ▶ Open the Tracking parameter category, and then click one or more of the individual tracker enable buttons.



Your Avid editing application creates and maps a tracker for each tracker enable button you click, and also enables the Tracking category.

To enable tracking for the Tracking parameter in 3D Warp effects:

- Open the Corner Tracking parameter category, and then click one or more of the individual tracker enable buttons.



Your Avid editing application creates and maps a tracker for each tracker enable button you click, and also enables the Corner Tracking category.

Once you enable tracking for a parameter, the Tracking window opens. For more information on the Tracking window, see [“Tracking Window Components” on page 315](#).

When you first enable tracking for a parameter, your Avid editing application creates appropriate default trackers and maps them to the parameter, as described in the table. For more information, see [“Creating and Mapping Trackers” on page 322](#).

Understanding Tracker Selectors and Tracker Function

Each parameter includes a number of tracker selectors appropriate to its function in controlling movement. When you enable tracking in a parameter, your Avid editing application looks for existing trackers and maps them to the parameter’s tracker selectors. If trackers do not yet exist, your Avid editing application creates them and then maps them to the parameter’s tracker selectors. In the Tracking parameter category, new trackers are created and mapped as you enable individual tracker selectors.

When you work in the Position, Scaling, and Rotation parameters, the number of trackers you can use is limited by the type of movement controlled by the parameter. For example, the Position parameter includes a single tracker selector since you need only one point to define movement in X and Y.

When you work in the Tracking parameter, you can use any number of trackers up to a total of four. The following table describes the kinds of motion that you can control with a given number of trackers.

Number of Trackers	Description
One	Controls position on the X and Y axes only. Use one tracker if you want your effect to move in only two dimensions on the plane of the screen.

Number of Trackers	Description
Two	Controls position, scaling, and rotation. Use two trackers if you want your effect to change size or rotate.
Three	Controls position, scaling, rotation, and skew. Skew refers to a transformation that tilts or squashes an object along one axis while retaining its orientation along the other axis. This has the effect, for example, of transforming a rectangle into a parallelogram. Use three trackers if you want your effect to skew in this manner.
Four	Controls position, scaling, rotation, skew, and perspective. Perspective refers to the way parallel lines appear to converge and changes depending on the angle from which an object is viewed. Use four trackers if you want to control perspective for your effect.

Creating and Mapping Trackers

Your Avid editing application automatically creates and maps trackers when you first enable tracking for an effect parameter. For most tracking work, you do not need to create additional trackers beyond those your Avid editing application creates automatically.

In some situations, you might want to create extra trackers. For example, you might want to track more than the minimum number of points necessary for a parameter so that you can experiment with different combinations of tracking points. You also might want to change the mapping of trackers so that an effect parameter uses a different tracker or combination of trackers from that originally created by your Avid editing application. For more information about the uses of different tracker combinations, see [“Understanding Tracker Selectors and Tracker Function” on page 321](#).

You can use up to eight trackers for each effect.

To create a new tracker manually:




1. In the Tracking window, click the New Tracker button.

For more information, see [“Opening The Tracking Window” on page 314](#).

A new tracker timeline display appears in the bottom area of the Tracking window. The tracker name uses the next letter of the alphabet that is not already in use, up to the letter D. If all of the letters A through D are in use, the name of any subsequent new trackers is “Untitled Tracker.”

2. (Option) If you want to rename the new tracker, click the Tracker Name text box, and type a new name.



The new tracker appears as an option in all the tracker selector Fast menus in the Effect Editor.

To map a tracker manually, do one of the following, depending on the interface style in the Effect Editor:



- ▶ Click the Fast Menu button for the appropriate tracker selector in the parameter, and then select the tracker you want.
- ▶ Click the tracker selector in the parameter, and then select the tracker you want.

Enabling, Disabling, and Deleting Trackers

You can enable and disable trackers as necessary. Enabling and disabling a tracker has a different effect depending on whether you do it in the Tracking window or in the Effect Editor.

- When you enable or disable a tracker in the Tracking window, you control whether or not the tracker displays in the Effect Preview monitor and whether or not your Avid editing application generates tracking data for that tracker.
- When you enable or disable a tracker in the Effect Editor, you control which sets of tracking data your Avid editing application uses to control the effect. This lets you compare the look of an effect under the control of different tracker combinations.

You can also delete existing trackers. When you do so, you permanently erase that tracker and any tracking data associated with it.

To enable or disable a tracker in the Tracking window:



- ▶ Click the Enable Tracker button for the tracker in the tracker's timeline.

To enable or disable all trackers at once:

- ▶ Alt+click (Windows) or Option+click (Macintosh) the Enable Tracker button for any tracker.

To enable or disable a tracker in the Effect Editor:

- ▶ Click the Enable button for the appropriate tracker selector.



In the Tracking (or Corner Tracking) parameter category, clicking the Enable button that controls the whole parameter disables all the trackers at the same time but does not change the enable status or the mappings of the individual trackers. When you click the Enable button for the whole parameter again, the system reenables all the individual trackers.

To delete a tracker:

- ▶ In the Tracking window, click the Close button in the top right corner of the tracker's timeline.

Setting Up Tracking in the Effect Preview Monitor


You define the region of interest (the area of an image that each tracker tracks) and the larger area it searches within by making direct adjustments to the tracking box display in the Effect Preview monitor.

Each tracking box display includes three elements:

- An inner rectangle used to define the target area
- An outer rectangle used to define the search area
- A data point locator, which appears at the center of the rectangles

Each rectangle has a corner adjustment handle.

The following illustration shows the tracking box display.



You can change the color of the tracking boxes display for a tracker. This might make it easier to see the display against the background image. For more information, see “Customizing the Display of Tracking Data” on page 334.

To display tracking boxes in the Effect Preview monitor:

1. If you have not already done so, enable, create, and map the trackers with which you want to work.
2. In the Display Tracking Data area of the Tracking window, ensure that Tracking Data is selected in the Display menu.
3. Make sure that the Enable Tracker button is active (purple) in the tracker timeline display of the Tracking window for each tracker that you want to display.
4. Make sure that you are monitoring the track in the Timeline that contains the material you want to track.



5. Move the position indicator to the first frame or field of the segment, or to the first frame or field of the tracker region.

A tracking box display appears in the Effect Preview monitor for each tracker. For more information on tracking regions, see [“Performing Offset Tracking” on page 332](#).

To move a tracking box display in the monitor:

- ▶ Click anywhere within the boxes except the adjustment handles, and drag the boxes to a new position.

To resize a box in a tracking box display:

- ▶ Drag the adjustment handle for the box.

For more information on what to consider when making these adjustments, see [“Guidelines for Positioning and Resizing Tracking Boxes” on page 325](#).



If you enable multiple trackers, you might find it difficult to select one. You can disable some of the trackers temporarily in the Tracking window to simplify the display in the Effect Preview monitor and make it easier to select and manipulate a particular tracker.

Guidelines for Positioning and Resizing Tracking Boxes

Positioning

When you position tracking boxes, consider the following:

- Locate the boxes over material that your Avid editing application can track successfully.
- Locate the boxes so that the tracking data you generate accurately represents the movement you want to track.

Tracking works most successfully on an area of the image that is easily distinguishable from its surroundings. For example, a bright dot tracks extremely well if darker material surrounds it. You often need to scrub through the entire clip to determine which areas are good candidates for tracking.

To represent the movement you want to track accurately, you must consider the geometry of the motion that you want to achieve. For complex movement, such as controlling a replacement sign for a bus that is receding into the distance as well as moving across the screen, you must track enough points to represent the change in shape and size of the sign over time. Tracking two corners lets you control changes in scale and rotation (the corners should be diagonally opposite if scaling on the X axis differs from scaling on the Y axis). Adding third and fourth trackers fills in the other two corners as needed for more complex transformations.

You do not have to track points at the exact location where you want the finished effect to appear. You can track any set of points that represent the right movement. For example, you might want to add a small sign to the door of a moving car. Since the door panel is a uniform surface you cannot track areas on it. However, you can gather tracking data to control the positioning and scaling you need for the sign, for example, by tracking two or more of the corners of the car window.

Resizing

When you resize either of the tracking boxes, consider the following:

- Define material that your Avid editing application can track successfully
- Ensure that tracking proceeds successfully from frame to frame or from field to field throughout the range of frames or fields you are tracking
- Minimize the length of time your Avid editing application spends generating tracking data

The smaller you can make the boxes, the less image information the tracking engine has to search and the faster it can work. However, if you set the boxes too small, you increase the possibility that your Avid editing application will lose the search pattern between one frame or field and the next.



You can also refine how your Avid editing application follows a target area by setting controls in the Tracking window. For more information, see “Setting Up Tracking in the Tracking Window” on page 326.

Size the Target Area box so that it is as small as possible while still enclosing a distinct area to track. The pattern needs to remain distinct throughout the range you are tracking.

Size the Search Area box so that it is as small as possible while remaining large enough to encompass the movement of the target area from one frame or field to the next. You often need to scrub through the clip you are tracking to check how much a prospective target area moves from one frame or field to another.

Setting Up Tracking in the Tracking Window

In addition to defining the search criteria for a tracker in the Effect Preview monitor, you can also set up the following aspects of tracking behavior in the Tracking window.

- Choose which tracking engine to use.
For more information on available tracking engines, see “Understanding Tracking Engines” on page 327.
- Choose whether the region to track is in the background or the foreground clip.

You can track either the background or foreground for a multilayer effect. You almost always want to track the background to define the movement of an effect or painted object layered above the background shot.

One situation in which you must choose Track Foreground is when you are stabilizing an image using a 3D Warp effect. For more information, see [“Stabilizing an Image” on page 346](#).

The following illustration shows the area of the Tracking window that contains these controls.



To switch the tracking engine:

- ▶ In the Setup Tracking area of the Tracking window, select the tracking engine you want to use from the Tracking Engine menu.

To switch between background and foreground tracking:

- ▶ In the Setup Tracking area of the Tracking window, select the option you want to use from the Track Background/Foreground menu.

Understanding Tracking Engines

The term *tracking engine* refers to the calculation methods that your Avid editing application uses to recognize a moving pattern and generate data for it.

The following table describes the tracking engines available in your Avid editing application.

Tracking Engine	Description
Correlation Tracker	This tracking engine is often the best first choice for tracking motion in an image. It usually produces accurate tracking data when the target area is distinctive, and usually generates tracking data faster than the FluidTracker when the area being searched is small. If you need to search a larger area, the Correlation Tracker might become too slow to be useful, in which case you should switch to the FluidTracker. This is the tracking engine that Avid DS uses.

Tracking Engine	Description
-----------------	-------------

FluidTracker	<p>If you need to search a large part of your image, FluidTracker might produce good tracking data faster than the Correlation Tracker.</p> <p>In the following two specific situations, FluidTracker usually produces more accurate data than the Correlation Tracker:</p> <ul style="list-style-type: none">• When the points you want to track start outside the visible area of the frame.• When you are using four trackers to control the corner-pinning of an image. <p>This tracking engine uses the same motion analysis methods that FluidMotion Timewarp uses.</p>
FluidStabilizer	<p>This tracking engine is designed to track camera motion and is recommended for use with the Stabilize effect. It is often particularly effective for removing camera motion when used in combination with the SteadyGlide feature. For more information on SteadyGlide, see “Understanding the SteadyGlide and Smoothing Options for Tracking” on page 336.</p> <p>FluidStabilizer divides the image into a grid, automatically selects a point of interest in each grid area, and then tracks each point using the same motion analysis methods that FluidMotion Timewarp uses. These points appear as highlighted green pixels in the image display.</p> <p>FluidStabilizer then uses further calculations to combine the motion of these points, de-emphasizing any values that are not consistent with the general pattern of motion. The result is a series of data points (displayed with the standard tracking data cross and dots) that, for many images, accurately represents the motion of the camera and is not distorted by other motion or noise in the image.</p>

Generating Tracking Data

You can generate tracking data for any number of the available trackers in a single operation.

You can generate tracking data for the entire length of the segment, or for any part of the segment starting from the location of the position indicator. This lets you stop tracking at any point in the segment and resume later, or retrack over any part of the segment whenever you need to do so.

You can also create separate tracking regions for different parts of your segment, and define a different target area for each region. This is primarily useful for performing offset tracking. Once you create a region, you can move the position indicator to the start of that region and generate tracking data for the region. For more information, see [“Offset Tracking” on page 330](#).

As your Avid editing application generates tracking data, it updates the tracker timeline displays to show the status of tracking data over time. For more information on the tracker timeline display, see [“Understanding Tracking Data” on page 332](#).

To generate tracking data:



1. In the Tracking window, click the Enable Tracker button for each tracker you want your Avid editing application to track.

To enable all trackers at once, Alt+click (Windows) or Option+click (Macintosh) the Enable Tracker button for any tracker.

2. Move the position indicator to the location where you want to start generating tracking data.

This location can be at any point in the segment, but in most cases is either:

- At the beginning of the segment.
- At the beginning of a region.
- At the location where you stopped generating tracking data and from where you want to resume tracking.

For information about moving to the beginning of a tracking region, see [“Using Tracker Regions” on page 331](#).



3. Click the Tracking button.

Your Avid editing application begins to generate tracking data.

As the tracking operation proceeds:

- The Effect Preview monitor displays each frame or field on which tracking is being performed, and shows the tracking data point for that frame or field as a cross.
- Your Avid editing application updates the timeline for each tracker to indicate the status of the tracking data over time. If you are tracking where there is no existing tracking data, your Avid editing application replaces the red bar at the bottom of the line with a black bar at the top as data is generated, as shown in the following illustration. If you are retracking where tracking data already exists, you see no change in the tracker timeline, but the old tracking data is being replaced with new data.



When you start tracking from the beginning of a tracking region, your Avid editing application steps back one frame from the region boundary before it starts tracking. This is normal behavior to ensure that motion at the region boundary is tracked correctly.

To stop a tracking operation, do one of the following:

- ▶ Press the space bar.
- ▶ Press Ctrl+period (Windows) or Command+period (Macintosh).
- ▶ Click any element of your Avid editing application's interface.

The tracking operation stops.

Offset Tracking

You can use your Avid editing application's offset tracking capabilities to create smooth effect motion from tracking data that you generate using more than one target area. This lets you track motion successfully when a single target area is not available for the full duration of a segment.

Understanding Offset Tracking

Motion tracking is simplest when you can track a single distinct area for the full length of a segment. For example, if the side of a moving bus is visible throughout the segment, you can select any area or set of areas on the side of the bus and track them throughout the segment.

Other situations are more complex. For example, if the bus is moving slowly and is also relatively close to the camera, you might find that an area you choose to track at the beginning of the segment moves out of the frame later in the segment. Or, the bus passes behind a foreground sign, again with the result that an area you choose to track at the beginning becomes hidden later in the segment.

In these situations, you can use offset tracking to generate useful tracking data. Offset tracking lets you track one target area until it becomes unavailable because it leaves the frame or is hidden by another object, then track another target area that shows the same kind of motion as the first. Your Avid editing application calculates the offset from the first set of tracking points to the second, and takes account of this offset when animating the final effect. The result is an effect that follows a continuous path.

If necessary, you can track more than just two targets. You can also track one target, switch to a second (for example, when the first becomes temporarily hidden), and then return to the first when it becomes visible again.

To track more than one target area in a segment, you add a new tracker region to a tracker timeline. You can then set a new target area in the first frame or field of the new region and track that target area.

Using Tracker Regions

You can add one or more new tracker regions to the tracker timeline and track a new target area for each of the regions.

In most cases, you use tracker regions with the offset tracking feature, so that your finished effect combines the tracking data from more than one target area into one continuous motion. For more information, see [“Understanding Offset Tracking” on page 330](#).

When you have multiple regions in the tracker timelines, you can move between them by using the Go to Previous Region and Go to Next Region buttons.

To add a new tracker region for a tracker:

1. In the tracker’s timeline, move the position indicator to the location where you want the new region to start.
2. Right click in the tracker’s timeline, and select Add New Tracker Region.

Your Avid editing application creates a new region that extends from the location of the position indicator to either the start of the next tracker region or the end of the timeline. The start of the new region appears as a vertical bar in the tracker timeline.



Tracker Region boundaries in a tracker timeline

To delete a tracker region for a tracker:

1. In the tracker’s timeline, move the position indicator to any location within the region.
2. Right-click in the tracker’s timeline, and select Delete Tracker Region.

Your Avid editing application deletes the tracker region and any tracking data for it. The vertical boundary bar for the region disappears from the timeline. A red bar appears at the bottom of the tracker’s timeline for the duration of the old region, indicating that you must retrack these frames to get new tracking data, as shown in the following illustration.



To go to the beginning of the previous or next tracking region:

- Click the Go to Previous Region or Go to Next Region button.



Go To Previous Region (left) and Go To Next Region (right) buttons

Performing Offset Tracking

When you start tracking from the beginning of a tracking region, your Avid editing application steps backward one frame from the region boundary before it starts tracking. This is normal behavior to ensure that motion at the region boundary is tracked correctly.

To perform offset tracking:

1. Make sure that offset tracking is enabled for each tracker you plan to use.



Offset tracking is enabled by default. The Offset Tracking button is purple when offset tracking is enabled.

2. In the first frame or field of your segment, set up a tracker for your first target area, as described in [“Preparing to Generate Tracking Data” on page 318](#).
3. Begin generating tracking data, as described in [“Generating Tracking Data” on page 328](#).
4. When the target area disappears, stop tracking by pressing the space bar.
5. (Option) If necessary, step back a few frames or fields in the segment until the position indicator is on the last frame or field with a good tracking data point.
6. Right-click in the tracker timeline and select Add New Tracker Region.

A vertical bar appears in the tracker timeline to show the beginning of the new region, and the tracking boxes for the tracker appear in the Effect Preview monitor.

7. Drag the tracking boxes to the location of your second target area and size them as necessary.



8. Begin tracking from the start of the new region by clicking the Tracking button.
9. (Option) If necessary, repeat steps 3 through 7 for additional target areas (or to return to tracking the original target area when it becomes visible again).

Understanding Tracking Data

After you create tracking data, a set of tracking data points exists for each tracker enabled during the tracking operation. You can display these points in the Effect Preview monitor. You can also view information about the status of the tracking data in the tracker timeline display.

Tracking Data in the Effect Preview Monitor

Tracking data points display in the Effect Preview monitor.


While tracking is taking place, your Avid editing application shows the location of the current tracking data point as a cross.

Once tracking stops, your Avid editing application displays, by default, every point created during the tracking operation. The data point for the current frame or field displays as a flashing cross. All other data points display as solid dots.

You can control which sets of data points display and how many of the points display. You can also manipulate the points directly in the monitor in a variety of ways. For more information, see [“Selecting, Deleting, and Moving Tracking Data Points” on page 338](#).

Tracking Data in the Tracker Timelines



The tracker timeline display shows you the status of tracking data over the length of the effect.



Example of the tracker timeline display. Left to right: Reference Frame Marker, starting Display Marker, vertical bar marking start of new region, and ending Display Marker.

The following table describes the display options.

Color	Description
Black Line at top of timeline	Tracking data exists for this part of the segment, and the data points for this part of the segment are not currently selected in the Effect Preview monitor. For more information, see “Generating Tracking Data” on page 328 .
White Line at top of timeline	Tracking data exists for this part of the segment, and the data points for this part of the segment are currently selected in the Effect Preview monitor. For more information, see “Selecting, Deleting, and Moving Tracking Data Points” on page 338 .
Red Line at bottom of timeline	Tracking data does not exist for this part of the segment.

Color	Description
Vertical Bar	Marks the start of a new tracking region. For more information, see “Offset Tracking” on page 330 .
 Display Markers	Define the beginning and end of a range of frames. When In to Out is selected in the Point Range menu, the Effect Preview monitor only shows tracking data points for this range of frames. For more information, see “Customizing the Display of Tracking Data” on page 334 .
 Reference Frame Marker	Marks the location of the reference frame — the frame at which the tracking data does not modify the effect. For more information, see “Setting the Reference Frame for a Tracker” on page 335 .

Customizing the Display of Tracking Data

You can customize how your Avid editing application displays tracking data in the following ways:

- You can enable or disable display for each tracker.
- You can customize the color used to display each tracker.
- You can control how many of the tracking data points display.
- You can control whether the Effect Preview monitor shows tracking data or shows the results of applying the tracking data to the effect.

To turn the tracking display on or off for a tracker:



- ▶ In the Tracking window, click the Enable Tracker button for the appropriate tracker. The Enable Tracker button is purple when the display is on.



Alt+click (Windows) or Option+click (Macintosh) the Tracking Box Display button for any tracker to turn the display on or off for all trackers at once.

To customize the display color for a tracker:



- ▶ Click the Tracker Color box, and then click the color you want to use.

To define the range of data points in the display:

1. (Option) If you want to define a range of frames for which you want data points to display, do one of the following:
 - ▶ Drag the Display Markers in any one of the tracker timelines to define the beginning and end of the range you want.

- Use the position indicator in the tracker timelines along with the Mark IN and Mark OUT buttons to define the beginning and end of the range you want.

The Display Markers move to the beginning and end points you establish.

2. In the Display Tracking Data area of the Tracking window, click the Point Range menu, and then select an option.

Option	Description
Current	Displays the data point at the current location of the position indicator for each enabled tracker.
In to Out	Displays the data points for the range currently defined by the Display Markers in the Tracking window for each enabled tracker. Shows the points for the current frame or field as flashing crosses.
All	Displays every data point for each enabled tracker. This is the default option. Shows the points for the current frame or field as flashing crosses.

To choose Tracking Data or Effect Results display:

- In the Display Tracking Data area of the Tracking window, select the option you want to use from the Display menu.



The Display menu affects what you see in the Effect Preview monitor once tracking data is available and while you are parked on a frame or are stepping through the effect. The Display menu does not affect what you see in the Effect Preview monitor while tracking is taking place (when the current data point always shows as a cross). When you play an effect with tracking data, for example, by clicking the Play button in the Effect Preview monitor, you always see the results of the effect.

Setting the Reference Frame for a Tracker

The reference frame for a tracked segment is the frame at which the tracking data makes no change to the appearance of the effect. For example, for a Stabilize effect, the reference frame is the frame at which the tracking data causes no change in the position of the image. The location of the reference frame is marked on the tracker timeline by a red diamond.

By default, your Avid editing application considers the first frame of a tracked segment to be the reference frame. In every frame after the first, the effect is modified by the tracking data for that frame.

You can choose to set the reference frame to any other frame in the segment. This might be useful when trimming changes the location of the head frame for the segment, or in other circumstances where the position of the reference frame influences the final look of the effect. For example, if you set the reference frame for a Stabilize effect to the frame at the midpoint of the segment, the tracking data at that frame causes no change in the position of the image. In all earlier and all later frames, the effect is modified by the tracking data for that frame.

To set the reference frame for a tracker:

1. In the tracker timeline, move the position indicator to the frame you want to set as the reference frame.
2. Right-click the tracker timeline, and select Set Reference Frame.

The red diamond reference frame marker moves to the location of the position indicator.

Understanding the SteadyGlide and Smoothing Options for Tracking

Your Avid editing application provides two options for processing tracking data to smooth the motion it represents. You can turn these options on or off at any time, and you can control the amount of smoothing they provide. The original set of tracking data points is not changed in any way by the processing. For information on using these options, see [“Using SteadyGlide or Smoothing to Process Tracking Data” on page 337](#).

SteadyGlide


SteadyGlide™ processes tracking data to reduce abrupt, jittery movements without affecting underlying motion. SteadyGlide is particularly useful for stabilizing unwanted camera motion without eliminating desirable motion. You typically use SteadyGlide with the Stabilize effect, or with Stabilize Tracking turned on for an effect parameter in the 3D Warp effect. For example, you can use SteadyGlide to reduce any jittery motion in a pan shot with a hand-held camera while retaining the underlying motion of the pan itself. For more information on stabilizing, see [“Stabilizing an Image” on page 346](#).

When you are using SteadyGlide, the display shows a graph of the jittery motions that your Avid editing application is removing. It is not easy to assess the final look of the effect from this information, so you should view the effect results to determine whether you need to adjust the smoothing value further.

Smoothing

Smoothing processes tracking data to smooth out the path between the tracking data points. The higher the Smoothing value you define, the smoother the path becomes. You typically use Smoothing when compositing an image or a paint object over a tracked region of a moving background, for example, when the motion of the tracked region is not completely smooth but you want the motion of the image or paint object to be smooth.

When you are using Smoothing, the display shows the smoothed curve that results from the processing, which gives a useful visual indication of the amount of smoothing your Avid editing application is applying. The following illustrations show typical results for Smoothing using different smoothing values.



Smoothing examples with the Smoothing Value set to 10 (left), 50 (center), and 90 (right)

Using SteadyGlide or Smoothing to Process Tracking Data

To use SteadyGlide or Smoothing:

1. In the tracker timeline, click the SteadyGlide button or the Smoothing button.



SteadyGlide (left) and Smoothing (right) buttons

The button is purple when the processing option is turned on.



SteadyGlide and Smoothing are mutually exclusive processing operations. You cannot perform both SteadyGlide and Smoothing at the same time. If you turn on one, the other is automatically turned off if it was on previously.

2. In the Smoothing Value text box, type a smoothing value between 1 and 100.

The smoothing value controls the extent of the smoothing performed by both the SteadyGlide and the Smoothing options. The larger the value, the more smoothing is performed.

If you are displaying tracking data in the Effect Preview monitor, the display updates to show the results from the processing.

3. (Option) If necessary, check the effect results and adjust the smoothing value until you are satisfied with the results, or click the SteadyGlide or Smoothing button again to turn off the processing if you decide you do not want it.

Selecting, Deleting, and Moving Tracking Data Points

You can manipulate tracking data points in the Effect Preview monitor in the following ways that are described in this topic:

- You can find a specific data point
- You can select individual data points or ranges of data points.
- You can delete points.
- You can move one or more points.

You can also move points outside the limits of the frame to extend the movement of an effect smoothly out of the frame, or stretch a range of points. For more information, see [“Moving Tracker Data Points Outside the Frame Boundary” on page 341](#) and [“Stretching a Range of Tracker Data Points” on page 341](#).

Unlike SteadyGlide or Smoothing processing, these adjustments change the tracking data itself. You can only reverse them by using your Avid editing application’s Undo feature, or by retracking to generate a new set of tracking data points.



If your tracking data points are very close together at normal magnification, you can use your Avid editing application’s standard methods to zoom in on your tracking data in the Effect Preview monitor and view it more clearly. For more information, see [“Using the Effect Preview Monitor” on page 78](#).

To find a specific data point when multiple data points are displaying for a tracker:

- Move the position indicator to the frame or field for which you want to find the data point.

The data point for that frame or field flashes in the Effect Preview monitor.

To isolate the point further, you can select Current in the Point Range menu in the Tracking window, so that the point for the current frame or field is the only point that appears in the Effect Preview monitor.

To select a single data point:

- ▶ Click the point in the Effect Preview monitor.

The point is highlighted with a circle in the monitor and the corresponding part of the tracker timeline display changes to white.

To select a single data point and move to the frame or field for that point:

- ▶ Double-click the point in the Effect Preview monitor.


The point is highlighted with a circle in the monitor and with a flashing cross, the corresponding part of the tracker timeline display changes to white, and your Avid editing application automatically moves to the frame or field for that point.

To select a contiguous range of data points, do one of the following:

- ▶ Click the first data point in the range you want to select, and then Shift+click the last data point in the range.
- ▶ Drag the pointer across the range of data points that you want to select to lasso them.

The points in the range are highlighted with a circle and the corresponding part of the tracker timeline display changes to white.



The following illustration shows a range of selected data points.



To delete one or more selected data points:

- ▶ Press the Delete key.

Your Avid editing application repositions the selected data points along a straight line between the two unselected points that bound the selected points. The data points remain fully functional. They display in the Effect Preview monitor at their newly calculated locations, and they remain available for you to modify further.



Selected points before deleting (left) and the result of deleting — points are repositioned in a straight line between the unselected bounding points


To move a single selected data point:

- Drag the point to a new location.

To move a range of selected data points:

- Drag any one of the points in the range to a new location.

All the data points move along with the one you drag and maintain their positions relative to one another, as shown in the following illustrations.



Before (left), during (center), and after (right) moving a selected range of data points. The points move as a group and maintain their positions with respect to one another.

Moving Tracker Data Points Outside the Frame Boundary

If you track a target area that moves out of the frame, the tracking engine can no longer track the target area and generates invalid data points. You have two options to ensure consistent motion if you want your effect to move smoothly out of the frame.

- You can use offset tracking to track a second target area that does not leave the frame until the end of the segment. For more information, see [“Offset Tracking” on page 330](#).
- You can move the very last data point outside the boundary of the frame so that it extends the line of motion that has been successfully tracked earlier in the segment. (You need to reduce the magnification in the Effect Preview monitor to less than 100% to view the area outside the frame.) You can then delete all of the invalid points between that final point and the last valid data point.


Your Avid editing application repositions the points you delete on a straight line. When the effect plays back, the repositioned data points ensure that the effect moves smoothly out of the frame. If the motion you are tracking is, for example, simple straight line movement, this might be quicker than setting up an extra tracking region.

Stretching a Range of Tracker Data Points

You can select a range of data points and then stretch them into a new position. In contrast to simply moving a range of points, the stretching process uses one moving point and one or two anchor points. As you move the moving point, all the other points in the selected range stretch to new relative positions.

This feature is useful for tracking data points that are slightly offset from the area you are tracking but otherwise represent the motion you are tracking accurately. For example, if you are tracking an area on a moving vehicle, changes in the image from frame to frame and in your Avid editing application’s updating of the target area might yield tracking data points that lag behind the area you are tracking.

The following illustration shows this behavior.



This illustration represents data points (dots) created by tracking an area (the rectangle containing the triangle) across a series of frames. For the first half of the process, the object is tracked accurately. During the second half of the process, a small amount of error is introduced, and by the end the data point lags behind the object somewhat. Stretching the points in the second half of the series so that the last point is positioned over the last triangle quickly creates a complete set of usable points.

You can select a range of points that are slightly out of the ideal position in this way and stretch them so that they more exactly represent the path of the object you want to follow. This provides the motion you need for your effect without retracking or moving many data points individually.

To stretch a range of data points:

1. Select the range of points as described in [“Selecting, Deleting, and Moving Tracking Data Points” on page 338](#).
2. In the Modify Tracking Data area of the Tracking window, click Stretch Points Mode.



The button is purple when Stretch Points mode is turned on.


3. Drag one of the selected points to a new location.

Your Avid editing application relocates the points proportionally along the path between the point you have moved and the anchor point or points. If you move a point at either end of the selected range, the point at the opposite end becomes the anchor. If you move a point in the middle of the range, the two end points become anchors.

The following illustrations show these two behaviors.



Stretching a range of points by moving one end. The point at the other end of the range becomes the anchor while you drag the moving point. After the stretching process, all the selected points are relocated proportionally between the point you have dragged and the anchor point.



Stretching a range of points by moving a point in the middle of the range. Both end points become anchors while you drag the moving point. After the stretching process, all the selected points are relocated proportionally between the point you have dragged and the two anchor points.

Limiting the Effect of Position Tracking Data to a Single Axis


You might want to track an area to generate data on its X, Y position but then control the movement of the effect on only one axis. You can limit the effect of Position tracking data to one axis to achieve this effect.



You can limit Position motion to a single axis when you want to stabilize a shot without eliminating camera motion in one direction, such as a pan. However, a more flexible approach to this problem for most shots is to use data from both axes and then use SteadyGlide to process the data. For more information, see “Stabilizing an Image” on page 346 and “Using SteadyGlide or Smoothing to Process Tracking Data” on page 337.

To limit the effect of Position tracking data to a single axis:

1. In the Effect Editor, open the Position parameter category and the Tracking subcategory.
2. Select either X Tracking Only or Y Tracking Only from the menu.



Playing Effects That Use Tracking Data

Once you have generated tracking data and have modified it to create acceptable sets of data points, you can play the effect to check its movement over time.



Tracking data does not alter the real-time status of an effect. If an effect is normally real time, it remains real time when it uses tracking data. If an effect normally requires rendering, it continues to require rendering when it uses tracking data. Playback of an effect while still in Effect mode also follows the normal behavior of the effect.

To play an effect that uses tracking data:



1. Move the position indicator to the beginning of the effect.
2. Click the Play button.
3. (Option) If you are not satisfied with the appearance of the effect, you can do one or more of the following to further modify its movement:
 - ▶ Adjust the effect's keyframe parameters.
For more information, see [“Working with Standard Keyframes” on page 148](#).
 - ▶ Modify the existing tracking data.
For more information, see [“Selecting, Deleting, and Moving Tracking Data Points” on page 338](#).
 - ▶ Retrack all or part of the segment to generate new tracking data.
For more information, see [“Generating Tracking Data” on page 328](#).

Understanding Stabilizing

If you need to eliminate unwanted motion in a video clip, such as motion from an unstable camera, or even more subtle motion such as gate weave introduced during the telecine process, you can stabilize the clip.

Stabilizing lets you track an object in a shot that should not be in motion and then use the tracking data to keep that object stationary and remove the unwanted motion. Objects such as buildings, telephone or light poles, and fixed objects in nature such as rocks or trees, are good candidates for tracking when you are stabilizing and you need to select a target manually.

Unlike other effects that use motion tracking, stabilizing works with only one layer of video, using the tracking data to move each frame of the video enough to keep the tracked object stationary.

You can also use stabilizing to create unusual special effects. For example, if you stabilize an object that is actually moving in a clip, you force other parts of the clip to move from frame to frame. You can take a clip of a person running down a street, stabilize on that person, and force the buildings in the shot into motion.

Your Avid editing application provides three effects that have stabilizing capabilities:

- The Stabilize effect

The Stabilize effect is the most versatile option for stabilizing. Its AutoStabilize feature handles all aspects of tracking and stabilizing a single clip automatically when you apply the effect. If you don't like the results of the automated process, you can adjust the effect's parameters manually, or even generate new tracking data. For more information, see [“Stabilizing an Image” on page 346](#).
- The Region Stabilize effect

The Region Stabilize effect does not work automatically, and has fewer controls than Stabilize. However, it provides the Progressive Source option, which lets you specify that the footage you are tracking is progressive material so that it is tracked correctly in an interlaced project.
- The 3D Warp effect

The 3D Warp effect does not work automatically, but it lets you have access to stabilizing and to all of the 3D Warp parameters in a single effect.

The tracking process exposes black around the edges of the frames, so a stabilized image typically requires resizing or repositioning to remove the exposed edges. Both the Stabilize effect and the Region Stabilize effect have options that can automatically remove exposed edges so that the stabilized image fills the frame.



Clips that contain extreme camera motion might be hard to stabilize successfully because they must be resized substantially to remove exposed edges. As a result, you might lose so much of the image information that the clip is no longer useful.

Stabilizing an Image

This topic describes how to use the Stabilize effect or the 3D Warp effect to stabilize an image.

The Stabilize effect uses AutoStabilize to track and stabilize an image automatically when you apply it to a single segment in the Timeline. AutoStabilize uses the tracking and effect parameter options that are most likely to result in a stable image. In many cases, you do not need either to interrupt the automatic process or to adjust effect parameters after it finishes. If you need to, you can adjust parameters after the automatic process, or even retrack.

AutoStabilize does not function when you apply the Stabilize effect to multiple selected segments in the Timeline. If you want to AutoStabilize multiple segments, apply the Stabilize effect to each segment individually.

AutoStabilize does not function when you use the Alt key modifier (Windows) or the Option key modifier (Macintosh) to nest an effect inside another effect, for example, by Alt-double-clicking in the Effect Palette or by Alt-dragging to the Timeline. If you want to AutoStabilize in a nest, step into the nest in the Timeline and apply the Stabilize effect directly to the nested layer. For more information, see [“Nesting Effects” on page 267](#).



The Region Stabilize effect is an alternative option for stabilizing a clip. For more information, see [“Using the Region Stabilize Effect” on page 350](#).

To stabilize a segment automatically:

1. Apply the Stabilize effect from the Image category in the Effect Palette.

The AutoStabilize process begins and does the following:

- Opens the Effect Editor (if necessary) and the Tracking window.
- Creates a tracker and enables the tracker in the Position parameter for the effect.
- Tracks the image using the FluidStabilizer tracking engine.
- Processes the tracking data using the SteadyGlide option and applies the data to the image.
- Uses the Auto-Zoom option to adjust the Scaling and Position parameters, which removes black edges from around the frame.

When the AutoStabilize process ends, the image in the Effect Preview monitor shows the results of the effect.

You can stop the tracking process at any time by pressing the space bar or by clicking anywhere in your Avid editing application’s interface. This lets you set different tracking options, and then track and stabilize manually.

2. Review the stabilized effect and, if necessary, make parameter adjustments.

For more information, see [“Reviewing and Adjusting a Stabilized Image” on page 348](#).

To stabilize a segment manually:

1. Do one of the following:

- ▶ Apply the Stabilize effect from the Image category in the Effect Palette, then stop the tracking process that starts automatically by pressing the space bar or by clicking anywhere in your Avid editing application’s interface.
- ▶ Apply the 3D Warp effect from the Blend category in the Effect Palette, or promote an effect that uses tracking data to 3D.



You can promote the Stabilize effect to 3D, so you can stabilize an image using the Stabilize effect and then promote it to access additional effect functionality. When you promote the Stabilize effect to 3D, Stabilize Tracking is automatically activated for all effect parameters that use tracking data. The Run Auto-Zoom option is not available after you promote the Stabilize effect to 3D.

2. Enable one or more trackers.

If you plan to use the FluidStabilizer tracking engine, do one of the following:

- ▶ For the Stabilize effect, open the Position parameter category and click the Enable button for one tracker.
- ▶ For the 3D Warp effect, open the Position parameter category, then the Position Tracking subcategory, and then click the Stabilize Tracking button.

If you plan to use either the Correlation Tracker or the FluidTracker tracking engine, do one of the following:

- ▶ For the Stabilize effect, open the Position, Scaling, or Tracking parameter category and click the Enable button for one or more trackers.
- ▶ For the 3D Warp effect, open the Position Tracking, Rotation Tracking, Scaling Tracking, or Corner Tracking parameter categories, then click the Stabilize Tracking button, and then enable one or more trackers.

For specific information on the number of trackers to use when stabilizing, see [“Understanding Tracker Selectors and Tracker Function” on page 321](#) and [“Guidelines for Using Multiple Trackers When Stabilizing” on page 349](#).

The Tracking window opens.

3. In the Tracking window, choose a tracking engine from the Tracking Engine menu.

The easiest way to stabilize an image is to use the FluidStabilizer tracking engine, which does not require you to set up regions of interest. If FluidStabilizer does not provide you with good results, you can track using one of the other tracking engines. For more information on the tracking engines and how they work, see [“Understanding Tracking Engines” on page 327](#).

4. If you are using the Correlation Tracker or the FluidTracker, set up each tracker for tracking by selecting the region of interest.

For more information, see [“Preparing to Generate Tracking Data” on page 318](#).

5. (Option) If you are using the 3D Warp effect, in the Tracking window, choose Track Foreground from the Track Background/Foreground menu.
6. Click Start Tracking to generate the tracking data.

For information on how tracking information displays in the Tracking window and in the Effect Preview monitor, see [“Understanding Tracking Engines” on page 327](#), [“Generating Tracking Data” on page 328](#), and [“Understanding Tracking Data” on page 332](#).

7. Review and adjust the effect, as described in [“Reviewing and Adjusting a Stabilized Image” on page 348](#).

Reviewing and Adjusting a Stabilized Image

After you stabilize an image, you typically need to review the results to determine whether the stabilized image looks good. You can also adjust the effect using one or more of the following options:

- SteadyGlide

This option often provides good results when you use it with FluidStabilizer tracking data, and is particularly useful if you want to remove jittery motion, such as that in a hand-held camera shot, while retaining underlying motion such as a pan. The AutoStabilize process uses SteadyGlide automatically. For more information, see [“Understanding the SteadyGlide and Smoothing Options for Tracking” on page 336](#).

- Auto-Zoom

This option automatically adjusts the Position and Scaling parameters for the effect so that exposed black edges are removed and the stabilized image fills the frame. The AutoStabilize process uses Auto-Zoom automatically.

- Position and Scaling parameters

Although in most cases Auto-Zoom provides good positioning and scaling results, you might want to make manual adjustments to the Position and Scaling parameters.

For information on how to stabilize an image, see [“Stabilizing an Image” on page 346](#).

To review the look of a stabilized effect:



- ▶ In the Effect Editor, click the Play Loop button.

The effect plays repeatedly to let you see how your Avid editing application repositions each frame or field in accordance with the tracking data.

To turn SteadyGlide processing on or off for the tracking data:



- ▶ In the Tracking window, click the SteadyGlide button for the tracker, and then type a smoothing value in the Smoothing Value text box.

For complete details on using SteadyGlide, see [“Using SteadyGlide or Smoothing to Process Tracking Data” on page 337](#).

To use Auto-Zoom to remove exposed black edges on a stabilized effect:

- ▶ In the Tracking subcategory of the Position parameter category, click Auto-Zoom.

Your Avid editing application processes the tracking information and generates values for the Position and Scaling parameters that reposition and enlarge the image enough to remove black edges. Any existing keyframes on the Position and Scaling parameters are removed.

If you retrack, turn SteadyGlide or Smoothing on or off, or change the smoothing values for SteadyGlide or Smoothing, Auto-Zoom recalculates Position and Scaling values so that black edges continue to be removed.

A warning message appears if no tracking data exists. A warning message also appears if the stabilized image moves too far offscreen to allow Auto-Zoom to calculate usable values.

To manually remove exposed black edges on a stabilized effect:

- ▶ In the Effect Editor, adjust the Position and Scaling parameter sliders until black edges are no longer visible in the effect.

A message box appears, informing you that Auto-Zoom will be turned off. If you want to use the Auto-Zoom option again later, you must click Auto-Zoom.

Guidelines for Using Multiple Trackers When Stabilizing

The number of trackers that you need when stabilizing depends on the complexity of the motion you want to stabilize. However, multiple trackers might introduce unnecessary additional motion that is detrimental to the final look of the clip, so you should use them only when they are absolutely necessary.

When the motion of an unstable camera is limited to movement on the X and Y axes only, you need only one tracker (typically enabled in the Position parameter category). Even when you see a small amount of rotational movement or change in scale in an image you want to stabilize, a single point usually stabilizes the image well enough to give an acceptable result without introducing unwanted motion.

If you are stabilizing a clip that shows significant changes in scaling, rotational, or other movement, or if you are using the Stabilize effect to create a special effect, you might need to use two or even more tracking points.

Using the Region Stabilize Effect

The Region Stabilize effect provides an alternative option for stabilizing an image. The Region Stabilize effect provides fewer controls than the Stabilize effect or the Stabilize Tracking option in 3D Warp, but its options might be all you need in some circumstances. Region Stabilize also provides the Progressive Source option, which lets you specify that the footage you are tracking is progressive material so that it is tracked correctly in an interlaced project.

To stabilize a clip with the Region Stabilize effect:


1. Enter Effect mode, for example, by selecting Toolset > Effects Editing.

For more information, see [“Entering Effect Mode” on page 41](#).

The Effects Editing toolset appears.

2. In the Effect Palette, click the Image category.
3. Drag the Region Stabilize Effect icon to the segment you want to stabilize.
4. Move the effect position bar to the segment with the Region Stabilize effect.

A wire frame appears in the Effect Preview monitor to indicate the region of interest. This is the area you want to use in stabilizing the image.



5. Reposition and resize the wire frame by doing one of the following:
 - Use the sliders in the Region of Interest parameter category.

- Click the wire frame, and drag it in the Effect Preview monitor.

Select a region that contains one or more features that do not change much from frame to frame, for example, objects such as buildings or rocks. Another approach is to shoot the scene with stabilization in mind: include an object, such as a reflective sticker, that you intend to use as your region of interest.



6. Click the Model Fast Menu button, and select the type of stabilization:

Option	Description
Translational	Keeps the region of interest steady along both the horizontal and the vertical axes.
Horizontal	Constrains horizontal motion in the region of interest. Features in the region of interest can move vertically but not horizontally.
Vertical	Constrains vertical motion in the region of interest. Features in the region of interest can move horizontally but not vertically.

7. (Option) Turn on Auto Zoom:

- a. Click the triangular opener for the Options parameter category.
- b. Select Auto Zoom.

Stabilization exposes black around the edges of the repositioned frames. Auto Zoom compensates by resizing and, if necessary, repositioning the clip to remove the exposed edges.

8. (Option) Select Progressive Source:

- a. Click the triangular opener for the Options parameter category.
- b. Select Progressive Source.

Select Progressive Source if your footage was captured or converted to progressive footage (not interlaced). If your sources are progressive, selecting Progressive Source produces smoother results.



Progressive Source has no effect in 24p projects because your Avid editing application assumes that you are using progressive footage.

If you click the Progressive Source button and your underlying source is not progressive, you may see motion artifacts between fields in the rendered effect.

9. Render and review the effect.

If the rendered clip does not perform as expected, see [“Making Adjustments to the Region Stabilize Region of Interest”](#) on page 352.

10. (Option) Add keyframes to further refine the motion of the stabilized clip.
11. Continue to review and refine the effect until you achieve the results you want.
12. (Option) Resize and, if necessary, reposition the clip to eliminate black edges.

Making Adjustments to the Region Stabilize Region of Interest

If the Region Stabilize effect does not perform as expected, it might be due to one of the following:

- If an object in your region of interest moves too far away from the region from one frame to the next, the rendered clip might display unexpected results.
You can increase the size of the region of interest, or reposition it, to cover large movement.
- An object in your region of interest might move over the course of the clip in a way that unpredictably affects the stabilization.
You can decrease the size of the region of interest to eliminate extraneous motion that is affecting the stabilization.
- The region of interest might not have enough features to allow Region Stabilize to track it effectively.
You can select a new region of interest.

You can also add keyframes to reestablish or refine the region of interest over the course of the clip.

Editing Segments That Use Tracking Data

Once tracking data exists for a segment, you can edit that segment in a number of standard ways without losing the tracking data and having to retrack.

Segment Editing with Segments That Use Tracking Data

Tracking data persists during Segment editing. For example, if you shift the position of a segment that contains tracking data, or copy a segment to another point in your sequence, the data is still available. If you lift a portion of the segment out of your sequence, tracking data is preserved on all parts of the segment for the range of frames in each part.

However, if you move only the foreground layer of a multilayer effect, the tracking data remains useful only to the extent that it corresponds, or can be made to correspond, to the background layer at its new location. For example, if you shift an effect segment with tracking data a few frames with respect to the background material beneath it, you might be able to continue to use the tracking data to follow the background area (perhaps by selecting all the points and moving them a little). If you shift the effect segment substantially, or even place it over a different background clip, the tracking data remains available but has no practical use.



Sometimes it might be useful to create a multilayer effect with motion tracking as a nested effect. If you do this, you can move or divide the nested effect during segment editing and be sure that the effect will stay in sync with the tracked material. For more information, see “Nesting Effects” on page 267.

Trimming Segments That Use Tracking Data

If you trim in from the edges of a segment, tracking data is preserved for both the new length of the segment and for the material you have trimmed. If you later trim the edges of the segment back out, the tracking data is still available to control the motion of your effect.

If you trim out beyond the tracked data for an effect, you must track over the range of these new frames to generate data for them.

If you edit a segment into a sequence by marking it to be longer than you will finally need, you can track the whole segment, trim it in, and know that you can adjust the trims back out when fine-tuning your sequence without having to retrack. This might be a useful approach if you know that a clip is likely to be trimmed.

Adding Transition Effects to Tracked Segments

If you add a transition effect to a tracked segment, you usually need to track the additional frames that the transition requires. For example, if you add a standard one-second, centered-on-cut dissolve at the beginning of a tracked segment, the dissolve uses one-half-second of new material from the tracked segment’s master clip.

It might be difficult to track these additional frames after you apply the transition effect because the Effect Preview monitor displays the combination of outgoing and incoming media created by the transition effect. In the case of a dissolve, for example, the monitor shows the blend of outgoing and incoming frames, which often obscures the pattern you need to track.

You can avoid this problem by doing the following:

1. Trim the tracked segment out by the number of frames that the transition requires.
2. Track the frames added by this trim.

3. Trim the tracked segment back in to the original edit point.
4. Add the transition effect.

Reusing Existing Tracking Data

You can reuse tracking data within the same effect. You can also copy and paste tracking data to another effect, as described in [“Copying and Pasting Tracking Data” on page 354](#).

Trackers that you initially create and map to one effect parameter are available for use in any other parameter in the effect that can use tracking data. For example, you might create a single tracker with the default Point A name in the Position parameter category. This tracker is available for use in other parameters such as Scaling.



The Tracking parameter and the Position, Scaling, and Rotation parameter categories form two mutually exclusive groups. You cannot have tracking enabled in both groups at the same time. For more information, see [“Effects and Effect Parameters That Use Tracking Data” on page 311](#).

You are less likely to find tracking information useful outside the effect for which you created it since the information refers specifically to the motion in one particular background clip. No other background clip is likely to contain exactly the same movement. However, there are some circumstances in which you might want to move tracking data to a new effect, such as the following two examples:

- You might want to move tracking data to an additional effect applied over the same background clip in the sequence. This might be a duplicate use of the background at another point in the sequence or an extra effect layered above the first (such as a second Picture-in-Picture effect tied to the same background movement).
- You might want to destabilize a stable shot so that it has a handheld look. To do this, you can track a segment that does have unsteady camera motion, and then copy the resulting tracking data to an effect on the segment you want to destabilize.

Copying and Pasting Tracking Data

You can copy one or more trackers and their associated tracking data and then paste those trackers into another effect. You can also copy one or more trackers and paste them within the same effect to create two versions of a tracker. This might be useful if you want to make two different sets of modifications to tracking data and then compare how each set changes the effect.

To copy and paste tracking data into another effect:

1. Enable the trackers you want to copy in the Tracking window.
2. Do one of the following:
 - ▶ Select Edit > Copy.
 - ▶ Press Ctrl+C (Windows) or Command+C (Macintosh).
3. Move the position indicator to the effect to which you want to copy the trackers.
4. Make sure that the Tracking window is active.
5. Do one of the following:
 - ▶ Select Edit > Paste.
 - ▶ Press Ctrl+V (Windows) or Command+V (Macintosh).

The trackers appear in the Tracking window below any existing trackers. For example, if you are pasting into an effect that has trackers T1 and T2, the pasted trackers are numbered T3 and T4.

6. (Option) If existing trackers in the effect have the same name or color as the trackers you paste, you might want to rename the trackers that have duplicate names or change their assigned colors to avoid confusion.

To copy and paste tracking data within the same effect:

1. Enable the trackers you want to copy in the Tracking window.
2. Do one of the following:
 - ▶ Select Edit > Copy.
 - ▶ Press Ctrl+C (Windows) or Command+C (Macintosh).
3. Do one of the following:
 - ▶ Select Edit > Paste.
 - ▶ Press Ctrl+V (Windows) or Command+V (Macintosh).

Duplicate copies of the enabled trackers appear in the Tracking window with new tracker numbers.

4. Rename the duplicate copies and change their assigned colors so that you can continue to distinguish between the different versions.

Conforming Symphony Meridien Sequences with Tracking Data

Tracking data in sequences originally created on Symphony Meridien systems is available for use when you open those sequences in your current Avid editing application. You can manipulate the data in the same ways that you can manipulate tracking data that you create in your current application. You can also add new regions to the tracker timelines, for example, to perform offset tracking.

The tracking engines in current Avid editing applications do not calculate tracking data in the same way as the tracking engine used in Symphony Meridien systems. As a result, if you retrack all or part of a segment containing tracking data created on a Symphony Meridien system, the new data that you create does not match the old data exactly.

Examples of Effects Using Motion Tracking

This topic includes two illustrated examples of typical uses of motion tracking to control effects. Studying these examples helps you to understand how you can use motion tracking in your own work.



If you find it difficult to distinguish details in the printed versions of the following illustrations, you can view them in full color in the online (PDF) version of this guide.

Example 1: Replacing the License Plate on a Moving Vehicle


This example uses motion tracking to track the license plate on a truck and then replace the plate with an imported graphic.

The license plate in the footage is white and the surrounding areas of the truck are generally dark, so the exact corners of the license plate are good targets for the tracking operation. However, if tracking the exact corners of the plate is difficult, you can track other points on the back of the truck to achieve the same control over the changing size and shape of the replacement plate. For more information, see [“Guidelines for Positioning and Resizing Tracking Boxes” on page 325](#).

All four corners of the license plate are tracked for this example to ensure that any skew and perspective changes are recorded by the tracking data. In fact, changes in perspective are relatively small in this clip because the plane of the back of the truck remains at almost exactly the same angle with respect to the plane of the screen. You might be able to achieve an acceptable finished look for this clip by using three trackers or even just two trackers on opposite corners of the license plate, especially since the replacement object is small.



The original materials for the example. On the left is the first frame of the video clip. The effect will replace the white license plate. On the right is the graphic for the replacement license plate. The graphic is blurred so that it will blend in with the clip. (You could do this in a graphics application or use Blur mode in the Paint Effect.) In the finished effect, a softened border is also applied to disguise the sharp edge of the graphic.



The location of the four tracking boxes at the four corners of the license plate (left), and the tracking data points generated for the four trackers. As the truck moves into the distance and the plate gets smaller, the points move closer together.

10 Motion Tracking and Stabilization



Images from the beginning, middle, and end of the original clip (top) and the finished effect. The replacement plate is positioned and sized manually in the first frame of the clip. The size and shape of the replacement changes under the control of the tracking data in the remaining frames of the clip.

Example 2: Special Effects Using Targets for Motion Tracking


This example uses special effects footage that has been specifically created to make use of motion tracking. White targets for tracking are part of the shot. After tracking these targets, you can use the tracking data to control the movement of an effect layer, for example, a keyed video image or an object created with the Paint Effect. In this example, the tracking data controls the movement of an object created with the Paint Effect.



The first frame of the clip. The original video (left) shows the target white dots on the wand. The finished effect (right) shows the image with the Paint object added.



The tracking boxes located over the targets (left), and the generated tracking data points for the entire clip (right).



Images from the beginning, middle, and end of the original clip (top) and the finished effect (bottom) with the Paint object.

11 Working with 3D Effects

This chapter describes procedures for creating and manipulating 3D effects.

- [Understanding 3D Effects](#)
- [Applying the 3D Warp Effect](#)
- [Using Xpress 3D Effects](#)
- [Promoting 2D Effects to 3D Effects](#)
- [Using Matte Keys with 3D Effects](#)
- [Real-Time Playback of 3D Effects](#)
- [Understanding 3D Geometry and Degrees of Rotation](#)
- [Working with 3D Effects Parameters](#)
- [Manipulating 3D Effects Directly](#)
- [Applying 3D Effects: Examples](#)

For reference information on 3D effects and their parameters, see [“Effects Reference” on page 555](#) and [“Effects Parameter Reference” on page 603](#).

Understanding 3D Effects

Avid 3D effects feature a wide range of digital video effects, including the following:

- Image effects such as blur (defocus), corner pin, and resize with rotation and perspective
- Two-channel segment effects including smooth-motion picture-in-picture
- Shapes, including page folds, balls, and slats
- Positioning, scaling, skewing, and rotation, with perspective
- Source cropping
- Internal borders including beveled and rounded edges
- Soft borders
- Trails and drop shadows with varying opacity

- Highlights and wipe generator
- Luma key and chroma key effects

You can create 3D effects in the following three ways:

- Apply the 3D Warp effect from the Blend category in the Effect Palette.

This option lets you create a 3D effect from scratch and have access to the full range of 3D effect parameters. For more information, see [“Applying the 3D Warp Effect” on page 362](#).

- Apply one of the effects from the Xpress 3D Effect category in the Effect Palette.

The effects in the Xpress 3D Effect category use a subset of the full 3D effect parameter set and are completely compatible with Avid Xpress® editing applications that include 3D effects capability. If you are working on sequences that need to maintain compatibility with Avid Xpress, the effects in the Xpress 3D Effect category are the only 3D effects you can use.

For more information, see [“Using Xpress 3D Effects” on page 363](#).

- Promote an existing 2D effect to 3D.

You can promote a wide variety of 2D effects to 3D, including titles and matte key effects. The reference information in [“Effects Reference” on page 555](#) indicates which effects you can promote to 3D. For more information, see [“Promoting 2D Effects to 3D Effects” on page 364](#) and [“Using Matte Keys with 3D Effects” on page 364](#).

Applying the 3D Warp Effect

All the 3D effects features are accessible through the 3D Warp effect in the Blend category.


For general information on adding effects to a sequence, see [“Applying Effects” on page 35](#).

To apply the 3D Warp effect:

1. Create a sequence by using standard Avid editing procedures.
For information about editing a sequence, see [“Creating and Editing Sequences” in the Help](#).
2. Enter Effect mode, for example, by selecting Toolset > Effects Editing.
For more information, see [“Entering Effect Mode” on page 41](#).
3. Click the Blend category.
4. Drag the 3D Warp Effect icon to a transition or a segment in the Timeline.



The 3D Warp Effect icon appears in the Timeline as shown in the following illustration.



5. In the Timeline, move the position indicator to the 3D Warp effect.

Using Xpress 3D Effects

The Effect Palette contains an Xpress 3D Effect category with four effects (3D Ball, 3D PIP, 3D Page Fold, and 3D Slats). Xpress 3D effects are fully compatible with Avid Xpress editing applications that include 3D effects capability. As a result, you can move sequences containing Xpress 3D effects to and from Avid Xpress editing applications. Xpress 3D effects use a subset of the parameters that are available for the 3D Warp effect.



To maintain compatibility when transferring sequences between Avid editing applications, use only Xpress 3D effects. Do not use the 3D Warp effect to create 3D effects.

Xpress 3D effects provide a fast way to apply basic 3D effects to your sequence, without using the 3D Warp effect to make custom adjustments. For example, the 3D Page Curl effect automatically creates a page curl effect when you apply it.



You can use the Shape menu in the Effect Editor to switch between the 3D shapes, but the name of the effect in the Effect Editor does not change when you change the shape. For example, when you are editing a 3D Ball effect, you can change the shape to 3D Slats. All of

the 3D Slats parameters apply to the effect but the name of the effect in the Effect Editor continues to be 3D Ball. This limitation applies to all the effects in the Xpress 3D Effect category.

Promoting 2D Effects to 3D Effects

You can promote many 2D effects to 3D. For example, if you have a 2D Picture-in-Picture effect, you can promote the effect to 3D and add 3D features like 3D borders, drop shadow, page curls, smooth curve movement, and rotation.



For information on creating a 2D Title effect, see [“Creating Titles” on page 381](#).

For reference information on which 2D effects you can promote to 3D, see [“Effects Reference” on page 555](#).

The following rules and restrictions apply to promoting effects to 3D:

- You cannot demote a 3D effect to a 2D effect (although you can immediately undo the promotion of a 2D effect to 3D if you decide that you do not want the 3D version).
- All effects that were real time in 2D are still real-time when you upgrade to 3D.

To promote a 2D effect or title to a 3D effect:

1. Enter Effect mode , for example, by selecting Toolset > Effects Editing.

For more information, see [“Entering Effect Mode” on page 41](#).

2. Click the effect icon in the sequence to select it.



3. In the Effect Editor, click the 3D Promote button.

Using Matte Keys with 3D Effects

A matte key is an effect made up of three components:

- High-contrast image or matte (also called the key)
- Background image (the image that shows through the lightest part of the matte)
- Foreground image (the image that shows through the darkest part of the matte)


For more information on Matte Key clips, see [“Creating a Matte Key Effect” on page 262](#).

You can promote real-time 2D Matte Key effects (graphics imported with alpha channel) to 3D Warp, and apply additional parameters, such as Shape Wipe effects, or X, Y, and Z positioning. You cannot promote matte keys created using the Matte Key effect from the 2D Effect Palette to a 3D matte key.

To create a matte key for use with 3D effects:


1. Import a graphic file containing an alpha channel.

Your Avid editing application creates a Matte Key clip when you import the file. In this example, the imported graphic is a title created in Adobe Photoshop.



Graphic master clip with no alpha channel (top) and Matte Key Effect clip with alpha channel (bottom) in a bin

2. Edit the Matte Key clip into your sequence as an overlay.



2D imported Matte Key title edited into a sequence

Ensure Render On-the-Fly is enabled so you can see the matte key as you are working with it. When Render-On-the-Fly is enabled, it displays a check mark in the Special menu (or the Clip menu on NewsCutter systems).

3. Promote the Matte Key clip to a 3D Warp effect as explained in [“Promoting 2D Effects to 3D Effects” on page 364](#).
4. Enter Effect mode, for example, by selecting Toolset > Effects Editing.
For more information, see [“Entering Effect Mode” on page 41](#).
5. Apply changes to additional parameters to achieve the effect you want.

Real-Time Playback of 3D Effects

In most circumstances, 3D effects play in real time, subject to the normal limitations on real-time playback described in [“Real-Time Playback of Video Effects” on page 151](#).

However, in the following cases, 3D effects cannot play in real time and appear in the Timeline with a blue dot:

- If a 3D effect has the HQ (Highest Quality) rendering option available and you turn on that option, the effect can no longer play in real time. For more information, see [“Rendering 3D Effects Using the HQ \(Highest Quality\) Option” on page 176](#).
- If you are working with HD media, the following 3D effects cannot play in real time:
 - 3D Shape effects (Ball, Page Fold, Slats), whether applied from the Xpress 3D effect category or by selecting from the Shape parameter category in the 3D Warp effect.
 - Titles promoted to 3D.
 - Imported moving Matte Key effects promoted to 3D.

In addition, some parameter adjustments to a 3D effect prevent the effect from being processed using hardware acceleration. As a result, the effect cannot play in real time.

Understanding 3D Geometry and Degrees of Rotation


This topic provides basic information about 3D coordinate geometry and degrees of motion.



Moving objects in 3D space requires an understanding of each of the 3D effects parameters and its correct order in the effects parameters hierarchy. For more information, see [“Effects Parameter Reference” on page 603](#) and [“Understanding 3D Parameter Hierarchy” on page 703](#).


In the discussions of 3D effects in this document, the terms X, Y, and Z refer to the three axes or dimensions of the image that you can manipulate in the 3D effect’s coordinate space:

- X refers to the image’s left/right direction (values increase from left to right).
- Y refers to the image’s up/down direction (values increase from bottom to top).
- Z refers to the image’s front/back dimension (values increase from back to front).




The Shape and Rotation parameters let you rotate the image around the X, Y, and Z axes. Note that you can rotate more than 360 degrees (from -720 to 720 degrees) between keyframes.

The following illustration shows how angles of rotation (in degrees) are distributed around a circle.



A positive number of degrees refers to a clockwise rotation; a negative number of degrees refers to a counterclockwise rotation. A rotation of $+45^\circ$ rotates the image clockwise by one-eighth of a full circle. A rotation of -45° rotates the image counterclockwise by one-eighth of a full circle.

The following illustration shows several rotation examples.



Working with 3D Effects Parameters

You work with 3D effect parameters in much the same way that you work with 2D effect parameters. You access, manipulate, and reset 3D effect parameters in the Effect Editor in just the same way as 2D effect parameters. You can save 3D effect adjustments as templates just as you can 2D effect adjustments. You can use the Enlarge and Reduce buttons to zoom in and out on the Effect Preview monitor just as you can with 2D effects. For more information, see [“Entering Effect Mode” on page 41](#), [“Using the Effect Editor” on page 89](#), and [“Working with Effect Templates” on page 47](#).

You can also manipulate 3D effects directly in the Effect Preview monitor. For more information, see [“Manipulating 3D Effects Directly” on page 368](#).


For specific information on each of the 3D parameters available in the Effect Editor, as well as important information on the hierarchy of 3D effects parameters, see [“Effects Parameter Reference” on page 603](#) and [“Understanding 3D Parameter Hierarchy” on page 703](#).

Manipulating 3D Effects Directly

You can perform a number of operations on an image by clicking buttons in the Effect Editor and dragging handles attached to the image in the Effect Preview monitor. This is similar to the procedures you use to directly manipulate 2D effects; some additional manipulations are possible, however, when working with 3D effects.

For more information on direct manipulation of 2D effects, see [“Manipulating Effects Directly in the Effect Preview Monitor” on page 98](#).

Various 3D effect handle buttons appear along the right side of the Effect Editor. You determine the direction and type of manipulation performed in the Effect Preview monitor by selecting one of the image manipulation buttons in the Effect Editor.



Use the Outline/Path button when you want to see the path a moving effect takes on the screen.

To manipulate a 3D effect handle in the Effect Preview monitor:

1. If your Avid editing application is not in Effect mode, enter Effect mode, for example, by selecting Toolset > Effects Editing.
For more information, see [“Entering Effect Mode” on page 41](#).
2. In the Effect Editor, click one of the image manipulation buttons to activate the specific handles.
3. Click the handles, and drag them to manipulate the image.
4. Click the image manipulation button a second time to turn off the handles.

The following illustrations show the handles for several image manipulation buttons.




Image manipulation handles. Top, left to right: Scale, Position, and Axis. Bottom, left to right: X, Y, and Z Rotation. When scaling, use the side handle to scale in X only, the top handle to scale in Y only, and the corner handle to scale in X and Y at the same time.

To see the path an image takes on the screen:



- ▶ Click the Outline/Path button.

Applying 3D Effects: Examples

The topics in this section provides examples of some basic 3D transition and segment effects, including the steps and values used to create them. You can use them to practice creating 3D effects, or to get ideas for building your own effects.

If you need more information while you are trying to complete the examples shown here, see the following sources:

- For basic information on effects editing, see [“Basics of Effects Editing” on page 35](#).
- For information on the 3D interface and moving in 3D space, see [“Understanding 3D Geometry and Degrees of Rotation” on page 366](#) and [“Working with 3D Effects Parameters” on page 368](#).
- For reference information on all 3D effects parameters and controls, see [“Effects Parameter Reference” on page 603](#).
- For basic information about editing a sequence, see [“Creating and Editing Sequences” in the Help](#).

In addition to re-creating the examples in this section, you can experiment with the default shape effects. For more information, see [“Shape” on page 718](#).



When you apply a shape effect, what you see in the Effect Preview monitor depends on where in the clip the position indicator is located. If the position indicator is at the start or end of the clip it might look as if the effect is missing.


Tips for Creating 3D Effects

The following tips apply to the examples in this section:

- Creating the sequence: Transition effects require only a two-clip sequence. Some of the segment effects require at least two tracks.
- Avoiding Insufficient Source errors: Several of these examples assume that you are creating a transition effect centered on the cut between the incoming and outgoing video. Leave enough material for the overlapping portions of the transition when you mark the source material.

If you receive an Insufficient Source message when you apply an effect to the transition, you did not leave enough source material behind for your Avid editing application to create the transition. For more information, see [“Sizing Effects to Fit the Media” on page 40](#).

- Using the Swap Sources button: When you use the 3D Warp effect as a transition and click the effect for the first time, your Avid editing application applies the effect to the incoming video. To apply the effect to the outgoing video, click the Swap Sources button in the Foreground parameter category. Click anywhere in the effect’s Timeline to view the results.



Creating a Page Fold Transition


This example uses the Page Fold effect, which treats the foreground video channel as though it were a sheet of paper being folded over to reveal another page beneath. Page Fold supports one highlight along the top edge the fold and a second lowlight under the fold.



Example of a Page Fold effect with highlight and lowlight: outgoing and incoming video sources (top) and stages of the effect (bottom)

To create the Page Fold effect:

1. Create a sequence, and apply the 3D Warp effect as described in [“Applying the 3D Warp Effect” on page 362](#).
2. Open and enable the Shape parameter category, and select Page Fold from the menu.



The default Page Fold effect appears on the incoming video. To apply the effect to the outgoing video, swap the video sources by doing the following:

- a. Open the Foreground parameter category, and click the Swap Sources button.
 - b. Click anywhere in the Effect Preview monitor's position bar to see the effect on the outgoing video.
3. Open and enable the Highlight parameter category.



4. Use keyframes to animate the Curl parameter in the Shape parameter category.
Set a value of 0 (no curl) on a keyframe at the start of the effect and a value of 100 on a keyframe at the end of the effect. For more information, see [“Working with Keyframes” on page 101](#).
5. Click the Play button or the Play Loop button to preview the effect.




Play (left) and Play Loop (right) buttons

6. (Option) Use the Transition parameters to adjust the length of the effect.
For more information, see [“Applying a Dissolve Effect Using the Transition Parameters” on page 64](#).

Creating a Cropped Foreground Effect

This example shows how to adjust 3D Warp parameters and apply them repeatedly as a template to create a consistent band of foreground segments — scaled and cropped with a soft border shadow — across a background.



Example of a cropped foreground effect: top and bottom video tracks (top left), finished look of the effect (top right) and use of the effect when saved as a template and applied to several segments in the Timeline (bottom)

To create a foreground band of footage:

1. Build the sequence with the background footage on the bottom track and the foreground footage on the top track.
In this example, dissolves are added between a series of foreground segments.
2. Apply the 3D Warp effect to one segment of the top video track.
3. Enter Effect mode, for example, by selecting Toolset > Effects Editing.
For more information, see [“Entering Effect Mode” on page 41](#).
4. Click the segment to display the parameters in the Effect Editor.
5. Adjust the effect parameters as shown in the following table.

Parameter Category	Parameter Settings
Crop	T (top): 600, L (left): -999, B (bottom): -600, R (right): 999

Parameter Category	Parameter Settings
Scaling	Wid:110, Hgt: 100
Position	Enable (leave parameter defaults)
Border	Select a dark color. For more information on color selection, see “Adjusting a Color Parameter for an Effect” on page 96 . Width: 40, Soft: 100, H (hue): 0, S (saturation): 0, L (luminance): 255

6. Save the parameters as a template by dragging the effect icon from the Effect Editor to a bin.
7. Apply the template from the bin to the remaining segments on the top track.
8. Click the Play button or the Play Loop button to preview the effect.



Play (left) and Play Loop (right) buttons

The foreground segments play through smoothly with the same scale, border, and cropping effect against the background.

Corner Pinning an Image

Corner pinning is a way of precisely positioning a foreground image over an image in the background video track, with matching perspective. You “pin” the foreground image onto the background image and adjust the corners to give the desired perspective.

This example shows the background and foreground videos used to create a segment transition using corner pinning. The segment starts with the foreground image “pinned” onto the video monitor in the scene. The image then moves off the TV and eventually fills the screen.



Example of a Corner Pin effect: background and foreground video (top), and stages of the effect (bottom). The foreground video starts pinned to the monitor screen in the background image, and moves off it until it fills the frame, completing the transition.

To corner pin an image:

1. Create a segment with two video tracks, placing the foreground video on the top track.
For information about editing a sequence, see “Creating and Editing Sequences” in the Help.



2. Apply the 3D Warp effect to the top track.

3. If your Avid editing application is not in Effect mode, enter Effect mode, for example, by selecting Toolset > Effects Editing.

For more information, see [“Entering Effect Mode” on page 41](#).

4. Position, scale, and rotate your image if necessary.


For best results, adjust the Position, Scale, and Rotate parameters before you use Corner Pin. The center of the image for Corner Pin scale and rotation adjustments will be closer to the apparent center of the image, and you can get the results you want more easily.

5. Position the corners using one of the following methods:

► Use the Corner Pin button:

- a. In the Effect Editor, click the Corner Pin button to activate the handles.
- b. Click the handles, and drag to manipulate the image.
- c. Click the Corner Pin button a second time to turn off the handles.





► Use the Quick Pin feature:

- a. In the Effect Editor, click the Corner Pin button to activate the handles.
- b. Press and hold the Ctrl and Alt keys (Windows), or the Command and Option keys (Macintosh), then position the pointer where you want the highlighted corner to be corner pinned, and click.

The next corner is highlighted.

- c. Continue using the Ctrl and Alt keys (Windows), or the Command and Option keys (Macintosh), while clicking until the image is positioned where you want it.

The next corners continue to be highlighted in a clockwise rotation each time you click.

- d. Click the Corner Pin button a second time to turn off the handles.

► Use the Corner Pin parameter category:

- a. In the Effect Editor, click the Corner Pin button to activate the handles.
- b. Use the X and Y sliders in the Corner Pin parameter category to position the image.

The Corner Pin parameter category has a button for each corner, letting you pin one corner at a time.

6. Click the Play button or the Play Loop button to review your edit.



Play (left) and Play Loop (right) buttons

To return a corner to the default position:


1. In the Corner Pin parameter category, click the button for the corner you want to reset.
2. Alt+click (Windows) or Option+click (Macintosh) the Corner Pin Enable button.

Creating a Stamp

The Stamp category of the 3D Warp effect lets you make certain effects — such as titles and Matte Key effects — remain on screen while other effects come and go, even though the effect segment itself has ended. For example, you can stamp a product or channel logo onto the lower corner to act as a type of watermark effect without adding additional layers onto the sequence.

In the following example, two effects are applied sequentially on the top track. Each one has Stamp enabled on the last keyframe, which lets each element remain in place as the next element appears on the screen.

Both elements remain in place, and you could add additional stamps until you enable Clear to clear the Stamp buffer.



Example of a Stamp effect: the stamp element zooms into position from full screen (top left), is “stamped” in place at the end of the first segment (top center), and remains in place for the second segment (top right)

To create a stamp:

1. Create the image you want to use as a stamp.

For example, you can use the Title tool to create a title or you could import a PICT image.

2. Create a segment with at least two video tracks.

For information about editing a sequence, see “Creating and Editing Sequences” in the Help.


If you want the stamp to be in the foreground, it must be on the top track.

3. Add the track with your stamp image to the segment.
4. Enter Effect mode, for example, by selecting Toolset > Effects Editing.

For more information, see [“Entering Effect Mode” on page 41](#).



5. Click the 3D Promote button to turn on the 3D parameters.
6. Create a keyframe at the point where you want the stamp to occur, and make sure the keyframe is selected.
7. Open and enable the Stamp parameter category, and select Stamp Image.



8. (Option) Repeat steps 6 and 7 to enable Stamp on more than one keyframe.
9. Click the Play button or the Play Loop button to review your edit.



Play (left) and Play Loop (right) buttons

To clear a stamp:

1. Create a keyframe at the point where you want the stamp to be cleared, and ensure the keyframe is selected.
2. In the Stamp parameter category, click the Clear Image button.
Everything in the Stamp buffer is cleared.

Applying a Chroma Key Effect

You can use the options in the Foreground category of 3D Warp to apply a chroma key effect. You also have the option of using the SpectraMatte option for a chroma key that has higher quality and gives you greater control over the final look of the effect. For more information, see [“Key: SpectraMatte Effect” on page 578](#).

To apply a Chroma Key effect:

1. Edit the foreground image onto track V2 and the background image onto track V1 in the Timeline.

For information about editing a sequence, see “Creating and Editing Sequences” in the Help.

2. Apply the 3D Warp effect to track V2.

For more information, see [“Applying the 3D Warp Effect” on page 362](#).



3. Open the Foregnd (foreground) parameter category, click the Fast Menu button, and select Chroma Key.
4. Click the Color Preview window, and press and hold the mouse.

5. When the eyedropper appears, drag it to the most representative area of color to be keyed and release the mouse.



When selecting a color, stay away from corners of the frame or the area immediately around the foreground because these areas might contain subtle shades of gray.

When you are finished, your Avid editing application replaces the color with the video on track V1.

6. (Option) If your Avid editing application includes the 3D Spill Suppression parameter category, use Spill Suppression if necessary to remove spill in the foreground image.
7. (Option) Use the sliders in the Foregnd parameter category to make refining adjustments to improve the look of the key.

12 Creating Titles

You can create titles in your Avid editing application using either the classic Avid Title tool or the Marquee® Title tool. Titles can incorporate text, graphic objects, imported graphics, and video. This chapter provides information on using the Title tool to create titles.

- [Opening the Title Tools](#)
- [Using Marquee](#)
- [Overview of Title Creation in the Title Tool](#)
- [Installing Fonts for Use in the Title Tool](#)
- [Understanding the Title Tool](#)
- [Toolbar Reference for the Title Tool](#)
- [Using the Selection and Text Tools](#)
- [Understanding the Drawing Environment](#)
- [Setting Up the Drawing Environment](#)
- [Creating Text](#)
- [Sizing and Positioning Text Objects](#)
- [Editing a Text String](#)
- [Formatting Text](#)
- [Creating Graphic Objects](#)
- [Creating Rolling and Crawling Titles](#)
- [Modifying and Manipulating Title Objects](#)
- [Modifying Box Corners, Lines, and Borders on Title Objects](#)
- [Understanding Color and Transparency Controls in the Title Tool](#)
- [Selecting Colors and Setting Transparency](#)
- [Adding Shadows to Title Objects](#)
- [Adjusting Shadows on Title Objects](#)
- [Manipulating Title Objects](#)
- [Saving Titles](#)

- [Revising a Title in a Bin](#)
- [Creating and Using Title Templates](#)
- [Saving and Recalling Title Styles](#)
- [Exporting a Title as a Graphics File](#)

Throughout this chapter:

- “Title” refers to both text and graphics.
- “Title tool” refers to the classic Avid Title tool.
- “Marquee” refers to the Marquee Title tool.

Opening the Title Tools

You can open either the Title tool or Marquee, and you can bring the Title tool to the foreground if it is covered by another window, using standard menu commands.


To open one of the Title tools:

1. (Option) In the monitor window, move the position indicator to the video frame you want to use as a background.

If you are not using video as the background, you can ignore this step. For more information, see [“Setting Up the Drawing Environment” on page 391](#).

2. Select Clip > New Title or Tools > Title Tool.

The New Title dialog box opens.



3. Do one of the following:

- ▶ To use Marquee, click Marquee.

Marquee opens. For information on Marquee, see [“Using Marquee” on page 383](#).

- ▶ To use the Title tool, click Title Tool.

The Title tool opens. The Text tool is automatically selected, and the pointer becomes an I-beam, ready for entering text.

If you know you want to create only Marquee titles or only standard titles for the current session, select **Persist** before you click **Marquee** or **Title Tool**. For the rest of your editing session, your Avid editing application automatically opens the title tool you selected.

You turn off automatic selection from the **Settings** list — open the **Marquee Title Setting** dialog box and click **Ask Me**.

To bring the Title tool to the foreground:

- ▶ Select **Windows > Title Tool**.

Using Marquee

Marquee is both an alternative tool for creating basic titles and a tool for creating much more sophisticated titles such as 3D and animated titles. Marquee opens from within your Avid editing application but has its own self-contained user interface, including its own Help system.

For information on opening Marquee, see [“Opening the Title Tools” on page 382](#).

For information on creating titles with Marquee and on using Marquee in conjunction with your Avid editing application, see the *Avid Marquee Title Tool User’s Guide* or the Avid Marquee Title Tool Help. The “Creating Basic Titles for Your Avid Editing Application” chapter provides a good starting point for basic work in Marquee.



You can promote titles created using the classic Avid Title tool to Marquee titles. You cannot use the classic Avid title tool to edit titles that you promote to or create in Marquee.

Overview of Title Creation in the Title Tool

The following is an overview of the tasks you perform to create a title with the Title tool:

- Set up the drawing environment.
For example, you can choose whether to display a color background or a frame of video from your sequence. You can also use safe colors or safe title and action guidelines, or apply a grid for the placement of objects. For more information, see [“Understanding the Drawing Environment” on page 389](#).
- Create a new title with the Title tool.

You create text and graphic objects, and then apply and adjust borders, colors, transparency, and shadows as necessary. For more information, start with [“Creating Text” on page 392](#) and [“Creating Graphic Objects” on page 400](#).

- Save the title and exit the Title tool.

When you save a new title, you select a resolution that is compatible with your project and a target drive for the title media. You can also save just the styles for the title for future use. When you close the Title tool, the new title appears in the bin and in the Source monitor, ready for editing. For more information, see [“Saving Titles” on page 421](#) and [“Editing with Titles” on page 431](#).

Installing Fonts for Use in the Title Tool

You can use any font that is installed on your system when you create titles in the Title tool. When installing and using fonts, consider the following:


- If you want to apply a special font that is not currently on the system, you must install the font first before creating titles.
- If you are bringing a project from another system, ensure that you have installed any fonts used in titles contained in the project. The fonts must match exactly (you cannot use variations of the font in the same font family). If the Title tool does not recognize a font contained in a title, the Font Replacement dialog box opens to let you substitute an alternative font.
- If you are bringing a project from the Macintosh platform to the Windows platform, or from the Windows platform to the Macintosh platform, you might need to substitute a font from the new platform for an existing font in the project. Windows and Macintosh fonts sometimes differ even when they have the same name. If the Title tool does not recognize a font contained in a title, the Font Replacement dialog box opens to let you substitute an alternative font.
- If you intend to create titles with font sizes of 128 points or larger, use TrueType® fonts. Some fonts cannot display consistently at sizes of 128 points or higher, but TrueType fonts can accommodate larger font sizes.



For more information on installing fonts, see your Windows or Macintosh system documentation.

Understanding the Title Tool

The following illustration shows a title over a video background.



Example of a title over a video background in the Title tool. The two dotted-line rectangles are the safe action area (outside) and safe title area (inside) guidelines.

The Title tool has the following major components:

- A video background based on a sequence or a color background that you create.

When your project uses the 16:9 aspect ratio, the Title tool uses the 16:9 aspect ratio also, and saved titles appear correctly in the monitors.

For more information, see [“Understanding the Drawing Environment” on page 389](#) and [“Setting Up the Drawing Environment” on page 391](#).

- The title or graphic in the foreground that you create.
- The safe title and safe action area guidelines.

For more information, see [“Understanding the Drawing Environment” on page 389](#) and [“Setting Up the Drawing Environment” on page 391](#).

- The toolbar at the bottom of the screen.

Topics throughout this chapter describe the use of these tools. For information on the two most widely-used tools, the Selection tool and the Text tool, see [“Using the Selection and Text Tools” on page 388](#). For detailed reference information on all the tools in the toolbar, see [“Toolbar Reference for the Title Tool” on page 386](#).


- In addition, title-related menu commands appear in the File, Edit, Object, and Alignment menus.





Topics throughout this chapter describe the use of these menu commands.











Toolbar Reference for the Title Tool



The toolbar at the bottom of the Title tool contains tools and menus you can use to create and edit text and objects. They work much like similar tools in other drawing and paint programs.

For a general introduction to the layout of the whole Title tool, see [“Understanding the Title Tool” on page 385](#).



Component		Description
1	Selection tool	 Changes the pointer to an arrow and lets you select text or objects for operations. For more information, see “Using the Selection and Text Tools” on page 388 .
2	Text tool	 Changes the pointer to an I-beam and lets you enter text. For more information, see “Using the Selection and Text Tools” on page 388 and “Creating Text” on page 392 .
3	Video Placement tool	 Changes the pointer to a hand and lets you pan around the entire video clip within the Title tool.
4	Drawing tools	 Let you draw boxes, circles, ovals, and lines. For more information, see “Creating Graphic Objects” on page 400 .

Component	Description
5 Text formatting tools	 <p>Let you set various text attributes such as font, font size, kerning, and leading. For more information, see “Formatting Text” on page 394.</p>
6 Color Selection boxes	 <p>Let you change the color of text and objects. For more information, see “Selecting Colors and Setting Transparency” on page 412.</p>
7 Transparency Level boxes	 <p>Let you change the transparency levels of text and objects. For more information, see “Selecting Colors and Setting Transparency” on page 412.</p>
8 Color and Transparency Blend tools	 <p>Let you create a blend between two colors or two transparency values. For more information, see “Selecting Colors and Setting Transparency” on page 412.</p>
9 Shadow tools	 <p>Let you create drop shadows and depth shadows for text and objects and to preview the degree of softness set for shadows. For more information, see “Adding Shadows to Title Objects” on page 415.</p>
10 Styles button	 <p>Displays examples of the styles you defined and lets you select one. For more information, see “Recalling a Title Style” on page 428.</p>
10 Save Style Parameter button	 <p>Displays the Title Style sheet and lets you modify it and save the changes. For more information, see “Saving a Title Style” on page 427.</p>
11 Line attribute tools	 <p>Let you change the corners of boxes, line and border thickness, and arrowhead styles. For more information, see “Modifying Box Corners, Lines, and Borders on Title Objects” on page 408.</p>
12 Templates button	 <p>Lets you create a standard format for text and graphics that you use regularly. The template prevents you from changing the position, colors, shadows, or graphics, which ensures consistency. For more information, see “Creating and Using Title Templates” on page 425.</p>
13 Background Selection tools	 <p>Let you switch between a video and an opaque background and change the color of opaque backgrounds. For more information, see “Setting Up the Drawing Environment” on page 391.</p>

Component		Description
14	Crawling Title button 	Lets you create crawling titles. For more information, see “Creating Rolling and Crawling Titles” on page 401 .
15	Rolling Title button 	Lets you create rolling titles. For more information, see “Creating Rolling and Crawling Titles” on page 401 .


Using the Selection and Text Tools


The Selection tool and the Text tool are the tools you use most frequently in the Title tool. You use the Selection tool when selecting and adjusting whole objects in a title (whole pieces of text or graphic objects). You use the Text tool when you create or edit text content.



Selection tool (left) and Text tool (right) in the Title Tool toolbar

To select a single object:


- ▶  Click the Selection tool, and then click an object.
Selection handles appear around the object.



To select multiple objects, do one of the following:

- ▶ Shift+click with the Selection tool.
- ▶ Click outside the objects, and drag to surround the objects with a lasso.

To use the Text tool:

- ▶  Click the Text tool, click anywhere within the text object, and begin typing.
An I-beam pointer indicates your position within the text. The Text tool remains selected until you select another tool.



By default, the Text tool is active when you open the Title tool, and you can begin entering text as soon as you click in the Title tool.

To switch between the Selection tool and the Text tool:

- ▶ Press the Alt key (Windows) or Option key (Macintosh), and click anywhere in the Title tool.

To use the Selection tool temporarily when another tool is active:

- ▶ Press and hold the Ctrl and Alt keys (Windows), or the Ctrl and Option keys (Macintosh).



After you use a tool in the toolbar, the Title tool reverts to the Selection tool, and the pointer becomes an arrow. To prevent a tool from automatically reverting to the Selection tool, double-click the tool's icon.

Understanding the Drawing Environment

This topic describes aspects of the display of titles and their backgrounds in the Title tool, as well as the display of visual guides that can help you as you create titles. For information on how to control these display features, see [“Setting Up the Drawing Environment” on page 391](#).

You can set or change these features at any time during your work on a title. These preferences are User settings, so they appear each time a particular user opens the Title tool.

Anti-Aliased Preview

Your Avid editing application creates text and objects in titles anti-aliased with an 8-bit alpha channel. Anti-aliasing ensures that text, lines, and object edges appear smooth, regardless of size. You can preview a title to see the title drawn with anti-aliasing, just as it will be saved. Your Avid editing application always saves titles in anti-aliased format.

The display behavior for title objects when anti-aliased preview is on is as follows:

- You can alter the graphics characteristics of title objects (including colors, shadows, borders, and transparency) without losing the anti-aliased preview.
- You can select text objects and apply text styles from the Styles menu without losing the anti-aliased preview.
- When you click a text object for editing, the Title tool displays the text without anti-aliasing. When you finish editing the text and click outside the object to deselect it, the Title tool restores the anti-aliased preview.

Safe Colors

If you plan to use your title for television broadcast, you can select the Safe Colors command from the Object menu. This command displays only low saturation colors for use in text, objects, and background. Colors with low saturation look best when combined with video. By default, Safe Colors is turned on.

Safe Title and Safe Action Guidelines

By default, the Title tool displays two outlined boxes to use as guidelines. The inner box is the safe title area. All text for television broadcast should remain within this inner box. The outer box is the safe action area for video display. These guidelines are self-adjusting for PAL and NTSC projects and for 4 x 3 or 16 x 9 display.



You can customize the Effect Grid display. For more information, see “Understanding the Effect Grid” on page 83.


Alignment Grid

You can display an alignment grid to help you position text and objects. The visible grid is not part of the title, and your Avid editing application does not store it when you save the title.

The snap grid is an invisible grid that helps position and connect objects. The snap grid has four lines for each line in the visible grid. Each square in the grid is subdivided by four invisible vertical and horizontal grid lines. Text and objects can snap to these lines.

Title Backgrounds

You use the Video Background button to switch between a video background and an opaque color background, or to update the video background with the currently selected frame in the Timeline.



Background Color window (left) and Video Background button (right) in the Title Tool toolbar

If there is a sequence in the Record monitor, the Title tool opens with a video background. The location of the position indicator in the Timeline at the time you open the Title tool determines the initial video frame that displays. If there is no sequence in the Record monitor, the Title tool opens with no video showing (the background appears black).

The Video Background button is green when you are creating a title for display over a video background.

The background video frame is a reference that helps you position title objects relative to the video you plan to edit the title over. It does not become part of the title you create. You can edit the title anywhere else in the current sequence or in another sequence.



When you create a title with a color background, it is opaque and you cannot key it over video.

You cannot create rolling or crawling titles with a color background. You can create a separate color background as a title and then edit the rolling or crawling title over it in the sequence.

Setting Up the Drawing Environment

Use the following procedures to set up the display of titles and their backgrounds in the Title tool, as well as the display of visual guides that can help you as you create titles. For more information, see [“Understanding the Drawing Environment” on page 389](#).

To switch the display of anti-aliased titles on or off:

- ▶ Select Object > Preview.

A check mark indicates that Preview mode is enabled.

To display only safe (low saturation) colors:

- ▶ Select Object > Safe Colors.

To turn the safe title area or safe action area guidelines on or off:

- ▶ Select Object > Safe Title Area/Global Grid.

To display a grid:

- ▶ Select Alignment > Show Alignment Grid.

To snap to a grid:

- ▶ Select Alignment > Align to Grid.

When you create or drag an object in the Title tool, the object snaps to the nearest grid line.

To update the video background:



1. Click the Video Background button in the toolbar to activate video background if you have not already done so.
2. Load the sequence into the Record monitor.
For information about editing a sequence, see “Creating and Editing Sequences” in the Help.
3. Move the position bar in the Timeline or in the monitor to display the new frame.
4. Click again in the Title tool to activate its window.

The background updates to reflect the current contents of the Record monitor.

To create a title that appears over an opaque color background:

1. (Option) Click the Video Background button to switch off the video background if it was previously turned on.
2. Click and hold on the Background Color (Bg) window.
The Title Tool Color Picker dialog box opens.
3. Use the Title Tool Color Picker dialog box, eyedropper, Windows Color dialog box, or Macintosh Colors panel to select a color.

For a description of how to use these tools, see [“Selecting Colors and Setting Transparency” on page 412](#).

The default background color is black.

Creating Text

You create new text by using the Text tool. You can also copy and paste text into the Title tool directly from a word processing or text editing application.

In addition to static text objects, you can also create text objects in the Title tool that scroll vertically on the screen (rolling titles) or that crawl horizontally across the screen (crawling titles). For more information, see [“Creating Rolling and Crawling Titles” on page 401](#).



Your Avid editing application limits the size of text objects you can create in the Title tool. Avoid pasting large blocks of text (numerous pages in a word processor) into the Title tool. Instead, consider pasting smaller blocks of text into separate text objects. For more information, see [“Page Count Limits for Rolling and Crawling Titles” on page 401](#).

To create text:

1. Click the Text tool in the toolbar.
The pointer becomes an I-beam.
2. Click the position in the frame where you want to add text.
An insertion point appears.
3. Type the text.
To insert a line return, press Enter (Windows) or Return (Macintosh).



Text is word-wrapped automatically as you type. You can adjust the wrapping by changing the width of the text object. For more information, see “Sizing and Positioning Text Objects” on page 393.



4. When you finish typing, click the Selection tool in the toolbar to deselect the text object.

To copy and paste text into the Title tool:

1. In a word processor or text editor, open the text file and select the text.
2. Select Edit > Copy.
3. In the Title tool in your Avid editing application, click the Text tool in the toolbar.
The pointer becomes an I-beam.
4. Click the position in the frame where you want to add text.
An insertion point appears.
5. Select Edit > Paste.
The pasted text takes on the attributes currently set in the Title Tool toolbar.

Sizing and Positioning Text Objects

You can resize and reposition text objects by dragging directly in the Title tool. When you resize a text object, the text remains the same size but rewraps to fill the reshaped area.

When you create text that is aligned on the left side using left justification (the default), you can eliminate the unused space on the right side of the newly created text object, especially if you want to use the Alignment menu commands.

To resize a text object:

1. Click the Selection tool, and click the text object.
2. Click one of the object selection handles for width, and drag to resize.



You can resize only the width of a text object. The height of a text object is automatically determined by the number of words and the size of text.

To eliminate unused space on the right side of a left-aligned text object:

- ▶ Click the middle selection handle on the right side of the text box, and drag it to the left until it is closer to the text.

To reposition a text object:

1. Click the Selection tool, and click the text object.
2. Move the text by doing one of the following:
 - ▶ Click in the middle of the object, and drag it to a new position.
 - ▶ Use the arrow keys to move the object one pixel at a time.
 - ▶ Use commands in the Alignment menu to position the text.

For more information, see [“Manipulating Title Objects” on page 418](#).

Editing a Text String

To edit an existing text string;



1. Click the Text tool, and click anywhere in the text.
2. Perform any of the following tasks:
 - ▶ Use the arrow keys to move around within the text string.
 - ▶ Type additional characters.
 - ▶ Press Enter (Windows) or Return (Macintosh) to insert a line return.
 - ▶ Drag to select characters.
 - ▶ Use the Cut, Copy, and Paste commands from the Edit menu.
 - ▶ Use the Delete key.
 - ▶ Change the formatting of the selected text, as described in [“Formatting Text” on page 394](#).

Formatting Text

The text formatting tools control the appearance of text. You can click a text object with the Selection tool to format all the text within it, or you can use the Text tool to select a string of text within a text object to format individual characters or words. The following illustration shows the text formatting controls in the Title Tool toolbar.



In addition to the text-specific formatting described in this section, you can modify or manipulate text objects in a variety of other ways. For more information, see [“Modifying and Manipulating Title Objects” on page 407](#).

While you type text, only the text color is apparent. Shadows, outlines, and other color attributes appear when you finish typing the text and click the Selection tool.



If you want to create text elements in the title with different appearances, create a separate text object for each set of attributes.

Setting Default Text Attributes

When you start your Avid editing application and open the Title tool, it uses default text attributes. You can change the defaults at any time. Changes you make to the default text attributes apply until you quit your Avid editing application.

To change the default text attributes:



1. Click the Selection tool.
2. Click in the Title tool but do not select any text.
3. Change any of the text attributes.

Whenever you start typing a new text string, the Title tool uses your new defaults.

Selecting a Font

The Font Selection button displays the name of the current font for a text selection and lets you change the font. When you first open the Title tool, the font listed is the preferred system font.



Font Selection button in the Title Tool toolbar

To display all the fonts currently installed on the system:

- Click the Font Selection button.

To change the font:

- ▶ Click the Font Selection button, and select a font.

The Title tool displays the name in the Font Selection button and uses this font for text until you change it during the editing session.



When you select a text object, the Font Selection button displays the name of the font in the text object.

Changing Point Size

The point size controls the size of the selected text. A *point* is a typographical unit of measure. There are 12 points to the pica and 72 points to the inch.

You can enter a point size either before or after you type text.



Point Size text box (left) and Point Size button (right) in Title Tool toolbar

To change the point size, do one of the following:

- ▶ Click the Point Size button, and select a standard point size from the menu.
- ▶ Double-click in the text box, type a point size between 5 and 999, and then press Enter (Windows) or Return (Macintosh).
- ▶ Click in the text box, and use the Up Arrow and Down Arrow keys to change the value incrementally.

Making Text Bold or Italic

The Bold and Italic buttons are located under the Point Size text box. The Object menu also contains commands for bold and italic.



Bold button (left) and Italic button (right) in Title Tool toolbar

To make text bold or italic:

1. Select the text you want to change.
2. Do one of the following:
 - ▶ Click the Bold button or the Italic button.
 - ▶ Select Object > Bold or Object > Italic.

To remove bold or italic formatting:

- ▶ Repeat the procedure.

Justifying Text

Justification controls the alignment of text in an existing text object and also when you type text in a new text object. The text justification buttons appear below the Font Selection button in the Title Tool toolbar.



Text justification buttons in the Title Tool toolbar

To justify the text, do one of the following:

- ▶ Click the left text justification button to align text with the left side of the text object.
- ▶ Click the center button to center the text.
- ▶ Click the right button to align text with the right side of the text object.

Kerning Text

Kerning improves the appearance of titles by controlling the amount of space between characters. You can expand or condense the character spacing to make text more readable or to create special effects, such as dramatically expanded spacing in a title.

You can kern the text for an entire text object, or you can manually kern individual character pairs or character strings. For example, if you mix italic and plain versions of a font in a title, you might want to adjust the spacing between characters.

You use the Kerning button to select predefined kerning options or the Kerning text box to specify your own custom kerning value. Positive numbers increase the spacing; negative numbers decrease the spacing. You can also use the arrow keys to make incremental adjustments.



Kerning text box (left) and Kerning button (right) in the Title Tool toolbar

 *For individual characters or selected groups of characters, the arrow keys provide the only way to adjust kerning.*

You can select the kerning value before you type text.

To adjust kerning manually with the arrow keys:



1. Click the Text tool in the toolbar.
2. Click between a character pair, or select a group of characters to be kerned.
3. Press the Alt key (Windows) or Option key (Macintosh), and use the Left Arrow key or the Right Arrow key to increase or decrease the kerning.

To adjust kerning with predefined sizes:

1. Select the text.
2. (Option) Click the Kerning button, and select Pair Kerning to eliminate excessive space between some character pairs.

Pair kerning works only on fonts that support kerning tables (for example, Palatino).

3. Click the Kerning button, and select a kerning option:

Option	Description
Loose	Adds space between letters
Normal	Leaves spacing unchanged
Tight	Closes up the spacing between the letters



Top to bottom: loose, normal, and tight kerning

To adjust kerning with the text box:

- ▶ Click in the Kerning text box, and type a positive or negative numerical value.
Values are a percentage of the point size.
- ▶ Click in the Kerning text box, and use the Up Arrow and Down Arrow keys to change the value incrementally.
The kerning for the entire text object changes.

Adjusting Leading

Leading controls the line spacing between lines in a title. Leading is measured in points, from baseline to baseline of the lines of text. The Title tool uses the leading that is built into the font as the default. Positive leading values add space and negative values decrease space. You might want to add leading for sans serif, tall, or boldface fonts, and for fonts with a strong vertical emphasis.



Leading text box in the Title Tool toolbar

To set leading:

- ▶ Click in the Leading text box, and type a number to indicate the leading value you want.
The Title tool adjusts leading immediately.

Creating Graphic Objects

You use the drawing tools to create graphic objects such as squares, rectangles, circles, ovals, and lines. After creating graphic objects, you can modify or manipulate them in a variety of ways. For more information, see [“Modifying and Manipulating Title Objects” on page 407](#).



Drawing tools in the Title Tool toolbar



By default, when you use a drawing tool and deselect the created object, the pointer reverts to the Selection tool. To avoid this, double-click the drawing tool when you select it in the Title tool toolbar.

To draw a square or a rectangle:



1. Click the Square and Rectangle tool in the toolbar.
The pointer becomes a crosshair pointer.
2. Click in the Title tool, and drag to create an object.
Shift-drag to constrain the object to a square.



Example of a rectangle drawn over a video background

To draw a circle or an oval:



1. Click the Oval tool in the toolbar.
The pointer becomes a crosshair pointer.
2. Click in the Title tool, and drag to create an object.
Shift-drag to constrain the object to a circle.

To draw a line:




1. Click the Line tool (slanted line) in the toolbar.
The pointer becomes a crosshair pointer.
2. Click in the Title tool, and drag to create a line.

Shift-drag to constrain the line to a horizontal or vertical line.

Creating Rolling and Crawling Titles

You can create title text and graphics that roll up the screen or crawl across the screen. You can refine the motion after you edit the title into your sequence.


 *Rolling and crawling titles are non-real-time effects. You can step through the effect in a Source monitor, the Composer monitor, or the Effect Preview monitor, but you must render the effect to play it.*

Rolling titles scroll vertically, moving from top to bottom or from bottom to top.




Left to right: example of start, middle, and end of a bottom-to-top roll.

Crawling titles scroll horizontally, moving from right to left or from left to right.



Left to right: example of start, middle, and end of a right-to-left crawl.

 *You cannot save a rolling or crawling title with a color background even though you can set the Title tool to display a color background while you create the title. To place your rolling or crawling title over a color background, you must export the background as a PICT file, reimport it (with Ignore Existing Alpha selected in the Import dialog box), edit it into your sequence, and then edit your title onto a new layer above the background graphic.*

Page Count Limits for Rolling and Crawling Titles

Rolling and crawling titles form pages in the Title tool that are similar to the pages you create with a word processor. A page in a rolling or crawling title is a unit the size of a PAL, NTSC, or HD frame. The following table lists the page limits for different projects.

HD Resolution	Type	Page limit	SD Resolution	Type	Page limit
1080i and 1080p	Rolling	29	NTSC	Rolling	67
	Crawling	4		Crawling	11
720p	Rolling	44	PAL	Rolling	56
	Crawling	6		Crawling	11

Typing more text, increasing the size of the font, or adjusting kerning and leading all affect the number of pages in the title. If you reach the page count limit while you are typing text, the title stops getting bigger and text entry stops.

If you attempt to change the text formatting in a way that would make the title exceed the page count limit, a message box opens. To cancel the operation and keep the title within the page count limit, click OK.

Workflow Options for Creating Crawling Titles

Rolling titles scroll in the direction of the roll as you type the text, but crawling titles do not scroll horizontally in the direction of the crawl during typing. When you create crawling text, consider the following workflow options:

- Type the text first as a rolling title. This lets you view the text as it scrolls down during typing, and provides you with a scroll bar on the right side of the screen for moving quickly through the text. You can then click the Crawl button in the toolbar to convert the text to a crawling title before resizing, reformatting, and saving the title.
- Use a small font size, such as 12 point, to view as much of the text in the window as possible before changing the font size and resizing the text box in a horizontal direction.
- Use other options to control the text in the Title tool. For example, you can create objects and move or copy them to specific pages, insert pages, and delete pages. For more information, see [“Working with Pages in Rolling or Crawling Titles” on page 405](#).

Using Auto Size Mode for Rolling and Crawling Titles

Auto Size mode adds or removes pages automatically as you add, delete, or reformat the text. Auto Size mode is on by default when you click the Rolling Title button or the Crawling Title button.

You can turn off Auto Size mode if you want to add extra pages before or after the text (for example, to make room for additional title elements). For more information, see [“Working with Pages in Rolling or Crawling Titles” on page 405](#).

To switch Auto Size mode off or on:

- ▶ Select Object > Auto Size Mode.

A check mark indicates that Auto Size mode is on.

Creating Text in a Rolling Title or a Crawling Title

Before you create a rolling or crawling title, set the text formatting defaults for attributes such as font, point size, leading, and kerning. For more information, see [“Setting Default Text Attributes” on page 395](#).

When you type the text for a rolling or crawling title, lines of text wrap within the safe title area, and the title scrolls down as you type. For rolling titles, this provides you with a sense of positioning, word wrap, and page count limitations.

To type rolling or crawling title text:

1. Do one of the following:

- ▶ Select Clip > New Title.
- ▶ Select Tools > Title Tool.


The Title tool opens.



2. Click the Text tool in the toolbar.

3. Do one of the following:

- ▶ Click the Rolling Title button to enter Rolling Title mode.
- ▶ Click the Crawling Title button to enter Crawling Title mode.



Top to bottom: Crawling Title button, Rolling Title button, and Page Number text box in the Title Tool toolbar

The button changes to green, and a Page Number text box appears in the lower right corner of the Title tool.



You cannot create rolling and crawling titles over a color background, although you can preview them with a color background. For rolling and crawling titles, the Background Selection tools are set to Video Background and the Video Background button changes to green.

4. Type the title text.

The text wraps automatically as you type.



5. When you are finished, click the Selection tool in the toolbar to select the new text object.

Resizing the Width of a Rolling Title or a Crawling Title

You resize titles by manipulating their object selection handles.



You can resize only the width of a rolling or crawling title. The Title tool determines the height of your title by the amount of text it contains.

If you resize a crawling title, save it before rendering to ensure the correct rendering result.

To resize a rolling title or a crawling title:



1. Click the Selection tool, and click the title object.
2. Click the object selection handle, and drag to resize the title until it appears as you want.

Using the Make Crawl Command to Position a Crawling Title

After you enter and edit your crawling title text, you can transform the title into a single-line text object and position it on the lower third of the screen.

To position a crawling title:

- ▶ Select Object > Make Crawl.

Scrolling Through a Rolling Title or a Crawling Title

When you create a rolling or crawling title, a scroll bar appears along the right side of the Title tool video background for moving vertically through the rolling title, and at the bottom for moving horizontally through a crawling title.

To scroll through a rolling or crawling title, do one of the following:

- ▶ Use standard techniques for scrolling, such as clicking the arrow icons, dragging the scroll box, or clicking in the scroll bar.
- ▶ Press the Home or the End key to go to the beginning or end of the title.
- ▶ Press the Page Up or the Page Down key on the keyboard to move through a rolling title one page at a time.
- ▶ (Rolling titles only) Press the Up Arrow or the Down Arrow key to move the pointer through a rolling title one line at a time.

Working with Pages in Rolling or Crawling Titles

When you first create a rolling title or a crawling title, a Page Number text box appears in the lower right corner of the Title tool. The Page Number text box reflects your current position in the title.

You can go to a specific page, add and delete pages, insert blank pages, and copy or move material to a page.



Page Number text box in the Title Tool toolbar

To go to a different page:

1. Click the Page Number text box.
2. Do one of the following:
 - ▶ Type a page number for a specific page.
 - ▶ Use the Up Arrow and Down Arrow keys to cycle through the page numbers.
3. Press Enter (Windows) or Return (Macintosh).

The selected page appears.

To add pages:

1. If Auto Size mode is on (a check mark appears next to Auto Size Mode in the Object menu), turn it off by choosing Object > Auto Size Mode.

The Add Page command is not available when Auto Size mode is on.

2. Select Object > Add Page.

The Title tool adds a page to the end of the title. You can select Add Page repeatedly to continue adding pages up to the maximum page count.

For more information on maximum page counts, see [“Creating Rolling and Crawling Titles” on page 401](#).

3. Select text or graphic objects in the title and position them within the range of available pages, or create new elements.

To insert a blank page into a rolling or crawling title:

1. Select Object > Insert Page.

The Insert Page dialog box opens.

2. Type a page number, and then click OK.

The Title tool inserts a blank page at that page number, and moves all objects after it by one page.

The Title tool inserts a page only if the left boundary of an object appears on the page whose number you typed. For example, you cannot insert a page in the middle of a long crawling title.

You cannot use the Insert Page command to add a blank page to the end of a roll or crawl.

To delete empty pages from a rolling or crawling title:

1. Select Object > Remove Page.

The Remove Page dialog box opens.

2. Type the page number of the page you want to remove, and then click OK.

If the page is empty, the page is removed and all pages after the removed page are moved by one page.

To remove excess pages at the end of a rolling or crawling title:

- ▶ Select Object > Auto Size Mode.

For more information on Auto Size mode, see [“Using Auto Size Mode for Rolling and Crawling Titles” on page 402](#).

To copy or move an object to a title page:

1. Create a text block or any other title object.
2. Select the object.
3. Do one of the following:

- ▶ Select Object > Copy to Page.

The Copy to Page dialog box opens.

- ▶ Select Object > Move to Page.

The Move to Page dialog box opens.

4. Type a page number, and then click OK.

The Title tool copies or moves the object, and automatically adds pages if necessary.

Formatting Rolling and Crawling Titles

You can modify the text attributes of a rolling or crawling title with the same methods used to format still text elements:

- To adjust font, point size, style, justification, kerning, and leading, see [“Formatting Text” on page 394](#).
- To create outlines surrounding the text, see [“Modifying Box Corners, Lines, and Borders on Title Objects” on page 408](#).
- To adjust color and transparency, see [“Selecting Colors and Setting Transparency” on page 412](#).
- To add a drop or depth shadow, see [“Adding Shadows to Title Objects” on page 415](#).

Modifying and Manipulating Title Objects

You can modify or manipulate title objects in a variety of ways:

- You can round the corners of a box, adjust the width of lines and text borders, or add arrowheads to lines.

For more information, see [“Modifying Box Corners, Lines, and Borders on Title Objects” on page 408](#).

- You can change or blend colors in any title object.

For more information, see [“Understanding Color and Transparency Controls in the Title Tool” on page 411](#) and [“Selecting Colors and Setting Transparency” on page 412](#).

- You can add and adjust drop or depth shadows for any title object.

For more information, see [“Adding Shadows to Title Objects” on page 415](#) and [“Adjusting Shadows on Title Objects” on page 416](#).

- You can modify the transparency level of any title object or of its shadow.

For more information, see [“Selecting Colors and Setting Transparency” on page 412](#).

- You can manipulate title objects by changing their layer order, grouping them, locking them to prevent accidental editing, aligning them with respect to one another, and distributing them evenly across the viewing area.

For more information, see [“Manipulating Title Objects” on page 418](#).

Modifying Box Corners, Lines, and Borders on Title Objects

You can use the line attribute tools to round the corners of a box, adjust the width of lines and text borders, or add arrowheads to lines. The following illustration shows the line attribute tools.



Left to right: Box Corner button, Border Width button, and Arrowhead button in the Title Tool toolbar



If you do not select an object and you select a line attribute, the Title tool makes that attribute the default for any new objects that you create.

You can use the Border Width button to change the width of lines created with the drawing tools or to apply a border outline to text or graphic objects.



Example of text with borders

To round box corners:

1. Select a box.
2. Click the Box Corner button, and do one of the following:
 - ▶ Select a standard rounding option.
 - ▶ Specify a custom corner radius by doing the following:
 - a. Select the Custom Radius option (the last item on the list).
The Enter New Corner Radius dialog box opens.
 - b. Type a whole number (in pixels) into the dialog box.
The maximum custom radius is 200.
 - c. Click OK.



Box Corner button and options, with Custom Radius option at bottom

To select a line or border width:

1. Select an object (such as a line, shape, or text object).
2. Click the Border Width button, and do one of the following:
 - ▶ Select from the standard widths.
 - ▶ Specify a custom width by doing the following:
 - a. Select the Custom Width option (the last item on the list).
The Enter New Line Width dialog box opens.
 - b. Type a whole number (in pixels) into the dialog box.
 - c. Click OK.

If you selected a line for modification, the width of the line changes. If you selected an object for modification, the width of the border changes.




Border Width button and options, including Remove Border option (top) and Custom Width option (bottom)

To remove a border:

- ▶ Click the Border Width button, and select the Remove Border option (the first item on the list).

To add arrowheads to a line:

1. Select a line.
2. Click the Arrowhead button, and do one of the following:
 - ▶ Select a standard arrowhead style.
 - ▶ Select the Edit Arrowhead option (the last item on the list), and specify a custom arrowhead as described in the following procedure.




Arrowhead button and options, including Remove Arrowhead option (top) and Edit Arrowhead option (bottom)

To change the arrowhead size:

1. Select a line.
2. Click the Arrowhead button.
3. Select the Edit Arrowhead option (the last item on the list).

The Arrowhead Size dialog box opens.



Arrowhead handle in the Arrowhead Size dialog box

- Click the handle on the arrowhead, and drag it vertically or horizontally to resize and reshape it.

The shape of the arrowhead is in proportion to the line width.

- Click OK.

The line changes to show the new arrowhead shape.


To remove an arrowhead:

- Select a line.
- Click the Arrowhead button
- Select the Remove Arrowhead option (the first item on the list).

Understanding Color and Transparency Controls in the Title Tool

You can select the color and transparency for text and graphic objects, for their shadows, and for their borders. This topic describes the options available. For information on how to make color, transparency, and blend changes, see [“Selecting Colors and Setting Transparency” on page 412](#).

The following illustration shows the boxes associated with color and transparency.



Left to right: Color Selection boxes, Transparency Level boxes, and Color and Transparency Blend tools in the Title Tool toolbar

- The Color Selection boxes control fill (Fill), shadow (Shad), and border (Bord) color, respectively.


These boxes provide access to the Title Tool Color Picker dialog box, which enables you to do the following:

- Select a color from the Title Tool Color Picker.
- Use an eyedropper to select a color from any open application on your computer.
- Use the Windows Color dialog box or the Macintosh Colors panel to select a color.

- The Transparency Level boxes control fill, shadow, and border transparency, respectively.


12 Creating Titles

- The Color and Transparency Blend tools appear when you select a Fill or Border Color Selection box or Transparency Level box. You can use these tools to blend two colors in a text or graphic object or in a border to create a color gradient, and to specify the direction of the blend. You cannot blend the shadow for a title object.
 - If you select a Color Selection box, the top boxes show the two colors that create the blend. The bottom box shows the blended color and lets you control the direction of the blend or transparency.



Example of a gradient blend (left) created with the Color Blend tools (right)

- If you select a Transparency Level box, the top boxes show the two transparency values that are used to create the blend. The bottom box lets you control the direction of the transparency blend.



Example of a transparency blend (left) created with the Transparency Blend tools (right)

Selecting Colors and Setting Transparency

To select a color for a title object:


1. Select a text or graphic object.

If you do not select an object, the color is applied to the next object you create.

2. Press and hold the mouse button with the pointer over one of the Color Selection boxes in the toolbar:

Box	Description
Fill	Applies the color to the selected object.
Shadow (Shad)	Applies the color to the selected object's shadow.
Border (Bord)	Applies the color to the selected object's outline or border.

The Title Tool Color Picker opens.



1	Grayscale selection bar	4	Shade selection palette	7	Original Color window
2	Eyedropper	5	Color selection bar		
3	Open the Windows Color dialog box or the Macintosh Colors panel	6	New Color window		



You can drag the Color Picker from the toolbar to create a floating palette.

3. Select a color:
- ▶ To select from the Title Tool Color Picker, drag the pointer along the color selection bar to the color you want, and then move the pointer down into the shade selection palette to select a shade. Your Avid editing application applies the color when you release the mouse button.
 - ▶ To use the eyedropper, drag the pointer to the Eyedropper icon and release the mouse button. The pointer changes to the eyedropper. Click the color you want from anywhere in the window to apply the color to the selected object.
 - ▶ To use the Windows Color dialog box or the Macintosh Colors panel, drag the pointer to the Round Button icon under the eyedropper, and release the mouse button. The Windows Color dialog box or the Macintosh Colors panel opens. For more information, see [“Adjusting a Color Parameter for an Effect” on page 96](#).

12 Creating Titles

- To select a grayscale value, click in the grayscale selection bar.

To create a blend between two colors for a title object:

1. Select text or another object.
2. Click the Color Selection box for either fill or border.


The Color Blend tools appear.



Color Selection boxes (left), Color Blend Selection boxes (top right), and Blend Direction box (bottom right) in the Title Tool toolbar

3. Click one of the Color Blend Selection boxes, and select a color by using either the Title Tool Color Picker, the eyedropper, the Windows Color dialog box, or the Macintosh Colors panel.
4. Click the other Color Blend Selection box, and select the second color for your blend.

The Blend Direction box appears below the two Color Blend Selection boxes. This box displays the blend and lets you specify the direction of the blend (for example, left to right).



Example of a gradient blend (left) created with the Color Blend tools (right)


5. Click the Blend Direction box, and drag clockwise or counterclockwise to achieve the effect you want.

As you rotate the pointer, the position of the two colors rotates. The change takes effect as soon as you release the mouse button.

To control transparency level:

1. Click the appropriate Transparency Level box, depending on whether the transparency will apply to an object or will adjust a shadow or border around the selected object.

The Transparency Level box displays the text “Hi” with a background that changes from black to white. A completely white background represents a fully transparent object or portion of an object. A transparency control with a slider opens. The following illustration shows an example.



Transparency Level boxes (left), Transparency Blend Selection boxes (center top), Blend Direction box (center bottom), and transparency control with slider (right) in the Title Tool toolbar

2. In the transparency control that appears, drag the slider until you attain the transparency you want, and then release the mouse button.

The Title tool immediately applies the transparency to your selection.




You might find it useful to turn off the shadow and shadow softness for an object while experimenting with transparency. Set the shadow value to zero in the Shadow Depth text box and the softness value to zero in the Soft Shadow dialog box, as described in “Adding Shadows to Title Objects” on page 415 and “Adjusting Shadows on Title Objects” on page 416.

Adding Shadows to Title Objects

You can add a depth shadow or drop shadow to any text or graphic object. A depth shadow extends from the edges of the object, as though the object were three-dimensional. A drop shadow is offset from the object itself, as though cast by a light source. You can place the shadow anywhere within the title without restriction. The following illustration shows an example of depth and drop shadows.



You can adjust the color or transparency of a shadow. You can also soften (blur) shadows or create a glow effect behind a title object. For more information, see [“Adjusting Shadows on Title Objects” on page 416](#).



Shadow Depth and Direction button (top), Shadow Depth text box (bottom left), and Drop and Depth Shadow button (bottom right) in the Title Tool toolbar

To apply shadows to text or objects:

1. Select text or an object.
2. Click the Drop and Depth Shadow button to switch between a drop or depth shadow.
3. Adjust the depth or direction of the shadow by doing one or more of the following:
 - ▶ Click the Shadow Depth and Direction button, and drag the shadow sample to any position.
 - ▶ Shift-click the shadow in the Shadow Depth and Direction button, and drag to restrict shadow placement to 45-degree angles around the title.
 - ▶ Press the Shift key, and use the arrow keys to move the shadow to any position around the title.
 - ▶ Type a value in the Shadow Depth text box to change the shadow depth by increments.

The Title tool automatically orients the shadow to the selected object. You can continue to follow these procedures to adjust the shadow until you achieve the effect you want.

Adjusting Shadows on Title Objects

You can adjust the color and transparency for a shadow using the same procedures you use to adjust color and transparency for title objects themselves. For more information, see [“Selecting Colors and Setting Transparency” on page 412](#).

You can also control the amount of softening or blurring on shadows you create in the Title tool. The value that you set applies immediately to any selected title. The value also becomes the new default setting and applies to any new title objects you create in current and future Title tool sessions. To change the degree of softening that applies to objects in the Title tool, you must set a new value. The following illustration shows a typical soft shadow.



The current degree of softness is always represented visually on the shadow display of the Shadow Depth and Direction button. The following illustration shows this representation for a Shadow Softness setting of 10.



You can use specific softness values to create a glow or halo around a title object.

For information on applying shadows to title objects, see [“Adding Shadows to Title Objects” on page 415](#).

To set a degree of softening or blurring for shadows:

1. Select Object > Soften Shadow.

The Soft Shadow dialog box opens.

2. Type a number in the Shadow Softness text box to represent the degree of softening you want.

Shadow softness values must be integer values between 4 and 40. The higher the value, the more blurred the shadows are. If you set the value to zero, shadows on title objects have no softening (hard edges).

3. Click OK to close the Soft Shadow dialog box.

To adjust shadow softness on-the-fly, using the Soft Shadow text box:

1. Select one or more objects in the Title tool.
2. Select Object > Soften Shadow.
3. Type a number in the Shadow Softness text box to represent a degree of softening.
4. Click Apply.

The Title tool applies the softness value to the selected title objects.

5. Repeat steps 3 and 4 until you are satisfied with the effect.
6. Click OK.

To adjust shadow softness on-the-fly, using the Up Arrow and Down Arrow keys:

1. Select one or more objects in the Title tool.
2. While pressing and holding the Shift and Alt keys (Windows) or the Shift and Option keys (Macintosh), press the Up Arrow and Down Arrow keys to adjust the softness value incrementally until you are satisfied with the effect.

Each press of the Up Arrow key adds 1 to the shadow softness value. Each press of the Down Arrow key subtracts 1 from the shadow softness value.

To confirm the current numerical value for shadow softness:

- ▶ Select Object > Soften Shadow, and check the number in the Shadow Softness text box.

To create a glow or halo around a title object:

1. In the Title tool, set Shadow Depth for the object to zero.
2. Set Shadow Softness for the object to a non-zero value.

The higher the Shadow Softness value, the softer the glow effect. In the following illustration, Shadow Softness is set to 10.



To create titles that do not have either softened shadows or glows, you must set the Shadow Softness to zero.

Manipulating Title Objects

You can manipulate title objects in the following ways using commands in the Edit, Object, and Alignment menus:

- You can cut, copy, and paste title objects.
- You can select all objects at once, and deselect any selected objects.
- You can change the layering order of title objects.

The last object created occupies the top layer, but you can move objects forward or backward within the screen area.

- You can group and ungroup title objects.

Combining objects into a group means that actions, such as moving or applying color, affect all objects in the group.

- You can lock and unlock title objects.

You lock objects to make sure that changes to default settings, such as the font setting or object position, do not affect the locked objects. You might also want to lock objects so that you do not inadvertently change them while working on other objects.

- You can align title objects to each other and to the frame, or distribute them evenly.

Aligning to the frame and distributing refers to the safe title area. For more information, see [“Understanding the Drawing Environment” on page 389](#).

For more information on how to select objects, see [“Using the Selection and Text Tools” on page 388](#).

To manipulate objects using the Edit menu (cut, copy, paste, select all, and deselect):



1. Click the Selection tool, and click an object.
2. Do one of the following:
 - ▶ To cut an object and move it to the Clipboard, select Edit > Cut.
 - ▶ To copy an object to the Clipboard, select Edit > Copy.
 - ▶ To paste an object from the Clipboard, select Edit > Paste.
 - ▶ To select all objects, select Edit > Select All.
 - ▶ To delete selected objects, select Edit > Delete.



You cannot delete locked objects. Unlock objects you want to delete. For more information, see the procedures for locking and unlocking objects below.

- ▶ To duplicate an object, select Edit > Duplicate.

To adjust the layering of objects in a title:



1. Click the Selection tool, and click an object.
2. Do one of the following:
 - ▶ To bring an object to the top layer, select Object > Bring To Front.
 - ▶ To send an object to the bottom layer, select Object > Send To Back.
 - ▶ To move an object forward one layer, select Object > Bring Forward.
 - ▶ To move an object back one layer, select Object > Send Backward.

To group objects:



1. Click the Selection tool, and Shift+click multiple objects.
2. Select Object > Group.

The Title tool creates a grouped object from the individual objects. Changes to any individual object in the group affect all objects in the group.

To ungroup objects:



1. Click the Selection tool, and click a grouped object.
2. Select Object > Ungroup.

Everything in the group becomes an individual object that you can move or change independently.

To lock objects:



1. Click the Selection tool, and click an object.
2. Select Object > Lock.

The Title tool locks the object. You cannot change the object until you unlock it.

A locked object displays hollow selection handles, as shown in the following illustration.



To unlock objects:



1. Click the Selection tool, and click a locked object.
2. Select Object > Unlock.

The Title tool unlocks the object. You can now change it.

To align objects to the frame:



1. Click the Selection tool, and click an object or Shift+click multiple objects.
2. Do one of the following:
 - ▶ Select Alignment > Align To Frame Left.
 - ▶ Select Alignment > Align To Frame Right.
 - ▶ Select Alignment > Align To Frame Top.
 - ▶ Select Alignment > Align To Frame Bottom (Shift+Ctrl+Z).
 - ▶ Select Alignment > Center in Frame Horiz. (Shift+Ctrl+C).
 - ▶ Select Alignment > Center in Frame Vert.

The Title tool aligns the objects within the safe title area.

To align objects to each other:

1. Click the Selection tool, and Shift+click or lasso multiple objects.
2. Do one of the following:
 - ▶ Select Alignment > Align Objects Left.
 - ▶ Select Alignment > Align Objects Right.
 - ▶ Select Alignment > Align Objects Top.
 - ▶ Select Alignment > Align Objects Bottom.

The Title tool uses the last object you selected as the reference object to which it aligns the others.



For information on aligning objects to a grid, see “Understanding the Drawing Environment” on page 389.

To distribute objects:

1. Click the Selection tool, and Shift+click at least three objects.
2. Do one of the following:
 - ▶ Select Alignment > Distribute Left to Right.
 - ▶ Select Alignment > Distribute Top to Bottom.
 - ▶ Select Alignment > Distribute First to Last.

The Title tool distributes the objects evenly from left to right.

The Title tool distributes the objects evenly from top to bottom.

The Title tool distributes the objects evenly between the position of the first object you select and the position of the last object you select.

This command is especially useful for aligning objects diagonally or for roughly positioning a group of objects and then lining them up without spreading them out to the edges of the safe title area.

Saving Titles

You can save a title and then exit the Title tool immediately. Alternatively, you can save a title and then continue creating titles, using the Save As command to save each additional title separately.

The Save As command is also useful for saving the latest version of a title without replacing the original. A keyboard shortcut makes this even quicker.

The Fast Save option also lets you work more quickly when creating and saving multiple titles in a Title tool session. Fast Save skips the steps that create anti-aliased images from title objects. Instead, just the raw title objects (text and graphics) are saved in the bin, with the prefix “unrendered.”

Fast-saved titles appear as black in the monitors and are labeled as “media offline” during editing. You can edit with the titles and then batch render them at a more convenient time. Fast Save is ideal for working with multipage rolling titles with complex styles and shading. For information on rendering fast-saved titles, see [“Creating Media for Unrendered Titles in a Bin” on page 443](#).

You can also save the attributes of a particular title as a title style or as a title template that you can apply repeatedly to other titles or title objects, in much the same way that you can save effect templates. For more information, see [“Saving and Recalling Title Styles” on page 426](#) and [“Creating and Using Title Templates” on page 425](#).



After you edit a title into a sequence and adjust effect parameters, you can also save a Title Effect template that contains only the effect information (without title media) for applying to other previously created titles. For more information, see [“Working with Effect Templates” on page 47](#).



Before you export a sequence using OMF® or creating an EDL from a sequence, always render fast-saved titles. Before you export a sequence using OMF, render all rolling or crawling titles.

To save the title and exit the Title tool:

1. Select File > Close.

If the contents of the title have changed since the last time it was saved, a dialog box opens, asking if you want to save the existing title.

2. Click Save.

The Save Title dialog box opens.

3. Type a name to identify the title in the bin, and then select a bin, drive, and resolution from the menus.

If you are saving a new title, the resolution you select becomes the default for future new title saves.

You can also use the Media Creation dialog box to set the resolution and drives for titles. For more information, see [“Media Creation Settings” in the Help](#).

4. Select or deselect Fast Save (Unrendered), depending on your needs.

Fast Save remains in effect until you deselect it, load a title that was saved without Fast Save selected, or exit the Title tool.

5. Click Save.

The Title tool closes, and your Avid editing application loads the new title into the Source monitor. A 2-minute Title Effect clip that corresponds to the new title appears in the bin.

To save multiple titles in a continuing Title tool work session:

1. Select File > Save Title.

The Save Title dialog box opens.

2. Type a name to identify the title in the bin, and then select a bin, drive, and resolution from the menus.

You must select a resolution that is compatible with the sequence. Titles do not play with incompatible media. For detailed information on mixing media resolutions in a project, see “Resolutions and Storage Requirements” in the Help.

You can also use the Media Creation dialog box to set the resolution and drives for titles. For more information, see “Media Creation Settings” in the Help.

3. Select or deselect Fast Save (Unrendered), depending on your needs.

Fast Save remains in effect until you deselect it, load a title that was saved without Fast Save selected, or exit the Title tool.

4. Click Save.

The new Title Effect clip appears in the bin.

5. Create another title.

6. Select File > Save Title as, and repeat steps 2 to 5 for each subsequent title that you create.

Your Avid editing application loads titles into the Source monitor as they are saved, so the most recently saved title always appears in the Source monitor.

To save a version of a title using the keyboard shortcut:

1. Press Shift+Ctrl+S (Windows) or Shift+Command+S (Macintosh).

The Save Title dialog box opens.

2. Type a name for the title.
3. Select a bin, a drive, and a resolution from the menus.
4. Click Save.

To quickly locate unrendered fast-saved titles in a bin:

1. Open the bin containing the unrendered fast-saved titles.
2. Select Bin > Select Unrendered Titles.

The fast-saved titles are highlighted in the bin.

Revising a Title in a Bin

If you want to revise a title that has not been edited into a sequence, you can reopen the title in the Title tool directly from the bin.

For information on revising a title that has been edited into a sequence, see [“Revising a Title in a Sequence” on page 440](#).

To revise a title in a bin:



1. Ctrl+double-click the Title Effect icon in the bin.

The title opens in the Title tool.



If the Title tool is already open, you can drag a Title Effect clip from the bin directly into the Title tool.

2. Edit the title, using the techniques described in [“Editing with Titles” on page 431](#).
3. Save the title with the same name and media parameters (bin, drive, and resolution) by choosing File > Save Title.

The revised Title Effect clip replaces the previous clip in the bin. The clip also appears in the Source monitor.

The Title tool remains open. You can continue creating additional titles, or select File > Close.

4. Save the title with a new name or change any of the media parameters (bin, drive, and resolution) by doing the following:
 - a. Select File > Save Title as.
The Save Title dialog box opens.
 - b. Rename the title, or select other options from the Bin, Drive, and Resolution menus.
If you keep the same name for the title, your Avid editing application retains the original Title Effect clip in the bin and creates a new clip with the same name plus a two-digit extension that adds incremental numbering for each revision.
 - c. Select or deselect Fast Save, depending on your needs.
For more information, see [“Saving Titles” on page 421](#).
 - d. Click Save to save the title and exit the Title tool.

Creating and Using Title Templates

Title templates let you create a standard format for text and graphics that you use regularly. After you set up your template, open the template, edit the text, and save the new title. The template prevents you from changing the position, colors, shadows, or graphics, which ensures consistency.

You can use the Moveable Templates option in the Templates menu to change the position of a template.

You can also use title styles to save and recall only the parameters that control the appearance of title objects. For more information, see [“Saving and Recalling Title Styles” on page 426](#).

To create a title template:

1. Open the Title tool by doing one of the following:
 - ▶ Select Clip > New Title.
 - ▶ Select Tools > Title Tool.
2. In the Title tool, create the text and graphic elements to include in the template.
3. Click the Templates menu, and select Save Template.
The Save Template dialog box opens.
4. Type a name for the template.
5. Click Save.

By default, the Title tool saves the template in a Title_Templates folder within the Settings folder for your Avid editing application, but you can save it elsewhere.

6. Close the Title tool, and click Don't Save in the dialog box.

To use a title template:

1. Open the Title tool by doing one of the following:
 - ▶ Select Clip > New Title.
 - ▶ Select Tools > Title Tool.
2. Click the Templates menu, and select Include Template.
The Open dialog box opens.
3. Select the template you want to use, and click Open.
The Title template opens.
4. Make any edits you want to the text.

5. (Option) If you want to change the position of a template, click the Templates menu, and select Moveable Templates. Then click the Arrow buttons to move the template within the Title Tool.

6. Close the Title tool, and click Save in the dialog box.

The Save Title dialog box opens.

7. Type a name for your title, and click Save.

The named title appears in the bin you specify. Now you can edit the title into the sequence. For more information, see [“Editing with Titles” on page 431](#).

Saving and Recalling Title Styles

As you begin to work with a title, you might set up some basic title parameters you can use again for other titles. You can save the following style parameters in the form of a title style:

- Font, style, size, justification, kerning, and leading.
- Fill color and transparency.
- Shadow color, transparency, depth, direction, softness, and type.
- Border color, transparency, and width.

You can also assign a title style to one of the function keys on your keyboard. You can then recall that style by pressing the appropriate function key.

Title styles save only the parameters that control the appearance of text or graphic objects in the Title tool. If you want to save the entire contents and layout of a title, including specific title objects themselves, use a title template. For more information, see [“Creating and Using Title Templates” on page 425](#).

The following illustration shows the location of the two buttons that let you select and define title styles.



Styles button (left) and Save Style Parameter button (right) in the Title Tool toolbar

See [“Title Style Sheet Options” on page 428](#) for information on Style sheet components.

Saving a Title Style

To save title parameters to a Style sheet:



1. Click the Selection tool, and click the object that you want to use as a basis for the title style.




2. Click the Save Style Parameter button.

A menu opens that lets you select either an existing title style name or Save As.

3. Select Save As.

The Title Style Sheet dialog box opens. The following illustration shows an example.



Top to bottom: Sample window, Function Key text box, and Style Name text box in the Title Style Sheet dialog box

4. Select the parameters that you want to include in the style using the information in [“Title Style Sheet Options” on page 428](#).

The Title tool uses the values from the currently selected object or from the current defaults if no object is selected.

5. (Option) Type a function key number in the Function Key text box to assign the style to a function key.

For example, typing 5 assigns the style to the F5 function key.

6. Type a name in the Style Name text box, and click Done when you are ready to exit the dialog box and save the values.

Title Style Sheet Options

The Title Style Sheet dialog box lets you create templates for the Title tool. Style sheets let you define and select basic text and drawing parameters that you can use with the Title tool. The following table describes the components of the Title Style Sheet dialog box.


Component	Description
Check boxes	Select the current attributes of the object that you want to include in the style. You can modify the attributes that are associated with a saved title. Use the check boxes to specify the attributes to save.
Function Key text box	(Option) Lets you designate a function key that you can use to apply the title style.
Style Name text box	This name appears in the Style list in the Title tool and in the Settings list.
Refresh button	Appears after you change an item in the dialog box. Click to display the change in the sample window.
Select All button Select None button	Let you select all or none of the check boxes.
Revert button	Returns the settings to those used when the style was last saved.
Done button	Closes the dialog box and saves your changes.
Convert to Marquee button	Converts your title style to Marquee format. For more information, see the <i>Avid Marquee Title Tool User's Guide</i> or the Avid Marquee Title Tool Help.
Close button	Acts as a Cancel button. A message box opens, asking whether you want to cancel or save your changes. If you created a new style from within the Title tool, clicking Cancel means that the Title tool does not create the new style.

Recalling a Title Style

You can recall a title style and use its attributes as the defaults in subsequent Title tool sessions.

To recall title style attributes using the Title Styles tear-off menu:

1. In the Title tool, click the Styles button to display the Title Styles tear-off menu.



The menu contains a scaled visual representation of each style. Arrows on the right and left let you scroll back and forth.

2. Drag the pointer to the style you want to recall, and release the mouse button.

The style attributes appear in the Title tool toolbar.

To recall a title style attribute using the Save Style Parameter button:



- ▶ Click the Save Style Parameter button, and select a style from the menu.

To recall a title style attribute using a function key:

- ▶ Press the appropriate function key.

The style attributes appear in the Title Tool toolbar.

Confirming Function Key Mapping of Title Styles

To verify which function key is assigned to a particular title style, do one of the following:

- ▶ Open the Title Style Sheet dialog box for the style from the Settings list in the Project window, and then check the function key number in the Function Key text box.
- ▶ In the Title tool, click the Styles button to display the Title Styles tear-off menu, and then position the mouse pointer over the style.

The tooltip that appears indicates the function key assignment along with the name of the style.


Applying Title Styles to Text Objects

To apply a title style directly to text objects:

1. Select one or more text objects.
2. Do one of the following:
 - ▶ Click the Styles button to display the Title Styles tear-off menu, and then select a title style.
 - ▶ If the style is assigned to a function key, press the appropriate function key.

Managing Title Styles

Your Avid editing application lists the available title styles in the Settings tab of the Project window. The following illustration shows a typical list of title styles.



To delete a style:

1. Select the style in the Project window.
2. Do one of the following:
 - ▶ Press the Delete key.
 - ▶ Select Edit > Delete.

To copy a style:

- ▶ Select the style in the Project window, and select Edit > Duplicate.

To rename a style, do the following:

- ▶ Change the name in the Project window.

Exporting a Title as a Graphics File

To export a title as a PICT graphics file:

1. With the Title tool open, select File > Export Title.
The Export Pict As dialog box opens.
2. Select the location where you want to export the file, type a file name, and click Save.
The Title tool saves the title.

13 Editing with Titles

This chapter provides information on editing titles created in the Title tool or in Marquee into sequences.

- [Displaying Title Clips and Frames in Bins](#)
- [Editing a Title into a Sequence](#)
- [Removing a Title](#)
- [Replacing a Title](#)
- [Fading a Title](#)
- [Adjusting Title Effect Parameters](#)
- [Revising a Title in a Sequence](#)
- [Replacing Fill Tracks in a Title](#)
- [Rendering Titles](#)
- [Guidelines for Handling Playback Issues with Rolling Titles](#)
- [Re-creating Title Media](#)
- [Troubleshooting Titles](#)


Throughout this chapter:

- “Title” refers to both text and graphics.
- “Title tool” refers to the classic Avid Title tool.
- “Marquee” refers to the Marquee Title tool.

Displaying Title Clips and Frames in Bins

When the Title tool or Marquee saves a title, it creates a Title Effect clip and saves it in the bin you select. One media object, referred to as a precompute, has references to the RGB and alpha channel information. Every time you make a change, your Avid editing application creates two additional media files. The original media files are not changed.

13 Editing with Titles



Rendered effect or precompute (left) and Title Effect clip (right) in Frame view in a bin




*Bins do not display rendered effects by default. To view rendered effects in the bin, select **Bin > Set Bin Display**, then select **Rendered Effects** and “**Show reference clips**” in the dialog box.*

For more information, see [“Managing Effect Media Files” on page 181](#).

When you have a bin in Frame view, you can display a frame from the title itself rather than display the Title Effect Clip icon for the clip. This is especially useful if you have many titles in the bin and want a quick visual reference.

To display a frame from the title:

1. Select one or more Title Effect clips.
2. Press the Home key on the keyboard.



Editing a Title into a Sequence

There are three basic methods for editing a title into a sequence:

- Mark edit points and then splice or overwrite the title into the sequence.

For more information, see [“Splicing or Overwriting a Title into a Sequence” on page 433](#).

- Mark edit points, and then drag the title directly into the sequence.

For more information, see [“Dragging a Marked Title into a Sequence”](#) on page 434.

- Place the position indicator, and then drag an unmarked title clip directly into the sequence at the location of the position indicator.

For more information, see [“Dragging an Unmarked Title into a Sequence”](#) on page 435.

Splicing or Overwriting a Title into a Sequence

To splice or overwrite a title into a sequence:

1. Load the sequence into the monitor window.



You must place titles on a track above the video that forms the background. If an upper track already exists with an open region for the title, you can go to step 3.

2. (Option) Select Clip > New Video Track.

Your Avid editing application adds the next video track for the sequence to the Timeline. For example, if the sequence includes only V1, your Avid editing application adds V2.



3. Double-click the Title Effect Clip icon in the bin to load the title clip in the monitor window.
4. Patch the title source to the video track in the sequence by clicking the Source Track button for track V1 in the Track Selector panel and dragging it to the Record Track button for track V2.



Example of patching from a Source Track button (left) to a Record Track button (right)




You can use any three-point editing method to edit a title into a sequence. The following steps are just one editing method. For other methods, see [“Creating and Editing Sequences”](#) in the Help.

5. Mark an IN point in the title clip.

Mark the IN point toward the middle of a static title clip so you can trim the title, if necessary. For rolling and crawling titles, set no marks and move the position indicator to the beginning of the clip if you want to use the full roll.

6. Mark IN and OUT points in the sequence.



7. Ensure all other Record Track buttons are deselected in the Track Selector panel.
8. Click one of the segment tools in the Timeline palette to edit the title into the sequence.



Segment tools in the Timeline palette

The Title Effect segment appears in the top video track.



Dragging a Marked Title into a Sequence

To mark a portion of a title clip and then drag the marked clip directly into the Timeline:

1. Load the sequence into the monitor window.

For more information, see “Creating and Editing Sequences” in the Help.



You must place titles on a track above the video that forms the background. If an upper track already exists with an open region for the title, you can go to step 3.

2. (Option) Select Clip > New Video Track.

Your Avid editing application adds the next video track for the sequence to the Timeline. For example, if the sequence includes only V1, your Avid editing application adds V2.



3. Double-click the Title Effect Clip icon in the bin to load the title clip into the monitor window.

4. Mark an IN point and an OUT point in the title clip to establish the duration that you want for the title.

Mark the IN point toward the middle of a static title clip so you can trim the title, if necessary. For rolling and crawling titles, set no marks and move the position indicator to the beginning of the clip if you want to use the full roll. Your Avid editing application uses the position indicator to determine the IN point on rolling titles.

5. Clear the title clip from the monitor window by choosing Clip Name > Clear Monitor.
6. Click either the Extract/Splice-in button or the Lift/Overwrite button, depending upon how you want to insert the Title effect.



Extract/Splice-in button (left) and Lift/Overwrite button (right)

7. Click the Title Effect Clip icon in the bin, and drag it to the Timeline.

As you drag the Title effect in the Timeline, a white outline of the title clip indicates location in the sequence.



8. Release the mouse button when you have the title positioned where you want it.
The Title effect appears in place in the sequence.



Dragging an Unmarked Title into a Sequence

If you are not concerned about the OUT point for your title, or if you plan on trimming the Title effect later, you can quickly drag the unmarked Title effect directly into the Timeline.

To apply a Title effect to a sequence without adding marks:

1. Load the sequence into the monitor window.

For more information, see “Creating and Editing Sequences” in the Help.



You must place titles on a track above the video that forms the background. If an upper track already exists with an open region for the title, you can go to step 3.

2. (Option) Select Clip > New Video Track.

Your Avid editing application adds the next video track for the sequence to the Timeline. For example, if the sequence includes only V1, your Avid editing application adds V2.

3. Move the position indicator to the location where you want the Title effect to begin.

- Click either the Extract/Splice-in button or the Lift/Overwrite button, depending upon how you want to insert the Title effect.



Extract/Splice-in button (left) and Lift/Overwrite button (right)



- Click the Title Effect Clip icon in the bin, and drag it to the Timeline.

As you drag the Title effect in the Timeline, a white outline of the title clip indicates location in the sequence.



- Release the mouse button when you have the title positioned where you want it.
The Title effect appears in place in the sequence.

Removing a Title

To remove a title segment:

- Move the position indicator to the segment containing the Title effect.
- Use the Track Selector panel to select the track containing the Title effect and to deselect all other tracks.
- Click the Mark Clip button under the monitor.
IN and OUT points appear surrounding the Title effect.
- Click one of the segment tools in the Timeline palette to remove the segment.



IN and OUT points appear surrounding the Title effect.



Segment tools in the Timeline palette



The Title effect remains in the bin. To remove the Title effect from the bin, select the effect in the bin and press the Delete key.

Replacing a Title

To replace a title in a sequence:



1. Click the Segment Overwrite tool in the Timeline palette.
2. Click the title segment currently in the sequence to select it.



3. Click the Mark Clip button to mark an IN point at the beginning of the title segment and an OUT point at the end of the segment.

4. Drag the new Title Effect clip from the bin to the marked segment.

The new title replaces the old title.

Fading a Title



You can use the Fade Effect button to fade a title. A dialog box opens that lets you enter the number of frames to fade up and fade down without opening the Effect Editor.

Rather than adding Dissolve effects that require rendering, you can use the Fade Effect button to quickly create keyframes in the title with the proper level settings for playback in real time. You can access the keyframes in the Effect Editor. For more information, see [“Using the Fade Effect Button” on page 38](#).

Setting Marks in a Rolling or Crawling Title

By default, a rolling or crawling title clip begins with the visible title just off screen and ends after the last element disappears off screen.

You can mark IN and OUT points of rolling or crawling titles in the Source monitor to change the start and finish points. For example, you might want the title to start with the screen full of text rather than start off screen.

You can play and mark a rolling or crawling title clip in the Source monitor by using standard procedures. For more information, see [“Controlling Playback” in the Help](#).

If you want to use the complete roll or crawl in the sequence, do not set marks. For information about adjusting the duration of the roll, see [“Trimming the Duration of Rolling and Crawling Titles” on page 438](#).



*You can view a crawling title frame by frame if you select **Special > Render On-the-Fly**.*

Trimming the Duration of Rolling and Crawling Titles

When you edit a title clip into a marked segment of a sequence, the clip plays back from beginning to end regardless of the duration of the segment. That is, the entire roll shrinks to fit within the duration of the marked segment in the sequence.

After you edit the clip into the sequence, you can trim the duration of the segment at any time, and the title adjusts to fit.

Unlike trimming other segments, trimming a rolling or crawling title does not remove any part of the title contents. As a result, the duration of the title determines how fast it plays. For example, the shorter you trim the title, the faster it rolls.



Rolling titles might jitter at certain speeds. You can trim the duration slightly to fix the problem.



If you trim your rolling title very short, it scrolls very fast and cannot display in real time, so you must render it. The maximum speed for an unrendered rolling title is one screen per second.

To trim the duration of a rolling title or a crawling title:

1. Use the Track Selector panel to select the track containing the Title effect and to deselect all other tracks.
2. Trim the title segment to the duration you want by using standard trim procedures.

For more information, see “Working with Trim Edits” in the Help.

The entire roll or crawl plays back within the new duration.

Adjusting Title Effect Parameters

After you edit a title into a sequence, you can open the Effect Editor and refine the title with keyframe control over effect parameters.

You can also promote a 2D title to 3D in the same way that you promote other effects from 2D to 3D. For more information, see [“Promoting 2D Effects to 3D Effects” on page 364](#).



Adjusting parameters might affect the real-time playback capabilities of your titles in various ways, depending on the particular options available with your Avid editing application.

To access the effect parameters for a Title effect:


1. If you are not in Effect mode, enter Effect mode, for example, by selecting Toolset > Effects Editing.

For more information, see [“Entering Effect Mode” on page 41](#).

The Effect Editor opens.

2. Click the Title Effect segment in the sequence to select it.

The Effect Editor displays the parameter controls.



3. Do one or more of the following to work with the Title effect parameters:

- ▶ Adjust Title effect parameters by using basic techniques described in [“Using the Effect Editor” on page 89](#).



For information on specific Title effect parameters, see [“Title Effects” on page 598](#).

- ▶ Use multiple keyframes to gradually change keyframeable parameters over time.

For more information, see [“Working with Keyframes” on page 101](#).

- ▶ Save effect templates of Title effect parameter adjustments to a bin for use in other sequences or projects as described in [“Working with Effect Templates” on page 47](#).

Revising a Title in a Sequence

If you want to revise a title after you edit it into a sequence, you must reopen the title in the Title tool directly from the sequence rather than revise the Title Effect clip in the bin.


To change a title in a sequence:

1. Click the Title Effect segment in the sequence to select it.
2. If you are not in Effect mode, enter Effect mode, for example, by selecting Toolset > Effects Editing.

For more information, see [“Entering Effect Mode” on page 41](#).

The Effect Editor opens.

3. Click the Edit Title button.



A dialog box opens, asking if you want to promote the title to Marquee.



You cannot edit titles that you promote to or create in Marquee with the Title tool. For information on Marquee titles and the Marquee Title tool, see the Avid Marquee Title Tool User's Guide or the Avid Marquee Title Tool Help.

4. Click No.
The Title tool opens.
5. Revise the title by using techniques described elsewhere in this chapter.
6. Save the title by using one of the following procedures.

To save the title with the same name and media parameters:

1. Select File > Save Title.

A message box opens, asking if you want to save the title and exit the Title tool.

2. Click Save.

The Title tool closes. The revised Title Effect clip replaces the previous clip in the sequence, the bin, and the Source monitor.

To save the title with a new name or parameters:

1. Select File > Save Title as.

A message box opens, asking if you want to save the title and exit the Title tool.

2. Click Save.

The Save Title dialog box opens.

3. Rename the title, or select other options from the Bin, Drive, and Resolution menus.



You cannot select Fast Save when revising a title in a sequence.

4. Click Save to save the title and exit the Title tool.

The Title tool closes, and the revised Title Effect clip replaces the previous clip in the sequence. The new clip with its new name also appears in the Source monitor and in the bin. The previous Title Effect clip is preserved in the bin.

Replacing Fill Tracks in a Title

You can replace the fill track of Title effects with video or graphics. The moving video or graphic effect then appears inside the title itself, keyed over the background.

To replace the fill track:

1. In the Timeline toolbar, click the Step In button to step into the effect.
2. Load the video you would like to use as replacement filler into the Source monitor.
3. Drag the Source Track button in the Track Selector panel to the Record Track button for the fill track to patch the new source video to the title fill track.
4. Using standard editing methods, edit the video from the Source monitor onto the fill track.

Rendering Titles

Rolling and crawling titles are non-real-time effects. You must render them before they will play back in real time. You might also need to render static titles in some circumstances, particularly when they are layered with other titles or other effects, or when the overall complexity of the sequence limits real-time playback for your system.

For more information on rendering Title effects, see [“Basics of Effects Rendering” on page 53](#).

Re-creating Title Media

You can use the Re-create Title Media command to:

- Regenerate title media that is offline.
- Generate title media for unrendered (Fast Saved) titles in a bin.
- Change the resolution of a title.

If you batch capture a sequence at a resolution different from the resolution at which the sequence was originally created, for example, you can use this command to re-create the titles at the new resolution. You need to do this when conforming an offline sequence with titles for online editing and output at uncompressed resolution.

You can re-create title media that is edited into a sequence in the Timeline, or you can create media for unrendered (Fast Saved) titles in a bin. For more information on Fast Save for titles, see [“Saving Titles” on page 421](#).



The Re-create Title Media command removes any nested edits inside a title, and replaces them with the new title’s graphic and alpha tracks.

Re-creating Title Media from the Timeline

To re-create title media from the Timeline:

1. Load the sequence containing the titles into the Record monitor.
2. Mark IN and OUT points in the sequence surrounding all the titles that you want to re-create.
3. In the Track Selector panel, select the Record Track button for each track that contains titles you want to re-create.
4. Select Clip > Re-create Title Media.

The Re-create Title Media dialog box opens.

5. Select a drive on which to store the re-created titles.
6. Select a resolution for the re-created titles.



The default drive and resolution are defined in the Titles tab of the Media Creation dialog box. For more information, see “Media Creation Settings” in the Help.

7. Click OK.

Your Avid editing application re-creates the title media file.

Creating Media for Unrendered Titles in a Bin

To create media for unrendered titles in a bin:

1. In the bin, select the titles for which you want to generate media.
To quickly select all the unrendered titles in the active bin, select **Bin > Select Unrendered Titles**.
2. Select **Clip > Create Unrendered Title Media**.
The Create Unrendered Title Media dialog box opens.
3. Select a drive on which to store the title media.
4. Select a resolution for the title media that is compatible with the sequence, such as a two-field resolution for a sequence containing two-field media.



The default resolution is the resolution specified at the time you originally saved the titles with the Fast Save option.

5. Click **OK**.

Your Avid editing application generates the title media file, and the title clip appears in the bin without the (unrendered) label in the name field.

Troubleshooting Titles

The following topics describe errors that might occur when working with Title effects and includes recommendations for resolving the problems.

Guidelines for Handling Playback Issues with Rolling Titles

The following limitations apply to rolling titles:

- Rolling titles might jitter slightly at certain speeds. You can adjust the duration by a few frames to fix the problem.
- Rolling titles cannot play back at a rate greater than one page per second. This situation occurs when you edit a lengthy title roll into a short segment in the sequence.

If you experience a playback problem with a title, do one or more of the following:

- Render the title or underlying effects.
For more information, see [“Basics of Effects Rendering” on page 53](#).
- For a rolling title, slow the roll by extending the duration of the clip. For more information, see [“Trimming the Duration of Rolling and Crawling Titles” on page 438](#).

- Separate title clips in the sequence.
- Store title and video media on separate drives, or use faster drives.

Guidelines for Handling Underrun Error Messages for Titles

When you edit with titles or graphics, you might experience an underrun error message because your Avid editing application could not load the graphic key in time.

Possible causes include the following:

- Insufficient drive speed
- Title rolling too fast
- Several graphics too close together

Possible solutions include the following:

- Render the clip and underlying video.
- Slow down the rolling title.
- Store the clip media on a drive other than the drive containing the underlying media.
- Add filler between sequential clips.
- Use faster drives.

Handling a Wrong Format Message for a Title

If you see an image in a monitor that says Wrong Format, the resolution of the Title effect is not compatible with the resolution of the video clips in the sequence. You can determine the resolution of the video clip, and then regenerate the title at the same resolution as the video clip.

To determine the resolution of the current video clip:

1. Open the bin containing the sequence.
2. Select Bin > Set Bin Display.
3. Select “Show reference clips.”

The master clips used in the sequence appear in the bin.

4. Check the resolution for any master clips in the Video column in Text view in the bin.

To correct a title’s resolution to match the resolution used in the video clips in the sequence, use the procedure described in [“Re-creating Title Media” on page 442](#).

Using Filtering for HD Titles

Titles created with the Title Tool or Marquee in an HD project might display undershoots and overshoots in the SD signal after you downconvert and output a sequence. This problem might also occur with imported animated graphics that contain an alpha channel (except for QuickTime imports). You can avoid this problem by using a console command to filter HD titles and imported graphics.

The HD title filter is disabled by default, and entering this command enables it. Note the following:

- Enter the command before creating titles or importing animated graphics. The command does not affect media already created.
- Using the title filter might result in a slight softening of sharp transitions between dark colors and light colors.

To turn on HD title filtering:

1. Select Tools > Console.
2. Enter **HDTITLEFILTER**.

This command works as a toggle, so the filter remains on until you type the command again.

Controlling Character Mapping for Title Text

Recent versions of Avid editing applications use different default character mappings from older versions. Some text objects might not display correctly when you open or edit them in the current version of your Avid editing application. In particular:

- Greek text objects created in older versions do not display correctly in recent versions.
- Certain characters, such as superscripts or other characters you enter using Alt key sequences, might not display correctly.

If you experience these problems, you can switch to the older, “classic” character mappings.

To turn classic character mapping on or off:

1. Ensure that the Title Tool is closed.
2. In the Settings tab of the Project window, double-click Interface.
The Interface Settings dialog box opens.
3. Click the General tab.
4. Select or deselect “Use Classic Character Mapping.”

5. Open the Title Tool, switch to a different font, and then switch back to the font you need.

This action clears any cached font information and ensures that the character mapping change takes effect. For more information, see [“Selecting a Font” on page 395](#).

14 Working with the SubCap Effect

This chapter provides information on the SubCap™ captioning and subtitling effect.

- [Understanding the SubCap Effect](#)
- [How the SubCap Effect Handles Caption Files](#)
- [Applying the SubCap Effect](#)
- [Entering Caption Text Directly in the Effect Editor](#)
- [Importing a Caption File](#)
- [Adding Information to a SubCap Effect](#)
- [Editing Text in the Master Caption List](#)
- [Adjusting SubCap Effect Parameters](#)
- [Synchronizing SubCap Effect Parameters and Information](#)
- [Exporting SubCap Effect Data to Caption Files](#)
- [Working with Unicode Text in the SubCap Effect](#)
- [Working with SubCap Effect Stylesheets](#)
- [Examples of SubCap Effect Parameter Adjustments](#)

Understanding the SubCap Effect

You use the SubCap effect to add text to the video in your sequences, either by entering text directly or by importing text from files formatted in standard captioning formats.



The SubCap effect composites text and any background effects such as drop shadows or background boxes into the video material. The text becomes a permanent part of the finished video material and is always visible. The text in a SubCap effect is therefore a form of *open captioning*, a common industry term that refers to captioning that is always visible to the viewer.



The SubCap effect does not provide closed captioning capabilities. Closed captioning encodes text information into the video signal instead of compositing it into the video frames themselves. A viewer can choose whether or not their television or other decoding equipment decodes this text information and displays it on screen.

The SubCap effect is typically used for two different types of text information:

- Text that provides a translation of the spoken dialogue in a program.
This case assumes a viewer who can hear the audio for the program but cannot understand the language in which it is spoken. Text items of this kind are usually known as *subtitles* in North America.
- Text that provides a full description of all the audio content in a program.
This case assumes a viewer who cannot hear the audio for the program and so needs a description not only of the spoken dialog but also of sound effects and the character of the music. Text items of this kind are usually known as *captions* in North America.

You might use the SubCap effect to create text that becomes part of the finished program. Alternatively, you might use the SubCap effect to create text that provides a preview during your production process but that is replaced in the finished program by closed caption text that is encoded into the video signal.

The SubCap effect has the following main features:

- Support for the EBU N19 (.stl) and the Avid DS caption file formats, including the storage of metadata such as contact and program information.
- Support for Unicode text entry.
- Parameter control over many aspects of text appearance, including fonts, colors, line length, and line spacing.
- Ability to apply parameter changes made on one caption effect clip to all other caption effect clips on the current track or throughout the sequence.
- Ability to save sets of parameter values for any caption effect clip as a stylesheet file that you can then apply to other caption effect clips in the same or other sequences.


How the SubCap Effect Handles Caption Files

Caption files contain a series of caption text items associated with starting and ending timecode values. They might also contain additional information about the project or about the formatting of the text. For example, the following sample shows two text items and their associated timecode in an Avid DS caption file:

```
00:00:02:00 00:00:03:00
Bob, are you there?

00:00:04:18 00:00:06:13
Yes, Sam.
Just behind the car.
```

When you import a caption file into a SubCap effect, your Avid editing application subdivides the effect at the timecode points specified by the file. This creates a series of separate effects, one for each caption. The following illustration shows this process for the file sample above:





Before (above) and after (below) importing a caption file. Before the import, the SubCap effect occupies the full length of its own caption track (white), above all the video tracks (gray). After the import, the caption track is automatically subdivided, creating separate effects for each caption. For the first effect, the text reads “Bob, are you there?” For the second effect, the text begins “Yes, Sam.”

The importing and subdividing process depends on a correspondence between the timecode values in the caption file and the timecode values for the effect clip. In the preceding example, importing the caption file successfully subdivides the caption track because the timecode range of the original effect (00:00:00:00 to 00:08:00:00) includes all of the specific timecode values in the caption file. If the timecode range of the original effect were different (for example, if the sequence timecode began at 00:30:00:00), the import could not take place.

The dialog box you use to import a caption file provides you with information about the timecode ranges of the file and the effect, and reports what the result of the import will be. This information lets you see in advance whether an import will be successful. For more information on importing a caption file, see [“Importing a Caption File” on page 453](#).

The following illustrations show two examples of this information in the “Select a file that contains caption data” dialog box. In the first case, timecode values correspond and the import will be successful; in the second case, timecode values are inconsistent and no import will occur.





Applying the SubCap Effect

The SubCap effect is available from the Caption category in the Effect Palette. You can apply the effect in any of the standard ways, for example, by dragging the effect icon from the Effect Palette onto the Timeline. For more information, see [“Applying Effects” on page 35](#).

You apply the SubCap effect to a video track above all the other video material in your sequence. In some circumstances (for example, for translations into more than one language) you might apply different instances of the effect to different tracks, and then turn the tracks on or off as necessary to create different language outputs.

Depending on how you plan to add text to the effect, you might need to divide the video track into segments using Add Edits:

- If you are adding text by typing it in directly, you must divide the video track at the points where you want the text to appear and disappear. To add captions to an entire sequence in this way, you must divide the video track into a series of segments that correspond to the points in the video material where you want each caption to begin and end.
- If you are adding text by importing a caption file, you only need to divide the video track at the points where you want the captions as a whole to begin and end. If you want captions to appear for the entire length of the sequence, you do not need to divide the track. When you import the caption file, your Avid editing application further subdivides the segment to which you apply the effect, based on the timecode information for each text item in the caption file.

To apply a SubCap effect for direct text entry:

1. (Option) If necessary, create a new video track in the Timeline.
For example, right-click in the Timeline and select New Video Track.
2. Ensure that the video track to which you want to apply the effect is the only selected track.
3. Move the position indicator to the point in the sequence where you want the caption text to appear.

4. Click the Add Edit button to add an edit point.
5. Move the position indicator to the point in the sequence where you want the caption text to disappear.
6. Click the Add Edit button to add an edit point.
7. In the Project window, click the Effect tab, and then select the Caption category.
8. Drag the SubCap effect to the segment in the Timeline created by the two Add Edits.

To apply a SubCap effect for import of a subtitles file:

1. (Option) If necessary, create a new video track in the Timeline.
For example, right-click in the Timeline and select New Video Track.
2. Ensure that the video track to which you want to apply the effect is the only selected track.
3. (Option) If you want captions from the imported file to apply to only part of the sequence, do the following:
 - a. Move the position indicator to the point in the sequence where you want captions defined in the caption file to start.
 - b. Click the Add Edit button to add an edit point.
 - c. Move the position indicator to the point in the sequence where you want captions defined in the caption file to end.
 - d. Click the Add Edit button to add an edit point.
4. In the Project window, click the Effect tab, and then select the Caption category.
5. Do one of the following:
 - a. Drag the SubCap effect to the video track to which you want to apply the effect.
 - b. Drag the SubCap effect to the segment in the Timeline that you created in step 3.

Entering Caption Text Directly in the Effect Editor

You can enter caption text directly in the Effect Editor.

Direct text entry in the Effect Editor has the following limitations:

- You cannot enter line breaks (carriage returns) in the Effect Editor text box. (You can insert line breaks directly in the Edit Master Caption List dialog box.)
- You can enter Unicode characters only as references. (You can enter Unicode characters directly in the Edit Master Caption List dialog box.)

- On the Macintosh, you might need to change the default system font to a font that supports all the characters you want to enter.

For more information, see [“Editing Text in the Master Caption List” on page 456](#) and [“Working with Unicode Text in the SubCap Effect” on page 460](#).


To enter caption text directly in the Effect Editor:

1. Move the position indicator to the SubCap effect to which you want to add text, and ensure that the track containing the effect is selected.
2. If it is not already open, open the Effect Editor, for example, by clicking the Effect Mode button.
3. In the Caption Text parameter category, enter the text in the text box.

Importing a Caption File

To import a caption file:

1. Follow the second procedure in [“Applying the SubCap Effect” on page 451](#) to create a SubCap effect that covers the part of the sequence you want to caption.
2. Move the position indicator to the effect you created in step 1, and ensure that the track containing the effect is selected.
3. If it is not already open, open the Effect Editor, for example, by clicking the Effect Mode button.
4. In the Caption Files parameter category, click Import Caption Data.
The “Select a file that contains caption data” dialog box opens.



5. Navigate to the location of the caption file you want to import.
6. From the Files of type menu (Windows) or the Enable menu (Macintosh), select the file type of the caption file you want to import:
 - EBU N19
 - Avid DS
7. In the list of files, select the caption file you want to import.

At the bottom of the dialog box, the Selected File Start and End boxes display the timecode range for the captions in the file — the starting timecode for the first caption in the file and the ending timecode for the last caption in the file. A message below these boxes indicates how many captions will be spliced into the sequence, or explains why importing the selected file into the effect will not be successful.

For more information on how the SubCap effect handles timecode ranges in caption files, see [“How the SubCap Effect Handles Caption Files” on page 449](#).

8. Do one of the following:
 - ▶ If you want to proceed with the import, click Open.
 - ▶ If you do not want to proceed with the import, select another file to import, or click Cancel.

If you click Open, your Avid editing application creates edit points and adds a new instance of the SubCap effect for each caption in the caption file. For each of these effects, your Avid editing application imports the appropriate caption text from the caption file.

Adding Information to a SubCap Effect

You can add information to a SubCap effect, including standard information categories such as program title and editor's name, as well as custom data that you define.

You can use settings in the Synchronize tab of the Global Properties dialog box to propagate the information changes you make in one instance of the SubCap effect in a sequence, either to all instances of the SubCap effect on the current track, or to all instances anywhere in the sequence. For more information, see [“Synchronizing SubCap Effect Parameters and Information” on page 457](#).

If you export the caption data from your sequence to the EBU N19 (.stl) format, any information that you add to SubCap effects is included in the file along with the caption text and timecode data. For more information, see [“Exporting SubCap Effect Data to Caption Files” on page 458](#).

To add information to a caption effect:

1. Move the position indicator to the SubCap effect to which you want to add information, and ensure that the track containing the effect is selected.
2. If it is not already open, open the Effect Editor, for example, by clicking the Effect Mode button.
3. In the Effect Editor, click Edit Global Properties.

The Global Properties dialog box opens.

4. In the Contacts, Custom, and Program tabs, enter information in the appropriate categories.

For information on the categories and limitations on the length of text that you can enter, see [“SubCap Effect Global Properties” on page 620](#).

5. Click OK.

Editing Text in the Master Caption List

You can view a list of all the captions in a sequence in the Master Captions List, and edit any of the captions from the list.

The Master Captions List also lets you modify text in the following ways that are not available in the Caption Text text box in the Effect Editor:

- Enter line breaks (carriage returns) in the text.
- Type Unicode characters directly.

For more information, see [“Working with Unicode Text in the SubCap Effect” on page 460](#).

To edit text in the Master Caption List:

1. Move the position indicator to any instance of the SubCap effect in the sequence, and ensure that the track containing the effect is selected.
2. If it is not already open, open the Effect Editor, for example, by clicking the Effect Mode button.

3. In the Caption Text parameter category, click Edit Master Caption List.

The Edit Master Captions List dialog box opens. The dialog box lists the video track, timecode range, and caption text for each caption in the sequence.

4. For each caption you want to edit, modify the text in the caption text box.

Press Enter (Windows) or Return (Macintosh) to enter a line break.

5. When you have finished editing all the captions you need to modify, click OK.

Adjusting SubCap Effect Parameters

The SubCap effect has a full range of parameter controls for adjusting the appearance of the caption text and its background box.

You can also change the position of the caption text and its background box on the screen by manipulating an anchor point directly in the Effect Preview monitor.

When you make adjustments to the parameter controls for a single SubCap effect in a sequence, you might want to have your changes apply to other instances of the SubCap effect in the same sequence. For more information on how to do this, see [“Synchronizing SubCap Effect Parameters and Information” on page 457](#).

To adjust a SubCap effect's parameters in the Effect Editor:

1. Move the position indicator to the SubCap effect in the sequence, and ensure that the track containing the effect is selected.
2. If it is not already open, open the Effect Editor, for example, by clicking the Effect Mode button.
3. Adjust one or more of the parameter controls in the Effect Editor.

For general information on working with parameter controls in the Effect Editor, see [“Effect Editor Controls” on page 90](#).

For reference information on the parameter controls for the SubCap effect, see [“SubCap Effect Parameters” on page 616](#).

Synchronizing SubCap Effect Parameters and Information

In most circumstances, you probably want the formatting and the additional information stored in all the SubCap effect clips in a sequence to be the same. When you change parameter values or global properties in one SubCap effect clip, you want all the other instances on that caption track, or all the other instances anywhere in the sequence, to update automatically.


The SubCap effect refers to such updating as *synchronizing*. You can customize how synchronizing operates for each effect parameter in the Effect Editor and for each information item in the Contacts, Custom, and Program tabs of the Global Properties dialog box.

To control how SubCap effect parameters and information items synchronize:

1. Move the position indicator to any instance of the SubCap effect in the sequence, and ensure that the track containing the effect is selected.
2. If it is not already open, open the Effect Editor, for example, by clicking the Effect Mode button.
3. Click Edit Global Properties.

The Global Properties dialog box opens.

4. Click the Synchronize tab.



5. For each effect parameter or information type in the list, select one of the following:

Option	Description
Clip	Changes to this item remain unique to the current effect clip and are not copied to any other SubCap effect clips in the sequence.
Track	Changes to this item are copied to any other SubCap effect clips on the track containing the current clip, but not to those on any other tracks in the sequence.
Sequence	Changes to this item are copied to all other SubCap effect clips in the sequence.

6. Click OK.

Exporting SubCap Effect Data to Caption Files

You can export caption data to a caption file. The caption data is then available for use outside the current sequence. For example, you might import it into another version of the sequence, or use it with captioning software other than your Avid editing application. You can export to either of the file formats supported by the SubCap effect.

If you export to an EBU N19 (.stl) caption file, any additional information that you have entered in the Contacts, Custom, or Program tabs of the Global Properties dialog box is exported along with the caption text and timecode information. For more information on entering additional information, see [“Adding Information to a SubCap Effect” on page 455](#).


If you export to an Avid DS caption file, only the caption text and timecode information is exported.

When you export caption data to a caption file, all of the caption data in the sequence is available for export. However, you can select which caption tracks to include in the export, and you can determine how the export resolves conflicts between captions on different tracks that overlap in time (a caption file can have only one caption for any given timecode range).

To export caption data to a caption file:

1. Move the position indicator to any instance of the SubCap effect in the sequence, and ensure that the track containing the effect is selected.
2. If it is not already open, open the Effect Editor, for example, by clicking the Effect Mode button.
3. In the Caption Files parameter category, click Export Caption Data.

The “Export caption data to the specified file” dialog box opens.



4. Navigate to the location where you want to store the exported file.
5. In the File name text box, enter a name for the caption file.
6. From the Files of type menu (Windows) or the Enable menu (Macintosh), select the caption file format you need, either EBU N19 or Avid DS.
7. In Tracks to Export, select the caption tracks from which you want to export data.

8. In the Conflicts list, select one of the following:

Option	Description
Use Higher Track	Where captions on multiple tracks overlap, your Avid editing application ignores the captions on the lower track or tracks and exports the caption on the higher or highest track.
Use Lower Track	Where captions on multiple tracks overlap, your Avid editing application ignores the captions on the higher track or tracks and exports the caption on the lower or lowest track.

9. Select Log to Console if you want your Avid editing application to log messages in the Console about the export process.

10. Click Save.

Your Avid editing application exports the caption data to the caption file.

If you selected Log to Console, information about the export process is written to the Console. The following is a typical message:

```
Starting caption export to: 'C:/Caption Files/test_higher.txt'...
    Found caption overlap at 00:00:31:26; ignoring the lower track.
Completed export of 21 captions.
```

Working with Unicode Text in the SubCap Effect

You can type Unicode text in the SubCap effect, for example, to create text that uses non-Western characters. To type Unicode text, you must use a font that includes the Unicode characters you need.

You cannot type Unicode text directly into the Caption Text text box in the Effect Editor. Instead, you type Unicode text in the Master Captions List, as described in [“Editing Text in the Master Caption List” on page 456](#).

Unicode text that you type in a caption in the Master Captions List displays in the Effect Editor’s Caption Text text box as *references* — sequences of hexadecimal characters preceded by an ampersand. For example, the Japanese Katakana character that transliterates as Na displays in the Caption Text text box as &30ca. Unless you are very familiar with these character codes, it is always better to view and edit Unicode text in the Master Captions List.

Working with SubCap Effect Stylesheets

You can save the current parameter values and information items for any SubCap effect clip as a *stylesheet*. You can then apply the values from a stylesheet to any SubCap effect clip. You can also set a stylesheet as the default to use when you create a new SubCap effect clip — all of the parameter values and information items from the default stylesheet are used as the initial values for the new effect clip, taking the place of the Avid-defined defaults.

Stylesheets let you maintain consistent formatting and metadata across many different sequences and projects. For example, they ensure that the caption style is the same for every episode of a television program or that every caption effect you create starts with the same look.




Caption stylesheets are XML files and are stored in a folder called Caption Effect Stylesheets inside the AVX2_Plug-Ins folder in the application folder for your Avid editing application. If you are comfortable editing XML files, you can edit caption stylesheets directly in any text editor.

You manage SubCap effect stylesheets in the Stylesheets tab of the Global Properties dialog box.

To create a new SubCap effect stylesheet:

1. Move the position indicator to the SubCap effect clip in the sequence that contains the parameter values and information items you want to save, and ensure that the track containing the effect is selected.
2. If it is not already open, open the Effect Editor, for example, by clicking the Effect Mode button.
3. Click Edit Global Properties.
4. Click the Stylesheets tab.



5. Click Create.

The Add New Stylesheet dialog box opens.

6. Type a name for the stylesheet in the Stylesheet Name text box, and click OK.

The new stylesheet appears in the list of stylesheets.

7. Click OK.

To delete a SubCap effect stylesheet:

1. Move the position indicator to any SubCap effect clip in a sequence, and ensure that the track containing the effect is selected.
2. If it is not already open, open the Effect Editor, for example, by clicking the Effect Mode button.
3. Click Edit Global Properties.
4. Click the Stylesheets tab.
5. Select the stylesheet you want to delete in the stylesheet list.
6. Click Delete.

The stylesheet is removed from the list.

7. Click OK.

To apply a SubCap effect stylesheet:

1. Move the position indicator to the SubCap effect clip in the sequence to which you want to apply the stylesheet values, and ensure that the track containing the effect is selected.
2. If it is not already open, open the Effect Editor, for example, by clicking the Effect Mode button.
3. Click Edit Global Properties.
4. Click the Stylesheets tab.
5. Select the stylesheet you want to apply in the stylesheet list.
6. Click Apply.
7. Click OK.

The values from the stylesheet are applied to the effect clip and are reflected on the Effect Editor's parameter controls and in the Contacts, Custom, and Program tabs in the Global Properties dialog box.

To set a SubCap effect stylesheet as the default for new SubCap effect clips:

1. Move the position indicator to any SubCap effect clip in a sequence, and ensure that the track containing the effect is selected.
2. If it is not already open, open the Effect Editor, for example, by clicking the Effect Mode button.
3. Click Edit Global Properties.
4. Click the Stylesheets tab.
5. Select the stylesheet you want to use as the default in the stylesheet list.
6. Click Set Default.
7. Click OK.
8. Restart your Avid editing application.

After the restart, the stylesheet you selected becomes the default. Its values become the default settings for any new SubCap effect clip.

Examples of SubCap Effect Parameter Adjustments

This topic provides two examples of caption text formatting. The examples illustrate and compare the effect of certain parameter changes on the appearance of caption text. They are not intended to represent an ideal finished look.

For more information on SubCap effect parameters, see “[Adjusting SubCap Effect Parameters](#)” on page 456 and “[Generator Effect Parameters](#)” on page 616.

Example 1



This example uses a single box as background for the entire text, a custom shadow, and keeps the Avid default settings for padding and row spacing. The following are the important parameter values that contribute to the look of the example:

Parameter	Value
Font Face	Arial Black
Font Size	20
Text Shadow	Custom (Radius 0.5, Angle 5.5)
Text Alignment	Center
Box Color and Opacity	R, G, and B all 95, Opacity 0.8
Box Style	One Box
Anchor Box to	Anchor to Bottom of Text
Box Width	Fixed Width (Wrap), Width 590
Padding	Vertical 2, Horizontal 3
Row Spacing	0

Example 2



This example uses a separate box for each row of the text, does not use a shadow, and uses custom values for padding and row spacing that allow the boxes to frame the text more elegantly than Example 1. The following are the important parameter values that contribute to the look of the example:

Parameter	Value
Font Face	Georgia
Font Size	20
Text Shadow	No Shadow
Text Alignment	Left
Box Style	Separate Boxes for Each Row
Anchor Box to	Anchor to Top of Text
Box Width	Each Row as Wide as Needed
Padding	Vertical 10, Horizontal 20
Row Spacing	15

15 Intraframe Editing

This chapter provides information on the intraframe editing features of your Avid editing application.

- [Understanding the Intraframe Effects](#)
- [Rendering Intraframe Effects](#)
- [Applying the Paint or AniMatte Effect to a Sequence](#)
- [Effect Editor Reference for the Paint and AniMatte Effects](#)
- [Using the Intraframe Drawing Tools](#)
- [Working with Vector-Based Objects](#)
- [Using the Previsualization Marker Tool for Film Projects](#)
- [Manipulating Intraframe Objects](#)
- [Layering, Grouping, and Locking Intraframe Objects](#)
- [Exporting a Matte Key Created With the AniMatte Effect](#)
- [Scratch Removal](#)
- [Intraframe Editing Examples](#)
- [Working with the Blur Effect and Mosaic Effect](#)

Understanding the Intraframe Effects

You can use the Paint Effect and the AniMatte effect to perform paint or animated matte effect operations within an individual frame or series of frames in a clip. You can also use the Scratch Removal effect to remove scratches and flaws from your video material, and the Blur and Mosaic effects to obscure part of an image by distorting the pixels within a defined area.

While many of the tools and parameters are the same for all the Intraframe effects, the result of applying each effect is different.

Your Avid editing application draws vector-based objects on the screen when you use Intraframe effects. Vector-based objects are composed of mathematically described lines and Bézier curves. You can edit vector-based graphics with greater control and efficiency than you can bitmapped objects, which are drawn on the screen as a pattern of pixels. For more information, see [“Working with Vector-Based Objects” on page 485](#).

Changes you make to an Intraframe effect are not limited to an individual frame. Any object you paint and any changes you make to it appear for the duration of the segment or clip. In most cases, you can change the parameters of the effect between keyframes, for example, to change the shape of the object or reposition it over time.

You can create multiple paint or matte shapes within a single effect. You can also add keyframes and apply effects separately to each of the shapes.

Paint Effect

The Paint Effect includes the following features:

- Creation of vector-based objects that you can animate and edit.
- Customizable paint brushes with preset templates and parameters for adjustable softness and rotation.
- A variety of paint modes including Blur, Clone, Colorize, Darken, Emboss, Erase, Lighten, Mosaic, Scratch Removal, and Unsharp Mask.
- Object selection with rescale, lock/unlock, and group/ungroup capabilities.
- Z-rotation of painted objects.
- Outline feathering with bias control.
- Magic Mask™ for quick and easy colorization.

AniMatte Effect

The AniMatte effect includes the following features:

- Keyframeable animation of matte effects.
- Modes for keying in and keying out images.
- Creation of mattes as vector-based objects that let you move, rescale, and reshape the mattes during a segment or transition.
- Freehand painting ability to create organic matte wipes.
- Magic Mask, brush shapes, Z-rotation, and feathering.
- Export of mattes to create keys in third-party applications.

Scratch Removal Effect

The Scratch Removal effect lets you remove scratches or other flaws by replacing them with clean material from elsewhere in the same frame or from another nearby frame. The Scratch Removal effect includes the same tools for drawing objects and painting brush strokes found in the Paint Effect, together with specific controls for selecting clean replacement material. For more information, see [“Understanding Scratch Removal” on page 505](#).

Blur Effect and Mosaic Effect

The Blur effect and Mosaic effect let you obscure parts of an image by distorting pixels. The Blur parameter category for the Blur effect is the same as the one that appears for the Blur mode of the Paint Effect. The Mosaic parameter category for the Mosaic effect is the same as the one that appears for the Mosaic mode of the Paint Effect. For more information, see [“Working with the Blur Effect and Mosaic Effect” on page 531](#).

Rendering Intraframe Effects

Intraframe effects are non-real-time effects. After you paint or draw a matte on a segment, you must render the effect to play it in real time. Regardless of how many objects you add to an individual segment, the effect plays back as a single stream of video. For more information, see [“Basics of Effects Rendering” on page 53](#).

In Effect mode, you can see the object as you step through each frame in the segment if Render On-the-Fly is selected in the Special menu (Clip menu on NewsCutter systems).

You can also use the Play Preview function to preview a Paint Effect while you are working in Effect mode. For more information, see [“Effect Editor Controls” on page 90](#).

Your Avid editing application renders painted objects to the screen starting with the bottom layer (closest to the video background).

Your Avid editing application renders a multitrack AniMatte effect to the screen starting with the top video track (farthest from the video background and appearing closest to you in three-dimensional space). For example, if the video background is on track V1, and you apply the AniMatte effect to track V2, the effect renders starting with the image on track V2.

However, if you draw multiple mattes in the same segment, these mattes are all objects that appear in the same foreground space, and they interact with each other much like multiple painted objects do in the same segment. For more information, see [“Layering, Grouping, and Locking Intraframe Objects” on page 501](#).

Remember these concepts as you use multiple objects and key modes in combination and layer them to generate new effects in a sequence. You can also combine the AniMatte effect with the Paint Effect to create custom effects.

Applying the Paint or AniMatte Effect to a Sequence

To apply the Paint Effect or AniMatte effect to a sequence:

1. Load a sequence into the Record monitor.
For information, see “Creating and Editing Sequences” in the Help.
2. Enter Effect mode by selecting Toolset > Effects Editing.
For more information, see “[Entering Effect Mode](#)” on page 41.
3. Do one of the following:



- ▶ To apply the Paint Effect, drag the Paint Effect icon from the Image category in the Effect Palette to a segment in the sequence.

The Paint Effect is a segment effect only. You cannot apply a Paint Effect to a transition.




- ▶ To apply the AniMatte Effect, drag the AniMatte effect icon from the Key category in the Effect Palette to a transition or a segment in the sequence.

You can apply an AniMatte effect to segments for multilayered effects or to transitions to create matte key wipes with your own custom shapes. (For information on creating keys, see “[Key Effects](#)” on page 251.)

The Effect Editor displays the default settings for the effect. Parameter sliders do not appear until you select one of the corresponding tools from the right side of the Effect Editor.








Effect Editor Reference for the Paint and AniMatte Effects





The following illustration identifies the different components of the Effect Editor that appear when you apply a Paint Effect to a segment in a video project and enter Effect mode.



The following table briefly describes the components of the Effect Editor for the Paint Effect.

For basic information on working with the Effect Editor, see “Using the Effect Editor” on [page 89](#).

Component		Description
1	Effect parameter categories	<p>Enable you to change the parameters of an effect.</p> <p>The same categories are available for both the Paint Effect and the AniMatte effect, with the following exceptions:</p> <ul style="list-style-type: none">• The AniMatte effect includes a Swap Src (swap sources) button in the Foreground parameter category that enables you to swap the foreground and background video images for matte keys composed of multiple video tracks. When you are building a single-track wipe, the Swap Src button enables you to swap the incoming and outgoing segments in the sequence.• The Magic Mask parameter category functions differently in the two effects. In the Paint Effect, you use the Magic Mask parameter category or the Color parameter category to make color selections. In the AniMatte effect, you use the Magic Mask parameter category to select a key color when you create a matte.
2	Brush Shape buttons	Change the shape of the brush.
3	Render Effect button	 Renders effects on selected tracks at the location of the position indicator in the effect's Timeline.
4	Outline/Path button	 Displays wire-frame representations of the painted object. Illustrates the movement of an object from the first keyframe through the last keyframe.
5	Brush Preview window	Displays the brush head with the parameters you select, such as color and shape. You also can use the window to reshape the brush head by dragging its control points.
6	Selection tool	 Selects an object so that you can change its parameters, move it, or delete it. With the Shift key pressed, selects multiple objects.
7	Z-Rotation button	 Rotates an object around the Z axis.
8	Reshape button	 Reshapes objects by manipulating anchor points at locations where new curves begin or straight lines intersect. Inserts additional control points.
9	Bring Forward button and Send Backward button	  Bring a painted object one layer forward on the screen or send an object one layer backward on the screen. With the Alt key (Windows) or Option key (Macintosh) pressed, bring a painted object to the front or send an object to the back.

Component	Description
10 Painting tool and Editing tool buttons	 <p>Enable you to paint shapes or draw mattes on frames in a sequence with freehand capability or with preset shapes.</p>
11 Tracking Tool button	 <p>Opens the Tracking Window, allowing you to generate and modify motion tracking data. For more information, see “Motion Tracking and Stabilization” on page 307.</p>
12 Previsualization Marker tool	 <p>Available in film projects. See “Using the Previsualization Marker Tool for Film Projects” on page 494.</p>
13 Grid button	 <p>Displays the Effect Grid. See “Understanding the Effect Grid” on page 83.</p>

Using the Intraframe Drawing Tools

You can use the Intraframe drawing tools for creating preset shapes or for creating freehand, vector-based objects and mattes with editable lines and Bézier curves. Additionally, the Selection tool enables you to select painted objects and mattes to move them, rescale them, and change their parameters.



Top to bottom: Rectangle, Oval, Polygon, Curve, and Brush tools in the Effect Editor



The parameter sliders do not appear until you select the corresponding drawing tool.

Your Avid editing application supports the use of a pen tool and graphics tablet with Intraframe drawing tools. For installation and configuration instructions, see the documentation that ships with your pen tool and tablet.

15 Intraframe Editing

When you work with a Paint or AniMatte effect in Effect mode, the pointer is the normal arrow when you select tools and options from the Effect Editor. However, once you select a paint or editing tool and position the pointer over the Effect Preview monitor, the pointer changes to a crosshair. This indicates that you can begin to paint or draw a matte on the frame.



After you use the Rectangle, Oval, Polygon, and Curve tools, your Avid editing application reverts to the Selection tool, and the pointer changes to an arrow. After you use the Brush tool, it remains the active tool, and the pointer remains a crosshair.

Understanding Intraframe Modes

The Paint Effect includes a wide variety of modes that offer many creative and corrective possibilities. Modes control the nature and appearance of the objects that you create with the drawing tools.

For example, if you create an oval shape with the Solid mode selected, a solid color oval appears in the frame. If you create the same oval shape and select the Lighten mode, the oval is not a solid color that masks part of the image beneath. Instead, it defines an area of the image that is lightened by an amount you specify.

The AniMatte effect provides two modes, Key In and Key Out. These modes enable you to key in or key out an image in a sequence.



For a complete listing of the characteristics of each Paint Effect mode as well as the Key In and Key Out modes in the AniMatte effect, see “Paint Effect Modes” on page 664 and “AniMatte Effect Mode Parameters” on page 676.

Understanding the Brush Tool



The Brush tool lets you use the mouse or a pen tool with a tablet to paint objects or mattes with precision directly on the images in a sequence. You also can change and customize the brush shape, determine the opacity of the paint or matte, adjust the outline feathering and softness values, and, for the Paint Effect, define the color.

You paint an object on the frame that displays in the Effect Preview monitor. The painted object is superimposed over the video background, appearing closer to you in three-dimensional space. Each object you paint is on its own foreground layer that you can work with individually or that you can group with other painted objects in the segment.



Example of a painted line over a gray background.

Selecting a Color for the Brush Tool

You can select the color that the Brush Tool uses by using the eyedropper, the parameter sliders, the Windows Color dialog box, or the Macintosh Colors panel. You can select the color before you begin painting or after you have painted an object. For more information, see [“Adjusting a Color Parameter for an Effect” on page 96](#).

When you use the Brush tool to paint an object, you can select a color quickly from a video segment.

To select a color from a video segment when using the Brush tool:



1. In the Effect Editor, click the Brush tool to make it the active paint tool.
2. In the Mode category, click the Fast Menu button, and then select Solid.
3. Press and hold the Alt key (Windows) or Option key (Macintosh), and drag the pointer to the Effect Preview monitor.

The pointer becomes an eyedropper.

4. Position the eyedropper over the color you want to select, and click it.


The color you pick becomes the new default color shown in the Color Preview window.

Painting with the Brush Tool

To begin painting with the Brush tool:



1. Apply the Paint Effect to a segment in the sequence as described in [“Applying the Paint or AniMatte Effect to a Sequence” on page 470](#).
2. Click the Brush tool in the Effect Editor.
3. Select a paint mode or key mode and parameters in the Effect Editor.
4. In the Brush parameter category of the Effect Editor, click one of the Brush Shape buttons.



Brush Shape tools in the Effect Editor

- The default shape of the brush head changes to your selection.
5. Position the pointer over the image in the Effect Preview monitor.
The pointer becomes a crosshair.
 6. Press and hold the mouse button, and drag to paint freehand style on the video background.
 7. Release the mouse button when you have finished painting the object.


Creating a Custom Brush Head

You can change the brush head to a custom shape by modifying the brush head in the Brush Preview window.

To create a custom brush head:



1. Click the Brush tool in the Effect Editor.
2. Click a Brush Shape button to use as the basis for your custom brush head.




Brush Shape tools in the Effect Editor

The shape appears as the brush head in the Brush Preview window.

3. In the Brush Preview window, click the brush head.
Control points appear on the brush head where curves merge or straight lines intersect.



You might need to increase the Size value for the brush head, for example to a value over 20, in order to see the control points. You can reduce the size of your custom brush head once you have adjusted its shape.



4. Click a control point, and drag it to change the shape of the brush head.
5. Repeat step 4 with other anchor points until you have the shape you need.




For brush shapes with rounded edges and curves, such as the oval, the ellipse, and the circle, clicking an anchor point creates direction bars and handles that enable you to edit the Bézier curve. For information on working with Bézier curves, see “Working with Vector-Based Objects” on page 485. You can use the direction bars and handles, and you can drag the object’s control points, but you cannot use the modifier key variations.

To rotate the brush head:



1. Click the Brush tool if the brush is not already active.
2. Click the Brush Shape button for the brush head you want to rotate.



Brush Shape tools in the Effect Editor

The shape appears in the Brush Preview window.

3. Do one of the following:
 - ▶ Drag the Spin slider to the right (clockwise rotation) or to the left (counterclockwise rotation) to rotate the brush head to the position you want.
 - ▶ Click the Spin slider, and use the numeric keypad to type a value from –360 to 360.

Saving and Applying Brush Templates

You can save a template of a custom brush to a bin so that you can reuse the parameters of the brush with an Intraframe effect.

To save a brush template:



1. In the Brush category, click the Brush Template icon, and then drag it to a bin.
A brush template appears in the bin, and the name of the template defaults to Brush.
2. Click the name of the template in the bin, type a unique name for the template, and press Enter (Windows) or Return (Macintosh).

To use a brush template:

- Click the template in the bin, drag it to the Brush Preview window, and release the mouse button.

The brush in the Brush Preview window assumes the same parameters as the brush template you saved to the bin.

Using the Brush Tool and the Path Parameter to Create a Signature Effect

The Path parameter slider is useful for creating a “signature” effect with the Paint Effect, in which a signature gradually appears on the screen as if written with an invisible pen.

To create the signature effect:



1. Apply the Paint Effect to a segment.
2. In the Effect Editor, click the Brush tool.
3. In the Mode category, click the Fast Menu button, and select Solid.
4. Drag the pointer in the Effect Preview monitor to paint a signature or other string of text.
5. Release the mouse button when you are satisfied with the text.
6. Use keyframes with the Path parameter to gradually reveal the text over time.

For example, in the simplest case, set the Path parameter to 0 on a keyframe at the beginning of the effect and to 100 on a keyframe at the end of the effect.

7. Render the Paint Effect to play it back in real time.

For more information, see [“Basics of Effects Rendering” on page 53](#).

Creating Rectangular and Oval Shapes

To paint with the Rectangle or Oval tool:


1. In the Effect Editor, click the Rectangle or Oval tool.



Rectangle tool (left) and Oval tool (right)

2. In the Effect Editor, select a paint mode or key mode and parameters.
3. Position the pointer where you want to begin painting in the frame.
4. Press and hold the mouse button, and drag to create the rectangle or oval.

As you drag, you describe the diagonal of the rectangle or oval. The rectangle or oval's anchor point is the point at which you start to drag. For example, if you drag to the right and down, the rectangle or oval is anchored to its upper left corner.



5. Release the mouse button to complete the shape.
6. (Option) Adjust the object's parameters.

Creating Shapes with the Polygon Tool

You can use the Polygon tool to paint a variety of create objects and mattes composed of straight-line segments, curved segments, or a combination of both.

To take full advantage of the Polygon tool, you should be familiar with the concepts behind vector-based graphics. For more information, see [“Working with Vector-Based Objects” on page 485](#).

The general workflow for working with the Polygon tool is:

1. Visualize the shape and position of the object you want to create.
2. Determine a location in the frame to begin painting, and click that location to create the initial control point.
3. Click additional control points as you continue to define the shape of the object.
Try to create the object with as few control points as possible. Fewer control points simplify your work if you need to modify the object later.
4. Double-click to create the final control point, or click the initial control point to create the closed polygon.

To create a polygon with straight-line segments:



1. In the Effect Editor, click the Polygon tool.
2. Select a paint mode or key mode and parameters in the Effect Editor.
3. Click in the frame where you want to place the initial control point.



The control points do not appear as tiny rectangles while you are painting the object.

4. Click in the frame where you want to place the next control point.

Your Avid editing application draws a straight-line segment between the initial control point and the control point you just created.




Segments appear as wire frames until you finish painting the object.

5. Click in the frame to create additional control points that further define the shape of the object.

A straight-line segment appears between each pair of adjacent control points.

6. When you are satisfied with the shape of the object, double-click in the frame to create the final control point or click the initial control point.

The object becomes a closed polygon.




7. (Option) Adjust the parameters of the polygon.

To create an object with curved segments:


1. In the Effect Editor, click the Polygon tool.
2. Select a paint mode or key mode and parameters in the Effect Editor.
3. Click in the frame where you want to place the initial control point, and release the mouse button.
4. Move the pointer to the location where you want to place the next control point.
5. Click and hold the mouse button to begin creating the first curved segment.

Direction bars with handles appear as a tangent to the curved segment. The pointer “leads” the direction handle that you use to determine the direction and height of the curve.



6. Drag the pointer, which is attached to the direction handle, to adjust the direction and height of the curved segment.
7. Release the mouse button when you are satisfied with the height and angle of the curved segment.
8. Move the pointer to the next location where you want to create a curved segment.
9. Repeat steps 3 to 8 to create additional curves if needed.
10. When you are satisfied with the shape of the object, double-click in the frame to create the final control point or click the initial control point.


The object becomes closed.



11. (Option) Adjust the parameters of the object.


To create a straight line following a curved segment:

1. Create one or more curved segments as described in the previous procedure.
2. Move the pointer to the location where you want to begin painting the straight line.
3. Click and then release the mouse button to create the control point.
4. Move the pointer to the location where you want the straight-line segment to end.
5. Click and then release the mouse button to create the control point.



6. Continue to create additional lines and curves.
7. When you are satisfied with the shape of the object, double-click in the frame to create the final control point or click the initial control point.

The object becomes closed.



8. (Option) Adjust the parameters of the object.

Creating Freehand Curved Objects

With the Curve tool, you can trace curved objects with freehand capability.

To paint with the Curve tool:

1. In the Effect Editor, click the Curve tool.
2. Select a paint mode or key mode and parameters in the Effect Editor.
3. Position the pointer where you want to begin painting in the frame.
4. Press and hold the mouse button, and drag the pointer as you paint a freehand curved shape on the frame.
5. When you are satisfied with the shape of the object, release the mouse button to complete the curved object.
6. Adjust the object's parameters if needed.

Selecting and Deselecting Intraframe Objects

You can select one or more Intraframe objects, for example to move them in the frame, rescale them, or change their parameters. When a segment contains multiple objects, you can use buttons to change your selection from one object to another.

To select an object:

- ▶ Click the Selection tool, and click an object.
Selection handles appear around the object.

To select multiple objects, do one of the following:

- ▶ Shift+click additional objects with the Selection tool.
- ▶ Drag a lasso around the objects you want to select.

When you select multiple objects, one set of selection handles appears around all the objects, which enables you to move, rescale, or otherwise change the parameters of all the selected objects simultaneously.

To change the selection from one object to another:

- ▶ Click one of the following buttons: Fast Forward, Rewind, Go to Next, or Go to Previous.

The Fast Forward and Rewind buttons are in the Effect Preview Monitor toolbar. To use the Go To Next button and the Go To Previous button in Effect mode, you must map them to your keyboard. For more information, see “The Command Palette” in the Help.

To delete an object:

1. Click the Selection tool.
2. Click the object you want to delete.
3. Do one of the following:

15 Intraframe Editing

- ▶ Press the Delete key.
- ▶ Select Edit > Delete.

To undelete an object:

- ▶ Select Edit > Undo.

Changing the Parameters of Intraframe Objects


You can change the parameters of an object you have already painted. Select the object (see [“Selecting and Deselecting Intraframe Objects” on page 483](#)), and perform any of the following procedures.

To move an object:

- ▶ Click anywhere within the object’s outline, and drag the object to a new location.

To rescale an object, do one of the following:

- ▶ Click one of the selection handles and drag.
- ▶ Press and hold the Alt key (Windows) or Option key (Macintosh) while you click one of the selection handles, and drag to rescale the object from its center.



Selection handles on a rectangular object

To change the color of an object:


1. Click the triangular opener for the Color parameter category.



2. Adjust the Hue, Sat (saturation), and Lum (luminance) sliders.

To add feathering to an object's edges:

1. Click the triangular opener for the Feathering parameter category.



2. Adjust the Bias, Hor (horizontal), and Vert (vertical) sliders.

Working with Vector-Based Objects


Intraframe effects are vector-based objects. Vector-based objects have several advantages over bitmapped objects. For example, you can create and edit vector-based objects with much greater precision than you can bitmapped objects. Also, vector-based objects are not subject to problems such as artifacting when you rescale them.

Before you begin working with the paint and editing tools included in the Intraframe effects, you must understand the basics of working with vector-based objects and Bézier curves.

The Elements of Vector-Based Objects

The objects you paint, the matte keys you draw, and the brush templates that appear in the Brush Preview window include a control point at the midpoint of each line or curve, also known as a join. The portion of the line or curve on each side of the control point is called a segment. The control point controls the direction of each segment as it passes through the join.


Control points for a painted object are visible when you select an object with the Selection tool and then click the Reshape tool. Also, when you click a brush template in the Effect Editor, the brush head displays visible control points in the Brush Preview window.



A control point at the midpoint of a curve


The following illustration shows the three types of joins:

15 Intraframe Editing



Left to right: straight-edge join, smooth join, and corner join

A control point associated with a smooth join or a corner join describes a Bézier curve. Clicking a control point makes it the active join. Tangents called direction bars appear on each side of the control point associated with a Bézier curve. At the end of each direction bar is a direction handle.



Direction bar with direction handles

Dragging a direction handle changes the way the segments pass through the control point to define the curve. When you drag a direction handle, you change the height and angle of the curve. The curve responds as if you are gently tugging it like a piece of string. The segments remain anchored to the control points on either side of the active join.

Straight-edge joins do not display direction bars and handles when you click them.

Reshaping an Intraframe Object with Straight Edges

To reshape an object composed of one or more straight edges, do one or more of the following:

- ▶ Click the Selection tool, click the object to select it, click the Reshape tool, and then drag one or more control points.



Selection tool (left) and Reshape tool (right)

For information on control points, see [“Moving Control Points” on page 493](#).

- ▶ Convert straight-edge joins to Bézier curves, and then manipulate the curves.

For more information, see the following topics:

- [“Experimenting with Bézier Curves and Direction Handles” on page 487](#)
- [“Creating a Corner Join on an Intraframe Object” on page 490](#)

- [“Reference for Modifying Lines and Curves in Intraframe Objects”](#) on page 491

Experimenting with Bézier Curves and Direction Handles

This topic provides two procedures that you can use to practice using Bézier curves and their direction handles. In the first procedure, you create a rectangle using the Rectangle tool, and then transform the rectangle into a circle by converting the straight-edge joins at the corners of the rectangle to smooth joins. In the second procedure, you alter the curve segments that comprise the circle by manipulating the Bézier direction handles.

To create a rectangle and transform it into a circle with Bézier curves:

1. Apply the Paint Effect to a segment in a sequence.
2. If your Avid editing application is not in Effect mode, enter Effect mode, for example, by selecting Toolset > Effects Editing.

For more information, see [“Entering Effect Mode”](#) on page 41.




3. In the Effect Editor, click the Rectangle tool.
4. In the Mode parameter category, click the Fast Menu button, and then select Solid.
5. Press and hold the mouse button, and drag in the Effect Preview monitor to paint a rectangular object.

Do not worry about picking a color or other parameters for this exercise.




6. Click the Selection tool, and click the object you just painted.
7. Click the Reshape tool, or double-click the object.

Each corner of the rectangle displays a control point.




8. Alt+click (Windows) or Option+click (Macintosh) the control point at the top left corner of the rectangle.

The straight-edge join becomes a smooth join with direction bars and handles.



9. Working in a counterclockwise direction, Alt+click (Windows) or Option+click (Macintosh) each control point until they have all been transformed into smooth joins.


The resulting shape is a circle. The control point at the top right of the circle is the active join and displays direction bars and handles.



To experiment with the direction handles:

1. Click the bottom direction handle, and drag away from the control point to increase the length of the direction bar.

Notice how the curve changes. Also, the direction bar and segment on the opposite side of the control point move in unison with the direction bar you are dragging. The control points adjacent to the active join serve as anchor points for the segments that compose the curve.




Example of dragging a direction handle.

2. Drag the direction handle toward the control point to shorten the direction bar.

Notice how the curve changes as you shorten the direction bar.

3. Shift+click the direction handle, and then drag it away from the control point.


Notice that the length of the direction bar on the opposite side of the control point does not change. This prevents the height of its associated segment from changing. However, the opposite direction bar does move in unison with the direction handle you are dragging, thereby changing the angle of the segment in unison.



Example of Shift+dragging a direction handle.

4. Shift+click the direction handle to revert the direction bars to their previous functionality.
5. Click the bottom direction handle, and drag it in a counterclockwise direction.

Notice how the curve changes as you drag the direction bar.



Example of rotating a direction handle without changing its length.

6. When you have finished experimenting, adjust the direction bar so that the object again resembles a circle.

Creating a Corner Join on an Intraframe Object

The painting tools do not create corner joins by default, but you can change an existing smooth join into a corner join. The procedure in this topic assumes you are starting with an object like the one created by following the procedure in [“Experimenting with Bézier Curves and Direction Handles”](#) on page 487.

To transform a straight-edge join into a corner join, first transform the straight-edge join into a smooth join and then transform the smooth join as described here. For more information, see [“Reference for Modifying Lines and Curves in Intraframe Objects”](#) on page 491.


To transform a smooth join into a corner join:

1. Alt+click (Windows) or Option+click (Macintosh) the bottom direction handle.

Although you might not notice it immediately, the smooth join is transformed into a corner join.


2. Drag the direction handle away from the control point.

The direction bar and the segment on the opposite side of the control point do not move in unison with this direction handle, and the active segment remains anchored to the adjacent control point.



3. Drag the direction handle in a counterclockwise direction.

Notice how the segment changes as you drag the direction bar.







- When you are finished experimenting, Alt+click (Windows) or Option+click (Macintosh) the direction handle.

The control point reverts to a smooth join.


Reference for Modifying Lines and Curves in Intraframe Objects

The following table summarizes how you can use the mouse and the modifier keys on the keyboard to modify lines and Bézier curves (smooth joins or corner joins).

Methods of Modifying Intraframe Lines and Curves

Illustration	Description	Action
	Smooth join: Drag one direction handle so that the direction bar on the opposite side of the control point moves and changes length in unison.	You do not have to press any of the modifier keys. Click one of the direction handles, and drag it.
	Smooth join: Drag one direction handle so that the direction bar on the opposite side of the control point moves in unison but does not change in length.	Shift+click a direction handle. To change it back, Shift+click the direction handle.
	Transform a straight-edge join (left) into a smooth join (right).	Alt+click (Windows) or Option+click (Macintosh) the control point. To change it back to a straight-edge join, Alt+click (Windows) or Option+click (Macintosh) the smooth join.
	Transform a smooth join (left) into a corner join (right).	Alt+click (Windows) or Option+click (Macintosh) one of the direction handles. To change it back to a smooth join, Alt+click (Windows) or Option+click (Macintosh) the direction handle.

Methods of Modifying Intraframe Lines and Curves (Continued)

Illustration	Description	Action
	Corner join: Drag one direction handle so that the direction bar on the opposite side of the control point moves independently of the bar on the opposite side of the control point.	You do not have to press any of the modifier keys. Click one of the direction handles, and drag it.

Adding and Removing Control Points

Placing more control points on an object enables the object to trace more detailed images. For example, if a segment of an object does not follow a curved section on a frame as well as you would like, and adjusting the control points and direction bars does not help, you can add a new control point.

Avid recommends that you remove a control point if the object does not need the control point to adequately define its shape. It is better to have fewer control points and to manipulate the direction bars to gain the same effect because fewer control points mean less work if you need to modify an object later.



Unnecessary number of control points (left) and minimum number of control points (right) for describing the curve

To add a control point:



1. Click the Selection tool, and click the object.
2. Do one of the following:



- ▶ Click the Reshape tool.
- ▶ Double-click the object.

3. Click the selected object where you want to add a new control point.

A new control point appears and is calculated so that the object does not change dramatically in shape. The new control point appears as part of the object for all keyframes in the segment.

Any changes you make to a control point, such as moving it or changing the angle of the associated curve, affect the keyframes you have selected in the segment. If you change a control point at a selected keyframe or add a keyframe to make changes, the changes are interpolated between the selected keyframe and adjacent keyframes.

To remove a control point:

- ▶ Click the control point, and press the Delete key.

To remove multiple control points:

- ▶ Shift+click the control points, and then press the Delete key.

Your Avid editing application attempts to reconstruct the object so that it does not change. The results you see might vary because of the internal mechanics and geometry of Bézier curve technology. However, adding and then removing the same control point should not dramatically change the curve of that section of an object.

Moving to Adjacent Control Points

You can move from a control point to an adjacent control point without having to click the mouse.

To move to an adjacent control point:

1. Click a control point.
2. Do one of the following:



- ▶ Click the Fast Forward button to move in a clockwise fashion to the next control point.



- ▶ Click the Rewind button to move in a counterclockwise fashion to the next control point.

Moving Control Points

Before you select control points for moving, first click the Selection tool, and click the object to display the control points.

To move a single control point manually:

- ▶ Drag the control point to its new location.

The control point's direction bars do not change orientation.

To move multiple control points manually:

- ▶ Click one control point, Shift+click or lasso additional control points that you want to move, and then drag one of the selected control points.

All other selected control points move in unison. To deselect the group, click any unselected control point.

To move all control points manually:

- ▶ Press Ctrl+A (Windows) or Command+A (Macintosh) to select all control points, and then drag one of the selected control points.

All other control points move in unison. To deselect the group, click outside the object to deselect it.

To move or “nudge” control points in 1-pixel increments:

1. Click a control point to select it, or Shift+click additional control points to move them as a group.
2. Nudge the control point or points using one of the following techniques:
 - ▶ To nudge selected control points to the left, press the Left Arrow key or the Trim Left key.
 - ▶ To nudge selected control points to the right, press the Right Arrow key or the Trim Right key.
 - ▶ To nudge selected control points up, press the Alt key (Windows) or the Option key (Macintosh) and the Left Arrow key, or press the Trim Left key.
 - ▶ To nudge selected control points down, press the Alt key (Windows) or the Option key (Macintosh) and the Right Arrow key, or press the Trim Right key.



The Effect Preview monitor must be the active window for arrow key movement of control points to work. Additionally, if your arrow keys are mapped to another function, such as Step Back and Step Forward, this feature might not function properly.

Using the Previsualization Marker Tool for Film Projects

The Previsualization Marker tool lets you place a marker in a segment to represent an effect that will be processed at an optical facility. This tool is applicable to 24-fps film projects only and does not appear in the Effect Editor for the Paint Effect in any other project types.

When you create an optical list, each marker, along with its position in the segment on a keyframe-by-keyframe basis, appears as an optical event. The editor at the optical facility can refer to the event as a cue for creating a visual effect, such as a rotoscoped object.

For example, the optical editor's assignment is to create an airplane that flies through the scene. The optical editor can use keyframe information from the optical list to plot the exact path of the effect as it moves through the scene. The marker's position at each keyframe is described with coordinates derived from the Effect Grid. Position is described in terms of compass coordinates and X, Y coordinates.

You can add multiple markers to a single scene to represent different effects, and use a unique color for each marker. The resulting optical list displays each marker and its unique color values to enable the optical editor to distinguish each marker.



You generate optical lists with Avid FilmScribe. For general information on using Avid FilmScribe, see the Avid FilmScribe Help.

To add a Previsualization Marker effect to a sequence:

1. Enable the Effect Grid and set the appropriate parameters for image scan size, aspect ratio, and film format.

For more information, see [“Displaying the Effect Grid in Effect Mode” on page 84](#).

2. If your Avid editing application is not in Effect mode, enter Effect mode, for example, by selecting Toolset > Effects Editing.

For more information, see [“Entering Effect Mode” on page 41](#).



3. In the Effect Editor, click the Previsualization Marker tool.
4. Adjust the sliders in the Color parameter category to determine the color of the marker.
5. Move the pointer to the location in the frame where you want to place the marker, and click the mouse.

A marker appears in the frame.

6. Use keyframes to move the marker throughout the segment.

To add more markers:

- ▶ Repeat steps 2 to 5 in the previous procedure.

To delete a marker:

- ▶ Click the marker to highlight it, and then press the Delete key.

To include the Previsualization Marker coordinate information in a cut list:

1. Select Output > FilmScribe to start FilmScribe.
2. Select File > New Cut List.
3. In the Lists pane, select Optical.
4. In the Options pane, select Key Frames.

The following illustration shows the presentation of Previsualization Marker information in a cut list.

Transfer:	Full Aperture
Grid:	Standard Film
Fields:	12
Subfields:	4
Scan Size:	(X: 720, Y: 486)

Key Frame Information		
KF	Footage	A Key #
(1)	220	0314+13
Marker1	(R: 255, G: 0, B: 6)	
	(N: 0.0, W: 0.0)	(X: 30, Y: 91)
Marker2	(R: 58, G: 61, B: 28)	
	(N: 0.0, W: 0.0)	(X: 243, Y: 194)

Top to bottom: grid information, keyframe number and reference numbers, and color and coordinate information for two separate markers

Manipulating Intraframe Objects

Intraframe effects include editing tools and additional parameters that enable you to perform the following operations:

- Move objects individually or in groups.
For more information, see [“Moving Intraframe Objects” on page 496](#).
- Reshape objects.
For more information, see [“Reshaping Intraframe Objects” on page 497](#).
- Rotate objects.
For more information, see [“Rotating Intraframe Objects” on page 498](#).
- Scale objects.
For more information, see [“Scaling Intraframe Objects” on page 499](#).
- Apply keyframed changes over time.
For more information, see [“Changing Intraframe Object Parameters over Time” on page 500](#).

Moving Intraframe Objects

The Selection tool also enables you to drag objects or mattes around the screen and in relation to the screen when you zoom out from a frame.

To move a painted object or matte:



1. In the Effect Editor, click the Selection tool.
2. Click the object you want to move.

The object outline becomes highlighted, and four selection points appear around the object.

3. Click the center of the object, and drag it to a new location.
4. Release the mouse button when the object is positioned in the location you want.

Reshaping Intraframe Objects

The Reshape tool lets you modify the shape of a painted object or matte on the screen using several different techniques. These procedures require some familiarity with vector-based graphics. For more information, see [“Working with Vector-Based Objects” on page 485](#).



You can use keyframes to change the shape of an intraframe object over time. For more information, see [“Changing Intraframe Object Parameters over Time” on page 500](#).



The default behavior of control points in an object or matte created with the Curve tool differs slightly from those created with the Polygon tool. When you drag one of the direction handles, the direction bar on the opposite side of the control point moves in unison but the length does not change in unison. The dimensions of the curved segments on each side of the control point are not equal because the Curve tool creates curves with freehand capability, not with a mathematical formula that describes a Bézier curve in the way that the Polygon tool does.

You can transform the direction bars at a control point so that their lengths change in unison when you drag one of the direction handles. To do so, Shift+click one of the direction handles. For more information, see [“Reference for Modifying Lines and Curves in Intraframe Objects” on page 491](#).

To reshape an object:




1. Click the Selection tool, and click an object or matte.
2. Do one of the following:



- ▶ Click the Reshape tool.
- ▶ Double-click the selected object.

The outline of the object becomes highlighted, and control points appear.



*To drag the control points only, **Alt+click** (Windows) or **Option+click** (Macintosh) the Reshape tool to hide the direction handles.*

3. Edit the shape of the object or matte:

- ▶ Click one or more of the object's control points and drag.
For information on moving control points, see [“Moving Control Points” on page 493](#).
- ▶ Edit the object by manipulating the direction bars at one or more control points.
For information on editing straight-line segments and curved segments, see [“Reference for Modifying Lines and Curves in Intraframe Objects” on page 491](#).

Rotating Intraframe Objects

You can select an object or matte and rotate it around the Z axis.


You can also change the rotation of an object over time by rotating the object on an individual keyframe basis. For more information, see [“Changing Intraframe Object Parameters over Time” on page 500](#).

To rotate an object or matte around the Z axis:



1. In the Effect Editor, click the Z-Rotation tool.
2. Click the object you want to rotate.

The object outline becomes highlighted, and a rotation handle appears within the object.



Center of rotation (+) and Z-Rotation handle

The + on the rotation handle marks the default center of the Z axis for the object. You can click the + and drag it anywhere on the screen to change the center of the object's rotation.

3. Click the rotation handle and drag the mouse to rotate the object in either a clockwise or a counterclockwise direction.

Scaling Intraframe Objects

You can rescale any object or matte that you create. Rescaling increases or decreases all dimensions of the object proportionately.

You can also use keyframes to change the scale of an intraframe object over time. For more information, see [“Changing Intraframe Object Parameters over Time” on page 500](#).

To rescale an object or matte:




1. In the Effect Editor, click the Selection tool.
2. Click the object you want to rescale.


The object outline becomes highlighted, and four selection points appear around the object.

3. Rescale the object using one of the following methods:
 - Click any selection point and drag.

Drag toward the center of the object to decrease the overall size. Drag away from the center to increase the overall size. When you drag a selection point, the object is anchored by the selection point that is diagonal to the one you are dragging.



- Alt+click (Windows) or Option+click (Macintosh) any selection point, and drag to rescale the object, using the center of the object as the anchor.



Changing Intraframe Object Parameters over Time

You can animate an intraframe object by changing parameters on an individual keyframe basis. The following parameters are keyframeable:

Parameter	For more information:
Position of an object on screen	See “Moving Intraframe Objects” on page 496.
Shape of an object	See “Reshaping Intraframe Objects” on page 497
Z-axis rotation of an object	See “Rotating Intraframe Objects” on page 498
Scale or relative size of an object	See “Scaling Intraframe Objects” on page 499
Feathering	See “Feathering” on page 608.
Foreground level	See “Foreground” on page 609.
Magic Mask	See “Magic Mask” on page 612.

For more information on using keyframes with parameters, see [“Working with Keyframes”](#) on page 101.

Layering, Grouping, and Locking Intraframe Objects

Intraframe effects include tools for navigating and adjusting layers of intraframe objects, for grouping objects for performing operations on several objects at once, and for locking objects to prevent further changes.

When you paint on a frame, the paint appears as an object in the foreground, seeming closer to you in three-dimensional space than the video frame. You can change the parameters of each painted object independently, including the object's orientation in relation to another object. For example, if you have three painted objects, you can stack or cascade them over each other to create three separate layers of objects in the foreground.

All compositing of painted objects takes place in the foreground and is not destructive to the video background. When you composite various Paint Effects on a frame, remember that your Avid editing application renders the Paint Effects to the screen beginning with the bottom layer.

Layering with the AniMatte effect works much as it does with the Paint Effect, but the image that appears in the foreground of an AniMatte effect is the video that you have chosen to key in or key out. Even though your Avid editing application renders matte keys starting with the highest track in a multilayer matte key, compositing of multiple AniMatte effects in the same segment occurs in the foreground and is not destructive to the video background.

You can use the Outline/Path button to locate an object or matte that is hidden by others on the screen. The Outline/Path button creates a wire-frame representation of each object, which enables you to locate, select, and manipulate the object.

To locate objects or mattes with the Path function:



1. In the Effect Editor, click the Outline/Path button.
Each object painted on the frame appears as a wire frame.
2. Select an object, and change its location or parameters.
3. Click the Outline/Path button to return to default viewing mode.

To change the layer order of an object or matte:



1. Click the Selection tool, and click an object on the screen.
If the object is hidden by other objects, use the Outline/Path feature to locate it as described in the previous procedure.
2. Do one of the following:



- ▶ To move the object one layer forward, click the Bring Forward button in the Effect Editor or select Object > Bring Forward.



- ▶ To move the object one layer backward, click the Send Backward button in the Effect Editor or select Object > Send Backward.
- ▶ To move the object to the front of the layers (appearing closest to you in three-dimensional space), Alt+click (Windows) or Option+click (Macintosh) the Bring Forward button in the Effect Editor or select Object > Bring to Front.
- ▶ To move the object to the back of the layers (appearing farthest from you in three-dimensional space), Alt+click (Windows) or Option+click (Macintosh) the Send Backward button in the Effect Editor or select Object > Send to Back.

To group painted objects or mattes:



1. Click the Selection tool, and click an object.

If the object or matte is hidden by other objects, use the Outline/Path feature to locate it as described in the first procedure in this topic.

2. Shift+click any additional objects you want to include in the group.
3. Select Object > Group.

The objects become grouped together, and you can manipulate the group as if it were a single object.

To ungroup painted objects or mattes:

1. Click the Selection tool, and click an object that is a member of the group.
2. Select Object > Ungroup.

The objects become ungrouped.



You can also group together groups of objects. If you then click the new group and select Ungroup, all objects become ungrouped completely.

To lock a painted object, matte, or group:



1. Click the Selection tool, and click an object or group.

If the object is hidden by other objects, use the Outline/Path feature to locate it as described in the first procedure in this topic.

2. Select Object > Lock.

To unlock a painted object, matte, or group:

1. Click the Selection tool, and click an object or group.
2. Select Object > Unlock.

Exporting a Matte Key Created With the AniMatte Effect

You can create a matte with the AniMatte effect and export it as a high-contrast matte without leaving Effect mode. The exported image is a high-contrast 32-bit PICT file that includes an alpha channel.

You can use the exported PICT file in the following ways:

- Import the file back into your Avid editing application to create a real-time Matte Key clip that you can edit into a sequence. You can use this clip as a garbage matte or promote the clip to 3D.
- Open the file in a third-party graphics application, edit the file, and import the file back into your Avid editing application.
- Use the file as a graphic in an application other than your Avid editing application.

When you import the PICT file back into your Avid editing application, your Avid editing application creates a Matte Key clip in the bin that you select. You can load the Matte Key clip into the Source monitor and edit it into a sequence as you can with any other imported matte key. The Matte Key clip appears as a high-contrast matte with transparent (black) and opaque (white) components.

When you open the high-contrast PICT file in a third-party application that supports alpha channels, select the file's alpha channel to view the high-contrast components of the matte. When you open the PICT file in an application that does not support alpha channels, the image appears completely white.

To export a matte key created with the AniMatte effect:

1. Use the AniMatte effect to create a matte key.
For more information, see [“Applying the Paint or AniMatte Effect to a Sequence” on page 470](#).
2. If your Avid editing application is not in Effect mode, enter Effect mode, for example, by selecting Toolset > Effects Editing.
For more information, see [“Entering Effect Mode” on page 41](#).
3. In the Timeline, move the position indicator to the frame you want to export.
4. Click the Effect Editor.
5. Select File > Export Matte PICT.



You must click the Effect Editor before you select File > Export Matte PICT. If you do not, your Avid editing application displays the default Export command in the File menu.

The Export PICT As dialog box opens.

6. Select the location where you want to save the PICT file, and then click Save.

Your Avid editing application saves the PICT file to the location you selected.

7. If necessary, open the PICT file in a third-party application and make changes to the file.

To import the matte key into your project:

1. Select the bin into which you will import the PICT file, and select File > Import.

The Select files to Import dialog box opens.

2. Select Graphic Files from the Files of Type menu.
3. Click Options.
4. In the Alpha area, click one of the following to select an alpha channel option:
 - Use Existing
 - Invert Existing
 - Ignore

Depending on your needs, you might have to select Invert Existing. In a high-contrast matte key with an alpha channel, the white regions are opaque, and the black regions are transparent.

For more information on importing a matte key, see “Importing Media Files” in the Help.

5. When you have finished selecting the options you need, click OK.
6. Select the resolution and video drive for storing the effect clip.
7. Select the files you want to import and click Open.

The PICT file appears as a Matte Key effect clip in the bin you selected.



8. Click the Source/Record Mode button below the Timeline.
9. Load the Matte Key effect clip into the Source monitor.

The clip appears in the Source monitor as a black-and-white, high-contrast image.

10. Edit the matte key into the sequence as described in [“Working with Imported Graphics and Animation” on page 265](#).

Scratch Removal

Your Avid editing application includes tools for fixing flaws such as dropout in video frames or defects in film-originated footage. You can replace a flaw with clean material from the same frame or field or from other nearby frames or fields.

Understanding Scratch Removal

The workflow for removing a flaw involves the following main steps:

1. Isolate the flawed material in a new segment.
2. Apply an Intraframe effect.
3. Use the Intraframe drawing tools and effect parameters to draw a shape that covers the flaw, and fill the shape with clean replacement material.
4. (Option) If the flaw persists over several frames or fields, use keyframes to adjust the covering shape so it continues to cover the flaw as the footage moves.

Frame and Field Processing

When you use Scratch Removal with two-field media, your Avid editing application can use either frame or field processing to determine the source of the replacement material that covers the flaw. For information on selecting the processing method, see [“Selecting Frame or Field Processing When Using Scratch Removal” on page 508](#).

Frame processing copies replacement material from Field 1 of the clean frame to Field 1 of the flawed frame and from Field 2 of the clean frame to Field 2 of the flawed frame. Field processing copies replacement material from only one field to all subsequent fields.




The following illustrations show the frame and field processing methods for a typical two-frame correction created by clicking the Scratch Removal button and using default parameter settings (Frame: 0; Offset: From Start). In the frame processing example, material is copied from the first (clean) frame to the second (flawed) frame. In the field processing example, material is copied from the first field of the effect segment to all the subsequent fields.




The Scratch Removal button appears by default on the Tool palette. You can also map the Scratch Removal button from the Command palette to the keyboard or to a button. For more information, see “Using the Tool Palette” and “The Command Palette” in the Help.

15 Intraframe Editing



Example of frame-based processing. Frame A is the clean frame and frame B is the flawed frame. The arrows indicate how your Avid editing application copies material — from Field 1 of the clean frame to Field 1 of the flawed frame and from Field 2 of the clean frame to Field 2 of the flawed frame.



Example of field-based processing. The arrows indicate how your Avid editing application copies material from the first field of the effect segment to all subsequent fields.

Frame processing is the default processing method. It preserves full video resolution and provides the smoothest correction in most circumstances, particularly when the flaw you are correcting extends over both fields of a frame. Most flaws that originate in film source material (for example, a scratch on a single frame of the film) extend across both fields of the video frame.

Field processing results in a better-looking correction under certain circumstances because it lets you select your replacement material with field accuracy. For example, in the field-based processing illustration above, changing the Field parameter value to +1 causes your Avid editing application to copy material from Field 2 of Frame A to both of the fields in Frame B. A field-based correction might be a good solution when you want to correct a flaw such as video dropout, which does not necessarily occur on both fields of one or more frames. However, field processing always results in at least one instance where material from an odd field is copied to an even field, or vice versa. Depending on the nature of your video material, this might result in a slight jitter on playback.

Options for Removing Flaws

You can often remove a flaw by replacing it with a clean area from the same frame or field. For example, you can replace a flaw on a uniform background such as sky by copying another portion of the sky over the flaw.

When you remove a flaw by using material from the same frame that contains the flaw, you can see both the flaw and all the available clean material as you work. This can be helpful for certain kinds of footage, making it easy to select the exact portion of the image that allows for the best replacement.

Replacing flaws with material from a nearby frame or field lets you correct flaws in more complex footage. For example, a flaw on an image such as a face might be very difficult to cover using material from the same frame or field — there might be no other area of the face in that image that shows similar tones, textures, and highlights. In this situation, it is better to replace the flaw by copying the same part of the face from an earlier or later frame that does not contain the flaw.

This method also provides an alternative for dealing with uniform areas such as sky since you can replace a flaw with the same area from a nearby clean frame.

When you use material from a nearby frame to replace a flaw, you cannot see the whole of the nearby frame as you work. Instead, you see the replacement area in the shape you draw to cover the flaw, and you use parameter sliders in the Effect Editor to adjust which portion of the nearby frame appears.

Selecting Material to Use When Correcting Flaws

When you isolate a flaw as a new segment to correct it, you must include enough clean material to make the correction. The Intraframe tools you use for removing flaws cannot reference frames outside the segment that you isolate.

In some cases, you can take all the clean material you need from the same frames that contain the flaw. In other situations, you need to include one or more completely clean frames along with the flawed frames in the segment you isolate.

For example, if a flaw persists across several frames in footage that includes no motion, the simplest way to correct the flaw is to include one clean frame before or after the flawed frames and use replacement material from the clean frame to cover the flaw in all the other frames. For more information on using replacement material from different points in your footage, see [“Examples of Scratch Removal Parameter Settings” on page 516](#).

Detecting Video Dropout in 24p or 25p Material

Because of the way some Avid editing applications handle the display of 24p or 25p material, you might not be able to see video dropout when you use the default Fast Frame Display mode.

To ensure that you can see dropout when you are working with 24p or 25p material, turn off Fast Frame Display mode by selecting **Special > Fast Frame Display**. (When Fast Frame Display is deselected, there is no check mark beside it in the menu.) You can then see every line of the full 24p or 25p frame.

For more information on how your Avid editing application displays 24p or 25p material, see “Displaying 24p and 25p Media” in the Help.



When you turn off Fast Frame Display, you slow down your Avid editing application’s display capabilities. If you turn off Fast Frame Display to check for flaws, you should turn it on again before you proceed with other editing operations.

Selecting Frame or Field Processing When Using Scratch Removal


To select frame or field processing when using Scratch Removal:

1. Move the position indicator to the effect’s icon in the Timeline.
2. If you are not in Effect mode, enter Effect mode, for example by choosing **Toolset > Effects Editing**.

For more information, see [“Entering Effect Mode” on page 41](#).

The Effect Editor opens.

3. Open the Mode parameter category of the Paint Effect or the Scratch parameter category of the Scratch Removal effect, and click the Frame Processing button.



Frame/Field parameter slider and Frame Processing button in the Effect Editor

If the Frame Processing button is selected (pink), your Avid editing application uses frame processing. The Frame/Field parameter slider is labeled Frame and is calibrated in one-frame increments from –5 to +5.

If the Frame Processing button is deselected (gray), your Avid editing application uses field processing. The Frame/Field parameter slider is labeled Field and is calibrated in one-field increments from –10 to +10.

For more information on frame and field processing, see [“Frame and Field Processing” on page 505](#).



When you are working with single-field material, the Frame Processing button does not appear in the Effect Editor.

Isolating a Flaw

If you need to correct a flaw on a single frame, you can use the Scratch Removal button to quickly create a two-frame segment and apply the Scratch Removal effect.



The Scratch Removal button appears by default on the Tool palette. You can also map the Scratch Removal button from the Command palette to the keyboard or to a button. For more information, see [“Using the Tool Palette”](#) and [“The Command Palette”](#) in the Help.

If a flaw persists over several frames, do one of the following:

- Use the Scratch Removal button to create a two-frame segment, and then use standard Trim mode methods to extend the segment.
- Insert add edits, and apply a Scratch Removal effect manually.



You cannot access frames outside the segment you mark when you are working with the Scratch Removal tools. When you isolate a flaw, you must include in the segment both the flawed frames and sufficient clean material to correct the flaws successfully. For more information on the relationship between flaws and clean material, see [“Understanding Scratch Removal” on page 505](#) and [“Examples of Scratch Removal Parameter Settings” on page 516](#).

For information on finding flaws in 24p or 25p material, see [“Detecting Video Dropout in 24p or 25p Material” on page 508](#).

To isolate a flaw by using the Scratch Removal button:

1. Find the frame containing the flaw:
 - ▶ Use the Step Forward button or the Step Backward button (in the toolbar under the monitor) to carefully cue the frame containing the flaw.
 - ▶ (Option) Press and hold the Alt key (Windows) or Option key (Macintosh) while clicking the Step Forward or the Step Backward button to step through one field at a time.



2. Move the position indicator to the frame containing the flaw.

3. Ensure that the Record Track button for the track containing the flaw is the highest selected track button in the Track Selector panel.



4. Click the Scratch Removal button.

Your Avid editing application creates a two-frame segment ending at the frame marked by the position indicator and applies the Scratch Removal effect to that segment. If an effect is already present at that point in the sequence, your Avid editing application auto-nests the Scratch Removal effect on top of the existing effect.



A Scratch Removal effect on a segment created by two add edits

To isolate a flaw by using add edits:

1. Find the series of frames or fields containing the flaw:
 - ▶ Use the Step Forward button or the Step Backward button (in the toolbar under the monitor) to carefully cue the frames containing the flaw.
 - ▶ (Option) If you are working with two-field media, press and hold the Alt key (Windows) or Option key (Macintosh) while clicking the Step Forward button or the Step Backward button to step through one field at a time if necessary.



2. Isolate the flawed frames, together with sufficient clean material to make your correction, by placing add edits before and after the frames to create a new segment.
3. Apply either the Paint Effect or the Scratch Removal effect from the Image category to the segment:

The Scratch Removal effect provides only those effect parameters specific to fixing flaws, while the Paint Effect provides Scratch Removal as one of many available Paint modes.

Removing a Flaw By Drawing a Shape

Once you isolate a flaw and apply an Intraframe effect to it, you can remove the flaw by replacing it with a clean area of video. The best way to do this is usually to draw a shape that covers the flaw and fill the shape with replacement material.

An alternative method is to draw a shape over your selected replacement material and then drag the replacement over the flaw. This works well when you are taking replacement material from the same frame that contains the flaw. For more information, see [“Removing a Flaw By Dragging Replacement Material” on page 512](#).

To remove a flaw by drawing a shape over it and filling the shape with replacement material:

1. Isolate the flaw, and apply the Paint Effect or the Scratch Removal effect by using the procedures described in [“Isolating a Flaw” on page 509](#).
2. If you are not in Effect mode, enter Effect mode, for example, by choosing Toolset > Effects Editing.

For more information, see [“Entering Effect Mode” on page 41](#).

The Effect Editor opens.

3. Select the segment if it is not already selected.
4. (Option) If you are working with the Paint Effect, do the following:
 - a. Click the triangular opener next to the Mode parameter category.
 - b. Click the Fast Menu button, and select Scratch Removal.
5. Click the triangular opener next to the Mode parameter category (Paint Effect) or the Scratch parameter category (Scratch Removal effect).
6. Select a shape tool or a brush in the Effect Editor.
7. Click the image, and drag to create an object that covers the flaw.
8. Make sure that the Object Visible button is selected in the Mode parameter category (Paint Effect) or the Scratch parameter category (Scratch Removal effect) of the Effect Editor.
9. (Option) Select frame or field processing.

For more information, see [“Selecting Frame or Field Processing When Using Scratch Removal” on page 508](#).

10. Use the Horizontal, Vertical, and Frame/Field sliders in the Effect Editor to select an area of replacement material to fill the object in the image and replace the flaw.

The replacement material appears in the object, replacing the flaw. For more information on using the Horizontal, Vertical, and Frame or Field parameter sliders, see [“Using the Scratch Removal Positioning Parameters” on page 515](#).

11. (Option) Use the Feathering parameters to help blend the replacement material into the surrounding area.





Original flaw (left) seen with a shape drawn around it, and the final effect (right) where clean material from a nearby frame appears within the shape

12. (Option) Animate the shape that contains the replacement material using keyframes to follow movement and changes in the frames of footage.

For example, you can resize, reshape, and reposition the shape over time, or you can use the Object Visible button to control when the shape is visible.

For more information, see [“Intraframe Example: Animating a Matte Key Effect” on page 527](#), [“Image: Paint Effect” on page 573](#), and [“Key: AniMatte” on page 576](#).

13. Render the effect to play it back in real time.

For more information, see [“Rendering Intraframe Effects” on page 469](#).



A standard Intraframe geometric shape such as an oval or a rectangle renders considerably faster than a series of brush strokes. In most cases of a single small flaw, a brush might be the easiest correction tool. If you need to correct several flaws that are close together, however, you save rendering time if you can cover them with a single shape rather than use several different brush strokes.

Removing a Flaw By Dragging Replacement Material

This procedure is an alternative to the flaw removal method described in [“Removing a Flaw By Drawing a Shape” on page 510](#). Consider this method when you are taking replacement material from the same frame that contains the flaw.

To remove a flaw by selecting replacement material and then dragging it over the flaw:

1. Isolate the flaw, and apply the Paint Effect or Scratch Removal effect by using the procedures described in [“Isolating a Flaw” on page 509](#).
2. If you are not in Effect mode, enter Effect mode, for example, by choosing Toolset > Effects Editing.

For more information, see [“Entering Effect Mode” on page 41](#).

The Effect Editor opens.

3. Select the segment if it is not already selected.
 4. (Option) If you are working with the Paint Effect, do the following:
 - a. Click the triangular opener next to the Mode parameter category.
 - b. Click the Fast Menu button, and select Scratch Removal.
 5. Click the triangular opener next to the Mode parameter category (Paint Effect) or the Scratch parameter category (Scratch Removal effect).
 6. (Option) Select frame or field processing.
- For more information, see [“Selecting Frame or Field Processing When Using Scratch Removal” on page 508](#).
7. Select a shape tool or a brush in the Effect Editor.
 8. Click a clean area of the image, and drag to create a selection that is appropriately sized for covering the flaw.

In most circumstances, you should make the object as small as possible while still covering the flaw completely.

9. Drag the replacement selection over the flaw.
10. (Option) Use the Feathering parameters to help blend the replacement material into the surrounding area.



Left to right: original flaw and selection, selection dragged over flaw, and the final effect

11. (Option) Animate the shape that contains the replacement material using keyframes to follow movement and changes in the frames of footage.

For example, you can resize, reshape, and reposition the shape over time, or you can use the Object Visible button to control when the shape is visible.

For more information, see [“Intraframe Example: Animating a Matte Key Effect” on page 527](#), [“Image: Paint Effect” on page 573](#), and [“Key: AniMatte” on page 576](#).

12. Render the effect to play it back in real time.

For more information, see [“Rendering Intraframe Effects” on page 469](#).

Removing Flaws Covering More Than One Frame or Field

You can use IN and OUT points to define multiple frames or fields of video that contain a scratch and then use the Scratch Removal button to quickly create a Scratch Removal effect that covers the scratched frames or fields together with the clean frame or field immediately before them. When you draw a shape to cover the scratch, your Avid editing application fills that shape with clean material in every frame or field of the effect.

This is useful when a scratch is repeated across several frames or fields. In particular, it allows for quick correction of a scratched frame in film-originated material that has been duplicated by the pulldown process in telecine transfer to video.

To remove a scratch covering more than one frame or field:

1. Mark an IN point at the first scratched frame or field.
2. Mark an OUT point at the last scratched frame or field.
3. Move the position indicator to one of the following locations:
 - Between the marked IN and OUT points
 - On the frame or field immediately before the marked IN point
4. Click the Scratch Removal button.



The Scratch Removal button appears by default on the Tool palette. You can also map the Scratch Removal button from the Command palette to the keyboard or to a button. For more information, see “Using the Tool Palette” and “The Command Palette” in the Help.

Your Avid editing application applies a Scratch Removal effect that covers the scratched frames or fields and the clean frame or field immediately before them.

The position indicator must be between the marked IN and OUT points or on the frame or field immediately before the marked IN point. If the position indicator is at any other location, your Avid editing application creates the Scratch Removal effect at that location and ignores the marked IN and OUT points.

5. (Option) Select frame or field processing.

For more information, see [“Selecting Frame or Field Processing When Using Scratch Removal” on page 508](#).

6. In the Effect Editor, select a shape tool or a brush.
7. Click the image, and drag to create a shape that covers the scratch.

Your Avid editing application replaces the material in the shape with material from the clean frame or field. The same clean material covers the scratch on every scratched frame or field within the effect.



The Scratch Removal positioning parameters reference the part of the clean frame that corresponds to the shape you draw by default. In most cases, you do not need to make any adjustments to these parameters to cover the scratch successfully.

- 8. (Option) Use the Feathering parameters to help blend the replacement material into the surrounding area.
- 9. Render the effect to play it back in real time.

For more information, see [“Rendering Intraframe Effects” on page 469](#).


In some unusual circumstances, you might need to animate the shape that contains the replacement material, using keyframes together with positioning adjustments to follow movement and changes. For example, if the image is changing rapidly from frame to frame and the scratch covers several frames, the clean material might not match the later scratched frames without repositioning.

Using the Scratch Removal Positioning Parameters

The Hor (horizontal), Vert (vertical), and Frame/Field sliders in the Scratch Removal mode of the Paint Effect or in the Scratch parameter category of the Scratch Removal effect let you control exactly which material you use from elsewhere in the same frame or in nearby frames to replace flawed material.

The Hor (horizontal) and Vert (vertical) sliders define the position of the replacement material relative to the shape you have drawn on the horizontal and vertical axes of the frame.

The Frame/Field slider defines which nearby frame or field is used as the source of the replacement material. Values represent an offset from the reference point defined in the Offset Fast menu.



Offset Fast Menu button in the Effect Editor

The following table shows the default settings.

Parameter	Default setting
Frame/Field	0

Parameter	Default setting
Offset	From Start

These settings correctly reference the clean frame or field whenever you use the Scratch Removal button to apply the Scratch Removal effect. The settings reference the clean frame when you use the Scratch Removal button without marking IN and OUT points to remove a scratch on a single frame or field. They also reference the clean frame when you use the Scratch Removal button with IN and OUT points to remove a scratch or other flaw that repeats across more than one frame or field.

The Frame Processing button lets you select between frame and field processing. If the Frame Processing button is selected, your Avid editing application uses frame processing. The Frame/Field parameter slider is labeled Frame and is calibrated in one-frame increments from –5 to +5.

If the Frame Processing button is deselected, your Avid editing application uses field processing. The Frame/Field parameter slider is labeled Field and is calibrated in one-field increments from –10 to +10.

For more information on field processing, see [“Frame and Field Processing” on page 505](#). For more information on these parameters, see [“Image: Scratch Removal” on page 574](#).



You cannot access frames more than 5 frames (or fields more than 10 fields) from the zero point as defined by the Offset Fast menu, regardless of the length of the segment.

You cannot access frames or fields outside the segment that contains the effect. If you are positioned six fields from the end of the segment, and you set the Field slider to 10 and the Offset to Relative, you reference the last field of the segment (six fields ahead of your position).


Examples of Scratch Removal Parameter Settings

The following examples illustrate several different settings for the Scratch Removal positioning parameters.

Example 1: Replacement Material in the Same Frame

Parameter	Setting
Vertical	–250
Horizontal	+250

Parameter	Setting
Frame/Field	0
Offset	Relative



In this example, the effect replaces the area of the rectangle covering the scratch (bottom left) with material from the area of the clean rectangle in the same frame or field (top right). Each frame or field in the segment uses replacement material from the same relative position in its own frame or field.

Example 2: Replacement Material from a Two-Frame Relative Offset


Parameter	Setting
Vertical	0
Horizontal	0
Frame/Field	+2/+4
Offset	Relative



In this example, the area of the rectangle covering the scratch (left) is replaced by the same coordinate area of the frame two frames (four fields) ahead (right). Each frame or field in the segment uses replacement material from two frames (four fields) ahead.

Example 3: Replacement Material from a Single Clean Frame

Parameter	Setting
Vertical	0
Horizontal	0
Frame/Field	0
Offset	From Start



In this example, the area of the rectangle covering a scratch in several frames is replaced by the area of the clean rectangle in the first frame of the segment. If the same parameter settings are used throughout the segment, then every frame in the segment references the first frame of the segment.

You can select From Start or From End from the Offset Fast menu in this way to cover a flaw in several frames with clean material from a single frame. In this example, the flaw first appears in frame 2, and it is replaced in every frame in which it appears by clean material from frame 1.

Intraframe Editing Examples

The topics in this section provide examples of how to use Intraframe techniques.

Intraframe Example: Colorizing with Magic Mask

You can use the Magic Mask effect to apply effects across a series of frames, using the chroma and luma values as the criteria for edge detection.

Magic Mask is primarily useful for localized colorization, which enables you to create garbage mattes and various chroma effects. For example, you can use Magic Mask to change the color of a white shirt to another color without having to create a detailed matte.

In this example, the goal is to colorize the window area through which we see the athletes walking to the pool. The odd shapes in the window area would normally make this task extremely time consuming, but because the region is high contrast with a consistent off-white color, Magic Mask makes the job simple.



To colorize the example image:

1. If you are not in Effect mode, enter Effect mode, for example, by choosing Toolset > Effects Editing.

For more information, see [“Entering Effect Mode” on page 41](#).

The Effect Editor opens.

2. In the Effect Palette, click the Image category.



3. Drag the Paint Effect icon to the segment of footage in the sequence.

4. Select the segment if it is not already selected.

The Paint Effect parameters appear in the Effect Editor.



5. For this example, in the Mode parameter category, click the Fast Menu button, and select Solid.

15 Intraframe Editing

In other applications of Magic Mask, you might select another mode such as Lighten, Darken, or Colorize.

6. Click the Rectangle tool (or another shape tool) in the Effect Editor, click in the Effect Preview monitor, and drag to draw a box surrounding the window region.



7. Open the Color category, and, using standard methods, select a color to apply to the window region.

For more information on selecting a color, see [“Adjusting a Color Parameter for an Effect” on page 96](#).



8. (Option) Click the Outline/Path button so you have an unobscured view of the object you want to colorize. Adjust the size and shape of the box as necessary.
9. In the Magic Mask category, click the Enable button.



Enable button for Magic Mask in the Effect Editor

Your Avid editing application activates the Magic Mask.

The default key color for Magic Mask might not match the color in your selection, so the color is not yet applied to the white area of the window.




Effect applied before selecting Magic Mask key color. The color effect does not appear.

10. In the Magic Mask parameter category, click in the Color Preview window, drag the pointer to the colored area of the window in the image, and then release the mouse button.

Your Avid editing application sets the Magic Mask key color to the color you selected, and applies the effect.

11. Click the Outline/Path button to switch between viewing the image with or without the effect.



Effect applied with key color selected from the image

12. Adjust the Magic Mask parameters, such as Gain and Soft (softness), to fine-tune the effect.

Your Avid editing application applies the colorization effect to areas where the rectangle shape extends beyond the window area in the image. You can quickly convert the rectangle to a polygon and adjust its shape around the window.

To reshape the rectangle:

1. Double-click the rectangle to select it and display its control points.
2. Drag the control points at the corners of the rectangle one at a time to surround the window area.



New shape restricts the Magic Mask effect to the window area

Intraframe Example: Applying the Paint Effect to Regions of a Clip

The Paint Effect includes a number of modes for applying special effects to traced regions of an image. This example describes using keyframes with the Blur mode to gradually blur a region of the clip. The effect gives the impression that the background is losing focus while the rest of the image is unaffected.

The background behind the woman is traced with the Paint Effect, and the Blur mode is gradually applied during the clip.



Before (left) and after (right) the blur effect

To apply the blur:

1. If you are not in Effect mode, enter Effect mode, for example, by choosing Toolset > Effects Editing.

For more information, see [“Entering Effect Mode” on page 41](#).

The Effect Editor opens.



2. From the Image category, drag the Paint Effect icon to the segment of footage in the sequence.

3. Select the segment if it is not already selected.

The Paint Effect parameters appear in the Effect Editor.



The next task is to trace the background region around the woman in the foreground to apply the effect. Because the woman moves during the clip, you must animate the traced shape by using keyframes.

4. Press the Home key to go to the beginning of the clip. Make sure both the first and last keyframes are selected.




5. In the Effect Editor, click the Reduce button to view the image in the Effect Preview monitor at 75 percent.

This makes it easier to include the outer edges of the footage in the traced area.



6. Click the Curve tool.
7. Click the image, and drag to draw a matte with freehand capability. Trace an outline around the woman and surrounding the background.
8. When you are satisfied with the shape of the matte, release the mouse button.




Complex polygon shape traced around woman and background

15 Intraframe Editing

9. In the Effect Preview monitor, click the last keyframe indicator to select the keyframe. Check the shape of the traced area around the woman, and adjust control points as necessary to make an accurate outline.
10. Before creating new keyframes to further animate the traced outline, apply the blur to the first and last keyframes to ensure a smooth effect across all keyframes:
 - a. In the Effect Preview monitor, click the first keyframe indicator to select it.
 - b. In the Mode parameter category, click the Fast Menu button, and select Blur.
 - c. Drag the Hor (horizontal) and Vert (vertical) sliders to 0.
 - d. Click the last keyframe indicator to select it.
 - e. Drag the Hor (horizontal) and Vert (vertical) sliders to 50.



Your Avid editing application applies the Blur mode effect.



11. Click elsewhere in the Effect Preview monitor's position bar to check the traced outline. Make adjustments as necessary.



As you adjust control points, your Avid editing application automatically creates new keyframes.

12. (Option) To soften the edges of the blurred outline around the woman, adjust the Feathering parameters.

For more information, see [“Feathering” on page 608](#).

13. Render the effect to play it back in real time.

For more information, see [“Rendering Intraframe Effects” on page 469](#).

Intraframe Example: Creating a Matte Key Effect

When you apply the AniMatte effect and create a matte key, the shape and location of the matte remain fixed over the course of the segment. The parameters of the matte are the same at both the first and last keyframes in the segment.

To apply a two-layer matte key:

1. For this two-layer effect, edit the image you want to use as the background onto one track and the image you want to use as the foreground onto the track above.


For more information, see “Creating and Editing Sequences” in the Help.

2. Enter Effect mode, for example, by selecting Toolset > Effects Editing.

For more information, see [“Entering Effect Mode” on page 41](#).

The Effect Editor opens.

3. In the Effect Palette, click the Key parameter category.
4. Drag the AniMatte Effect icon from the Effect Palette to the upper track in the Timeline.



5. Press the Home key to go to the beginning of the clip. Ensure both the first and last keyframes are selected.



6. In the Effect Editor, click the Reduce button to view the image in the Effect Preview monitor at 75 percent.

This makes it easier to include the outer edges of the footage in the traced area.



7. Click the Curve tool.




8. In the Mode parameter category, click the Fast Menu button, and select Key In.

9. Click the image, and drag to draw a matte with freehand capability.

10. When you are satisfied with the shape of the matte, release the mouse button.

The area outside the border of the matte reveals the underlying image on the lower track (V1 in the example), and the area inside the border of the matte displays the image on the upper track (V2).




In this example, a series of shapes are drawn to key out all areas of the foreground image

11. In the Foreground parameter category, click the Swap Src (swap sources) button to check the traced outline.



The foreground and background footage are reversed in the key. This lets you easily spot areas where the outline encroaches on the foreground image.



In this example, swapping sources on one of the shapes reveals edges from the foreground image

12. Click the Swap Src button to restore your effect to a matte that keys in your selection.
13. Animate the effect as described in [“Intraframe Example: Animating a Matte Key Effect” on page 527](#).

Intraframe Example: Animating a Matte Key Effect

This topic is a continuation of the example that is created by following the procedure in [“Intraframe Example: Creating a Matte Key Effect” on page 525](#).

When you have moving video, you must use animation to change the shape and location of the matte in order to follow the changes of the video over the course of the segment.



Foreground and background layers (left) and the composite image (right). In this example, the matte shape is animated to follow the movement of the men in the foreground footage.

To animate a Matte Key effect:

1. Under the monitor, click the Step Forward button or the Step Backward button as many times as necessary to park on a frame in which the matte no longer provides a clean key due to the motion of the foreground or background image.



2. If you are not in Effect mode, enter Effect mode, for example, by choosing Toolset > Effects Editing.

For more information, see [“Entering Effect Mode” on page 41](#).

The Effect Editor opens.

3. Adjust the matte outline as follows:



- ▶ Click the Reshape tool, and drag control points to change the shape.

You can also Shift+click multiple control points for repositioning as a group. For information, see [“Adding and Removing Control Points” on page 492](#).

- ▶ Edit the object by manipulating the direction bars at one or more control points. For information, see [“Reference for Modifying Lines and Curves in Intraframe Objects” on page 491](#).

- ▶ Click the Swap Src button if necessary to swap the view of the foreground and background images to examine edges.



- ▶ Reposition the matte if necessary by selecting the shape and dragging it with the Selection tool.

As you adjust control points, your Avid editing application automatically creates new keyframes.

4. Repeat the procedure as needed to create a matte that keys the images cleanly over the course of the segment.
5. (Option) To soften the edges of the matte key, adjust the Feathering parameters. For more information, see [“Feathering” on page 608](#).
6. Render the effect to play it back in real time.

For more information, see [“Rendering Intraframe Effects” on page 469](#).

Intraframe Example: Creating a Single-Layer Organic Matte Wipe

You can use the AniMatte effect to create a custom matte wipe. Additionally, you can create soft edges and other useful variations by adjusting the parameters of the AniMatte wipe. Multiple video tracks are not necessary. You apply the AniMatte effect to a transition on a single track of video and then draw the matte wipe as described in this section.

To create an organic matte wipe:

1. Create a sequence that contains a transition (an incoming and an outgoing segment).

For more information, see [“Creating and Editing Sequences” in the Help](#).



Outgoing segment (left) and incoming segment (right)

2. Enter Effect mode, for example, by selecting Toolset > Effects Editing.

For more information, see [“Entering Effect Mode” on page 41](#).

The Effect Editor opens.

3. Apply the AniMatte effect to a transition as described in [“Applying the Paint or AniMatte Effect to a Sequence” on page 470](#).



4. In the Mode parameter category, click the Fast Menu button, and select Key In.



5. In the Effect Preview Monitor toolbar, click the Reduce button three times to reduce the image to 25 percent of its normal viewing size.

6. Click the first keyframe indicator in the Effect Preview monitor’s position bar.


The first keyframe indicator is highlighted, and the last keyframe is deselected.



7. Click the Curve tool.

8. Press and hold the mouse button, and drag to draw a custom shape to the right of the image displayed in the Effect Preview monitor.


Draw a matte that is at least as wide as the frame in the Effect Preview monitor.




9. When you are satisfied with the shape of the object, release the mouse button to complete the matte wipe.

15 Intraframe Editing

10. Click the last keyframe indicator in the Effect Preview monitor's position bar.
Your Avid editing application highlights the last keyframe indicator, and deselects the first keyframe.
11. Click the matte wipe within its borders and drag it so that it covers the frame in the Record monitor. Make sure to position the leading edge of the wipe so that it is beyond the left border of the frame.



12. In the Effect Preview Monitor toolbar, click the Enlarge button three times to restore the video image to 100 percent.
13. Click in the middle of the Effect Preview monitor's position bar to view the edge of the wipe.



14. (Option) To soften the edges of the wipe, adjust the Feathering parameters.
For more information, see [“Feathering” on page 608](#).
15. Render the effect to play it back in real time.
For more information, see [“Rendering Intraframe Effects” on page 469](#).

Working with the Blur Effect and Mosaic Effect

The Blur effect and Mosaic effect, found in the Image category, let you obscure part of an image by distorting the pixels within a defined area.

The Blur effect and Mosaic effect act as intraframe effects. The Blur parameter category for the Blur effect is the same as the one that appears for the Blur mode of the Paint Effect. The Mosaic parameter category for the Mosaic effect is the same as the one that appears for the Mosaic mode of the Paint Effect.



The Blur and Mosaic effects are non-real-time effects. When you finish creating one of these effects, you must render the effect to play it in real time.



Effect Editor Reference for the Blur Effect and Mosaic Effect






You control the Blur and Mosaic effects by using the following parameters in the Effect Editor:

Parameter	Description
Acceleration	Adjusts the effect's speed from one keyframe to the next when the Blur or Mosaic object moves within a segment.
Feathering	Adds soft edges to a Blur or Mosaic object. Modifying the outline can make an object stand out from or blend into the background.
Blur or Mosaic	Controls the overall appearance of the object area, allowing for varying degrees of distortion.

For basic information on working with the Effect Editor, see [“Using the Effect Editor” on page 89](#).

The following buttons appear on the right side of the Effect Editor for the Blur and Mosaic effects.

Button	Description
Selection tool	 Selects an object so you can change its parameters, move it, or delete it. With the Shift key pressed, selects multiple objects.
Z-rotation tool	 Rotates an object around the Z axis.

Button		Description
Reshape tool		Lets you reshape objects by manipulating anchor points at locations where new curves begin or straight lines intersect. Inserts additional control points.
Bring Forward		Brings an object one layer forward on the screen.
Send Backward		Sends an object one layer backward on the screen.
Rectangle tool		Creates a square or rectangle object. The pointer changes to a crosshair when clicked.
Oval tool		Creates a circle or oval to create an object. The pointer changes to a crosshair when clicked.

Creating and Modifying Blur and Mosaic Effects

To create a Blur or a Mosaic effect:

1. Select Toolset > Effects Editing.
2. In the Effect Palette, click the Image category.
3. Drag the Blur Effect icon or the Mosaic Effect icon to a segment in the sequence.



Blur Effect icon (left) and Mosaic Effect icon (right)

4. Click either the Rectangle tool or the Oval tool.



Rectangle tool (left) and Oval tool (right)

5. Click in the Effect Preview monitor and drag to create an object.
A wire-frame outline of the object appears, and the default Blur or Mosaic effect appears in the Effect Preview monitor.
The following illustration shows a Mosaic effect in an oval object.



To modify the attributes of blur and mosaic objects:

1. Click the Selection tool, and click the object you want to change.
2. Use the Feathering parameter category to adjust the appearance of the outline of the object:

Parameter	Description
Hor (horizontal)	Adjusts the range of pixels along the X axis to which the effect applies.
Vert (vertical)	Adjusts the range of pixels along the Y axis to which the effect applies.
Fixed Aspect	Locks the horizontal and vertical sliders so that they move in unison. This controls how smoothly the effect blends with the background image.
Anti-alias	Reduces the jaggedness of the edges of the object.

3. Use the sliders in the Blur or Mosaic parameter category to adjust the appearance of the blur or mosaic distortion:

Parameter	Description
Opac (opacity)	Controls how prominently the blur or mosaic appears against the background image. A value of 0 makes the blur or mosaic transparent, while a value of 100 makes it fully opaque.
Hor (horizontal) and Vert (vertical)	Change the size of each tile within the effect along the X or Y axis, respectively. This controls the coarseness of the blur or mosaic.
Blur Visible or Mosaic Visible	Switches the effect on and off in the Effect Preview monitor.

4. Use the Z-Rotation and Reshape tools to customize the shape of the blur or mosaic object:

Parameter	Description
Z-rotation	Lets you rotate the object around a Z axis by manipulating the resize handles.
Reshape	Lets you create an irregular object by moving the resize handles individually.
Bring Forward and Send Backward	Apply when objects overlap. You use the buttons to define which object appears closer to the viewer.

The following illustration shows the handles on an object in a Mosaic effect.



5. Drag the center handle of the object to match the movement of the image in the clip.
Your Avid editing application automatically adds a keyframe each time you drag the object to a new position.

16 PlasmaWipe Effects

- [Understanding PlasmaWipe Effects](#)
- [Folder Structure for PlasmaWipe Effects](#)
- [Using PlasmaWipe Effects](#)
- [Creating Gradient Images for PlasmaWipe Effects](#)
- [Understanding PlasmaWipe Frame and Border Effects](#)
- [Applying and Adjusting PlasmaWipe Frame and Border Effects](#)
- [Creating Custom PlasmaWipe Border and Frame Effects](#)
- [Using PlasmaWipes with HD Projects](#)

Understanding PlasmaWipe Effects

PlasmaWipe effects are two-stream, real-time effects that use gradient image bitmaps to create wipes and segment effects. There are 64 preset effects, and you can create your own by creating new gradient images.

PlasmaWipe effects uses the Level parameter value to define a threshold point that changes gradually from black to white. Your Avid editing application replaces gray tones in the gradient image that are lighter than the threshold point by outgoing video, and gray tones that are darker than the threshold point by incoming video. As the threshold point gets closer to white, more of the incoming video appears. The result is a smooth, custom wipe.

The following illustration shows the black and white gradient image used by the Horiz Twirl PlasmaWipe effect and the resulting effect, with softness applied. The effect gradually reveals the incoming image in a curling spiral pattern.



Top, left to right: outgoing image, gradient bitmap image, and incoming image. Center: stages of the gradient image as the Level parameter value changes from near black to near white. Bottom: sample frames of the transition effect that result from the gradient image stages above them.

You can use PlasmaWipe effects on transitions to create custom wipes. You can use PlasmaWipe effects on segments as static wipes. For example, you can design a PlasmaWipe effect that gives the impression of fog on the top and bottom of the video image, or to create a custom border for an effect similar to a picture-in-picture effect. For information on the effects in the Border category, see [“Understanding PlasmaWipe Frame and Border Effects” on page 548](#).



Although PlasmaWipe effects are real-time, they are processor-intensive effects. They might be more likely than most real-time effects to require rendering if you combine them with other effects or multiple video streams.

Folder Structure for PlasmaWipe Effects

The installer for your Avid editing application automatically installs the PlasmaWipe effects. Several PlasmaWipe effect categories appear in the Effect Palette, and a PlasmaWipes folder is created in the SupportingFiles folder of your Avid editing application. The following shows the default locations for the folder:


- (Windows) *drive:\Program Files\Avid\Avid editing application*
SupportingFiles\PlasmaWipes
- (Macintosh) *Macintosh HD/Applications/Avid editing applicaton*
Supporting Files\PlasmaWipes



(Macintosh only) If you create additional folders for your custom PlasmaWipe effects, back them up before you run the PlasmaWipes installer to replace or update the PlasmaWipes folder. The installer deletes and replaces the entire PlasmaWipes folder.

There are parallel folders for NTSC (720x486) and PAL (720x576) resolutions. When you create your own PlasmaWipe effects for use in SD projects, you create two versions of each effect, one for each resolution. For information on using PlasmaWipe effects in HD projects, see [“Using PlasmaWipes with HD Projects” on page 553](#).

The following illustration shows the default PlasmaWipes folder structure.



Using PlasmaWipe Effects

To use a PlasmaWipe effect:

1. Apply the PlasmaWipe effect to a transition or segment.
2. Enter Effect mode, for example, by selecting Toolset > Effects Editing.
For more information, see [“Entering Effect Mode” on page 41](#).
The Effect Editor opens.
3. Adjust parameters (and add keyframes if necessary) in the Effect Editor.

Creating Gradient Images for PlasmaWipe Effects

You can use three different approaches to create an image for a PlasmaWipe effect:

- Create a black and white gradient image in a graphics tool such as Adobe Photoshop.
For more information, see [“Creating a Custom Image for a PlasmaWipe Effect” on page 539](#).
- Modify an existing image to create a black and white gradient image.
For more information, see [“Creating a PlasmaWipe Effect from an Existing Image” on page 540](#).
- Create a wipe by drawing a wide brush stroke that changes smoothly from black to white.
For example, you can use the Pencil tool in Photoshop to create this type of image. For more information, see [“Creating a PlasmaWipe Image Using the Pencil Tool” on page 541](#).

This document describes how to create gradient images using Adobe Photoshop. However, you can use any graphics tool, such as Corel® Paint Shop Pro®, that lets you create black and white gradient images and save the image as a raw image file (with a .raw extension).

The images in the PlasmaWipes folders are raw Photoshop images. You can open and inspect the images in Photoshop to get ideas for new effects.

Because PAL and NTSC require different resolutions for graphic images you must create two versions of your image as follows:

- A 720x576 pixel image for PAL
- A 720x486 pixel image for NTSC

It is better to start with a 720x576 image because it is the highest resolution.

The following tips apply to working with gradient images:

- Keep the graphic smooth without too many hard edges. This increases the number of levels (gradients) and creates a smoother wipe.
- Do not use dithering or antialiasing because they might add artifacts to the wipe. For example, when a graphics application performs antialiasing, it smooths out the edge of a line by blending the colors along the edge. These blended colors might force small portions of the incoming or outgoing video to appear at inappropriate times.
- If you use Photoshop, use the histogram to view the gradient levels of the image. This lets you ensure that the image uses all the available gradient values and that the effect plays smoothly.

For more information, see [“Using the Histogram to Analyze PlasmaWipe Images” on page 542.](#)

For information on the effects in the Border category, see [“Understanding PlasmaWipe Frame and Border Effects” on page 548.](#)

Creating a Custom Image for a PlasmaWipe Effect

This sample procedure uses Adobe Photoshop, but you can use any graphics tool that creates black and white gradient images and lets you save an image as a raw image file.

To create a gradient image using Adobe Photoshop:

1. Create a new file with the following characteristics:
 - Image size: 720 pixels (width) by 576 pixels (height)
 - Resolution: 72 pixels/inch (you can use any resolution)
 - Mode: Grayscale
2. Create a black and white graphic.

For example, use the Gradient tool to create a basic pattern with the following settings:

 - Foreground: black
 - Background: white
 - Opacity: 100%
3. (Option) Use distortion filters such as Spherize, Twirl, or Ripple to modify the image.

The following illustration shows a gradient image modified by two separate distortion operations.



Left to right: Gradient image, image with Swirl filter applied, and image with Ripple filter applied

4. (Option) Perform image operations to create different effects.

For example, you can copy different gradient images to separate layers and experiment with blending the layers.




For information on blending layers, see your Photoshop documentation.

5. Save the image as a raw image file as described in [“Saving a PlasmaWipe Image for PAL and NTSC” on page 545](#).

Creating a PlasmaWipe Effect from an Existing Image

This sample procedure describes how to create a gradient image from an existing image using Adobe Photoshop. You can use any graphic, but images with rich texture often give the best results.



Examples of PlasmaWipe images: image used by Falling Text effect (left) and image used by Lava Flow 3 effect (right)

To create a gradient image from an existing image using Adobe Photoshop:

1. Open an existing graphics file.
2. Select Image > Image Size.
The Image Size dialog box opens.
3. Change the image size to 720 pixels x 576 pixels.
4. Deselect Constrain Proportions.
5. Click OK.

6. Select Image > Mode > Grayscale.
7. Open the Histogram palette and use the histogram to ensure that the image uses the full range of gradient values.
For more information on using histograms, see [“Using the Histogram to Analyze PlasmaWipe Images” on page 542](#).
8. Click OK.
9. Save the image as a raw image file as described in [“Saving a PlasmaWipe Image for PAL and NTSC” on page 545](#).

Creating a PlasmaWipe Image Using the Pencil Tool

This sample procedure describes how to use Adobe Photoshop to create a gradient image similar to the images in the PlasmaWipes/Avid/Paint folder. The wipe effect simulates uncovering the incoming video by wiping away the outgoing video with a brush or cloth.


To create a gradient image using the Pencil tool in Adobe Photoshop:

1. Ensure that the background color selection is set to black and the foreground color selection box is set to white.
2. Create a new file with the following characteristics:
 - Image size: 720 pixels (width) by 576 pixels (width)
 - Resolution: 72 pixels/inch (you can use any resolution)
 - Mode: Grayscale
 - Background Contents: Background Color
3. Select the Pencil tool.
The pencil tool is useful for this method because it creates hard edges.
4. Click Other Dynamics in the Brushes palette.
5. In the Opacity Jitter parameter area, click the Control menu and select Fade.
6. Enter a high Step number in the Control text box (for example, 500).
This creates a pencil stroke that fades from white to black (foreground to background color) in small increments.
7. Click Brush Presets, and select a wide pencil shape, for example 100 pixels or higher.
You can also create a custom brush.
8. Close the Brushes palette.
9. Set Opacity to 100%.

10. Start anywhere in the image and draw back and forth across the image, covering the entire image from top to bottom.

This creates a wide pencil mark that changes the color from white to black.

Draw the line as if you are painting the wipe backwards from white to black. When the wipe plays, the darkest parts of the image are replaced by incoming video first. For example, to create an effect similar to Paint Strokes 4, start drawing in the upper left corner and draw concentric rectangles until you reach the center. This wipe starts in the center and spreads out in concentric rectangles. Paint Strokes 2 creates a wipe effect with a crisscross pattern.



Examples of PlasmaWipe Paint images: image used by Paint Strokes 4 effect (left) and image used by Paint Strokes 2 effect (right)

11. (Option) Apply filters to the image to change the edges.
For example, select Filter > Distort > Ripple to apply a Ripple effect.
12. Save the image as a raw image file as described in [“Saving a PlasmaWipe Image for PAL and NTSC” on page 545](#).




When you resize the image for NTSC, select Resample Image > Nearest Neighbor. This maintains the sharp edges in the image.

Using the Histogram to Analyze PlasmaWipe Images


The Histogram palette in Adobe Photoshop shows the distribution of grayscale value for your PlasmaWipe image. Other graphics tools also typically provide a histogram display.

The wider the range of gradient values (levels), the smoother the resulting animation. For example, the following illustrations show two histograms. The one with the wide range of gradient values creates a smoother animation.



Histogram examples: image that does not use all available gradient values (left) and image that does use all available values (right)

A horizontally smooth histogram results in an animation that does not have abrupt changes. If the histogram has a wide vertical range, the wipe might come in quickly and then slow down. The following illustrations show two histograms. The image with the peak creates an animation that starts quickly, slows down as it gets to the middle of the effect, and then speeds up again. The image with the smooth histogram creates an animation with a constant speed.



Histogram examples: image that will not animate at a constant speed (left) and image that will animate at a constant speed (right)


Depending on the effect you want to create, the image associated with either type of histogram might create an acceptable animation as long as it uses the full range of gradients.



If you want to change the speed of the wipe, you can use keyframes to control the Level parameter.

You can use Adobe Photoshop commands such as Equalize, Auto Levels, or Auto Contrast to increase the range of gradient values. For more information, see your Adobe Photoshop documentation.

Adjustments such as Equalize might result in a histogram that has a wide range of gradients but that has many gaps in the values. In a short wipe effect the gaps are not noticeable. In a long effect, the gaps might create doubled frames in the animation. You can use a blur filter such as Gaussian Blur to smooth out the range. For more information, see your Adobe Photoshop documentation.



Example of a histogram with gaps

Testing a PlasmaWipe Animation

You can use the following procedure in Adobe Photoshop to preview the animation for your gradient image. This example uses the Horiz Twirl image from the PlasmaWipes folder.


To test an animation:

1. Select Image > Adjustments > Brightness/Contrast.


The Brightness/Contrast dialog box appears. The following illustration shows the image and the Brightness/Contrast dialog box.



2. Move the Contrast slider all the way to the right to view the animation with hard edges.



3. To view the animation with some softness applied, move the Contrast slider to the left to select a lower Contrast number.



4. Move the Brightness slider from left (-100) to right (+100) to view the animation.
The following images show three stages of the animation.



Saving a PlasmaWipe Image for PAL and NTSC

This sample procedure is for use with Adobe Photoshop and assumes that you have created a PAL version of your image (720x576 pixels), for example, as described in [“Creating a Custom Image for a PlasmaWipe Effect” on page 539](#).

To save a gradient image:

1. Make a backup copy of the image.
2. If the image has multiple layers, flatten the image.
3. Select File > Save As.

The Save As dialog box appears.

4. Name the file, and select Format > Photoshop Raw (*.RAW).

The system saves the file as a raw Photoshop image with a .raw extension. This is the 720x576 (PAL) version of the image.

5. Save an NTSC version of the image by doing the following:
 - a. Select Image > Image Size.
 - b. In the Height text box, change the image height to 486 pixels. Keep the image width at 720 pixels.
 - c. Deselect Constrain Proportions.

- d. Select Resample Image, and then select Resample Image > Bicubic, or, if the image has hard edges, select Resample Image > Nearest Neighbor.
- e. Click OK.
- f. Select File > Save As.
The Save As dialog box opens.
- g. Name the file as described in step 4.



The name you choose for the image becomes the name of the effect that appears in the Effect Palette. Ensure you use exactly the same name for the PAL and NTSC versions of the file.

6. Store the two images in the PlasmaWipes folder structure.

For more information, see [“Storing Images in the PlasmaWipes Folder Structure” on page 546.](#)

Storing Images in the PlasmaWipes Folder Structure

You must store your PlasmaWipe images in the correct folders so that your Avid editing application can recognize the files. For more information on the folder structure, see [“Folder Structure for PlasmaWipe Effects” on page 537.](#)

To store your Plasma Wipe image files:

1. Give your image files unique names so that you can recognize the files if you copy them to another system.




The name you choose for the image becomes the name of the effect that appears in the Effect Palette. Ensure you use exactly the same name for the PAL and NTSC versions of the file.

2. Create new folders to organize your new effects. Create identical folders within the 720x486 folder and the 720x576 folder in your PlasmaWipes folder.

Do not store your files in the Avid folders because the folders might be overwritten when you update your Avid software. Create folders within the 720x486 folder and the 720x576 folder at the same level as the Avid folder. You can use any number of nesting levels for your folders in order to organize your effects. Your Avid editing application system displays the full path as part of the name in the effect category. The following illustration shows the Effect Palette with the full default path in the effect category.

(Macintosh only) If you create additional folders for your own custom PlasmaWipe effects, back them up before you run the PlasmaWipes installer to replace or update the PlasmaWipes folder. On the Macintosh operating system, the installer deletes and replaces the entire PlasmaWipes folder.



3. Copy your images to the new folders.
 4. Restart your Avid editing application.
- Your new effects appear in the Effect Palette.



If you move sequences that use your new wipes to another system, you must copy the wipes to that other system. You must maintain the same folder structure on each system that uses your effects.

Adjusting an Existing PlasmaWipe Effect While Your Avid Editing Application is Running

If you add new effects, you must restart your Avid editing application to see the effects in the Effect Palette. However, you can adjust a PlasmaWipe effect that you have previously created without having to restart. This helps when testing changes to one of your effects.

To adjust an existing effect while your Avid editing application is running:

1. Edit the older version of the effect into a sequence.
2. Locate the PlasmaWipes folder and replace the old effect with the new effect in the appropriate folder.
3. In the Timeline bottom toolbar, click the Video Quality menu button and select a lower video quality.
4. Click the effect icon in the Timeline and move the position indicator to update the effect in the Timeline.

5. Click the Video Quality menu button and select a higher video quality.

Your Avid editing application replaces the effect with the new version.

Understanding PlasmaWipe Frame and Border Effects

PlasmaWipe frame and border effects let you add a variety of edge treatments to a clip. The following illustrations show several examples.



Top left: Stone Frame Medium effect. Top right: Stone Frame Large effect applied to a resized and repositioned Picture-in-Picture effect. Bottom, left to right: Soft Sky effect, Soft Window effect used as a picture-in-picture, Soft Window effect used to darken edges.

Frame and border effects are in the PlasmaWipe Avid Borders category of the Effect Palette.

Border effects let you darken the edges and corners of an image or give a tint or shadow to the sky as though the image were shot through a lens filter. Border effects include the following:

- Round Border
- Soft Sky
- Soft Window
- Square Border

Frame effects allow for textured, colored frames and have the word Frame in their name. There are three versions of each:

- Large places a frame around the entire image and is intended for use with DVE effects such as picture-in-picture (PIP) effects.
- Medium and Small remain centered in the image and cannot be resized or repositioned.

Frame effects are segment effects only. You can use Border effects like Soft Sky as either segment effects or transition effects, but they are intended primarily as segment effects.



You can achieve effects similar to frame effects if you import a Matte key created in an application such as Photoshop. Frame effects have the added benefit of allowing you to adjust the frame color within your Avid editing application.

Default Values for PlasmaWipe Frame Effects

Frame effects have different default values from other PlasmaWipes effects because frame effects usually have crisp edges between the video and the frame graphic. Other PlasmaWipe effects often blend video clips together and can benefit from some amount of softness.

In order to determine which default values to use, the PlasmaWipes software looks for the words *border* and *frame* in the pathname to the effect source graphic. If both words appear in the path, the software applies the frame effect defaults (and only allows the effect to be used as a segment effect). Otherwise the software applies the defaults used for all other PlasmaWipes. For example, the following two effects use the frame effect defaults:

- PlasmaWipes/720x486/Avid/Borders/Stone Frame Large
- PlasmaWipes/720x486/MyEffects/MyFrames/Large Stone Border

Applying and Adjusting PlasmaWipe Frame and Border Effects

To apply a PlasmaWipe frame effect or border effect:


- ▶ Drag the effect icon from the Effect Palette to the segment in the Timeline.

To apply a PlasmaWipe frame or border effect to an existing DVE such as a Picture-in-Picture effect:

1. Apply the Picture-in-Picture effect to a clip in the Timeline.
2. Double-click the effect's icon in the Timeline.

Your Avid editing application steps into the effect and displays the nested tracks.

3. Drag the frame or border effect icon from the Effect Palette to the upper track in the nested effect.



4. Double-click the Picture-in-Picture effect icon again to step out of the nested effect.
5. Adjust the parameters for the Picture-in-Picture effect.



The Frame Large effects are designed for use with DVEs such as the Picture-in-Picture effect.

To adjust a frame effect or border effect:

1. (Option) If the effect is part of a nested effect, step into the effect.
2. For Frame effects, adjust the Border and Blend color to change the color of the frame.

The color modifies the effect as follows:

- Border adjusts the base color of the frame.
- Blend Color adjusts the highlight color.

3. Adjust the Soft (softness) and Foreground Level parameters.

If you want to adjust a border effect to darken the edges of an image, use the Foreground Level parameter to expand the border to the edges of the image. Then modify the border using the Soft, Border color, and Border Blend parameters.



You usually do not want to keyframe the Foreground Level parameter on a frame effect. The source graphics for PlasmaWipe frame effects have a sharp transition between black and white values and you might find that the change from foreground to background video happens too quickly.


Creating Custom PlasmaWipe Border and Frame Effects

For border effects such as Soft Sky or Square Window, you can use the technique described in [“Creating Gradient Images for PlasmaWipe Effects” on page 538](#).

Frame effects have the following unique requirements:

- You must use an image with a 4:3 aspect ratio to create the frame graphic.
For example, start with a 720x540 pixel image. After you create the frame graphic, save it as the correct size for PAL or NTSC as described in [“Saving a PlasmaWipe Image for PAL and NTSC” on page 545](#).
- For best results, keep distinct boundaries between the black, white, and gray portions of your image. Do not blend between black and gray or between white and gray areas.

For example, the following illustration shows the image for the Stone Frame Small effect.



Foreground video displays through the black area and background video displays through the white area. If you allow the gray area to blend with the black, portions of the frame might appear within the background video area and portions of the foreground video might appear within the frame.

The histogram for a frame graphic does not need to contain a wide range of gradient values. In fact, there will be large portions of the image that are completely black or white.

To create a custom frame graphic:

1. Create a new file with the following characteristics:
 - Image size: 720 pixels (width) by 540 pixels (height)
 - Resolution: 72 pixels/inch (you can use any resolution)
 - Mode: Grayscale



The 720x540 size ensures that the original image has a 4:3 aspect ratio. This lets you create a frame that fits correctly within the video image.

2. Display the Photoshop grid to allow for precise placement of the frame and interior area.
Use a grid size of one gridline every 36 pixels.
3. Create a frame graphic using the grid lines as a guide.
4. Modify the grayscale image and apply filter effects as necessary.
5. Color the inside of the frame black.
6. If you want background video to appear around the frame, color that area white.
7. Flatten the image to remove extra layers.
8. Make a copy of the image.
9. Save one copy as 720x576 (PAL) and another as 720x486 (NTSC) as described in [“Saving a PlasmaWipe Image for PAL and NTSC” on page 545.](#)



Select the Nearest Neighbor resampling option to avoid blending between the black, white, and gray areas of the image.

To create a frame graphic from an existing image:

1. Open an existing image, such as a graphic of a stone slab, piece of wood, or wooden frame.
2. Select Image > Image Size.
The Image Size dialog box appears.
3. Change the image size to 720 pixels x 540 pixels.
4. Deselect Constrain Proportions.
5. Click OK.
6. Select Image > Mode > Grayscale.
7. Use the Photoshop grid with a grid size of one gridline every 36 pixels to allow for precise placement of the frame and interior area.
8. Modify the grayscale image and apply filter effects as necessary.
9. Color the inside of the frame black.
10. If you want background video to appear around the frame, color that area white.
11. Flatten the image to remove extra layers.
12. Make a copy of the image.
13. Save one copy as 720x486 (for NTSC) and another as 720x576 (for PAL) as described in [“Saving a PlasmaWipe Image for PAL and NTSC” on page 545.](#)



Select the Nearest Neighbor resampling option to avoid blending between the black, white, and gray areas of the image.

Using PlasmaWipes with HD Projects

The PlasmaWipe effects that ship with your Avid editing application include files that are optimized for the following SD resolutions:

- NTSC resolutions (720x486)
- PAL resolutions (720x576)

HD projects require one of the following resolutions for PlasmaWipes:

- 1080i and 1080p projects require 1920x1080
- 720p projects require 1280x720

Several examples of each resolution are available in the Goodies folder on your Avid editing application installation disk. You can install these effects on your system and use them to create custom PlasmaWipe effects for your HD project.

To install the HD versions of the PlasmaWipes effects:

1. Navigate to the HDPlasmaWipes folder in the Goodies folder on your Avid editing application installation disk.
2. For 1080i and 1080p projects, copy the contents of the 1920x1080 folder to the following location:
 (Windows) C:\Program Files\Avid\Avid editing application\Supporting Files\Plasma Wipes\1920x1080\Avid\Custom
 Macintosh HD/Applications/Avid editing application\Supporting Files/Plasma Wipes/1920x1080/Avid/Custom
3. For 720p projects, copy the contents of the 1280x720 folder to the following location:
 (Windows) C:\Program Files\Avid\Avid editing application\Supporting Files\Plasma Wipes\1280x720\Avid\Custom
 Macintosh HD/Applications/Avid editing application\Supporting Files/Plasma Wipes/1280x720/Avid/Custom
4. Copy the files in the 720x486 folder to the following folder:
 (Windows) C:\Program Files\Avid\Avid editing application\Supporting Files\Plasma Wipes\720x486\Avid\Custom
 Macintosh HD/Applications/Avid editing application\Supporting Files/Plasma Wipes/720x486/Avid/Custom



You must copy the 720x486 files. The 1020x1080 and 1280x720 versions require these files.

5. Restart your Avid editing application and open the Effect palette.

The new HD PlasmaWipe effects appear in the Effect palette under the PlasmaWipes categories.

To create new HD PlasmaWipe effects:

1. Create a new PlasmaWipe effect file at either 1920x1080 or 1280x720 resolution.

Either copy one of the existing HD PlasmaWipe effect files or create a new file using the proper resolution. For more information, see [“Creating Gradient Images for PlasmaWipe Effects” on page 538](#).

2. Save the effect and store it in the corresponding Custom folder.

For example, if you create a file named MyPlasmaWipe.raw at 1920x1080 resolution, store it in the following location:

(Windows) C:\Program Files\Avid\Avid editing application\Supporting Files\Plasma Wipes\1920x1080\Avid\Custom\MyPlasmaWipe.raw

Macintosh HD/Applications/Avid editing application\Supporting Files/Plasma Wipes/1920x1080/Avid/Custom/MyPlasmaWipe.raw

3. Create a 720x486 version of the file and store it in the corresponding 720x486 folder by doing the following:

- a. Open the HD version of the image in Adobe Photoshop.
- b. Change the Image Size to 720x486.
- c. Use File > Save As to save the file to the 720x486 directory, for example:

(Windows) C:\Program Files\Avid\Avid editing application\Supporting Files\Plasma Wipes\720x486\Avid\Custom\MyPlasmaWipe.raw

Macintosh HD/Applications/Avid editing application\Supporting Files/Plasma Wipes/720x486/Avid/Custom/MyPlasmaWipe.raw

For more information on creating a 720x486 (NTSC) version, see [“Saving a PlasmaWipe Image for PAL and NTSC” on page 545](#).



You must create the 720x486 version as well as the HD resolution version. Your Avid editing application does not recognize the HD PlasmaWipe effect until you create the corresponding 720x486 version.

17 Effects Reference

This chapter provides reference information for all standard effects available for your Avid editing application.

For information on effects editing, begin with [“Basics of Effects Editing” on page 35](#). For reference information on parameters for effect adjustment, see [“Effects Parameter Reference” on page 603](#).

Effects are listed within their effect categories, as follows:

- [“Blend Effects” on page 556](#)
- [“Box Wipes” on page 559](#)
- [“Conceal Effects” on page 560](#)
- [“Edge Wipes” on page 561](#)
- [“Film Effects” on page 562](#)
- [“Generator Effects” on page 564](#)
- [“Illusion FX Effects” on page 564](#)
- [“Image Effects” on page 570](#)
- [“Key Effects” on page 575](#)
- [“L-Conceal Effects” on page 579](#)
- [“Matrix Wipes” on page 580](#)
- [“Motion Effects” on page 581](#)
- [“Peel Effects” on page 582](#)
- [“PlasmaWipe Effects” on page 584](#)
- [“Push Effects” on page 585](#)
- [“Reformat Effects” on page 586](#)
- [“Sawtooth Wipes” on page 587](#)
- [“Shape Wipes” on page 588](#)
- [“Spin Effects” on page 590](#)
- [“Squeeze Effects” on page 591](#)
- [“Timewarp Effects” on page 592](#)
- [“Title Effects” on page 598](#)
- [“Xpress 3D Effects” on page 599](#)

Reference information includes:

- An illustration of the effect’s icon
- A description of the effect
- Information on where to apply the effect (to transitions, single-layer segments, or multilayer segments)

Effects that you can apply to transitions have active transition parameters available at the bottom of the Effect Editor. For more information, see [“Transition Parameters” on page 615](#)


- Indication of the real-time status of the effect, where appropriate.
All standard Avid effects are real-time effects unless otherwise noted in this chapter. For more information, see [“Playing Real-Time Effects” on page 51](#).
- Information on whether you can promote the effect (to 3D or SpectraMatte)
For more information, see [“Promoting 2D Effects to 3D Effects” on page 364](#) and [“Promoting a Chroma Key Effect to the SpectraMatte Effect” on page 262](#).
- Information on the processing bit depth capabilities of the effect
Most effects support both 8-bit and 16-bit processing. For more information, see [“Using 16-Bit Processing Support for Rendered Effects” on page 172](#).
- Information on the RGB processing capabilities of the effect
Most effects support processing in the RGB color space, but a small number of effects do not.
- A cross-referenced list of effect parameter categories available for that effect
- Where useful, illustrations of the effect’s behavior

For illustrations that help you understand the differences between similar types of transition effects, see [“Comparison of Similar Effects” on page 601](#).









Blend Effects

Blend effects are general two-channel 2D effects, except for 3D Warp. (Two specialized blend effects are also available for creating a film look. For more information, see [“Film: Film Dissolve and Film Fade” on page 563](#).)

Blend: 3D Warp


	Provides direct access to a full set of parameter categories for making 3D and other advanced adjustments to effects. For information on using the 3D Warp effect, see “Applying the 3D Warp Effect” on page 362 .	
Apply to	Transitions, single-layer segments, or multilayer segments	
Real-time status	Real-time in most circumstances. For more information on real-time playback for 3D effects, see “Real-Time Playback of 3D Effects” on page 366 .	
Bit depth processing	8-bit and 16-bit. 16-bit requires the use of the HQ (Highest Quality) button in the Effect Editor. For more information, see “Rendering 3D Effects Using the HQ (Highest Quality) Option” on page 176 .	
RGB processing	Available for most parameter categories. For more information, see “3D Effect Parameters” on page 703 .	
Parameter categories	Shape ; Corner Pin ; Corner Corner Tracking ; Crop (3D) ; Scaling (3D) ; Axis ; Skew ; Rotation ; Position (3D) ; Perspective ; Target ; Border (3D) ; Highlight ; Highlight Color ; Lowlight Color ; Defocus ; Shadow ; Trail ; Stamp ; Foreground (3D) ; Spill Suppression ; Erode/Expand ; Background Color (3D)	

Blend: Dip to Color, Dissolve, Fade from Color, and Fade to Color

	Dip to Color fades from the outgoing video to any color and then fades up to the incoming video.	
	Dissolve blends images from the outgoing video with the incoming video over time.	
	Fade from Color fades from any color to incoming video.	
	Fade to Color fades from the outgoing video to any color.	
	Apply to	Transitions
	Bit depth processing	8-bit and 16-bit
	RGB processing	Available
	Parameter categories	Foreground ; Background Color ; Grid (not available for all project types)
	Illustrations	<div></div>

Left to right: outgoing image, middle of Dissolve effect, incoming image

Blend: Picture-in-Picture

 Creates a picture within a picture. Video on the top layer, where you apply the effect, appears inside the video on the bottom layer. On a transition, the incoming video appears inside the outgoing video.

Apply to

Transitions, multilayer segments

Promotes to

3D

Bit depth processing

8-bit and 16-bit


RGB processing

Available

Parameter categories


Border; Foreground; Scaling; Position; Crop; Grid (not available for all project types)

Illustrations



Left to right: outgoing image, Picture-in-Picture effect, incoming image

Blend: Superimpose

 Blends the image from the top video track (where you apply the effect) with the image from the bottom video track over time. The Foreground Level slider controls the blend percentage over time. When Level=100, only the top image is visible, and when Level=0, only the bottom image is visible.

Apply to

Multilayer segments

Promotes to

3D

Bit depth processing

8-bit and 16-bit


RGB processing

Available

Parameter categories

Foreground; Grid (not available for all project types)

Illustrations




Left to right: bottom track, Superimpose effect, top track


Box Wipes

Box Wipes use an expanding box shape to create transitions to the incoming video.


 For examples of similar effects, see “Comparison of Similar Effects” on page 601.




Incoming video begins as a box and wipes out the outgoing video as the box expands to fill the screen.
Eight Box Wipe effects, named for the direction in which the effect moves, are available:




- Bottom Box




- Bottom Left to Top Right
- Bottom Right to Top Left




- Left Box




- Right Box
- Top Box



- Top Left to Bottom Right



- Top Right to Bottom Left



The effect icons for the category indicate the starting position of the box.

Apply to

Transitions, multilayer segments

Promotes to

3D

Bit depth processing

8-bit and 16-bit


RGB processing


Available


Parameter categories

Border; Foreground; Grid (not available for all project types)


Illustrations









Left to right: outgoing image, middle of Bottom Box effect, incoming image























Left to right: outgoing image, middle of Top Left to Bottom Right effect, incoming image

Conceal Effects


Conceal effects use a predefined path to overlap one video channel over the other.









 *For examples of similar effects, see “Comparison of Similar Effects” on page 601.*


	Incoming video slides on top of the outgoing video. Eight Conceal effects, named for the direction in which the wipe moves, are available:	
	• Bottom Left to Top Right	
	• Bottom Right to Top Left	
	• Bottom to Top	
	• Left to Right	
	• Right to Left	
	• Top Left to Bottom Right	
	• Top Right to Bottom Left	
	• Top to Bottom	
	The effect icons for the category indicate the starting position of the box.	
Apply to	Transitions, single-layer segments, or multilayer segments	
Promotes to	3D	
Bit depth processing	8-bit and 16-bit	
RGB processing	Available	
Parameter categories	Border ; Foreground ; Grid (not available for all project types)	
Illustrations	<div></div> <p>Left to right: outgoing image, middle of Bottom Left to Top Right effect, incoming image</p> <div></div> <p>Left to right: outgoing image, middle of Right to Left effect, incoming image</p>	

Edge Wipes

Edge Wipes wipe an edge across the screen to reveal one video channel on top of the other.

 Incoming video begins at the edge or center of the screen and moves out to wipe away the outgoing video. Eight Edge Wipe effects, named for the direction in which the wipe moves, are available:

-  • Horizontal
-  • Horizontal Open
-  • Lower Left Diagonal
-  • Lower Right Diagonal
-  • Upper Left Diagonal
-  • Upper Right Diagonal
-  • Vertical Open
-  • Vertical


 The effect icons for the category indicate the starting position of the box.

Apply to	Transitions, multilayer segments
Promotes to	3D
Bit depth processing	8-bit and 16-bit
RGB processing	Available
Parameter categories	All Edge Wipes: Foreground ; Grid (not available for all project types) Horizontal, Horizontal Open, Vertical Open, and Vertical effects: Border Lower Left Diagonal, Lower Right Diagonal, Upper Left Diagonal, Upper Right Diagonal effects: Scaling

Illustrations



Left to right: outgoing image, middle of Horizontal Open effect, incoming image




Left to right: outgoing image, middle of Upper Right Diagonal effect, incoming image

Film Effects

Film effects emulate many of the effects an optical house can produce.

Film: Mask Effects — 1.66 Mask, 1.85 Mask, 16:9 Mask, Anamorphic Mask, Mask



Masks out with a black background any area of the image that is not inside a specified rectangle. Five Film Mask effects are available:

- 1.66 Mask — the rectangle is 1.66 times wider than it is tall.
- 1.85 Mask — the rectangle is 1.85 times wider than it is tall.
- 16:9 Mask — the rectangle is 16 units wide by 9 units high.
- Anamorphic Mask — the rectangle is 2.35 times wider than it is tall.
- Mask — you can define a custom rectangle by adjusting the effect’s Scaling and Position parameters.

Apply to

Single-layer segments

Promotes to

3D

Bit depth processing

8-bit and 16-bit


RGB processing

Available

Parameter categories


Background Color; Scaling; Position; Grid (not available for all project types)

Illustrations



Original image (left) and 1.66 Mask effect

Film: Blowup



Modifies the size and portion of an image.

Apply to

Single-layer segments

Promotes to

3D

Bit depth processing

8-bit and 16-bit

RGB processing

Available

Parameter categories

Background Color; Blowup; Crop; Grid (not available for all project types)

Illustrations



Original image (left) and Blowup effect

Film: Film Dissolve and Film Fade



The Film Dissolve effect blends the outgoing frame to the incoming frame over time. It has preset parameters that emulate film's response to light when dissolving to another (nonblack) picture.



The Film Fade effect blends to the incoming frame over time. It has preset parameters that emulate film's response to black material. Use this effect for fade-ins and fade-outs.

For both effects, the Level parameter is preset to Kodak™ specifications. Avid does not recommend adjusting the Level parameter. The Level set at 0% shows all of the outgoing frame; the Level set at 100% shows all of the incoming frame.

Apply to	Transitions
Promotes to	3D
Bit depth processing	8-bit and 16-bit
RGB processing	Available
Parameter categories	Foreground; Grid (not available for all project types)

Illustrations




Left to right: outgoing image, middle of Film Dissolve effect, incoming image

Generator Effects

Generator effects let you add subtitle, captioning, timecode, or production comment text to your video.


Generator: SubCap

 Lets you add caption or subtitle text to the video in your sequences. For more information, see [“Working with the SubCap Effect” on page 447](#).

You cannot keyframe SubCap parameters and you cannot promote the SubCap effect.

Apply to	Segments on video tracks above all other video content
Bit depth processing	8-bit and 16-bit
RGB processing	Not available
Parameter categories	See “SubCap Effect Parameters” on page 616 and “SubCap Effect Global Properties” on page 620 .

Generator: Timecode Burn-In

 Lets you add timecode displays that update in real time, or text annotations, to the video in your sequences.

You cannot keyframe Timecode Burn-In parameters and you cannot promote the Timecode Burn-In effect.

Apply to	Single-layer segments. A typical use is to apply the effect to an empty video track above all other video content. You can then turn the track on or off as necessary to display timecode information or other annotations for some versions of the sequence but not others.
Bit depth processing	8-bit only
RGB processing	Not available
Parameter categories	See “Timecode Burn-In Effect Parameters” on page 621 .

Illusion FX Effects

The Illusion FX category contains a variety of transition and segment effects. Illusion FX effects use the AVX plug-in architecture.

Most Illusion FX effects have an Input Parameters parameter category containing controls that vary from one Illusion FX effect to another. For more information, see [“Illusion FX Effect Parameters” on page 626](#).

Several Illusion FX effects share a Border effect parameter category that has different controls from the Border parameter category in other effect types. For more information, see [“Border Parameter for Illusion FX Effects” on page 626](#).

This topic groups information for the Illusion FX effects in three tables as follows:

- Segment effects (except FluidBlur and FluidColorMap)
- Transition effects (except FluidMorph)
- FluidBlur, FluidColorMap, and FluidMorph

These three effects use high-quality blurring techniques and are non-real-time.

Illusion FX: Segment Effects — Color Mix, Crystal, Film Grain, Flare, Kaleidoscope, Lightning, Motion Blur, Pattern Generator, Pinch, Radial Blur, Ripple, Sparkler, Sphere, Swirl, Twist, Wave



Eighteen Illusion FX effects are segment effects. FluidBlur and FluidColorMap are described separately in the final table in this topic. The following are the remaining segment effects:

- Color Mix lets you blend a solid color with the image.
- Crystal uses polygons to create a mosaic effect. You can control the size of the polygons and the randomness of their shape.
- Film Grain adds a grainy texture to a video clip to simulate the imperfections present in some film footage, such as 16mm stock.
- Flare creates a random ring flare. You can control the brightness, size, and center of the flare.
- Kaleidoscope creates an animation that resembles a kaleidoscope. You can control the number, angle, and position of the mirrors as well as the source area for the effect.
- Lightning creates a random lightning pattern
- Motion Blur lets you blur the edges of moving objects. FluidBlur and Motion Blur are similar effects. FluidBlur creates a higher quality effect because it blurs in the direction of travel, but FluidBlur is a non-real-time effect that always requires rendering.


- Pattern Generator creates a clip using a solid color, a variety of color bars, or a grid. The frames can be numbered automatically, and a circle can be animated. This effect is useful for testing purposes.
- Pinch pinches the image in toward, or pushes it out from a user-defined point. You can control the amount of distortion and the area affected.
- Radial Blur blurs the image inward or outward from a user-defined point, and around a user-defined rotation. You can control the zoom factor.
- Ripple creates ripples on the image, as if you dropped a stone into a pond. You can control the number of ripples; their size, speed, and spread; and the color and direction of the light.
- Sparkler creates random sparks or fireworks. You can control the number and nature of the sparks.
- Sphere creates a spherical distortion in the image. You can control the size and position of the sphere.
- Swirl distorts the image by swirling the pixels within a circular area. You can control the size and position of the circle and the amount of swirl.
- Twist distorts the image by twisting the two ends in opposite directions. You can control the position and the amount of the twist.
- Wave distorts the image by applying a user-defined number of waves to it. You can control the size of the waves.

Apply to	Single-layer segments
Bit depth processing	8-bit only
RGB processing	Available
Parameter categories	For all effects: Input Parameters ; Grid (not available for all project types) For Crystal, Kaleidoscope, Pinch, Radial Blur, Ripple, Sphere, Swirl, Twist, and Wave effects: Border For Kaleidoscope effect: Center ; Offset For Lightning effect: Generation ; Core ; Glow For Pattern Generator effect: Background ; Number ; Circle For Ripple effect: Motion ; Generation ; Illumination For Sparkler effect: Generation ; Movement ; Glow ; Core

Illustrations



Top, left to right: examples of Color Mix, Crystal, and Film Grain. Center, left to right: examples of Flare, Kaleidoscope, and Lightning. Bottom, left to right: examples of Motion Blur, Pattern Generator, and Pinch



Top, left to right: examples of Radial Blur, Ripple, and Sparkler. Center, left to right: examples of Sphere, Swirl, and Twist. Bottom: example of Wave

Illusion FX: Transition Effects — Iris, Melt, Pagecurl, Particle Blast, Particle Orbit, Particle Wind, Random Blend, Rollup, Shear



Ten Illusion FX effects are transition effects. FluidMorph is described separately in the final table in this topic. The following are the remaining transition effects:

- Iris wipes the foreground clip away to reveal the background clip, using a circle that radiates out from the center. You can control the softness of the edge of the circle.
- Melt melts away the foreground clip to reveal the background clip. The foreground clip “melts” downward off the screen, while being distorted in a random “liquid” manner along the horizontal lines; the vertical lines are not distorted. You can control the strength of the distortion.
- Pagecurl treats the foreground video channel as though it were a sheet of paper being rolled over to reveal another page beneath. Pagecurl and Rollup are similar effects. Rollup has more flexibility, but Pagecurl adds a highlight along the curled edge.
- Particle Blast divides the foreground image into circular particles and then blows away the particles from the center outward.
- Particle Orbit divides the foreground image into circular particles, which then orbit around their original position. You can control the size and spacing of the particles.
- Particle Wind divides the foreground image into circular particles and then blows the particles away directionally.
- Random Blend uses a random pattern to blend the image of the incoming and outgoing video.
- Rollup rolls up the foreground clip to reveal the background clip. You can control the size and direction of the rollup. Rollup and Pagecurl are similar effects. Rollup has more flexibility, but Pagecurl adds a highlight along the curled edge.
- Shear divides the foreground clip into strips and moves alternate strips away in opposite directions to reveal the background clip.


Apply to Transitions

Bit depth processing 8-bit only

RGB processing Available

Parameter categories For all effects: [Input Parameters](#); [Grid](#) (not available for all project types)
For Melt, Particle Blast, Particle Orbit, Particle Wind, Rollup, and Shear effects:
[Border](#)

Illustrations



Top, left to right: examples of Iris, Melt, and Pagecurl
Center, left to right: examples of Particle Blast, Particle Orbit, and Particle Wind
Bottom, left to right: examples of Random Blend, Rollup, and Shear

Illusion FX: FluidBlur, FluidColorMap, and FluidMorph



FluidBlur creates a motion blur. The amount of blur is based on the amount of motion in the clip. Only objects that are moving from one frame to the next are blurred. FluidBlur creates a higher quality effect than the Illusion FX Motion Blur effect because it blurs in the direction of travel. You must render this effect to see the result.

FluidColorMap creates animation based on the amount of motion in a scene. Motion maps to color values as follows:

- Direction of movement maps to unique chroma (color) values. A different color is used for each direction within a 360° circle. Your Avid editing application uses the Vectorscope layout (used in the Video Input tool) as a compass of color values.
- Motion magnitude maps to luminance (brightness) and color saturation values. Motion magnitude is defined as the amount of pixels an object moves between frames (or fields).

FluidMorph lets you morph between two clips.

Apply to	Single-layer segments (FluidBlur and FluidColorMap) Transitions (FluidMorph)
Real-time status	Non-real-time

Bit depth processing	8-bit only
RGB processing	Available
Parameter categories	For all effects: Input Parameters ; Border ; Grid (not available for all project types) For FluidMorph: Source

Image Effects

Image effects are general effects that apply to a single stream of video or (in the case of Scratch Removal and Submaster) that modify all the layers of video beneath them.

Image: Avid Pan & Zoom


 Lets you import a high-resolution still image, and then pan and zoom over it. You can preview the movement in real time with no filtering and render the effect with a wide range of filtering options that provide exceptional image quality. For more information, see “Using Avid Pan & Zoom” on page 293 .	
Apply to	Single-layer segments
Bit depth processing	8-bit only
RGB processing	Available
Parameter categories	Other Options button ; Display ; Display Options ; Size ; Position ; Velocity ; Path ; Filtering ; Background ; Advanced ; Cache ; Render Mode ; Grid (not available for all project types)

Image: Blur Effect and Mosaic Effect



The Blur Effect applies a blur effect to a selected area that you can animate and edit on one frame or a series of frames. This is useful for distorting or disguising part of an image.



The Mosaic Effect applies a tile effect to a selected area that you can animate and edit on one frame or a series of frames. This is useful for distorting or disguising part of an image.

Apply to	Single-layer or multilayer segments
Bit depth processing	8-bit and 16-bit
RGB processing	Available
Parameter categories	For both effects: Acceleration ; Corner Tracking ; Feathering ; Grid (not available for all project types) For Blur Effect: Blur For Mosaic Effect: Mosaic

Illustrations



Blur Effect (left) and Mosaic Effect (right)

Image: Color Correction



The Color Correction effect lets you access the tools available in Color Correction mode from the Effect Palette. Depending on your Avid editing application, you might use the Color Correction effect when you need to create a color correction that can be nested within other effects, when you want to apply automatic color corrections in a single step, or when you want to apply a color correction saved as an effect template.

Apply to	Single-layer segments
Bit depth processing	8-bit and 16-bit
RGB processing	Available
Parameter categories	Grid (not available for all project types) Color Correction parameters (the set of parameters available depends on the Color Correction toolset available on your Avid editing application)

Image: Color Effect




	Modifies the luminance, chroma, color style (posterized or solarized), and color gain of the segment. You can use the Color Effect to perform keyframeable color corrections.
Apply to	Single-layer segments
Bit depth processing	8-bit and 16-bit
RGB processing	Available
Parameter categories	Luma Adjust ; Luma Range ; Luma Clip ; Chroma Adjust ; Color Style ; Color Gain ; Grid (not available for all project types)


Image: Flip, Flip-Flop, and Flop




Flip flips the video image vertically.



Flip-Flop flips the video image both horizontally and vertically.




Flop flips the video image horizontally, which reverses the camera angle.




Apply to

Single-layer segments




Promotes to

3D




Bit depth processing

8-bit and 16-bit




RGB processing

Available




Parameter categories

[Grid](#) (not available for all project types)



Illustrations



Top: original image. Bottom, left to right: Flip effect, Flip-Flop effect, and Flop effect

Image: Mask



Masks out any area of the image that is not inside a rectangle defined by the Scaling and Position parameters of the effect. The area surrounding the rectangle is masked by the effect's background color.

Apply to	Single-layer segments
Promotes to	3D
Bit depth processing	8-bit and 16-bit
RGB processing	Available
Parameter categories	Background Color ; Scaling ; Position ; Grid (not available for all project types)

Image: Paint Effect



Enhances the creative and corrective powers of your Avid editing application by allowing you to create vector-based objects that you can animate and edit with customizable paint brushes on one frame or a series of frames. For examples of the Paint Effect, see [“Intraframe Editing” on page 467](#).

Apply to	Single-layer or multilayer segments
Bit depth processing	8-bit and 16-bit
RGB processing	Available
Parameter categories	Acceleration ; Corner Tracking ; Mode ; Feathering ; Magic Mask ; Color ; Brush ; Grid (not available for all project types)

Image: Resize



Modifies the size and position of the video. The background color displays where no video is present. Use the H Pos, V Pos, and Size sliders to specify the size and position of the video. Use the Crop parameters to remove the edges of the picture.

Apply to	Single-layer segments
Promotes to	3D
Bit depth processing	8-bit and 16-bit
RGB processing	Available
Parameter categories	Background Color ; Scaling ; Position ; Crop ; Grid (not available for all project types)

Illustration



Left to right: original image, Resize effect with reduced image, Resize effect with enlarged image

Image: Safe Color Limiter



Lets you limit the color values of video material to a specific range, for example, to meet safe color standards set by a broadcaster. For more information, see [“Working with the Safe Color Limiter Effect” on page 823](#).

Apply to	Single-layer segments
Bit depth processing	8-bit and 16-bit
RGB processing	Available
Parameter categories	422 Safe ; Source Monitor Analysis ; Composite/Luma Levels ; RGB Levels ; Grid (not available for all project types)

Image: Scratch Removal



Lets you remove scratches and other flaws by drawing an object to cover the scratch, and then filling the object with clean replacement material. For examples of the Scratch Removal effect, see [“Examples of Scratch Removal Parameter Settings” on page 516](#).

Apply to	Single-layer segments
Real-time status	Non-real-time
Bit depth processing	8-bit and 16-bit
RGB processing	Available
Parameter categories	Acceleration ; Corner Tracking ; Scratch ; Feathering ; Brush ; Grid (not available for all project types)

Image: Stabilize



Lets you eliminate unwanted motion in a video clip, such as motion from an unstable camera or even more subtle motion such as that introduced during the telecine process as a result of gate weave. For more information, see [“Stabilizing an Image” on page 346](#).

Apply to	Single-layer segments
Bit depth processing	8-bit and 16-bit
RGB processing	Available
Parameter categories	Border ; Background Color ; Scaling ; Position ; Crop ; Corner Tracking ; Grid (not available for all project types)

Image: Submaster



The Submaster effect creates a single media file for all the video on the layers below the effect. This lets you group several effects that reside on different video layers and render them as one effect, which can sometimes be quicker than rendering each effect separately.



The Submaster effect does not render each track separately, so you cannot play each track separately after you render the Submaster effect.


Apply to	Video track above all the video tracks you want to include in the Submaster effect.
Bit depth processing	8-bit and 16-bit
RGB processing	Not applicable
Parameter categories	Grid (not available for all project types)

Key Effects





Key effects combine two or more video streams, using components from one of the streams.

The Chroma Key and Luma Key effects share a Key parameter category. For more information, see [“Key Effects Key Parameters” on page 676](#).


Key: AniMatte

	Enables you to generate custom matte effects that you can apply to a segment or transition in a sequence. You can use a variety of brushes and painting tools to create matte effects that you can animate. For examples of the AniMatte Effect, see “Intraframe Editing” on page 467 .	
Apply to	Transitions or multilayer segments	
Bit depth processing	8-bit and 16-bit	
RGB processing	Available	
Parameter categories	Acceleration ; Corner Tracking ; Foreground ; Mode ; Feathering ; Magic Mask ; Brush ; Grid (not available for all project types)	

Key: Chroma Key

	Replaces one part of the video image with another video image based on color. The key color in the video on the higher track is replaced with the video from the lower track number. Chroma Key is used most frequently with a foreground image shot in front of a highly saturated color screen.	
Apply to	Transitions or multilayer segments	
Promotes to	SpectraMatte	
Bit depth processing	8-bit and 16-bit	
RGB processing	Available	
Parameter categories	Key ; Secondary Key ; Spill Suppression ; Profile ; Foreground ; Acceleration ; Scaling ; Position ; Crop ; Grid (not available for all project types)	
Illustration	<div></div>	
	Left to right: background image, key image, and Chroma Key effect	

Key: Luma Key


	Replaces part of the video image with another video image based on luminance	
Apply to	Multilayer segments	
Promotes to	3D	
Bit depth processing	8-bit and 16-bit	
RGB processing	Available	
Parameter categories	Key ; Foreground ; Scaling ; Position ; Crop ; Grid (not available for all project types)	

Illustration



Left to right: key image, background image, and Luma Key effect

Key: Matte Key


	A three-layer track effect. The bottom layer is the background image, the middle layer is the foreground image, and the top layer contains the grayscale matte or alpha channel.	
Apply to	Multilayer segments	
Promotes to	3D	
Bit depth processing	8-bit and 16-bit	
RGB processing	Available	
Parameter categories	Chroma Key Profile , Secondary Key , and Spill Suppression Parameters ; Foreground ; Acceleration ; Scaling ; Position ; Crop ; Grid (not available for all project types)	

Illustration



Left to right: background image, foreground image, high-contrast matte image, and Matte Key effect




Key: RGB Keyer



Replaces part of the video image with another video image based on color. The key color in the video on the higher track is replaced with the video from the lower track. You can also perform post-key color correction with the RGB Keyer.


Apply to	Multilayer segments
Real-time status	Non-real-time
Bit depth processing	8-bit only
RGB processing	Available
Parameter categories	Key Color; Chroma Key; Matte Control; Color Correction; Grid (not available for all project types)

Illustration



Left to right: background image, key image, and RGB Keyer effect


Key: SpectraMatte Effect



Replaces one part of the video image with another video image based on color. Provides advanced controls and analytical tools for adjusting the key. The key color in the video on the higher track is replaced with the video from the lower track number.





Each parameter is individually keyframeable, except Luma Curve, which uses the advanced keyframe display as a luminance adjustment curve. For more information, see [“Luma Control Parameters” on page 687](#).

Apply to	Multilayer segments
Promotes to	3D
Bit depth processing	8-bit and 16-bit
RGB processing	Available
Parameter categories	Bypass; Key Color; Matte Analysis; Chroma Control; Luma Control; Matte Processing; Spill; Scaling; Position; Crop; Grid (not available for all project types)


Illustration			
	Left to right: background image, key image, and SpectraMatte effect		

L-Conceal Effects

L-Conceal effects overlap one video channel over another, using a predefined L-shaped path.

	Incoming video slides vertically over one half of the screen and then slides horizontally to fill the remaining half of the screen. Four L-Conceal effects, named for the direction from which the effect begins, are available:
	<ul style="list-style-type: none">• Bottom Left
	<ul style="list-style-type: none">• Bottom Right
	<ul style="list-style-type: none">• Top Left• Top Right

The effect icons for the category indicate the starting position of the incoming video.








Apply to	Transitions or multilayer segments
Promotes to	3D
Bit depth processing	8-bit and 16-bit
RGB processing	Available
Parameter categories	Border ; Foreground ; Grid (not available for all project types)
Illustration	

Left to right: outgoing image, example of middle of effect for the Bottom Right L-Conceal, and incoming image


Matrix Wipes

Matrix wipes reveal one video channel on top of another video channel, using blocks or bands that appear in a predefined position or path.

All Matrix Wipe effects share custom grid parameters, accessible from the More Options button. For more information, see [“Custom Grid” on page 608](#).

	Incoming video begins as blocks or bands that follow a pattern while wiping out the outgoing video. You can customize the grid size by clicking the Other Options button.	
	Five Matrix Wipe effects are available:	
	<ul style="list-style-type: none">• Grid	
	<ul style="list-style-type: none">• One-WayRow	
	<ul style="list-style-type: none">• Speckle	
	<ul style="list-style-type: none">• Spiral	
	<ul style="list-style-type: none">• Zig-Zag	
Apply to	Transitions or multilayer segments	
Bit depth processing	8-bit and 16-bit	
RGB processing	Not available	
Parameter categories	Custom Grid (More Options button); Border ; Foreground ; Grid (not available for all project types)	

Illustrations



Top: outgoing image (left) and incoming image (right). Center, left to right: middle of effect for Grid, One-Way Row, and Speckle. Bottom: middle of effect for Spiral (left) and Zig-Zag (right)

Motion Effects

Freeze Frame, Variable Speed, and Strobe Motion effects are traditional (source-side) motion effects that you create as new clips. For more information, see [“Creating Traditional Motion Effects” on page 199](#).

For other motion effects, see [“Timewarp Effects” on page 592](#).

Motion Effect: Freeze Frame

Creates a new clip that repeats the current frame in the Source monitor for the specified duration

Apply to Current frame in the Source monitor

Parameters Accessible from the Clip menu. For more information, see [“Freeze Frame Parameters” on page 694](#).


Motion Effect: Variable Speed and Strobe Motion









Variable Speed creates a new clip with slow motion, fast motion, or reverse motion. Strobe Motion creates a new clip with stuttering effect. The Strobe Motion effect can be used in combination with the Variable Speed effect.


Apply to	Clip marked with IN and OUT points in the Source monitor
Real-time status	Real-time or non-real-time, dependent on the type of motion being represented. For more information, see “Playback Capabilities for Traditional Motion Effects” on page 207 .
Parameters	Available in the Motion Effect dialog box. For more information, see “Variable Speed and Strobe Motion Parameters” on page 695 .

Peel Effects

Peel effects treat outgoing video like a sheet of paper being peeled from incoming video.


 Outgoing video is peeled from incoming video starting from one corner or side of the screen. Eight Peel effects, named for the direction in which the effect moves, are available:

-  • Bottom Left Corner
-  • Bottom Right Corner
-  • Bottom to Top
-  • Left to Right
-  • Right to Left
-  • Top Left Corner
-  • Top Right Corner
-  • Top to Bottom

 The effect icons for the category indicate the starting position of the effect.

Apply to	Transitions, multilayer segments
Promotes to	3D
Bit depth processing	8-bit and 16-bit
RGB processing	Available
Parameter categories	Border ; Foreground ; Grid (not available for all project types)


Illustrations



Top: outgoing image (left) and incoming image (right)

Bottom, left to right: middle of effect for Bottom Left Corner, Right to Left, and Top Right Corner

PlasmaWipe Effects

 PlasmaWipe effects use gradient image bitmaps to create wipes and segment effects. There are 64 preset effects, and you can create your own by creating new gradient images. For more information on using PlasmaWipe effects, see [“PlasmaWipe Effects” on page 535](#).

The preset PlasmaWipe effects are grouped into the following categories:

- Borders lets you apply a variety of edge treatments to effects. For more information, see [“Understanding PlasmaWipe Frame and Border Effects” on page 548](#).
- Center creates a variety of center wipes.
- Horiz creates a variety of horizontal wipes.
- Lava creates several shape wipes based on images of lava. These effects are examples of effects that you can create using existing images. For more information, see [“Creating a PlasmaWipe Effect from an Existing Image” on page 540](#).
- Paint creates several wipes that simulate uncovering the incoming video by wiping away the outgoing video with a brush or cloth. These effects are examples of how to create an effect using the Adobe Photoshop Pencil tool. For more information, see [“Creating a PlasmaWipe Image Using the Pencil Tool” on page 541](#).
- Techno are free form shape wipes and segment effects that you can create using the techniques described in [“Creating Gradient Images for PlasmaWipe Effects” on page 538](#).


When you experiment with PlasmaWipe effects, keyframe the Level parameter to see how the effect changes over time









Apply to	Transitions, single-layer segments, or multilayer segments, depending on the specific effect
Bit depth processing	8-bit only
RGB processing	Not available
Parameter categories	Border ; Chroma Key Profile , Secondary Key , and Spill Suppression Parameters ; Foreground ; Acceleration ; Grid (not available for all project types)


Push Effects

Push effects move one video channel to fill the screen while the other video channel is pushed out of the screen.

 For examples of similar effects, see *“Comparison of Similar Effects”* on page 601.

 Incoming video pushes out outgoing video starting from a corner or side of the screen. The border is on the incoming video. Eight Push effects, named for the direction in which the effect moves, are available:

-  • Bottom Left to Top Right
-  • Bottom Right to Top Left
-  • Bottom to Top
-  • Left to Right
-  • Right to Left
-  • Top Left to Bottom Right
-  • Top Right to Bottom Left
-  • Top to Bottom

 The effect icons for the category indicate the starting position of the effect.

Apply to	Transitions or multilayer segments
Bit depth processing	8-bit and 16-bit
RGB processing	Available
Parameter categories	Border; Foreground; Grid (not available for all project types)

Illustrations








Top: outgoing image (left) and incoming image (right)
Bottom, left to right: middle of effect for Bottom Left to Top Right, Right to Left, and Top Right to Bottom Left


Reformat Effects

Reformat effects let you reformat media to different aspect ratios, for example, when you need to reformat a film aspect ratio for television programming. The 14:9 Letterbox, 16:9 Letterbox, and 4:3 Sidebar effects resize the media to conform to the aspect ratio you select. Pan and Scan lets you select a portion of the media to reformat.

Reformat: 14:9 Letterbox, 16:9 Letterbox, 4:3 Sidebar

	Reformats media to a different aspect ratio (14:9 letterbox, 16:9 letterbox, or 4:3 sidebar) by distorting the media. For more information, see “Using the Reformat Effects” on page 281 .	
	Apply to	Single-layer or multilayer segments
	Bit depth processing	8-bit and 16-bit
	RGB processing	Available
	Parameter categories	Background Color ; Position H (14:9 Letterbox only); Grid (not available for all project types)
Illustration	<div></div> <p>Original image (left) and 16:9 Letterbox effect</p>	


Reformat: Pan and Scan





	Lets you reformat media to different aspect ratios, for example, when you need to reformat a film aspect ratio for television programming. For more information, see “Working with the Pan and Scan Effect” on page 282 .	
	Apply to	Multilayer segments, or single-layer segments in certain circumstances. For more information, see “Combining the Pan and Scan Effect with Transition Effects” on page 292 .
	Bit depth processing	8-bit only
	RGB processing	Available
	Parameter categories	Aspect Ratios ; Scaling ; Position ; Actions ; Grid (not available for all project types)

Sawtooth Wipes

Sawtooth wipes create a transition between shots, using a jagged edge like the teeth of a saw.

All Sawtooth Wipe effects share custom grid parameters, accessible from the More Options button. For more information, see [“Custom Grid” on page 608](#).


 Incoming video appears with a sawtooth edge and expands to fill the screen. . Four Sawtooth Wipe effects, named for the direction in which the effect moves, are available:

-  • Horizontal Sawtooth (moves left to right)
-  • Horizontal Open Sawtooth
-  • Vertical Open Sawtooth
-  • Vertical Sawtooth (moves top to bottom)

The effect icons for the category indicate the starting position of the effect.

Apply to	Transitions or multilayer segments
Bit depth processing	8-bit and 16-bit
RGB processing	Not available
Parameter categories	Custom Grid (More Options button); Foreground ; Grid (not available for all project types)

Illustrations














Left to right: outgoing image, middle of Horizontal Sawtooth (top) and Vertical Open Sawtooth (bottom), and incoming image

Shape Wipes

Shape Wipes reveal one video channel on top of another video channel, using a growing or moving geometric shape.



Some Shape Wipe effects have custom grid parameters, accessible from the More Options button. For more information, see [“Custom Grid” on page 608](#).

	Incoming video uses a geometric shape to fill the screen and wipe out the outgoing video. Nine Shape Wipe effects, named for the shape they use, are available:	
	• 4 Corners	
	• Center Box	
	• Circle	
	• Clock	
	• Diamond	
	• Ellipse	
	• Horizontal Bands	
	• Horizontal Blinds	
	• Vertical Blinds	
	The effect icons for the category indicate the shape of the effect.	
	Apply to	Transitions or multilayer segments
	Bit depth processing	8-bit and 16-bit
	RGB processing	Not available
	Parameter categories	All effects: Foreground ; Grid (not available for all project types) 4 Corners, Center Box, Circle, Ellipse, Horizontal Bands, Horizontal Blinds, and Vertical Blinds effects: Border Center Box, Circle, Diamond, and Ellipse effects: Scaling ; Position Horizontal Bands, Horizontal Blinds, and Vertical Blinds effects: Custom Grid (More Options button)

Illustrations



Outgoing image (left) and incoming image (right)




Top, left to right: middle of effect for 4 Corners, Center Box, and Circle. Center, left to right: middle of effect for Clock, Diamond, and Ellipse. Bottom: middle of effect for Horizontal Bands, Horizontal Blinds, and Vertical Blinds


Spin Effects

Spin effects rotate one or more video channels.

Spin: X Spin and Y Spin



Outgoing video is squeezed until it appears as a line (vertical for X Spin, horizontal for Y Spin). Incoming video then expands from that line until it fills the screen. Border appears only on the incoming video.



Apply to

Transitions

Bit depth processing

8-bit and 16-bit


RGB processing


Available


Parameter categories

Border; Foreground; Grid (not available for all project types)

Illustration








Left to right: outgoing image, stages of the X Spin effect, incoming image

Spin: Z Spin



Incoming video begins as a dot in the center of the screen and then enlarges to full screen while rotating counterclockwise one full revolution, covering the outgoing video

Apply to

Transitions or multilayer segments

Promotes to

3D

Bit depth processing

8-bit only


RGB processing


Available


Parameter categories

Border; Foreground; Grid (not available for all project types)

Illustration






















Left to right: outgoing image, stages of the Z Spin effect, incoming image

590

Squeeze Effects

Squeeze effects expand a video channel from a single point or line until it fills the screen, obscuring the second video channel.

 For examples of similar effects, see *“Comparison of Similar Effects”* on page 601.




Incoming video squeezes over the outgoing video, beginning as a point or line at a specific location on the screen and expanding to fill the screen. Fifteen Squeeze effects, named for the starting location or the movement of the effect, are available:

Apply to	Transitions or multilayer segments
Promotes to	3D
Bit depth processing	8-bit and 16-bit
RGB processing	Available

Parameter categories [Border](#); [Foreground](#); [Grid](#) (not available for all project types)

Illustrations



Top: outgoing image (left) and incoming image (right)
Bottom, left to right: middle of effect for Bottom Centered, Centered Zoom, and Right to Left


Timewarp Effects

Timewarp effects are motion effects that you apply directly to segments in a sequence and customize using the Motion Effect Editor. The Timewarp effect itself is described fully in [“Understanding Timewarp Effects” on page 210](#). The other effects in the Timewarp effect category are templates with different preset parameters for the Timewarp effect.

You can use several specialized FluidMotion Edit parameters to correct artifacts in a Timewarp effect that uses the FluidMotion rendering option. For more information, see [“FluidMotion Edit Parameters for Timewarp Effects” on page 698](#).

For reference information on traditional (source-side) motion effects, which create new clips with changed rates of play, see [“Motion Effects” on page 581](#).

Timewarp: 0% To 100% and 100% to 0%

 0% to 100% is a template for the Timewarp effect that ramps motion in a sequence from 0% (freeze frame) to 100% (full speed). 100% to 0% is a template for the Timewarp effect that ramps motion in a sequence from 100% (full speed) down to 0% (freeze frame). These two effects are the inverse of one another.


Apply the effect to a sequence in the Record monitor, and customize it using the Motion Effect Editor. For more information, see [“Understanding FluidMotion Timewarp Effects” on page 238](#).

Apply to	Single-layer segments
Bit depth processing	8-bit and 16-bit
RGB processing	Available
Parameter categories	All parameters and controls appear in the Motion Effect Editor. For more information, see “Motion Effect Editor Reference” on page 219 .

Illustrations




Speed Graph and Position Graph default settings for 0% To 100%




Speed Graph and Position Graph default settings for 100% To 0%

Timewarp: FluidFilm 2:3 Cadence and FluidFilm Progressive

 FluidFilm 2:3 Cadence is a template for the Timewarp effect that lets you create a film look from interlaced video sources. Use this effect in NTSC projects.


FluidFilm Progressive is a template for the Timewarp effect that lets you create a film look from interlaced video sources. Use this effect in PAL projects.

 *You can also use the templates as a starting point to create a video look from sources originally shot on film by switching the input and output format values.*

Apply the effect to a sequence in the Record monitor, and customize it using the Motion Effect Editor. For more information, see [“Understanding FluidMotion Timewarp Effects” on page 238](#).

Apply to	Single-layer segments
Real-time status	Non-real-time
Bit depth processing	8-bit and 16-bit
RGB processing	Available
Parameter categories	All parameters and controls appear in the Motion Effect Editor. For more information, see “Motion Effect Editor Reference” on page 219 .

Timewarp: Pulldown Insertion and Pulldown Removal

 Pulldown Insertion is a template for the Timewarp effect that inserts 2:3 pulldown into a sequence. Pulldown Removal is a template for the Timewarp effect that removes 2:3 pulldown from a sequence. These two effects are the inverse of one another.


Source material without 2:3 pulldown has the cadence AA BB CC DD, where each letter represents a field. Pulldown Insertion uses the cadence AA BB BC CD DD. Using Pulldown Insertion slows the source material to 4/5 (80% speed).

Source material with 2:3 pulldown has the cadence AA BB BC CD DD, where each letter represents a field. Pulldown Removal uses the cadence AA BB CC DD. Using Pulldown Removal speeds up the source material to 5/4 (125%).


Apply the effect to a sequence in the Record monitor, and customize it using the Motion Effect Editor. For more information, see [“Understanding FluidMotion Timewarp Effects” on page 238](#).

Apply to	Single-layer segments
Bit depth processing	8-bit and 16-bit
RGB processing	Available
Parameter categories	All parameters and controls appear in the Motion Effect Editor. For more information, see “Motion Effect Editor Reference” on page 219 .

Illustrations



Speed Graph and Position Graph default settings for Pulldown Insertion



Speed Graph and Position Graph default settings for Pulldown Removal

Timewarp: Reverse Motion




Reverse motion is a template for the Timewarp effect that creates a reverse motion effect at 100% speed.

Apply the effect to a sequence in the Record monitor, and customize it using the Motion Effect Editor. For more information, see [“Understanding FluidMotion Timewarp Effects” on page 238](#).


Apply to	Single-layer segments
Real-time status	Non-real-time
Bit depth processing	8-bit and 16-bit
RGB processing	Available
Parameter categories	All parameters and controls appear in the Motion Effect Editor. For more information, see “Motion Effect Editor Reference” on page 219 .

Illustration



Speed Graph and Position Graph default settings for Reverse Motion


Timewarp: Speed Boost and Speed Bump

 Speed Boost and Speed Bump are templates for the Timewarp effect. Speed Boost starts out at half speed, reaches approximately double speed at the midpoint, and returns to half speed at the end. Speed Bump starts out at full speed, slows to approximately half speed at the midpoint, and returns to full speed at the end.


Apply the effect to a sequence in the Record monitor, and customize it using the Motion Effect Editor. For more information, see [“Understanding FluidMotion Timewarp Effects” on page 238](#).

Apply to	Single-layer segments
Bit depth processing	8-bit and 16-bit
RGB processing	Available
Parameter categories	All parameters and controls appear in the Motion Effect Editor. For more information, see “Motion Effect Editor Reference” on page 219 .

Illustrations




Speed Graph and Position Graph default settings for Speed Boost




Speed Graph and Position Graph default settings for Speed Bump

Timewarp: Timewarp


 Apply the effect to a sequence in the Record monitor, and customize it using the Motion Effect Editor. For more information, see [“Understanding FluidMotion Timewarp Effects” on page 238](#).

Apply to	Single-layer segments
Bit depth processing	8-bit and 16-bit
RGB processing	Available
Parameter categories	All parameters and controls appear in the Motion Effect Editor. For more information, see “Motion Effect Editor Reference” on page 219 .

Timewarp: Trim to Fill

 Trim to Fill is a preset effect using the Timewarp effect that changes the playback speed to a constant rate. You can change the rate by trimming the clip.

Apply the effect to a clip in the Timeline. Your Avid editing application displays the current speed in the Timeline along with the clip name. The default speed is 100%. To change the speed, enter Trim mode and trim the effect shorter (faster) or longer (slower). When you perform the trim operation you are trimming the effect, not the clip. The beginning and ending frames (and the number of source frames) remain the same.

 *You can achieve a similar result using the Fit to Fill check box for traditional Motion effects or the Fit to Fill button on the Command palette. However, the Trim to Fill effect lets you access the higher quality Blend rendering options available for Timewarp effects.*


For more information, see [“Understanding FluidMotion Timewarp Effects” on page 238](#).


Apply to	Single-layer segments
Bit depth processing	8-bit and 16-bit
RGB processing	Available
Parameter categories	All parameters and controls appear in the Motion Effect Editor. For more information, see “Motion Effect Editor Reference” on page 219 .

Title Effects

You create Title effects with the Title tool or with Marquee and save them to bins as Title clips. Titles can incorporate text, graphic objects, imported graphics, and video. You edit a Title clip into a sequence on its own video layer above all other material. Your Avid editing application keys the title over the underlying video layers.

Title Effects: Crawling Title and Rolling Title

 By default, crawling titles scroll from right to left on the screen, while rolling titles scroll from the bottom to the top of the screen. For more information, see [“Creating Rolling and Crawling Titles” on page 401](#).



Apply to	A segment above other video layers
Real-time status	Non-real-time
Bit depth processing	8-bit and 16-bit
RGB processing	Available
Parameter categories	Open with Title Tool or Marquee (Edit Title button); Foreground ; Position ; Scroll Position ; Crop ; Grid (not available for all project types)

Title Effects: Title








For information on creating titles, see [“Creating Titles” on page 381](#).

Apply to	A segment above other video layers
Promotes to	3D
Bit depth processing	8-bit and 16-bit
RGB processing	Available
Parameter categories	Open with Title Tool or Marquee (Edit Title button); Foreground ; Scaling ; Position ; Crop ; Grid (not available for all project types)

Xpress 3D Effects

Xpress 3D effects provide a limited set of parameter categories for creating basic 3D effects that are fully compatible with Avid Xpress editing applications that include a 3D effects option.

 Xpress 3D effects provides basic 3D PIP and 3D shape effects that are compatible with Avid Xpress editing application. Four effects are available.

-  • 3D Ball
-  • 3D PIP
-  • 3D Page Fold
-  • 3D Slats

Once you apply one of the effects, you can switch to another shape by making a selection from the menu in the Shape parameter category, or you can switch to 3D PIP by turning off the Shape parameter category.

Apply to	Transitions, single-layer segments, or multilayer segments, depending on circumstances
Real-time status	Real-time in most circumstances. For more information on real-time playback for 3D effects, see “Real-Time Playback of 3D Effects” on page 366 .
Promotes to	3D Warp (for the complete set of 3D parameter categories)
Bit depth processing	8-bit and 16-bit. 16-bit requires the use of the HQ (Highest Quality) button in the Effect Editor. For more information, see “Rendering 3D Effects Using the HQ (Highest Quality) Option” on page 176 .
RGB processing	Available for most parameter categories. For more information, see “3D Effect Parameters” on page 703 .
Parameter categories	For all effects: Shape ; Target ; Border (3D) ; Foreground (3D) ; Background Color (3D) 3D PIP, 3D Page Fold, and 3D Slats effects: Crop (3D) 3D PIP and 3D Ball effects: Scaling (3D) ; Position (3D) 3D PIP effect: Axis ; Rotation ; Shadow ; Trail

Comparison of Similar Effects


Four effect categories have similar results: Box Wipe, Conceal, Push, and Squeeze. Examples of these effects are shown here to assist you in using these effects.



Top Left to Bottom Right Box Wipe effect



Top Left to Bottom Right Conceal effect



Top Left to Bottom Right Push effect



Top Left Squeeze effect

18 Effects Parameter Reference

This chapter provides reference information for all effect parameters in your Avid editing application.


- Effect parameter controls that you use to define colors are described in [“Color Parameter Controls” on page 604](#). Color controls appear in a number of 2D and 3D effect parameter categories.
- Effect parameter categories that are common to multiple 2D effects across at least two effect categories are listed in [“Common 2D Effect Parameters” on page 605](#).
- Effect parameter categories that are unique to a single 2D effect category are listed by the effect category, as follows:
 - [“Film Effects Blowup Parameter” on page 616](#)
 - [“Generator Effect Parameters” on page 616](#)
 - [“Illusion FX Effect Parameters” on page 626](#)
 - [“Image Effect Parameters” on page 652](#)
 - [“Key Effect Parameters” on page 676](#)
 - [“Motion Effect Parameters” on page 694](#)
 - [“Reformat Effect Parameters” on page 697](#)
 - [“FluidMotion Edit Parameters for Timewarp Effects” on page 698](#)
 - [“Rolling Title and Crawling Title Effect Parameters” on page 702](#)
- Effect parameter categories for 3D effects are listed in [“3D Effect Parameters” on page 703](#).

Effect parameters are keyframeable unless otherwise noted in this chapter. You can set keyframeable parameters to different values at different points in an effect’s duration to alter the effect over time. If a parameters is not keyframeable, you cannot change its value over the duration of an effect.


Color Parameter Controls

Many effect include parameter controls that let you select a color, for example, to color a border or a background. These controls let you define a color in three ways:

- You can use your operating system’s color controls (the Windows Color dialog box or the Macintosh Colors panel).
- You can use an eyedropper tool to select a color from an image.
- You can use parameter sliders to define a color. Depending on the effect, the sliders might use hue, saturation, and luminance values to define a color, or they might use red, green, and blue values.



Examples of color parameter controls: with hue, saturation, and luminance sliders (left) and with red, green, and blue sliders (right). The Other Options button and the Color Preview window are highlighted in each example.

Parameter	Description
Other Options button 	Opens the Windows Color dialog box or the Macintosh Colors panel for precise color selection. For more information, see “Adjusting a Color Parameter for an Effect” on page 96 .
Color Preview window	Displays the currently selected color, and provides access to the eyedropper tool for selecting a color from an image. For more information, see “Adjusting a Color Parameter for an Effect” on page 96 .
Hue	Identifies the hue or tint of the color. Hue is measured as values on a color wheel ranging from 0 to 255. The start (0) and end (255) values are both red.
Sat (saturation)	Specifies the amount or intensity of the color. Values range from 0 to 255, where 0 is no chrominance and 255 is a fully saturated color.
Lum (luminance)	Specifies the brightness of the color. Values range from 0 to 255, where 0 is black and 255 is full brightness or white.
R (red)	Specifies the red component of an RGB color definition. Values range from 0 (no red) to 255 (maximum amount of red).
G (green)	Specifies the green component of an RGB color definition. Values range from 0 (no green) to 255 (maximum amount of green).


Parameter	Description
B (blue)	Specifies the blue component of an RGB color definition. Values range from 0 (no blue) to 255 (maximum amount of blue).

Common 2D Effect Parameters

This section describes, in alphabetical order, 2D effect parameters that are common to multiple effects across at least two effect categories.

Acceleration

Acceleration adjusts the speed of an effect over time by having the effect ease in and ease out of every keyframe. This gives the effect a more natural appearance. **This parameter is not keyframeable.**




The overall speed of an effect depends on its duration, which in turn depends on the length of the clip in the sequence. To slow down or speed up the movement of an effect, change the length of the clip or use add edits to limit the portion of the clip affected by the effect.

The slider controls ease in and ease out motion. Values range from 0 (no ease in and ease out motion, so the effect maintains a constant speed throughout its path) to 100 (maximum ease in and ease out motion).

Background Color

Background Color sets the color for the background in effects that display a background, for example, a Fade to Color effect. For more information on the parameter controls, see [“Color Parameter Controls” on page 604](#).




For information on the 3D equivalent of this parameter category, see [“Background Color \(3D\)” on page 705](#).

The Avid Pan & Zoom effect and the Illusion FX Pattern Generator effect have Background parameters that provide similar capabilities to the Background Color parameters. For more information, see [“Background Parameters” on page 656](#) and [“Pattern Generator Effect Background, Number, and Circle Parameters” on page 640](#).

Border

Border lets you specify the color, softness, and width of a border, for example, on the incoming image in a transition. Some effects also include Blend Color parameters for blending border color.




For information on the 3D equivalent of this parameter category, see [“Border \(3D\)” on page 705](#).

The Border parameter category for Illusion FX effects has different parameters that are described in [“Border Parameter for Illusion FX Effects” on page 626](#).

Parameter	Description
Color and Blend Color subcategories	Let you set the border color and the border blend color. For more information on the parameter controls, see “Color Parameter Controls” on page 604 .
Width	Specifies the width of the border. Values range from 0 (no border) to 100 (widest border).
Soft (softness)	Blends the border with the background image, giving the border a soft appearance. Values range from 0 (no softness) to 255 (maximum softness).
Fixed Border	Turns off the Blending option. For PlasmaWipe effects, Fixed Border lets you specify whether the border can change shape during the effect. For the Frame and Border PlasmaWipe effects the border is used to create the effect.

Brush

Brush enables you to define the shape, size, and softness of the brush for creating brush strokes on an image. You can also customize the shape and rotate the head of the Brush tool to create a variety of new effects. **This parameter is not keyframeable.**



Brush is available in the following effects: [Image: Paint Effect](#), [Image: Scratch Removal](#), [Key: AniMatte](#), [FluidMotion Edit for Timewarp Effects](#).

Parameter	Description
Path	Controls the percentage of paint or the matte that is visible from the initial point of pressure to the completion of the brush stroke. Values range from 0 (no paint visible) to 100 (entire stroke visible). Unlike other Paint Effect parameters, you can adjust Path only after you finish painting.
Soft (softness)	Adjusts the softness of the brush head. Values range from 0 (hard center) to 100 (softest overall head).
Size	Adjusts the size of the brush head. Values range from 0 to 100 pixels.
Shape buttons	Changes the brush head to a new shape.
Spin	Lets you rotate the brush head 360 degrees in the clockwise and counterclockwise directions. Values range from -360 degrees (maximum clockwise rotation) to 360 degrees (maximum counterclockwise rotation). The default position is 0 degrees.

Crop

Crop removes video from the top, bottom, left, and right edges of the video.




For information on the 3D equivalent of this parameter category, see “Crop (3D)” on page 707.

Parameter	Description
T (top)	Removes video from the top of the inner or incoming video. Values range from 0 (top of the screen) to 999 (bottom of the screen).
B (bottom)	Removes video from the bottom of the inner or incoming video. Values range from –999 (top of the screen) to 0 (bottom of the screen).
L (left)	Removes video from the left side of the inner or incoming video. Values range from 0 (left side of the screen) to 999 (right side of the screen).
R (right)	Removes video from the right side of the inner or incoming video. Values range from –999 (left side of the screen) to 0 (right side of the screen).

Custom Grid

In Matrix Wipe, Sawtooth Wipe, and some Shape Wipe effects, you can use a grid to define the position or progress of certain effects over time. You define the grid by clicking the More Options button to open a dialog box, and then either selecting a standard preset grid or entering a custom number of rows and columns. The minimum number of rows and columns is 2 x 2, and the default number is 8 x 6.



Feathering

Feathering adds soft edges to a painted object or a matte key. Adding a soft edge can make a composited object look more natural against the background.




Feathering is available in the following effects: [Image: Blur Effect](#) and [Mosaic Effect](#), [Image: Paint Effect](#), [Image: Scratch Removal](#), [Key: AniMatte](#), and [FluidMotion Edit for Timewarp Effects](#)

Parameter	Description
Bias	<p>Increases control over the dissipation of pixels around the edges of a painted object or matte. Adjusting bias is especially effective when you trace an element on the screen with the Paint Effect.</p> <p>Values range from 0 (feathers pixels starting at the outside edge) to 100 (feathers pixels starting at the inner portion of the edge). The default value of 50 feathers pixels starting at the center portion of the edge.</p>
Hor (horizontal) and Vert (vertical)	<p>Lets you select the dominant direction in which feathering of an object or matte appears.</p> <p>Hor (horizontal) extends feathering in both the positive and negative directions along the X axis (right to left and left to right on the screen). Vert (vertical) extends feathering in both the positive and negative directions along the Y axis (upward and downward on the screen). Values range from 0 pixels (no feathering) to 63 pixels (maximum feathering).</p>
Fixed Aspect	<p>Gangs the Hor and Vert sliders together so that they move in unison when you drag either one. Horizontal is the dominant direction.</p>
Anti-alias	<p>Decreases the jagged appearance of a selected object’s edges. Use anti-aliasing in combination with feathering to improve the appearance of an object’s edges.</p>

Foreground

Foreground sets the relative amount of the effect to be displayed over time. The set of available parameters varies depending on the effect.




For information on the 3D equivalent of this parameter category, see [“Foreground \(3D\)” on page 710](#).

Parameter	Description
Level	<p>Controls the opacity of the foreground image. Values range from 0 (transparent) to 100 (opaque).</p> <p>For PlasmaWipe effects, Level controls the amount of the effect at any given point. As you increase the value, the effect reveals more incoming video.</p>
Swap Sources	<p>Swaps the image source for the foreground and background layers of the effect.</p>
Reverse Animation	<p>Reverses the entire effect, including the direction of movement as well as the incoming and outgoing sources.</p> <p>This maintains the shot continuity while reversing the movement. This option effectively creates a mirror image of the sequence of keyframes for the effect as they appear in the Effect Preview monitor's position bar.</p> <p>The Reverse Animation parameter is only available for certain effects that do not use advanced keyframes. To reverse an effect that uses advanced keyframes, for example an edge wipe, use the Reverse Keyframes shortcut menu command in the Effect Editor. For more information, see “Reversing Advanced Keyframes” on page 137.</p>
Invert Key	<p>Reverses the key as follows:</p> <ul style="list-style-type: none">• With a Chroma Key effect, displays the key color regions while showing the background image source through the foreground image area.• With a Luma Key effect, displays the background image source through the darker areas rather than the lighter areas of the foreground image source.• With a Matte Key effect, effectively reverses the black and white areas of the alpha channel so that foreground and background are reversed.
Show Alpha	<p>Displays the grayscale alpha channel used to apply the key effect to the foreground and background source. This lets you examine problem areas of the key while making adjustments.</p>

Grid

Grid defines the Effect Grid associated with an effect. Grid parameters set in the Effect Editor override settings in the Grid Settings dialog box for that effect only. **This parameter is not keyframeable, and is not available in all project types.**



Parameter	Description
Enable button	Turns the local Grid effect on or off. If you disable the local Grid effect, your Avid editing application uses the global settings defined in the Grid Settings dialog box.
Type menu	<p>Selects one of the following grid types:</p> <ul style="list-style-type: none"> • Square • Standard Film • Academy <p>The Academy grid includes a safety margin on the left that is used for adding the optical sound track.</p> <ul style="list-style-type: none"> • Super 35 • Anamorphic
Fields	Determines the number of tick marks along the grid axes as well as the number of visible grid points. Values range from 8 to 32.
Sub (subfields)	Determines the snap-to-grid feature between visible grid points. The value determines how many jumps are in between each visible point. Values range from 0 (turns off the snap-to-grid feature) to 10 (provides 10 jumps between each visible point).
Source Scan Size	Applies to film projects, where an optical house scans film for the addition of visual effects. Values range from 720 to 9999 for Horizontal and from 243 to 9999 for Vertical.
Source Grid Offset	Move the grid on the image. The Inset slider shrinks the grid proportionally. Values are set to approximately 15% of the current values in the Source Scan Size sliders.
Transfer menu	<p>Specifies how the film was transferred to video as follows:</p> <ul style="list-style-type: none"> • Full Aperture — The transfer includes everything that is visible in the frame. • Academy — The transfer does not include the sound track area on the left side of the film.

Magic Mask

Magic Mask lets you apply effects across a series of frames, using the chroma and luma values as the criteria for edge detection. After you pick a color with the eyedropper, you can adjust the Hue, Sat, and Lum sliders to fine-tune the color selection.




Magic Mask is available in the following effects: [Image: Paint Effect](#), [Key: AniMatte](#).

Parameter	Description
Color controls	<p>Let you select a color from the video background and then refine it. For more information on the parameter controls, see “Color Parameter Controls” on page 604.</p> <p>To colorize your effect, use the controls in the Paint Effect’s Color parameter category in conjunction with one of the Paint Effect modes.</p>
Gain	<p>When you use the Paint Effect, Gain increases or decreases the range of pixels surrounding the color you pick that Magic Mask enables you to modify in conjunction with your selected paint mode. Gain includes or excludes pixels surrounding the color you pick that falls within a specified color range, or tolerance.</p> <p>When you use the AniMatte effect, Gain increases or decreases the effect of Magic Mask on pixels that are contiguous to your color selection within the borders of a matte key. Gain applies color correction to pixels that fall within the specified color range, or tolerance, of the color you pick with the eyedropper.</p> <p>The tolerance you adjust with the Gain slider is relative to the RGB values of the color you picked.</p> <p>Values range from 0 to 63 pixels. Decreasing the value lessens the color range and includes fewer pixels contiguous to the matte key or color selection. Increasing the value expands the range and includes more pixels surrounding the matte key or color selection.</p>
Soft (softness)	<p>Increases or decreases the amount of softness applied to a color selection and contiguous pixels that fall within a specified tolerance. The tolerance you adjust with the Soft slider is relative to the RGB values of the color picked in the selection. Values range from 0 to 63.</p>

Position

Position sets the horizontal and vertical position of the effect.



For information on the 3D equivalent of this parameter category, see [“Position \(3D\)” on page 715](#).


Some other effects have position parameter categories that differ from the standard Position parameter category. These variations are described in the following topics:

- [“Position Parameters” on page 653](#) (for the Avid Pan & Zoom effect)
- [“14:9 Letterbox Position H Parameter” on page 697](#) (for the 14:9 Letterbox Reformat effect)
- [“Rolling Title and Crawling Title Effect Parameters” on page 702](#) (for Rolling and Crawling Titles)

Parameter	Description
X	Moves the video from side to side. Values range from –999 to 999. Negative values move the image to the left. Positive values move the image to the right.
Y	Moves the video up and down. Values range from –999 to 999. Negative values move the image to the top. Positive values move the image to the bottom.
Tracking	<p>Lets you use tracking data to control the position of the effect. For more information, see “Effects and Effect Parameters That Use Tracking Data” on page 311.</p> <p>By default, when Tracking is enabled, your Avid editing application maps a tracker named Point A to the T1 tracker selector.</p> <p>The Axis menu lets you to use the data for both X and Y axes or for a single axis only. For more information, see “Limiting the Effect of Position Tracking Data to a Single Axis” on page 343.</p>

Scaling

Scaling resizes the effect by adjusting height and width.




For information on the 3D equivalent of this parameter category, see [“Scaling \(3D\)” on page 717](#).

Parameter	Description
X	Stretches or compresses the width of the effect. Values range from 0 to 400, where 100 indicates 100% scaling (normal size).
Y	Stretches or compresses the height of the effect. Values range from 0 to 400, where 100 indicates 100% scaling (normal size).
Fixed Aspect	Gangs the X and Y sliders together so that they move in unison when you drag either one. When Fixed Aspect is enabled, you cannot change the aspect ratio of the effect.
Tracking	Lets you use tracking data to scale the effect. For more information, see “Effects and Effect Parameters That Use Tracking Data” on page 311 . By default, when Tracking is enabled, your Avid editing application maps two trackers named Point A and Point B to the two tracker selectors.


Tracking

Lets you use tracking data to control the effect. When you enable an individual selector, your Avid editing application maps a tracker to that selector. Trackers are named Point A, Point B, and so on. For Intraframe effects, you can only enable trackers when an Intraframe object is selected. For more information, see [“Motion Tracking and Stabilization” on page 307](#).



Transition Parameters

Transition parameters let you define the length and position of a transition effect. They appear at the bottom of the Effect Editor and are active for all transition effects. **Transition parameters are not keyframeable.**



Transition Effect Alignment button (left, with menu open below) and Transition Effect Duration box (right) in the Effect Editor

Parameter	Description
Transition Effect Alignment	<p>Specifies the start of the transition effect relative to the cut point in the sequence. The following menu options are available:</p> <ul style="list-style-type: none"> Ending at Cut — The transition effect starts a number of frames before the cut defined by the duration, such that the effect completes at the cut point in the video. Centered on Cut — The transition is centered on the cut so that half the effect occurs before the cut point and half occurs after the cut point in the sequence. Starting at Cut — The transition effect starts immediately after the last frame of the outgoing video is displayed. Custom Start — Lets you specify the number of frames before and after the cut to be included in the effect. <p>The icon on the Transition Effect Alignment button shows the alignment status at the currently selected cut point. If the cut point does not have a transition effect, the icon is a vertical bar. If the cut point has an existing transition effect, the icon indicates the alignment of the transition effect.</p>
Transition Effect Duration	<p>Specifies the length of time that the effect will span the transition. The format (for example, 1:00 is 1 second and 0 frames) is determined by the Transition Effect Duration setting you select at the top of the Effect Preview window.</p>

Film Effects Blowup Parameter

Blowup lets you enlarge and reposition the image.



Parameter	Description
Field	Controls the size of the image. Values range from 0 (leaves the image size unchanged) to 12 (increases the image to the maximum size).
X Pos (X position)	Lets you position the image horizontally on the screen. Values range from -24 to 24, where 0 is unchanged.
Y Pos (Y position)	Lets you to position the image vertically on the screen. Values range from -18 to 18, where 0 is unchanged.



Generator Effect Parameters

This section contains reference summaries for the effect parameters that are unique to the Generator effect category.

SubCap Effect Parameters

SubCap parameters control the text and appearance of subtitles or captions. For illustrated examples of the use of SubCap effect parameters, see [“Examples of SubCap Effect Parameter Adjustments” on page 463](#). **SubCap effect parameters are not keyframeable.**

Category	Control	Description
	Edit Global Properties	Opens the Global Properties dialog box, which lets you add information to a caption effect, manage parameter stylesheets, and synchronize effect parameters and information across all effects on a track or all effects in a sequence. For more information, see “Adding Information to a SubCap Effect” on page 455 , “SubCap Effect Global Properties” on page 620 , “Working with SubCap Effect Stylesheets” on page 461 , and “Synchronizing SubCap Effect Parameters and Information” on page 457 .
	Bypass Effect	Turns the display of the subtitle on or off.

Category	Control	Description
Caption Files	Import Caption Data	Opens the “Select a file that contains caption data” dialog box, which lets you import caption data from an EBU N19 or a DS caption file. For more information, see “Importing a Caption File” on page 453 .
	Export Caption Data	Opens the “Export caption data to the specified file” dialog box, which lets you export caption data to an EBU N19 or a DS caption file. For more information, see “Exporting SubCap Effect Data to Caption Files” on page 458 .
Text Appearance	Color	Sets the color of the text. For more information on the parameter controls, see “Color Parameter Controls” on page 604 .
	Opacity	Sets the opacity of the text. Values range from 0 (fully transparent) to 1 (fully opaque) in 0.1 increments.
	Font Face	Sets the font used for the text. If you need support for Unicode characters, select a font that is Unicode-enabled.
	Font Size	Sets the size of the text font in vertical pixels (scan lines). Values range from 0 to 999.
		 <i>If caption objects are very large (for example, if you are working with a very large font size), you might experience performance limitations, for example, during real-time playback.</i>
	Line Weight	If Basic Outline is selected in the Outline menu, extends the outline into the text characters, making the outline thicker and the text characters thinner. If No Outline is selected in the Outline menu, varies the thickness of the text characters. Values range from 0 to 999.
	Outline Weight	Controls the thickness of the outline outside the text characters. The higher the value, the thicker the outline becomes and the further it extends beyond the edges of the text characters. Values range from 0 to 999.
	Outline menu	<p>Select Basic Outline to add an outline to text characters. Use the Line Weight and Outline Weight thumbwheels above the Outline menu to control the thickness of the outline. Use the Color control below the Outline menu to set the color of the outline.</p> <p>Select No Outline, then adjust the Line Weight thumbwheel to vary the thickness to text characters without using a differently colored outline.</p> <p> <i>Style sheets created in previous releases of Avid editing applications do not include the properties that control outlines. You must resave existing style sheets to add outline properties to them.</i></p>
	Color	Sets the color of the outline surrounding text characters. For more information on the parameter controls, see “Color Parameter Controls” on page 604 .


Category	Control	Description
	Text Shadow	<p>Sets the type of shadow used for the text. The options are:</p> <ul style="list-style-type: none">• No Shadow• Standard Shadow• Custom Shadow <p>If you select Standard Shadow, your Avid editing application applies a default shadow offset and direction. The shadow appears a little below and to the right of the text.</p> <p>If you select Custom Shadow, use the Radius and Angle sliders to control the offset and direction of the shadow:</p> <ul style="list-style-type: none">• Radius controls the shadow offset. Values range from 0 (no offset) to 1 (maximum offset) in 0.1 increments.• Angle controls the direction of the shadow. Values range from 0 to 6.3 in 0.1 increments, where both 0 and 6.3 place the shadow directly to the right of the text and 3.1 (the slider’s midpoint) places the shadow directly to the left of the text. <p>The shadow color is calculated automatically based on the hue and opacity set for the text.</p>
	Text Alignment	Sets the alignment of the text (Left, Center, or Right) within its background box.
Box Appearance	Color	Sets the color of the background box. For more information on the parameter controls, see “Color Parameter Controls” on page 604 .
	Opacity	Sets the opacity of the background box. Values range from 0 (fully transparent) to 1 (fully opaque) in 0.1 increments.
	Box Style	<p>Sets the style for the background box. The options are:</p> <ul style="list-style-type: none">• One Box — a single box surrounds the entire caption text, even if the text appears in multiple rows.• Separate Boxes for Each Row — each row of text has its own background box.
	Anchor Box to	<p>Controls the position of the box with respect to the text. The options are:</p> <ul style="list-style-type: none">• Anchor to Bottom of Text — the bottom of the box is anchored to the bottom of the text. As more text is typed into a multi-row caption, the text and the box expand up the screen from the anchor position.• Anchor to Top of Text — the top of the box is anchored to the top of the text. As more text is typed into a multi-row caption, the text and the box expand down the screen from the anchor position.

Category	Control	Description
	Justify Anchor	<p>Controls the horizontal location of the anchor with respect to the box. The options are:</p> <ul style="list-style-type: none"> • Anchor Left — the anchor is positioned at the left corner of the box (either top or bottom, depending on the value set in the Anchor Box to control). • Anchor Center — the anchor is positioned at the center of either the top or bottom edge of the box (depending on the value set in the Anchor Box to control). • Anchor Right — the anchor is positioned at the right corner of the box (either top or bottom, depending on the value set in the Anchor Box to control).
	Anchor Position	<p>Controls the location of the anchor for the text and its background box. This anchor point displays in the Effect Preview monitor and you can also position it by dragging it directly in the monitor. For more information, see “Adjusting SubCap Effect Parameters” on page 456.</p> <p>The X slider controls the horizontal location of the anchor; the Y slider controls the vertical location of the anchor. Values range from –999 to +999, where 0 is the center of the screen.</p>
	Box Width	<p>Controls how the width of the background box is determined. The options are:</p> <ul style="list-style-type: none"> • Fixed Width (Clip) — the width of the box is fixed at the size set by the Box Width thumbwheel. Caption text overflows the box and is not visible when it exceeds the width of the box. • Fixed Width (Wrap) — the width of the box is fixed at the size set by the Box Width thumbwheel. Caption text wraps to a new line when it exceeds the width of the box. • Each row as wide as widest — the box for each line of text is the width of the widest line of text. • Each row as wide as needed — the box for each line of text is as wide as it needs to be to accommodate that line of text. <p>Use the Box Width thumbwheel to set a fixed width for the background box. Values range from 0 to 2000.</p>

Category	Control	Description
	Number of Rows of Text	<p>Controls how many rows of text are allowed for the caption. The options are:</p> <ul style="list-style-type: none">As Many Rows as Needed — allows as many rows as are needed to accommodate the caption text and observe other settings such as box width.Exactly N Rows — sets an exact number of rows. If there is more text for the caption than can fit in the number of rows, the overflow text is not visible. If there is not enough text to fill the number of rows, one or more empty rows display.At Most N Rows — sets a maximum number of rows. If there is more text for the caption than can fit in the number of rows, the overflow text is not visible. If there is not enough text to require the maximum number of rows, your Avid editing application uses only the number of rows needed for the text . <p>Use the Row Count thumbwheel to set an exact or a maximum number of rows. Values range from 1 to 25.</p>
	Padding	<p>Adds extra pixels of padding between the edges of the background box and the edges of the text it contains. Use the Vertical slider to add padding to the top and bottom of the box, and the Horizontal slider to add padding to the sides of the box. Values range from 0 to 999.</p>
	Row Spacing	<p>Adjusts the line spacing between rows of text. Values range from –10 to 50, where 0 represents no change to the default line spacing for the font. Negative values move rows of text closer together. Positive values move rows of text further apart.</p>
Caption Text	Edit Master Caption List	<p>Opens the Master Caption List dialog box, which lets you view and edit all of the captions in the current sequence. For more information, see “Editing Text in the Master Caption List” on page 456.</p>
	Caption text box	<p>Displays the caption text and lets you enter caption text. For more information, see “Entering Caption Text Directly in the Effect Editor” on page 452.</p>

SubCap Effect Global Properties

Tab	Option	Description
Contacts	Publisher	<p>Enter up to 32 characters of text that describe the publisher of the content, for example a company name.</p>
	Country of Origin	<p>Select a country name from the list. (Your Avid editing application converts the name to a standard country code in a .stl file.)</p>

Tab	Option	Description
	Editor's Name	Enter up to 32 characters of text in each of these text boxes to record information about the editor and translator for the content. For example, you might enter an e-mail address or telephone number in the Contact Details text boxes.
	Editor's Contact Details	
	Translator's Name	
	Translator's Contact Details	
Custom		Enter up to 576 characters of text in the text box that records any custom information that you want to include with the effect.
Program	Revision Date	Enter dates to track the original creation date and the latest revision date for the content.
	Creation Date	
	Language	Select a language from the list. (Your Avid editing application converts the language name to a standard language code in a .stl file.)
	Original Program Title	Enter up to 32 characters of text in each of these text boxes to record information about the titles of the program and episode.
	Original Episode Title	
Translated Program Title		
	Translated Episode Title	
 <i>The character limits for the information categories in the Contacts, Custom, and Program tabs are imposed by the EBU N19 (.stl) caption file standard.</i>		
Stylesheets		Displays a list of caption parameter stylesheets, and lets you manage and apply stylesheets. For more information see “Working with SubCap Effect Stylesheets” on page 461.
Synchronize		Displays a list of all SubCap effect parameters and information categories and lets you define how changes to these parameters and categories propagate in a sequence. For more information, see “Synchronizing SubCap Effect Parameters and Information” on page 457.

Timecode Burn-In Effect Parameters

Timecode Burn-In parameters control the content and appearance of the timecode displays. **Timecode Burn-In effect parameters are not keyframeable.**

Category	Description
Display 1, Display 2, Display 3	Let you add up to three timecode displays to the video. Click the Enable button for the category to activate the display.
	Each Display category contains Reader and Type menus, and Timecode Display and Appearance subcategories, as described in the following rows of this table.

Category	Description
Reader menu	<p>Selects the basic type of timecode or other information for the display. The following options are available:</p> <ul style="list-style-type: none">TimecodeSource Timecode <p>The timecode of the source clip at the current location. If there are multiple clips on different tracks in the timeline, you can use the Source Track menu to select the clip whose timecode you want to display, as described in the Timecode Display row of this table.</p> <ul style="list-style-type: none">Edgecode (if available for film-originated material)Source Edgecode (if available for film-originated material) <p>The edgecode of the source clip at the current location. If there are multiple clips on different tracks in the timeline, you can use the Source Track Number menu to select the clip whose edgecode you want to display, as described in the Timecode Display row of this table.</p> <ul style="list-style-type: none">FramesSource Clip Name <p>The name of the source clip at the current location. If there are multiple clips on different tracks in the timeline, you can use the Source Track menu to select the clip whose name you want to display, as described in the Timecode Display row of this table.</p> <ul style="list-style-type: none">Sequence NameSource Bin Column, Sequence Bin Column <p>The information from the bin column you select. Select the bin column name you want to use from the Column Name menu that appears below the Display Label and Display Fields buttons. To display a custom, user-defined bin column, select either Custom Property or Enhancement from the Column Name menu, and then type the name of the custom column in the text box that appears below the Column Name menu.</p> <ul style="list-style-type: none">Other Counters <p>Select Other Counters to display a submenu, the Bin Timecode Column. Select this submenu to display auxiliary timecodes and film related options.</p>

Category	Description
Type menu	<p>Selects an option to control how your Avid editing application calculates the timecode to display. These are equivalent to options available in the Tracking Information menus above the monitors (for more information, see “Tracking Format Options” in the Help).</p> <p>Depending on your selection in the Reader menu, options in the Type menu might not be relevant or might result in an unchanged display. For example, if you select Frames in the Reader menu, the Start and Absolute options yield the same display.</p> <p>The following options are available:</p> <ul style="list-style-type: none"> • Current • End • Duration • Mark IN • Mark OUT • I/O • Remaining • Absolute
Display Label	<p>If this option is selected, the display begins with a label identifying the timecode format, for example, Mas TC1 01:00:01:16. If this option is deselected, the display shows only the timecode itself, for example, 01:00:01:16.</p>
Display Fields	<p>If this option is selected, the display shows the field number, for example, 01:00:01:16.2 for field-based media.</p>

Category	Description
Timecode Display	<p>Provides additional controls for selecting the format or source of the information that appears in the timecode displays. The controls vary depending on the selection you make in the Reader menu, as follows:</p> <ul style="list-style-type: none">• If Timecode, Source Timecode, Edgecode, or Source Edgecode is selected in the Reader menu, a Timecode Format menu appears that lets you select the timecode format when multiple timecode formats are available for the material. For more information, see “Displaying Timecodes in a 24p or 25p Project” in the Help.• If Edgecode or Source Edgecode is selected in the Reader menu, a Film Controls subcategory appears, containing a Film Type menu that lets you select the film type. In most circumstances you can use the “default film type” option. However, depending on the information available in your bins and your selection in the Film and 24p Settings dialog box for a film project, you might have more than one ink number format that you can display. For more information, see “Film Shoot Specifications” and “Film and 24P Settings” in the Help.• If Source Timecode, Source Edgecode, or Source Clip Name is selected in the Reader menu, a menu appears that lets you select the track in the Timeline that is the source of the timecode or clip name information. You can select Current Track, which refers to the track the Timecode effect is on, or any other video or audio by its track name, for example, V3.• If Frames is selected in the Reader menu, a Local Frame Count button appears below the Display Label and Display Fields buttons. Select Local Frame Count to display the frame number for the current clip. Deselect Local Frame Count to display the frame number for the sequence.• If Sequence Name is selected in the Reader menu, the Timecode Display category does not contain any controls.

Category	Description
Appearance	<p>Each Display category and the Notes Track category contain an Appearance subcategory. The Appearance subcategory contains the following subcategories and controls:</p> <ul style="list-style-type: none"> • Position — Use the X and Y sliders to set the position of the display’s anchor point within the video frame. You can also position the display directly in the monitor by dragging the anchor point (located at the top left corner of the display). • Font Size — Use the thumbwheel to set the font size used for the display’s text. The font size value is in absolute pixels, based on the font’s metrics. The relative size of the display’s text changes when you switch between SD and HD because HD resolutions have more vertical pixels than SD resolutions. Text that is relatively large and readable in SD becomes considerably smaller if, for example, you switch the project type to an HD format. If you need to switch resolutions and need your timecode display to maintain the same relative size, render the effect. • Text — Use the color controls to set the color of the text (you can use the R, G, and B sliders, or use the Other Options button or the eyedropper to pick a color, as described in “Adjusting a Color Parameter for an Effect” on page 96). Use the Text Opacity slider to set the opacity of the text — values range from 0 (fully transparent) to 1 (fully opaque) in 0.1 increments. Use the Line Weight thumbwheel to control the width of the black outline around text characters (when Use Text Outline is selected), or to add thickness to the text characters (when Use Text Outline is deselected). • Background — Use the color controls to set the color of the rectangular background for the display (you can use the R, G, and B sliders, or use the Other Options button or the eyedropper to pick a color, as described in “Adjusting a Color Parameter for an Effect” on page 96). Use the Border Opacity slider to set the opacity of the rectangular background — values range from 0 (fully transparent) to 1 (fully opaque) in 0.1 increments.
Notes Track	<p>Lets you enter a text annotation in the text box, for example, a comment that you want to display in a review version of a sequence. This category also contains an Appearance subcategory for controlling the look of the notes track, as described in the previous row of this table.</p> <p>The anchor point for the notes track is always visible in the monitor. The display itself appears as soon as you type text in the text box.</p>


Illusion FX Effect Parameters

This section contains reference summaries for the effect parameters that are unique to the Illusion FX effect category.


Border Parameter for Illusion FX Effects

The Border parameter category is available for the following Illusion FX effects: Crystal, FluidBlur, FluidColorMap, FluidMorph, Kaleidoscope, Melt, Particle Blast, Particle Orbit, Particle Wind, Radial Blur, Ripple, Rollup, Shear, Sphere, Swirl, Twist, and Wave.

Use the Left, Right, Top, and Bottom sliders to prevent black edges of the source clip from warping into the effect.




Color Mix Effect Input Parameters




Parameter	Description
Color Level	Sets the amount of color to add. Values range from 0 (no color) to 100 (maximum color).
Color controls	Selects the color. For more information on the parameter controls, see “Color Parameter Controls” on page 604.

Crystal Effect Input Parameters




Parameter	Description
Size	Sets the radius of the polygons in pixels.
Jitter	Sets the randomness of the shape of the polygons. A value of 0 creates regular hexagons — the higher the value, the more random the shapes.
Random Seed	Sets the base number your Avid editing application uses to calculate all random values. Each value results in a different random effect. This parameter is not keyframeable.
Anti-alias	Sets whether or not transformed areas are smoothed. This parameter is not keyframeable.

Film Grain Effect Input Parameters




Parameter	Description
Level	Sets the amount of graininess.
Size	Sets the size of the individual grain elements.
Color	Simulates the slight color and luminance imperfections in film footage caused by the chemical processes used to transfer the negative to the film. The default setting applies a balanced combination of color and luminance imperfections. Higher values add more color imperfections and fewer luminance imperfections. Lower values add more luminance imperfections and fewer color imperfections.
Field Mode	Causes the grain pattern to update every field.
Hilite Grain	Adds grain to the brighter areas of the image.
Shadow Grain	Adds grain to the darker areas of the image.

Flare Effect Input Parameters



Parameter	Description
Brightness	Sets the brightness of the flare. Values range from 0 (no flare) to 100 (maximum brightness).
Size	Sets the diameter of the flare ring.
Width	Sets the distance between the inner and outer edges of the flare ring.
Amount	Sets the amount of distortion to the flare ring (0 is no distortion).
Random Seed	Sets the base number your Avid editing application uses to calculate all random values. Each value results in a different random effect. This parameter is not keyframeable.
X, Y	Sets the center of the flare ring.


FluidBlur Effect Input Parameters



Parameter	Description
Blur Amount	Sets the level of blur for objects that are moving. The amount of blur ramps linearly from 0 to the Blur Amount value as the pixel motion increases from the Lower Motion Threshold value to the Upper Motion Threshold value. The faster an object moves, the more it is blurred.

Parameter	Description
Lower Motion Threshold, Upper Motion Threshold	Your Avid editing application does not blur objects moving less than the Lower Motion Threshold number of pixels between frames or fields or more than the Upper Motion Threshold number of pixels between frames or fields. Your Avid editing application blurs objects whose movement falls between the two values by the Blur Amount.
Trail	Instructs your Avid editing application to add an amount from the previous frame's (or field's) blur to the current frame. This produces smooth movement, especially as objects move along curved paths.
Sharpen Leading Edge	Lets you keep the front edge of an object crisp and clear while other portions are blurred.
Progressive Source	If your sources are progressive, enabling Progressive Source produces smoother results. Use this option if your footage was captured or converted to progressive footage (that is, not interlaced). This option has no effect in 24p projects because your Avid editing application assumes that you are using progressive footage.

FluidColorMap Effect Input Parameters




Parameter	Description
Min Motion Threshold, Max Motion Threshold	<p>Objects moving less than the Min Motion Threshold number of pixels between frames (or fields) have the minimum saturation and luminance. Objects moving more than the Max Motion Threshold number of pixels between frames (or fields) have the maximum saturation and luminance. The amount of saturation depends on the Constant Saturation value.</p> <p>Brightness and color saturation increase as the motion of an object increases from the minimum threshold value to the maximum threshold value. The faster an object moves, the brighter and more color saturated it becomes.</p>

Parameter	Description
Constant Saturation	Controls how much the Min Motion Threshold and Max Motion Threshold values affect the color saturation (these values always control the luminance of the image). When the Constant Saturation value is low, the Min Motion Threshold and Max Motion Threshold values strongly affect saturation as well as luminance. When the Constant Saturation value is high, the values affect saturation to a lesser degree. If you set Constant Saturation to the maximum value, motion has no effect on color saturation.
Progressive Source	If your sources are progressive, enabling Progressive Source produces smoother results. Use this option if your footage was captured or converted to progressive footage (that is, not interlaced). This option has no effect in 24p projects because your Avid editing application assumes that you are using progressive footage.


FluidMorph Effect Source and Input Parameters

Source Menu




Option	Description
Still->Still	Your Avid editing application takes snapshots of the first frame of outgoing video and the last frame of incoming video and creates an output that is a morph of the two images.
Stream->Stream	Your application creates the output by morphing the two clips, frame by frame.
Stream->Still	Your application creates the output by morphing each frame of the outgoing video with the last frame of incoming video.
Still->Stream	Your application creates the output by morphing the first frame of the outgoing video with each frame of the incoming video.

Input Parameters



Parameter	Description
Feature Match	<p>When Feature Match is selected, your Avid editing application attempts to match features between the two clips when it creates the morph for each frame.</p> <p>When Feature Match is deselected, your Avid editing application creates the morph based on the brightness of the two images.</p>
Swap Sources	Specifies whether to apply the effect to incoming or outgoing video. This parameter is not keyframeable.
Progressive Source	Use this option if your footage was captured or converted to progressive footage (that is, not interlaced). If your sources are progressive, enabling Progressive Source produces smoother results. This option has no effect in 24p projects because your Avid editing application assumes that you are using progressive footage.


Iris Effect Input Parameters



Parameter	Description
Amount	Sets the proportion of each clip to be displayed. Values range from 0 (displays all of the foreground clip) to 100 (displays all of the background clip). Typical keyframing has a value of 0 at the first keyframe and 100 at the last keyframe.
Softness	Sets the size of the area over which the pixels are faded from the foreground clip to the background clip.
X, Y	Sets the center of the iris wipe.
Swap Sources	Specifies whether to apply the effect to incoming or outgoing video. This parameter is not keyframeable.

Kaleidoscope Effect Input, Center, and Offset Parameters

Input Parameters



Parameter	Description
Symmetry	Sets the number of mirrors.
Angle	Sets the angle of the mirrors.
Scale	Sets the scale of the image.

Center Parameters



Parameter	Description
X	Sets the horizontal location of the center of the mirrors.
Y	Sets the vertical location of the center of the mirrors.

You can also set the center of the mirror by clicking and dragging the crosshair marker within the image.

Offset Parameters




Parameter	Description
X, Y	Use the X and Y sliders to set the offset from the original source area. You can also click the corresponding marker, and drag within the image.

Parameter	Description
Anti-alias	Sets whether or not transformed areas are smoothed. This parameter is not keyframeable.

Lightning Effect Generation, Core, and Glow Parameters

Generation Parameters




Parameter	Description
Amount	Sets the proportion of the lightning to be displayed. Values range from 0 (no lightning) to 100 (complete lightning bolt). Typical keyframing has a value of 0 at the first keyframe and 100 at the last keyframe.
Branch Probability	Sets the likelihood that the lightning has few or many branches. A value of 0 displays no branches. The higher the value, the more branches are likely.
Random Seed	Sets the base number upon which all random values are calculated. Each value results in a different random effect. This parameter is not keyframeable.
Render Mode menu	Click to set the quality of the rendered lightning: <ul style="list-style-type: none">• Quick — use to view just the motion of the lightning.• Standard — use to view the full lightning without anti-aliasing while editing the animation.• Anti-aliased — use to ensure that fine branches do not break up.

Core Parameters




Parameter	Description
Width	Sets the radius of the core in pixels.
Color controls	Selects the color for the core of the lightning. For more information on the parameter controls, see “Color Parameter Controls” on page 604 .

Glow Parameters



Parameter	Description
Width	Sets the radius of the glow in pixels.
Color controls	Selects the color for the glow surrounding the lightning. For more information on the parameter controls, see “Color Parameter Controls” on page 604 .


Melt Effect Input Parameters



Parameter	Description
Bleed	Changes the melt image to a more dramatic effect.
Melt Up	Reverses the direction of the melt.
Amount	Sets the progression of the effect. A value of 0 has no effect, and all of the foreground clip shows. The higher the value, the more of the foreground clip melts away to reveal the background clip. Typical keyframing has a value of 0 at the first keyframe and 100 at the last keyframe.


Parameter	Description
Strength	Sets the strength of the distortion. The higher the value, the greater the distortion.
Random Seed	Sets the base number upon which all random values are calculated. Each value results in a different random effect. This parameter is not keyframeable.
Anti-alias	Sets whether or not transformed areas are smoothed. This parameter is not keyframeable.
Swap Sources	Specifies whether to apply the effect to incoming or outgoing video. This parameter is not keyframeable.

Motion Blur Effect Input Parameters











Parameter	Description
Amount	Sets the length of the blur.
Direction	Sets the direction of the blur. A value of 0 degrees is 3 o'clock. Positive values move counterclockwise.

Pagecurl Effect Input Parameters




Parameter	Description
Turn Left	Controls the direction of the page curl. For examples, see the following table. This parameter is not keyframeable.
Reverse	When Reverse is selected, incoming video peels on. When Reverse is deselected, outgoing video peels off. For examples, see the following table. This parameter is not keyframeable.
Swap Sources	Specifies whether to apply the effect to incoming or outgoing video. For examples, see the following table. This parameter is not keyframeable.

The following table describes the possible Pagecurl parameter combinations and shows an example of the results.


Parameter Values	Result	Parameter Values	Result
Turn Left: Off Reverse: Off Swap Sources: Off	 Outgoing video peels off	Turn Left: Off Reverse: Off Swap Sources: On	 Incoming video peels off
Turn Left: On Reverse: Off Swap Sources: Off	 Outgoing video peels off	Turn Left: On Reverse: Off Swap Sources: On	 Incoming video peels off
Turn Left: Off Reverse: On Swap Sources: Off	 Incoming video peels on	Turn Left: Off Reverse: On Swap Sources: On	 Outgoing video peels on
Turn Left: On Reverse: On Swap Sources: Off	 Incoming video peels on	Turn Left: On Reverse: On Swap Sources: On	 Outgoing video peels on

Particle Blast Effect Input Parameters



Parameter	Description
Amount	Sets the progression of the effect. The larger the difference in the Amount value between keyframes, the faster the effect happens.
Size	Sets the radius of the particles.
Spacing	Sets the space between the center of the original position of the particles. This parameter is not keyframeable.
Front Speed	Controls whether the particles in the center of the blast start to move before the particles at the outside edges.
Front Randomness	Allows particles nearest the center to move at different speeds.
Speed	Sets the speed at which particles move apart.
Speed Randomness	Allows particles to move at different speeds to give a more natural effect.
Acceleration	Controls how quickly a particle reaches the full speed of the blast. The higher the value, the more quickly the particle reaches full speed.
Bumpiness	Adds a shadow to the edge of the particles.
Swap Sources	Specifies whether to apply the effect to incoming or outgoing video. This parameter is not keyframeable.

Particle Orbit Effect Input Parameters




Parameter	Description
Amount	Sets the progression of the effect. The larger the difference in the Amount value between keyframes, the faster the effect happens.
Size	Sets the radius of the particles.
Spacing	Sets the space between the center of the original position of the particles. This parameter is not keyframeable.
Bumpiness	Adds a shadow to the edge of the particles.
Speed	Sets the speed at which particles orbit.
Swap Sources	Specifies whether to apply the effect to incoming or outgoing video. This parameter is not keyframeable.

Particle Orbit Effect Parameter Example


When you use this effect as a transition effect, Avid recommends the following parameter changes:

- At the first keyframe, set initial Amount and Bumpiness values to 0 so the transition begins smoothly.
- Add a keyframe to increase the Amount value during the transition. For example, change the value from 0 to 40.
- At the same keyframe, set the Size value. For example, reduce Size from 10 to 0.
- (Option) At the same keyframe, increase Bumpiness. Increasing Bumpiness gives additional texture to the particles. For example, change the value from 0 to 100.

The following illustration shows four frames from a transition effect using the values in the example.



Particle Wind Effect Input Parameters




Parameter	Description
Amount	Sets the progression of the effect. The larger the difference in the Amount value between keyframes, the faster the effect happens.
Size	Sets the radius of the particles.
Spacing	Sets the space between the center of the original position of the particles. This parameter is not keyframeable.
Front Speed	Controls whether the particles near the front edge (where the wind first hits) start to move before the particles at the outside edge.

Parameter	Description
Front Randomness	Allows particles nearest the front to move at different speeds.
Speed	Sets the wind speed.
Speed Randomness	Allows particles anywhere within the effect to move at different speeds, giving a more natural effect.
Acceleration	Controls how quickly a particle reaches the full speed of the wind. The higher the value, the more quickly the particle reaches full speed.
Angle	Sets the source direction of the wind. A value of 0 degrees is 3 o'clock. Positive values move counterclockwise.
Bumpiness	Adds a shadow to the edge of the particles.
Swap Sources	Specifies whether to apply the effect to incoming or outgoing video. This parameter is not keyframeable.


Pattern Generator Effect Background, Number, and Circle Parameters

Background Parameters



Parameter	Description
Pattern Type menu	Sets the pattern to be used: <ul style="list-style-type: none">• Solid color• EBU bars (75%)• Color bars (75%)• Color bars (100%)• EIA bars• SMPTE bars• Color ramps• Cross ramp• Grid <p>If you select the Grid option, the background color is black if Base Color has 50% or greater luminance, or white if Base Color has less than 50% luminance.</p>
Axis menu	Determines whether color bars are drawn horizontally (X axis) or vertically (Y axis).
Color controls	Sets the color of the clip (when the Pattern Type is set to Solid Color) or of the grid lines (when the Pattern Type is set to Grid). The background color of the grid is black if Base Color has 50% or greater luminance, or white if Base Color has less than 50% luminance. For more information on the parameter controls, see “Color Parameter Controls” on page 604 .


Number Parameters



Parameter	Description
Number Offset	Sets the offset of the number from the current frame number.


Parameter	Description
Opacity	Sets the opacity of the number.
Text Size	Sets the size of the number.
Stroke Width	Sets the width of the number stroke.
Color controls	Sets the color of the number. For more information on the parameter controls, see “Color Parameter Controls” on page 604 .
Position	Sets the horizontal (X) and vertical (Y) position of the center of the number.

Circle Parameters




Parameter	Description
Size	Sets the radius of the circle.
Width	Sets the width of the circle outline.
Opacity	Sets the opacity of the circle.
Color controls	Sets the color of the circle. For more information on the parameter controls, see “Color Parameter Controls” on page 604 .
Position	Sets the horizontal (X) and vertical (Y) position of the circle.


Pinch Effect Input Parameters



Parameter	Description
Amount	Sets the progression of the effect. The larger the difference in the Amount value between keyframes, the faster the effect happens.
Size	Sets the diameter of the affected area.
Position	Sets the horizontal (X) and vertical (Y) center of the effect.
Anti-alias	Sets whether or not transformed areas are smoothed. This parameter is not keyframeable.


Radial Blur Effect Input Parameters



Parameter	Description
Zoom	Sets the scaling of the blur. Smaller values zoom in and larger values zoom out.
Angle	Sets the rotation of the blur.  <i>This effect can take a long time to render. The greater the angle, the longer the rendering takes.</i>
Position	Sets the horizontal (X) and vertical (Y) center of the effect.

Parameter	Description
Render Mode menu	Determines whether just the center marker shows, or how the effect is rendered. Locate shows the center marker — use this option while setting up the center. <ul style="list-style-type: none">• Locate• Render Low Quality• Render Medium Quality• Render High Quality


Random Blend Effect Input Parameters



Parameter	Description
Amount	Sets the amount of blend.
Random Scale	Sets the amount of randomness. This allows your Avid editing application to blend different portions of the image at different rates.
Swap Sources	Specifies whether to apply the effect to incoming or outgoing video. This parameter is not keyframeable.

Ripple Effect Motion, Generation, and Illumination Parameters


Motion Parameters



Parameter	Description
Amount	Sets the progression of the effect. The larger the difference in the time value between keyframes, the faster the effect happens.


Parameter	Description
Wave Speed	Sets how fast the waves move.
Ripple Spread	Sets the width of the ripple from the inner ring to the outer ring.
Reflections	When Reflections is selected, waves reflect off the edges of the image, as though hitting a wall.

Generation Parameters




Parameter	Description
Strength	Sets the height of the waves.
Length	Sets the distance between the wave peaks.
Number of Ripples	Sets the number of ripples.
Random Seed	Sets the base number upon which all random values are calculated. Each value results in a different random effect. This parameter is not keyframeable.
Anti-alias	Sets whether or not transformed areas are smoothed. This parameter is not keyframeable.

Illumination Parameters



Parameter	Description
Color controls	Sets the color of the light. For more information on the parameter controls, see “Color Parameter Controls” on page 604.
Angle	Sets the source direction of the light. A value of 0 degrees is 3 o’clock. Positive values move counterclockwise.

Rollup Effect Input Parameters



Parameter	Description
Amount	Sets the proportion of each clip that displays. Values range from 0 (displays all of the foreground clip) to 100 (displays all of the background clip). Typical keyframing has a value of 0 at the first keyframe and 100 at the last keyframe.
Curl Size	Sets the size of the roll.
Direction	Sets the direction of the rollup. A value of 0 degrees is 3 o’clock. Positive values move counterclockwise.
Anti-alias	Sets whether or not transformed areas are smoothed. This parameter is not keyframeable.
Swap Sources	Specifies whether to apply the effect to incoming or outgoing video. This parameter is not keyframeable.


Shear Effect Input Parameters



Parameter	Description
Amount	Sets the proportion of each clip that displays. Values range from 0 (displays all of the foreground clip) to 100 (displays all of the background clip). Typical keyframing has a value of 0 at the first keyframe and 100 at the last keyframe.
Min Width, Max Width	Sets the minimum and maximum possible width of the slats.
Width Randomness	Controls the variety of sizes of slats. Your Avid editing application creates slats of various widths in between the minimum and maximum width value.
Spread	Sets the randomness of when individual strips start moving. A value of 0 causes all strips to start at the same time.
Angle	Sets the direction of the effect. A value of 0 degrees is 3 o'clock. Positive values move counterclockwise.
Random Seed	Sets the base number upon which all random values are calculated. Each value results in a different random effect. This parameter is not keyframeable.
Anti-alias	Sets whether or not transformed areas are smoothed. This parameter is not keyframeable.
Swap Sources	Specifies whether to apply the effect to incoming or outgoing video. This parameter is not keyframeable.


Sparkler Effect Generation, Movement, Core, and Glow Parameters

Generation Parameters




Parameter	Description
Birth Rate	Sets the number of sparks generated every frame.
Lifetime	Sets (in frames) how long each spark lives.
X, Y	Sets the center of the effect.
Link Speed	If you keyframe the center of the effect, Link Speed causes your Avid editing application to add the movement of the center to the movement of the sparks.
Length	Sets the cumulative exposure of the sparks. For example, a value of 3 produces an image that looks as though you left a virtual camera shutter open for the last three frames.
Speed Bias X, Speed Bias Y	Sets the bias to the direction of the sparks. Your Avid editing application adds these values to the initial random directions.

Movement Parameters



Parameter	Description
Speed	Sets the value around which the speed of the sparks is randomized.
Gravity	Sets the attraction of the sparks downward or upward. The greater the value, the more the sparks are attracted downward.
Air Resistance	Sets the air resistance. The higher the value, the less the sparks radiate outward.
Wind X, Wind Y	Sets a virtual directional wind, which affects the trajectory of the sparks. The Air Resistance value must be greater than 0 for Wind to have an effect.
Turbulence	Adds randomness to the movement of the sparks.

Core and Glow Parameters



Parameter	Description
Core Radius	Sets the radius of the core in pixels.
Glow Radius	Sets the radius of the glow in pixels.
Color controls	Sets the color of the core or glow. For more information on the parameter controls, see “Color Parameter Controls” on page 604 .

Sphere Effect Input Parameters



Parameter	Description
Amount	Sets the scale of the distortion. Negative values distort the image inward. Positive values distort it outward.

Parameter	Description
Size	Sets the diameter of the circle as a normalized proportion of the vertical size of the image.
X, Y	Sets the center of the effect.
Anti-alias	Sets whether or not transformed areas are smoothed. This parameter is not keyframeable.

Swirl Effect Input Parameters



Parameter	Description
Amount	Sets the scale of swirl. Negative values swirl the image counterclockwise. Positive values swirl it clockwise.
Size	Sets the diameter of the circle as a normalized proportion of the vertical size of the image.
X, Y	Sets the center of the effect.
Anti-alias	Sets whether or not transformed areas are smoothed. This parameter is not keyframeable.


Twist Effect Input Parameters



Parameter	Description
Amount	Sets the amount of twist.
X, Y	Sets the center of the effect.
Axis menu	Click to set whether the twist applies horizontally (X axis) or vertically (Y axis).

Parameter	Description
Anti-alias	Sets whether or not transformed areas are smoothed. This parameter is not keyframeable.

Wave Effect Input Parameters



Parameter	Description
Amount	Sets the scale of swirl. Negative values swirl the image counterclockwise. Positive values swirl it clockwise.
Minimum Size, Maximum Size	Sets the minimum wavelength and the maximum wavelength.
Horizontal Factor, Vertical Factor	The amount of horizontal distortion and vertical distortion. Values range from 0 (no distortion) to 100 (maximum distortion).
Number of Waves	Sets the number of waves. Wave effects are superimposed upon each other.
Speed	Sets the progress of the effect.
Random Seed	Sets the base number upon which all random values are calculated. Each value results in a different random effect. This parameter is not keyframeable.
Anti-alias	Sets whether or not transformed areas are smoothed. This parameter is not keyframeable.

Image Effect Parameters

This section contains reference summaries for the effect parameters that are unique to the Image effect category.

Avid Pan & Zoom Effect Parameters

Other Options Button


The Other Options button opens a file selection dialog box that lets you specify the image file for the Pan & Zoom effect. For more information, see [“Using Avid Pan & Zoom” on page 293](#). **This parameter is not keyframeable.**



If you move an image file after you reference it in the effect, the image is no longer accessible to the effect. The next time you open the effect, a dialog box opens that lets you locate the file.

Display Fast Menu


The Display Fast menu lets you choose how you view the image as you work on it. For more information, see [“Controlling Your View of an Avid Pan & Zoom Image” on page 296](#). **This parameter is not keyframeable.**



Option	Description
Source	Shows you the entire image scaled to fit inside the Effect Preview monitor. Use Source as you draft the effect.
Target	Shows you the results of your pan and zoom settings. Use Target for previewing your moves.

Options Parameter

Show Action Safe selects or deselects the display of the safe action area. When Show Action Safe is selected, the safe action area appears as a rectangle superimposed on the field of view. For more information, see [“Controlling Your View of an Avid Pan & Zoom Image” on page 296](#). **This parameter is not keyframeable.**



Size Parameter

The Zoom Factor slider in the Size category controls how far you zoom into or out from the source image. Values range from 0.1 to 20. At 0.1, your Avid editing application scales down the image to one-tenth the size of the original. At 1, your Avid editing application applies no magnification to the source image. At 20, your Avid editing application scales up the image to 20 times the size of the original. The larger the Zoom Factor, the smaller the field of view rectangle appears when you use Source mode. For more information, see [“Adjusting the Field of View for an Avid Pan & Zoom Image” on page 296](#).




Position Parameters

You control pan either by using the X and Y Position parameters or by dragging the field of view across the source image. The Position parameters refer to the center of the field of view. A Position of 0, 0 centers the field of view over the center of the image. For more information, see [“Adjusting the Field of View for an Avid Pan & Zoom Image” on page 296](#).



Velocity Parameters

The Avid Pan & Zoom effect uses Velocity In and Velocity Out at each keyframe to modify apparent camera speed as it pans across the image between keyframes. It modifies changes in the Zoom Factor setting in the same way. For more information, see [“Modifying Apparent Camera Speed for an Avid Pan & Zoom Effect” on page 298](#).




Parameter	Description
Velocity In	<p>Controls the rate of movement from the selected keyframe to the midpoint between the selected keyframe and the next keyframe (the first half of the time between keyframes).</p> <ul style="list-style-type: none">Linear — Makes no modification to the pan and zoom movement. Apparent camera movement begins immediately with no ease in.Constant — Does not use the keyframe’s Position parameters to calculate the speed of the effect, but uses the keyframe’s Position parameters to determine the path of the effect (the pan) and the keyframe’s Zoom Factor to calculate the zoom between the selected keyframe and the next keyframe. <p>When you select Constant for Velocity In, your Avid editing application automatically selects Constant for Velocity Out.</p> <ul style="list-style-type: none">Ease In — Modifies movement by providing a slight acceleration at the beginning of the time between the selected keyframe and the next keyframe.
Velocity Out	<p>Controls the rate of movement from the midpoint between the selected keyframe and the next keyframe to the next keyframe (the second half of the time between keyframes).</p> <ul style="list-style-type: none">Linear — Makes no modification to the pan and zoom movement . Parameters change at a constant rate up to the next keyframe.Ease Out — Modifies the pan and zoom movement by providing a slight deceleration into the next keyframe.Constant — Does not use the keyframe’s Position parameters to calculate the speed of the effect, but uses the keyframe’s Position parameters to determine the path of the effect (the pan) and the keyframe’s Zoom Factor to calculate the zoom between the selected keyframe and the next keyframe. <p>When you select Constant for Velocity In, your Avid editing application automatically selects Constant for Velocity Out.</p> <ul style="list-style-type: none">Hold — At the midpoint between the selected keyframe and the next keyframe, the image freezes (pan and zoom movement stop). Movement resumes at the next keyframe. The effect disregards the Velocity In value of the next keyframe. If you have Background set to Video, the background continues to update.

Path Fast Menu


The Path Fast menu selects the interpolation option for Position parameter changes at keyframes. For more information, see [“Controlling Path Changes at Keyframes for an Avid Pan & Zoom Effect” on page 300](#). **This parameter is not keyframeable.**



Option	Description
Linear	Creates straight-line changes from one keyframe to the next.
Spline	Smooths out changes at keyframes to create a more natural movement. A Spline path is smooth through all points. If you move a point the effect recalculates the entire path. <div> <i>If you combine a Spline path with Constant velocity, when you move a keyframe, the path recalculation might result in a change to the velocity of the effect. For more information, see “Velocity Parameters” on page 653.</i></div>

Filtering Fast Menu

Filtering controls the method by which the effect renders, which determines the quality of the rendered result. The options let you trade off the clarity or sharpness of the resized image and the speed at which the effect renders. **This parameter is not keyframeable.**




The following table ranks the Filtering Fast menu options from fastest render and lowest quality image to slowest render and highest quality image. For more information, see [“Setting a Rendering Option for an Avid Pan & Zoom Effect” on page 302.](#)

Option	Description
Real-Time	Renders most quickly but creates a draft-quality image. Your Avid editing application always uses this option during uncompressed play.
Triangle	Creates fairly soft images.
Quadratic	Creates slightly sharper images than Triangle filtering.
Cubic	Creates sharper images than Quadratic filtering although still fairly soft.
B-Spline Catmull	Creates results similar to Cubic filtering when you zoom out (shrink the image) by a large amount. Creates a sharper image than Cubic filtering when you: <ul style="list-style-type: none">Stay close to the original size of the image (little zooming in or zooming out).Zoom in past the source image resolution.
Gaussian	Creates an image that is relatively soft but sharper than B-Spline Catmull.
Avid High Qual	Creates sharp images when you zoom out.

Option	Description
Avid Ultra Qual	Creates extremely sharp images when you zoom out, but has the longest rendering time.

Background Parameters


These parameters are not keyframeable.



Parameter	Description
Background Fast Menu button	Click to select what the effect uses outside the field of view if your image does not fill the entire screen. Color — Lets you select a color using the color controls. Video — Uses the video from the segment upon which you placed the Avid Pan & Zoom effect.
Color controls	Selects a background color. For more information on the parameter controls, see “Color Parameter Controls” on page 604 .

Advanced Parameters

The Advanced parameter category provides controls for the rare case in which an image for Avid Pan & Zoom comes from a video source. **These parameters are not keyframeable.**



Parameter	Description
Source Has Square Pixels	When this option is selected (the default), the Avid Pan & Zoom effect produces rectangular pixels. When this option is deselected, your Avid editing application makes no changes to pixel shape. For more information, see “Adjusting for Source Image Pixel Aspect Ratio and Color Levels in an Avid Pan & Zoom Effect” on page 304 .

Parameter	Description
Levels	<p>Controls how the effect treats the color levels in the image.</p> <ul style="list-style-type: none">• RGB — Use this option (the default) for images with a black level of 0 and a white level of 255. Most images you import (except those from a video source) use these values. Your Avid editing application maps colors in the source image to video black and white levels, which are 16 and 235 respectively.• 601 — Use this option for images from a video source, where the black level is 16 and the white level is 235. 601 refers to the ITU-R-601 standard for video black and white levels. When this option is selected, your Avid editing application makes no adjustment to color levels.

Cache Fast Menu

The Cache Fast menu gives you control over the amount of memory your Avid editing application uses to store your images for playback. (A full resolution image is always used for rendering.) **This parameter is not keyframeable.**



Option or Action	Description
Video Resolution	Stores the resized source image at 720 x 480 pixels, using about 1 MB per image. Use this option if you have many images in your sequence and you need to limit how much memory they occupy.
Image Resolution	Stores the resized source image at its original resolution. The amount of memory your Avid editing application uses varies with the size of the image.
Multi-Resolution	Stores eight versions of the image at the original resolution and various lower resolutions. Uses about twice the memory of Image Resolution.
Free Current Cache	Frees all memory used for image storage and then reverts to Image Resolution. Select this option to free up memory after you render the clip.
Cache All	Acts as a global switch that sets the same Cache parameter for all instances of the effect in a sequence.
Free All Caches	Frees the caches for all instances of the plug-in in that sequence.

Render Mode Parameter

If you are working in a progressive project, click the Progressive check box in the Render Mode parameter category. Selecting this option creates a smoother animation when using progressive frames. For more information, see [“Setting a Rendering Option for an Avid Pan & Zoom Effect” on page 302](#). **This parameter is not keyframeable.**

Blur Effect Blur Parameters

Blur lets you blur a selected area with horizontal and vertical controls. This is useful for distorting or disguising part of an image. You can also create this effect using the Paint Effect by selecting Blur mode in the Mode parameter category. For more information, see [“Paint Effect Mode Parameters” on page 663](#).





Parameter	Description
Opac. (opacity)	Controls the relative strength of the blur. Values range from 100 (maximum blur) to 0 (minimum blur).
Blur Visible	Lets you add a keyframe and have the blurred area suddenly “pop” onto the screen at the position marked by the keyframe. You must have at least three keyframes to create this effect.
Hor (horizontal) and Vert (vertical)	Defines the horizontal and vertical dimensions of the blurred area.

Color Effect Parameters

Luma Adjust Parameters


Luma Adjust lets you manipulate the brightness and contrast of the image.





Parameter	Description
Bright (brightness)	Changes the brightness of the image. Values range from -100 to +100, where 0 indicates no change, -100 darkens the image, and +100 brightens the image. <div></div> <div>Left to right: original image (Brightness=0), adjustment to Brightness -50, adjustment to Brightness +50</div>
Cont (contrast)	Controls the contrast of light and dark areas in the image. Values range from -100 to +100, where 0 indicates no change, -100 minimizes contrast, and +100 maximizes contrast. <div></div> <div>Left to right: original image (Contrast=0), adjustment to Contrast -50, adjustment to Contrast +50</div>
Invert	Reverses the image's brightness, such that the brightest parts become the darkest and the darkest parts become the lightest.

Luma Range Parameters


Luma Range parameters let you adjust the range of brightness from black to white.



Parameter	Description
Fast Menu button	<p>Selects values for mapping video to alpha ranges.</p> <ul style="list-style-type: none">16 to 235 — This option is the default for video images.0 to 255 — This option lets you map normal video to alpha ranges. This is useful if you want to expand a high-contrast image to the full dynamic range. For example, use this value when you want to convert video to alpha for Matte Key effects. <p> <i>When you change the Luma Range to 0 to 255, your Avid editing application attempts to go from 0 to 255 but the Low Clip and High Clip values in the Luma Clip parameter category clip these values. If you want to “open up” the image to the full dynamic range, you need to change the Low Clip value to 0 and the High Clip value to 255.</i></p>
W Point (white point)	<p>Lets you set the white point in the image. All pixels with that value become white, and all pixels with higher values are clipped to white. The default is 235 (the broadcast value for white).</p>
B Point (black point)	<p>Lets you set the black point in the image. All pixels with that value become black, and all pixels with lower values are clipped to black. For example, you could use the eyedropper to select a shadow on the floor and change it from gray to black, clipping everything below that shade to black. The default is 16 (the broadcast value for black).</p> <p> <i>Black point control does not change the Black setup level. To adjust the Black setup level, use the Video Output tool. For more information, see “Basic Video Output Calibration” in the Help.</i></p>
Gamma	<p>Lets you adjust the midtones in an image without affecting the extreme white or black values. If you lower the value you darken midtones and bring the image closer to black. If you raise the value you lighten the midtones and bring the image closer to white.</p> <p>For example, a person shot in front of a window in daylight might be very dark, almost in silhouette. You can use gamma correction to increase the midtones without changing the blacks or whites. Values range from –100 to +100 with 0 being no change.</p> <p>The W Point, B Point, and Luma Clip sliders control the number of shades of gray in an image. The Gamma point moves the distribution of the shades closer to black (negative values) or closer to white (positive values).</p>

Luma Clip Parameters

Luma Clip parameters let you determine the levels at which your Avid editing application limits the brightness or darkness in the image.



Parameter	Description
High	Clips brightness values. No pixel in the image can be brighter than the High value. The default is 235 (the broadcast value for white).
Low	Clips darkness values. No pixel in the image can be darker than the Low value. The default is 16 (the broadcast value for black). You do not normally adjust these value when preparing video for broadcast. They let you adjust the brightness and contrast (using other controls in the Color Effect) while still maintaining legal broadcast values for black and white.

Chroma Adjust Parameters

Chroma Adjust parameters let you alter the hue and saturation levels of the image.






Parameter	Description
Hue	<p>Causes all hues in the image to rotate around the color spectrum. Values are measured as degrees on a color wheel from -180 to +180, where 0 does not change the hue. For example, a value of -20 makes skin tones look more green, while a values of +20 makes skin tones look more red.</p> <p>The value range for this parameter is reversed in some previous versions of Avid DNA-based editing applications, for example, Avid Media Composer Adrenaline. In those versions, a value of -20 makes skin tones look more red, while a value of +20 makes skin tones look more green. The current direction of rotation matches that in older Avid Meridien systems and in all Avid Symphony systems.</p> <p>You can use a console command to reverse the range and match the behavior of a previous version of your Avid editing application that uses the opposite range. For example, if you open a sequence created in a previous version, enter ChromaHueReverse in the Console so that any color adjustment using the Hue parameter matches that created by the original setting. To return to the default setting, type the command again.</p> <p>If the command is enabled, the following message appears in the console when you start your Avid editing application: Reversing Software Color Effect Chroma Adjust Hue is enabled.</p>
Sat (saturation)	Varies the saturation of all colors in the image. Values range from -100 to +100, where -100 removes all saturation (the image displays as grayscale) and +100 maximizes saturation. Zero is the default.

Parameter	Description
Invert	Reverses the colors in both Hue and Saturation so that all colors display as their complement.

Color Style Parameters

The Color Style parameters let you create posterized or solarized looks for the image.



Parameter	Description
Post (posterization)	Posterization lets you limit the number of colors in the image by controlling the number of luminance steps that display. This gives the image a graphic appearance. Values range from 0 to 25, where 0 displays all colors and 25 displays the least number of colors. <div>Left to right: original image , adjustment to Posterization 10, adjustment to Posterization 20</div>
Solar (solarization)	Solarization lets you make the lightest pixels in the image dark to achieve a partial inversion of the luminance. The value defines a threshold, and your Avid editing application inverts values above the threshold. Values range from 0 to 255, where 0 is normal luminance and 255 inverts all luminance values in the image. Values of 0 to 127 display the lightest pixels in the image as dark. Values of 128 to 255 display the lightest pixels as dark and the darkest pixels as light, which gives the appearance of a film negative. <div>Left to right: original image , adjustment to Solarization 100, adjustment to Solarization 200</div>

Color Gain Parameters

The Color Gain parameters allow individual control of color gain for each of the three color components: red, green, and blue. Values range from 0 to 200, where 100 leaves the color unchanged, values lower than 100 increase the amount of the color, and values higher than 100 increase the amount of the color.



Mosaic Effect Mosaic Parameters

Mosaic lets you create a tiled effect for a selected area with horizontal and vertical controls. This is useful for distorting or disguising part of an image. You can also create this effect using the Paint Effect by selecting Mosaic mode in the Mode parameter category. For more information, see [“Paint Effect Mode Parameters” on page 663](#).



Parameter	Description
Opac. (opacity)	Controls the relative strength of the effect. Values range from 0 (least amount of distortion) to 100 (greatest amount of distortion).
Mosaic Visible	Lets you add a keyframe and have the distorted area suddenly “pop” onto the screen at the position marked by the keyframe. You must have at least three keyframes to create this effect.
Hor (horizontal) and Vert (vertical)	Defines the horizontal and vertical dimensions of the distorted area.

Paint Effect Mode Parameters

Mode parameters and options affect the overall nature of the Intraframe editing you perform using the Paint Effect. **This parameter is not keyframeable.**




A Mode parameter is also available in FluidMotion Edit and is described in [“FluidMotion Edit Parameters for Timewarp Effects” on page 698](#).




Parameter	Description
Fast menu	Provides different mode options for Intraframe editing. For information about the available modes, see “Paint Effect Modes” on page 664 .
Opac. (opacity)	Sets the transparency level of a painted object created with the Paint Effect. Values range from 0 (makes a painted object transparent) to 100 (makes an object opaque).
Object Visible	Lets you add a keyframe to a segment or transition and have a painted object or matte suddenly “pop” onto the screen at the position marked by the keyframe. You must have at least three keyframes to create this effect.
Hor (horizontal), Vert (vertical)	These parameters are available for the Clone, Scratch Removal, Mosaic, Blur, and Unsharp Mask modes. When you use one of these parameters with the Clone and Scratch Removal modes, it controls the horizontal or vertical position of the painted object in the frame relative to its original position. When you use one of these parameters with the Mosaic, Blur, and Unsharp Mask modes, it controls the extent of the tiling, blurring, or sharpening effect in the horizontal or vertical direction.
Amt (amount)	This parameter is available for the Darken and Lighten modes. It controls the extent of the darkening or lightening effect.
Angle	This parameter is available for the Gradient and Emboss modes. It controls the direction of the gradient or the extrusion effect.
Frame/Field	Controls which frame or field is the source for clean replacement material when you are working in Scratch Removal mode. For more information, see “Scratch Removal Effect Scratch Parameters” on page 674 .
Offset Fast menu	Defines the position from which the Frame or Field parameter is measured when you are working in Scratch Removal mode. For more information, see “Scratch Removal Effect Scratch Parameters” on page 674 .

Paint Effect Modes

The Paint Effect provides modes that you can use to paint with a variety of styles. When you click a painting tool for the first time, the default setting is Solid mode, which enables you to paint an opaque object on the video background with a brush stroke.

The illustrations in the following table show the same image in every case. This enables you to compare the different modes easily but does not necessarily illustrate the most common use of each mode.

Mode	Description
Solid	Applies paint as a solid color superimposed on the video background.  Solid mode with Opacity set to 75%
Erase	Removes paint from a frame. (Inverts the key in an AniMatte effect.)  A rectangular object in Erase mode that removes paint from the oval object beneath it
Outline	Creates an outline that is useful for tracing images in a frame.
Clone	Duplicates an area from a frame and applies it to another area of the frame.  An oval object in Clone mode that has been moved from higher in the image, taking an area of the upper part of the image with it

Mode	Description
Colorize	Tints the selected area using the value in the Color parameter category. 
Hue	Changes the hue in a selected area using the value of the Hue slider in the Color parameter category without affecting the saturation and luminance levels. 
Saturation	Changes the saturation in a selected area using the value of the Sat slider in the Color parameter category without affecting the luminance levels and the hue. 

Mode	Description
------	-------------

Luminance Changes the luminance in a selected area using the value of the Lum slider in the Color parameter category without affecting the saturation levels and hue.



Darken Only Reduces the luminance levels in a selected area only if the result would be darker than the background color.






Light areas are darkened in the selected oval while darker areas of the trees remain unaltered




Lighten Only Increases the luminance levels in a selected area only if the result would be lighter than the background color.




The reverse of the example for Darken Only. Dark areas in the selected oval are lightened while light areas, mainly the dirt roads, remain unaltered.

Mode	Description
Darken	Reduces the luminance levels in a selected area using the value of the Amount slider.  <p>Luminance in the selected oval is reduced by 50.</p>
Lighten	Increases the luminance levels in a selected area using the value of the Amount slider.  <p>Luminance in the selected oval is increased by 50.</p>
Add	Adds color to the colors in a selected area using the value of the Color parameter category. 

Mode	Description
Subtract	Removes color from the colors in a selected area using the value of the Color parameter category. <div></div>
Invert	Inverts the RGB values of the colors in a selected area. <div></div>
Mosaic	Applies a tile effect to a selected area with horizontal and vertical controls, which distorts or disguises the area. <div></div>
Blur	Blurs a selected area with horizontal and vertical controls, which distorts or disguises the area. <div></div>

Mode	Description
Median	Takes the nine values surrounding each pixel, ranks them, and replaces the pixel with the value in the middle, creating a slight softening effect. Median filters are often used to remove noise from an image. <div>An aerial photograph showing a dirt road winding through a forest. A semi-transparent oval highlights a section of the road and surrounding trees, demonstrating the softening effect of the median filter.</div>
Unsharp Mask	Sharpens a selected area of an image to create more defined edges with horizontal and vertical controls. <div>An aerial photograph of the same scene as above. A semi-transparent oval highlights the same area, but the edges of the road and trees are noticeably sharper and more defined.</div>
Gradient	Dissipates the paint in a gradient. Use the Angle slider to set the direction of dissipation. 100% of the value in the Color parameter category appears at one end of the gradient, 0% at the other end. <div>An aerial photograph of the same scene. A semi-transparent oval highlights an area where a gradient effect has been applied, showing a smooth transition from a darker purple color on one side to a lighter, more transparent purple on the other.</div>

Mode	Description
Emboss	Creates a three-dimensional extrusion effect in a selected area. Use the Angle slider to adjust the direction of the extrusion.
Scratch Removal	Replaces scratched or otherwise flawed areas of a frame with clean material from a nearby source. For more information, see “Understanding Scratch Removal” on page 505 .
Color Adjust	Adjusts the brightness, contrast, hue, and saturation of the selected area. Inverts the chroma and luma values of the selected area. For more information, see “Color Effect Parameters” on page 658 and “Chroma Adjust Parameters” on page 661 .
Luma Range	Adjusts the range of brightness from black to white and the position of the midtone point with respect to the white and black points. For more information, see “Luma Range Parameters” on page 659 .
Luma Clip	Limits the brightness or darkness values in the selected area. For more information, see “Luma Clip Parameters” on page 660 .
Color Style	Adjusts the selected area to create posterization and solarization effects. For more information, see “Color Style Parameters” on page 662 .
Color Gain	Provides individual adjustments of the three color channels (red, green, and blue). For more information, see “Color Gain Parameters” on page 663 .
Color Match	Provides the same Color Match control that appears in the Color Correction tool. Lets you adjust the color automatically in the selected area using selected input and output color values.




Click the Enable Color Match button to activate the color match for the selected area.

Click the Use NaturalMatch™ button to enable the NaturalMatch feature.

For more information on the Color Match control and the NaturalMatch feature, see [“Using the Color Match Control” on page 756](#).

Paint Effect Color Parameters

Use these controls in conjunction with one of the Paint Effect modes to colorize your selection. For more information on the parameter controls, see [“Color Parameter Controls” on page 604](#). **This parameter is not keyframeable.**



Safe Color Limiter Parameters

422 Safe Parameter

422 Safe controls how the effect handles chroma sub-sampling when limiting colors, offering a choice between performance and guaranteed accuracy.

When 422 Safe is deselected (the default value), effect processing is fast. However, depending on the image, a small number of transient pixel values might exceed your safe color ranges. When 422 Safe is selected, effect processing is slower, but every pixel in every frame is guaranteed to be within your safe color ranges.

In many situations, you can leave 422 Safe turned off. If you know that every pixel throughout your material must be guaranteed safe, turn 422 Safe on. Alternatively, you can leave 422 Safe turned off while you edit and adjust effects, then turn it on before you render or output your finished sequence to guarantee that every pixel in your output is color safe.

Source Monitor Analysis Menu

The Source Monitor Analysis menu determines whether the effect analysis display appears in the Source monitor. For more information, see [“Using the Safe Color Limiter Analysis Display” on page 825](#).

Control	Description
Highlight Out of Range Colors	The effect analysis display appears in the Source monitor and highlights pixels with out of range color values.
Source Monitoring – Off	The effect analysis display does not appear and the Source monitor reverts to the normal display of Source footage.

Composite/Luma Levels Parameters

Composite/Luma Levels controls how limits for composite signal and luminance are measured and set. For more information, see [“Understanding the Safe Color Limiter Effect” on page 823](#).

Control	Description
Enable button	When the Enable button is turned on, the effect limits the video so that it is within the limits for composite or luminance set with the Composite L, Composite H, Luma L, and Luma H sliders. When the Enable button is turned off, the effect does not take account of the composite or luminance limits.
Composite L	Controls the lower limit for the composite signal. For example, if Composite L is set to -20 IRE, any pixels with a lower composite value are modified so that their composite value is no lower than -20.
Composite H	Controls the upper limit for the composite signal. For example, if Composite H is set to 110 IRE, any pixels with a higher composite value are modified so that their composite value is no higher than 110.
Composite units	Controls the unit of measurement used for composite limits. IRE measures in IRE units, and mVolts measures in millivolts.
Luma L	Controls the lower limit for luminance. For example, if Luma L is set to 7.5 IRE, any pixels with a lower luminance value are modified so that their luminance value is no lower than 7.5.
Luma H	Controls the upper limit for the luminance signal. For example, if Luma H is set to 100 IRE, any pixels with a higher luminance value are modified so that their luminance value is no higher than 100.
Luminance units	Controls the unit of measurement used for luminance limits: <ul style="list-style-type: none">• 8 Bit — Measures on a scale from 0 to 255.• % — Measures on a percentage scale. Percentage values can be lower than 0 or higher than 100.• IRE — Measures in IRE units.• mVolts — Measures in millivolts.


RGB Levels Parameters

RGB Levels controls how limits for RGB color gamut are measured and set. For more information, see [“Understanding the Safe Color Limiter Effect” on page 823](#).

Control	Description
Enable button	When the Enable button is turned on, the effect limits the video so that it is within the limits for RGB color levels set with the RGB Gamut L and RGB Gamut H sliders. When the Enable button is turned off, the effect does not take account of the RGB color level limits.
RGB Gamut L	Controls the lower limit for RGB color gamut. For example, if RGB Gamut L is set to 16 using 8 Bit units, any pixels with a lower red, green, or blue level are modified so that their red, green, and blue levels are no lower than 16.
RGB Gamut H	Controls the upper limit for RGB color gamut. For example, if RGB Gamut H is set to 235 using 8 Bit units, any pixels with a higher red, green, or blue level are modified so that their red, green, and blue levels are no higher than 235.
RGB Gamut units	Controls the unit of measurement used for RGB gamut limits: <ul style="list-style-type: none">• 8 Bit — Measures on a scale from 0 to 255.• % — Measures on a percentage scale. Percentage values can be lower than 0 or higher than 100.• IRE — Measures in IRE units.• mVolts — Measures in millivolts.

Scratch Removal Effect Scratch Parameters

Scratch controls the position and appearance of replacement material that you use to cover scratches and other flaws.



Frame/Field slider (top) and Frame Processing button (bottom) in the Scratch parameter category

Parameter	Description
Opac. (opacity)	Controls the opacity of the replacement material used in a Scratch Removal effect. Values range from 0 (transparent) to 100 (opaque).
Object Visible	Lets you add a keyframe to a Scratch Removal effect and have replacement material suddenly “pop” onto the screen at the position marked by the keyframe. You must have at least three keyframes to create this effect.


Parameter	Description
Hor (horizontal)	Defines the position of the replacement material relative to the shape you have drawn on the horizontal axis of the frame. Negative values indicate the number of pixels the replacement material is to the left of the shape, positive values the number of pixels to the right. The default value is 0.
Vert (vertical)	Defines the position of the replacement material relative to the shape you have drawn on the vertical axis of the frame. Negative values indicate the number of pixels the replacement material is above the shape, positive values the number of pixels below. The default value is 0.
Frame/Field parameter slider	<p>Defines which nearby frame or field is the source of the replacement material. To select frame or field processing, use the Frame Processing button.</p> <p>If Frame Processing is selected, the slider is labeled Frame and is calibrated in one-frame increments from -5 to +5. If Frame Processing is deselected, the slider is labeled Field and is calibrated in one-field increments from -10 to +10.</p> <p>For more information, see “Understanding Scratch Removal” on page 505.</p> <p>Values represent an offset from the reference point defined in the Offset Fast menu.</p> <p>A value of 0 indicates the frame or field that is the reference point. A positive value indicates a later frame or field than the reference point. A negative value indicates an earlier frame or field than the reference point. The default value of -1 provides an instant correction when you are working with the normal two-frame effect created by the Scratch Removal button.</p>
Offset Fast Menu button	<p>Defines the reference or zero point for the Frame or Field slider. The following three choices are available:</p> <ul style="list-style-type: none"> • Relative — The Frame or Field slider is set relative to the frame containing the shape that covers the flaw. • From Start — The Frame or Field slider is set relative to the first frame of the segment. This is the default. • From End — The Frame or Field slider is set relative to the last frame of the segment.
Frame Processing button	Lets you select frame or field processing when you are working with two-field media. The button does not appear when you are working with single-field material. For more information, see “Selecting Frame or Field Processing When Using Scratch Removal” on page 508 .

Key Effect Parameters

This section contains reference summaries for the effect parameters that are unique to the Key effect category.

Key Effects Key Parameters


Key selects the primary key color to be replaced by video in the Chroma Key and Luma Key effects. **This parameter is not keyframeable**



Parameter	Description
Color controls	Define the key color. For more information on the parameter controls, see “Color Parameter Controls” on page 604 .
Gain	Specifies how much of the foreground and the background video displays. Values range from 0 (shows only the foreground) to 63 (replaces all the foreground video with the background video).
Soft (softness)	Determines how the bordering colors along the edge of the key appear. Colors that border the luminance or chroma specified for the key display as a blend of the foreground and the background video. The higher the Softness value, the more of the background video is blended in the border colors. Use the Soft slider to improve the appearance of the edges of the keyed areas.

AniMatte Effect Mode Parameters

Mode parameters and options affect the overall nature of the Intraframe editing you perform using the AniMatte effect. A Mode parameter is also available in FluidMotion Edit and is described in [“FluidMotion Edit Parameters for Timewarp Effects” on page 698](#).




Parameter	Description
Fast menu	Provides the following two modes for the AniMatte effect: <ul style="list-style-type: none">• Key In — For two-track video effects, displays the image on the higher track (foreground) within the matte selection while revealing the image on the lower track (background) outside the matte selection. For single-track matte wipes, displays the incoming segment within the matte selection.• Key Out — For two-track video effects, displays the image on the lower track (background) within the matte selection while revealing the image on the higher track (foreground) outside the matte selection. For single-track matte wipes, displays the outgoing segment within the matte selection.
Opac. (opacity)	Controls the transparency level of the image within the border of a matte or wipe created with the AniMatte effect. Values range from 0 (transparent) to 100 (opaque).
Object Visible	Lets you add a keyframe to a segment or transition and have a painted object or matte suddenly “pop” onto the screen at the position marked by the keyframe. You must have at least three keyframes to create this effect.

Chroma Key Profile, Secondary Key, and Spill Suppression Parameters

Profile Parameter

Profile provides a graphical representation of the foreground level and acceleration applied to effect keyframes:

- Foreground level affects the opacity of the effect. The greater the opacity, the closer to the top of the Profile graph the keyframe appears.
To adjust the foreground level, select the appropriate keyframe indicator, then click the round white keyframe indicator that appears on the Profile graph, and drag it up or down to increase or decrease the opacity of the foreground image.
- Acceleration affects the rate of movement into and out of keyframes. The greater the acceleration, the more rounded the lines appear in the Profile window. You can adjust Acceleration with the Acceleration slider only. For more information, see [“Acceleration” on page 605](#).



Secondary Key Parameters

Secondary Key selects a second background color to key out. For example, the floor in a blue-screen shot or a green-screen shot might be a shade slightly different from the background. You can select the floor color as your secondary color and key it out. **This parameter is not keyframeable.**



For a description of each parameter, see [“Key Effects Key Parameters” on page 676](#).

Spill Suppression Parameters

Spill Suppression neutralizes the selected color without affecting the luminance. The spill color changes to a grayscale, allowing it to blend more easily with the foreground image. **This parameter is not keyframeable**



Use the Spill Suppression key color to fix the following problems:

- Remove background color spill from the foreground image. Color spill occurs when the background color is present in the foreground image due to backdrop reflection.
- If the foreground object retains an outline of the chroma key color, you can use Spill Suppression to reduce the color effect in the outline.

For a description of each parameter, see [“Key Effects Key Parameters” on page 676](#).

RGB Keyer Parameters

Key Color Parameters

Key Color selects a color for the chroma key. For more information on the parameter controls, see [“Color Parameter Controls” on page 604](#). (The RGB Keyer uses the V (value) control for defining color rather than the Luminance control used in many other effects.)

This parameter is not keyframeable



Chroma Key Parameters

Chroma Key lets you fine-tune the key effect. **This parameter is not keyframeable.**



Parameter	Description
Gain	Adjusts the threshold of the key. Values range from 0 to 100.
Soft (softness)	Softens the edge of the key. Values range from 0 to 100.
Show Alpha	Displays the grayscale alpha channel used to apply the key effect to the foreground and background sources. Viewing the alpha channel directly lets you examine problem areas of the key while making adjustments.
Spill	Suppresses the spill from the key color onto foreground objects that often occurs due to color reflection in the scene. Values range from 0 to 100.
Level	Controls transparency of the foreground elements against the key background.
Reverse	Inverts the key.

Matte Control Parameters

Matte Control lets you fine-tune the edges of the matte used in the chroma key. **This parameter is not keyframeable.**



Parameter	Description
Blur	Uses a box filter to blur the matte for the key. Values range from (a blurring of 0 pixels) to 100 (a blurring of 10 pixels).

Parameter	Description
Erode	Decreases or “erodes” the outer edges of the blurred matte key.

Color Correction Parameters

Color Correction lets you perform post-key color correction of the foreground elements in the Chroma Key effect. Because the foreground and background elements are often shot at different times and locations, post-key color correction is especially useful for maintaining the key while matching the visual characteristics of the foreground to the background. **This parameter is not keyframeable.**



Parameter	Description
Hue	Specifies the hue or tint of the foreground elements. Hue is measured as values on a color wheel ranging from -180 to +180.
Sat (saturation)	Specifies the amount or intensity of the color. Values range from -100 to +100.
Bright (brightness)	Specifies the brightness level. Values range from -100 to +100.
Cont (contrast)	Controls the contrast of light and dark areas in the picture. Values range from -100 to +100, where a value of 0 indicates the image is unchanged. A negative value reduces contrast. A positive value increases contrast.

SpectraMatte Parameters

Bypass Parameter

Bypass toggles the SpectraMatte effect on and off. When it is selected, you see the original foreground image in the Effect Preview monitor. When it is deselected, you see the composite of foreground and background created by the effect. Use Bypass, for example, when you want to use the eyedropper to select the key color from the blue or green screen part of the foreground image.



Bypass on (left) and off (right)

Key Color Parameters

Key Color defines the color from the foreground image that you want to replace with the background image. For more information on the parameter controls, see [“Color Parameter Controls” on page 604](#).

The SpectraMatte effect uses the color you select as the basis for defining a range of color values to use in the key. In the SpectraGraph display, this range appears as a wedge keyed out of the CbCr swatch. For an explanation of how this wedge is calculated, see [“How the SpectraMatte Effect Calculates Key Color Values” on page 255](#).

Matte Analysis Parameters


Matte Analysis lets you display and customize analytical views of the SpectraMatte effect. The controls do not have any impact on the finished look of the effect.

Parameter	Description
Show Alpha	Shows the alpha matte currently being generated by the effect in the Effect Preview monitor. This lets you check the effect of your parameter adjustments, such as the Matte Processing parameters that change the edges of the matte. For more information on the alpha matte display, see “Understanding SpectraMatte Analysis Displays” on page 253 . This parameter is off by default.



Foreground image (left) and Show Alpha display (right)

Parameter	Description
SpectraGraph	<p>Shows the SpectraGraph display, which shows the color values in the foreground image superimposed on a CbCr color swatch, in the Effect Preview monitor. For more information on the alpha matte display, see “Understanding SpectraMatte Analysis Displays” on page 253. This parameter is off by default.</p> <p>If Show Alpha is also selected, SpectraGraph displays an alpha matte for the CbCr color swatch, which can help you see the superimposed color data more clearly.</p>



SpectraGraph display (left) and SpectraGraph with Show Alpha display (right)


Parameter	Description
SpectraGraph Source Monitor menu	Controls how effect information displays in the Source monitor. <ul style="list-style-type: none">Source Monitoring - Off — the Source monitor does not display an analysis view.SpectraGraph in Source Monitor — shows the SpectraGraph display in the Source monitor. This is the default menu selection.



- Alpha in Source Monitor — Shows the alpha matte display in the Source monitor.



SpectraGraph Brightness	Controls the brightness of the CbCr color swatch in the SpectraGraph display, which can help you see the superimposed color data more clearly. Values range from 0 to 100.
----------------------------	--




SpectraGraph Brightness = 0 (left) and 100 (right)

Chroma Control Parameters

Chroma Control changes how color values are calculated in the key by adjusting various aspects of the shape and edge of the key color wedge in the SpectraGraph display.

Parameter	Description
-----------	-------------


Tolerance	Controls the range of hues in the key color. In the SpectraGraph display, the Tolerance value is visible as the width or spread of the key color wedge. Values range from 0 to 180 and represent the angle between the two sides of the wedge. The default value is 90.
-----------	---





Tolerance = 45 (left) and 135 (right)

Key Sat (saturation) Line	Controls the saturation level at which keying begins. In the SpectraGraph display, the Key Sat Line value creates a line perpendicular to the center line of the key color wedge. This line modifies the shape of the wedge by blunting its point, which has the effect of retaining color values on the inside of the line in the foreground image — that is, low saturation color values across the full hue range defined by the key color wedge.
---------------------------	--

Values range from 0 to 100, where 0 places the line at the location of the Key Saturation value and 100 places the line at the location of the Key Color. The default value is 0.



Left: examples of Key Sat Line values — Key Sat Line = 50 (top) and Key Sat Line = 100 (bottom)
Right: diagram of the effect of the Key Saturation Line (highlighted) on a key wedge (gray area). The small squares indicate the Key Saturation value (near the center crosshair) and the Key Color value (inside the wedge)


Parameter	Description
Key Saturation	<p>Controls the saturation level at which keying begins. In the SpectraGraph display, the Key Saturation value is the point of the key color wedge. Higher Key Saturation values move the wedge out from the center of the CbCr swatch. Unlike the Key Sat Line parameter, Key Saturation does not change the basic shape of the key wedge.</p> <p>Values range from 0 to 100, where 0 is zero saturation (the center of the CbCr swatch) and 100 is the same saturation value as the key color. The default value is 0.</p> <div></div> <p>Left: examples of Key Saturation values — Key Saturation = 50 (top) and Key Saturation = 99 (bottom)</p> <p>Right: diagram of the Key Saturation value (the small square at the point of the wedge)</p>

Parameter	Description
-----------	-------------

Inner Softness

Controls the extent of the blend gradient by adjusting where the gradient begins to increase from 0 (full transparency of foreground values). In the SpectraGraph display, this is visible because this changes where the solid black area of the key color wedge ends and the blended area begins.

Values range from 0 to 100. The higher the value, the narrower the softness gradient, and the more color values near the edges of the key color wedge are completely keyed out rather than blended between foreground and background. When Inner Softness is 0, the gradient extends inwards from the edges of the wedge all the way to the Key Color value. When Inner Softness is 100, the gradient extends only a small percentage of the way from the edges of the wedge towards the Key Color value. The default value is 10.




Left to right: Inner Softness = 0, 10 (the default), and 100





Outer Softness

Controls the extent of the blend gradient by adjusting where the gradient begins to decrease from 1 (full opacity of foreground values). In the SpectraGraph display, this is visible as a change in where the solid color area outside the key color wedge ends and the blended area begins.

Values range from -100 to +100. Negative values increase the range of color values that are fully opaque in the foreground image and reduce the extent of the blend gradient. Positive values reduce the range of color values that are fully opaque in the foreground and increase the extent of the blend gradient.



Left to right: Outer Softness = -100, 0 (the default), and 100


Parameter	Description
Alpha Offset	<p>Controls the position of the blend gradient by adding an offset to the blend gradient values. Unlike Inner Softness and Outer Softness, which alter the extent of the blend gradient by moving either its inner or outer edge, Alpha Offset shifts the entire gradient. This effectively expands or contracts the whole key color wedge.</p> <p>Values range from -100 to +100. Negative values expand the key color wedge. Positive values contract the key color wedge.</p> <div></div> <p>Alpha Offset = -50 (left) and 50 (right)</p>
Opacity	<p>Controls the overall opacity level of the foreground image. Values range from 0 (transparent) to 100 (opaque).</p> <div></div> <p>Opacity = 100 (left) and 65 (right)</p>

Luma Control Parameters

Luma Control adjusts the key based on the luminance characteristics of pixels in the foreground image.


Parameter	Description
Enable Luma Curve	Turns the Luma Curve parameter on or off. When Enable Luma Curve is selected, the SpectraMatte effect uses the luminance graph in the Luma Curve advanced keyframe display to adjust the key.

Parameter	Description
Luma Curve	<p>Modifies the alpha value of blended pixels by adding an offset based on their luminance. Your Avid editing application uses a graph that you create in the advanced keyframe graph area for the Luma Curve parameter to calculate the offset.</p> <p>For example, you can use this parameter to increase the transparency level of very bright pixels so that they are more completely keyed out while leaving darker pixels unaffected. The Luma Curve parameter only applies to pixels in the foreground image that are already blended (neither fully opaque nor fully transparent) as a result of the chroma parameter settings in the effect.</p> <p>The parameter works by repurposing the advanced keyframe graph. The horizontal axis becomes a luminance scale, while the vertical axis represents the alpha offset. You add adjust points on the graph you create a curve that defines the alpha offset across the luminance range. For information on working with the advanced keyframe graphs, see “Understanding Keyframes” on page 101.</p> <p>The following illustration shows three points on a Luma Curve advanced keyframe graph. The left and right points represent luminance values of zero luminance and full brightness respectively, while the center point represents a luminance value roughly half-way between. The first two points are set to a positive offset of 75, while the third is set to an offset of 0. The resulting curve interpolates offset values across the full luminance range. The offset remains at 75 for all pixels darker than the luminance midpoint, then gradually decreases to 0 across the range of pixels above the luminance midpoint. As a result, darker foreground pixels become much less transparent (if they were already partially transparent), while the brightest pixels are unchanged.</p>





The Luma Curve graph can have as many points as necessary to define the curve you need, and does not need to be a specific width. The outside two points on the graph always represent the luminance limits, regardless of their exact horizontal location.

Values range from -100 to +100. Negative values increase the transparency of affected pixels, while positive values decrease the transparency. A value of -100 makes an almost fully opaque pixel fully transparent. A value of +100 makes an almost fully transparent pixel fully opaque.

Parameter	Description
Suppress Shadow	<p>Lets you remove shadows cast by foreground subjects onto areas of key color such as blue or green screens by increasing the saturation value of pixels for the purposes of calculating the key. The darker the pixel, the more the saturation value is increased. The change in saturation value is used only while calculating the key and does not affect the appearance of the image.</p> <p>Values range from 0 to 100. The higher the value, the more saturation is boosted for the purposes of calculating the key.</p> <p>In the SpectraGraph display, the impact of the Suppress Shadow parameter is clearly seen in the superimposed color data. As the Suppress Shadow value increases, color values move outward into areas of higher saturation, with darker values moving further than brighter ones.</p> <p>The following illustration shows the display for a Suppress Shadow setting of 80. Color values have moved out from the center to areas of higher saturation. Darker pixels have moved furthest and have “overtaken” lighter pixels.</p> 

Matte Processing Parameters

Matte Processing adjusts the alpha matte that the effect uses to generate the key by blurring or softening. This is primarily used as a way to improve the look of the edges of a key.


Parameter	Description
Matte Blur	<p>Controls the amount of blurring that is applied to the matte.</p> <p>Values range from 0 to 100, where higher values result in a greater degree of blurring. The default value is 0.</p> <p>Use the menu to control how the blurring applies:</p> <ul style="list-style-type: none">• Blur — Adds blurring to both the inside and the outside of the matte edge.• Erode — Adds blurring to the inside of the matte edge only.• Dilate — Adds blurring to the outside of the matte edge only. <div></div> <p>Left to right: example of an Alpha Matter before blurring, and menu settings of Blur, Erode, and Dilate (the Blur value is set to 50 in all cases)</p>
Soften Alpha Saturation	<p>Softens alpha values where edges of the key color wedge meet. In the SpectraGraph display, this is visible as a slight rounding off of the point where two edges meet in the key color wedge. The default value is On. Turning Soften Alpha Saturation off changes the alpha value of a small range of color values and might improve the look of the edges of some keys.</p> <div></div> <p>Soften Alpha Saturation on (left) and off (right)</p>

Spill Parameter

Spill removes key color that has been reflected onto the foreground subject from the blue or green screen background.


Spill correction works by replacing color values that might be affected by spill with color values that are unaffected. For example, if green is the key color, some greenish-blue color values are replaced by blue color values.

You control the range of color values that are affected using the two Spill parameter controls. For details of the effect of each parameter, see the following table. In combination, the two parameters establish a zone around the key color wedge where spill correction takes place. Color values within the zone are replaced by color values on the “safe” side of the zone (away from the key color wedge), as shown by the red arrows in the following illustration.




In most cases, you should make relatively subtle corrections using the Spill parameters. If you correct too large a range of values, you correct color values that do not need adjustment and change the look of the entire foreground image in an undesirable way.


The following illustrations show examples of the effect of spill correction in the SpectraGraph display.





NoSpill correction (both Spill parameter values are 0). Greenish colors are visible near the edges of the key color wedge. (The wedge is adjusted so that it has no blend gradient to simplify the image and clarify these examples.)



Spill correction with Spill Saturation = 100 and Spill Angle Offset = 0. The correction is most evident in the blues, where greenish-blue values near the edges of the key color wedge have been replaced with bluer values.



Spill correction with Spill Saturation = 100 and Spill Angle Offset = 30. The correction is now much more obvious, with all greenish values completely eliminated. Although a correction like this certainly eliminates all spill, it is likely to be too extreme for many images, effectively performing a bad color correction. Here, for instance, pale blue and yellow color values have also been lost.


Parameter	Description
Spill Saturation	<p>Controls the saturation level at which spill correction begins. In the SpectraGraph display, this parameter defines the point of the spill correction zone that surrounds the key color wedge, as shown in the following illustration.</p> <p>Values range from 0 to 100, where 0 is the current Key Saturation parameter value and 100 is 0 saturation (the center point of the CbCr swatch).</p>  <p>Diagram of the spill correction zone surrounding the key color wedge. The location of the Spill Saturation value is highlighted.</p>
Spill Angle Offset	<p>Controls the range of colors that undergo spill correction by changing the spread of the spill correction zone.</p> <p>Values range from 0 to 100. The offset is added on either side of the zone. The default spread of the zone is the same as that of the key color wedge, that is, the value set by the Chroma Control Tolerance parameter. For example, if Tolerance is set to 90 and Spill Angle Offset is set to 20, 20 degrees are added on either side of the default angle, and the final angle between the two sides of the spill correction zone is 130 degrees.</p>  <p>Diagram of the additional angles set by the Spill Angle Offset parameter (highlighted), which extend the spread of the zone defined by the Chroma Control Tolerance parameter.</p> <p>In most cases, you should limit Spill Angle Offset adjustments to the lower end of the value range. Larger adjustments usually result in unwanted color correction of the foreground image.</p>

Motion Effect Parameters

This topic contains reference summaries for effect parameters that are unique to traditional (source-side) motion effects.

Freeze Frame Parameters

You access the Freeze Frame parameters from the Clip menu. For more information, see [“Creating a Traditional Freeze Frame Effect” on page 199](#). **These parameters are not keyframeable.**



Parameter	Description
Duration	Specifies the length of the Freeze Frame clip. To enter a custom duration: <ol style="list-style-type: none">1. Select Clip > Freeze Frame > Other.2. In the dialog box, type a custom duration, and then click OK.

Parameter	Description
Two Field Freeze Frames	<p>Determine how your Avid editing application creates the Freeze Frame media when you are working in two-field resolutions (for example, 20:1, 3:1, 2:1, or uncompressed).</p> <ul style="list-style-type: none"> Using Duplicated Field — Uses a single field. This option reduces the vertical resolution of the image by one-half, resulting in a lower quality image. Using Both Fields — Uses both fields. This option is especially useful when there is motion in the footage. Using Interpolated Field — Creates a second field by combining scan line pairs from the first field in the original media. This might result in a slightly softer look to the freeze frame.

Variable Speed and Strobe Motion Parameters

Variable Speed and Strobe Motion parameters appear in the Motion Effect dialog box. To open the Motion Effect dialog box, use the procedure in [“Creating Traditional Motion Effects” on page 199](#). For more information, see [“Creating a Traditional Variable Speed Effect” on page 201](#) and [“Creating a Traditional Strobe Motion Effect” on page 204](#). **These parameters are not keyframeable.**



If a Strobe Motion effect becomes unrendered because it has been trimmed to a longer duration, the effect does not play and you must render it again.

To indicate reverse motion at full play rate, slow or fast, enter a negative play rate or a percent.

Parameter	Description
Variable Speed	<ul style="list-style-type: none"> Duration <i>n</i> Frames — The duration of the effect in frames. Doubling the number of frames causes the frame rate to be half the current rate. Rate <i>n</i> FPS — The rate of speed in frames per second (fps) at which the video is played. Normal speed is 30 fps for NTSC video, 25 fps for PAL video. % Speed — The percent of speed at which the video is played. Normal speed is 100%. Fit To Fill — Sets the Variable Speed parameters, so the duration of the motion effect matches the IN to OUT duration marked in the sequence.
Strobe Motion	<ul style="list-style-type: none"> Update every <i>n</i> frames — Specifies the update rate in frames for the Strobe Motion effect. For example, entering a rate of 5 causes every fifth frame to display in the Strobe Motion effect.

Parameter	Description
Render 2-Field Motion Effect Using	<p>These options are available for two-field media in interlaced projects only.</p> <ul style="list-style-type: none">• Duplicated Field — Uses a single field. For two-field media, this reduces the information stored by half because it drops one field of the image, resulting in a lower quality image. For single-field media, this is usually the best choice because of its speed (the other options do not improve effect quality for single-field media). Rendering is faster than for any other option.• Both Fields — Uses both fields. For example, the first two frames of a half-speed (50%) slow motion effect repeat the original Frame 1 (both fields) twice. This option is good for shots without inter-field motion and still shots. With footage that includes inter-field motion, this method might result in minor shifting or bumping of the image because it disturbs the original order of fields: a Field 1 appears both before and after the corresponding Field 2. Rendering is relatively fast. For best results, use evenly divisible frame rates with this option.• Interpolated Field — Creates a second field by combining scan line pairs from the first field in the original media. This option calculates the motion effect at the field level rather than the frame level. Because your Avid editing application considers all fields and does not disturb the original order of fields, the smoothest effect results. This method is best for video-originated material or film-originated material transferred at 24 fps. Rendering takes longer using this option than for effects created using either Duplicated Field or Both Fields. The rendering time is similar to that needed for VTR-Style.• VTR-Style — Creates a second field by shifting selected video fields of the original media by a full scan line. This option also creates the motion effect at the field level rather than the frame level, but because pixels are not filtered, the final image is sharper than that created by the Interpolated Field option. The image might display some slight jitter at certain speeds. This technique is similar to that used by high-quality professional video decks when playing footage at less than normal speed. Rendering takes longer using this option than for effects created using either Duplicated Field or Both Fields. The rendering time is similar to that needed for Interpolated Field.• Ignore Render Setting — If a specific motion effect type is set in the Motion Effects Render Using option of the active Render setting, your Avid editing application automatically selects that motion effect type, makes all other motion effect type options unavailable, and displays the Ignore Render Setting check box. Select the Ignore Render Setting check box to temporarily override the active Render setting and make all four motion effect types available.
Target Drive	Click to select a drive on which to store the rendered effect.

Reformat Effect Parameters

This section contains reference summaries for effect parameters that are unique to the Reformat effect category.

14:9 Letterbox Position H Parameter


Shifts the image horizontally. Drag the slider to the left to shift the image to the left. Drag the slider to the right to shift the image to the right.



Pan and Scan Aspect Ratios and Actions Parameters

Aspect Ratios Parameters


The Aspect Ratios parameter sets the Source and Target aspect ratios. For more information, see [“Selecting the Source and Target Aspect Ratios for the Pan and Scan Effect” on page 284](#). **These parameters are not keyframeable.**



Parameter	Description
Source Fast menu	Specifies the aspect ratio of the source media. Supported source aspect ratios are: <ul style="list-style-type: none">• 1.33 (4:3)• 1.66• 1.78 (16:9)• 1.85• 2.35• 15:9 anamorphic• 16:9 anamorphic
Target Fast menu	Specifies the aspect ratio to which Pan and Scan conforms the media. Supported target aspect ratios are: <ul style="list-style-type: none">• 1.33 (4:3)• 16:9 anamorphic

Actions Parameters


The Actions parameter category lets you control certain aspects of the Pan and Scan effect. **These parameters are not keyframeable.**



Parameter	Description
Establish Origin	Saves the current Scaling and Position values as a customized default setting. For more information, see “Setting an Origin in the Pan and Scan Effect” on page 288 .
Subdivide Effect	Divides a Pan and Scan effect into a series of segments based on the segment boundaries on the video tracks below the Pan and Scan track. For more information, see “Subdividing the Pan and Scan Effect” on page 289 .
Reset to Origin	Resets the Scaling and Position values to the current customized Origin values. If you have not established an origin, Reset to Origin resets the values to the default values for the current Target aspect ratio. For more information, see “Setting an Origin in the Pan and Scan Effect” on page 288 .

FluidMotion Edit Parameters for Timewarp Effects

FluidMotion Edit provides tools to correct artifacts (distorted areas) that might appear in a Timewarp effect when you select the FluidMotion rendering option. The following illustration shows the default FluidMotion Edit display in the Effect Editor.




The Feathering and Brush parameters function similarly for FluidMotion Edit as they do for the AniMatte effect and Paint Effect. For more information, see “Feathering” on page 608 and “Brush” on page 607.

For information on adjusting a parameter with a thumbwheel, see “Changing a Parameter with a Slider in the Effect Editor” on page 94.

Display Parameters


Display gives you control over how your Avid editing application represents the motion information for manipulation. **This parameter is not keyframeable.**



Parameter	Description
Fast menu	Selects which image appears in the Effect Preview monitor and the way in which your Avid editing application displays motion vectors. <ul style="list-style-type: none">• Color Warp 50% — Displays the image (frame or field) that your Avid editing application creates halfway between outgoing Image A and incoming Image B as a grayscale image with a color overlay. Color in the overlay represents the speed (saturation) and direction (hue) of each pixel’s motion between Image A and Image B.• Warp 50% — Displays the image (frame or field) that your Avid editing application creates halfway between outgoing Image A and incoming Image B.• Image A — Displays outgoing frame or field A.• Image B — Displays incoming frame or field B.
Show Vectors	When Show Vectors is selected, your Avid editing application displays the motion vectors in an overlay. Deselect Show Vectors to see the underlying image.
Motion Color Threshold	Sets the range of motion that appears in the Color Warp display. <ul style="list-style-type: none">• Min (minimum) — Sets the minimum relative speed to display.• Max (maximum) — Sets the maximum relative speed to display.

Mask Parameters


Mask defines the width of a border around an image. FluidMotion does not use masked-out border pixels when creating new images. Use Mask to eliminate artifacts on the edge of an image caused by the black borders that are often present around the edges of NTSC and PAL images. **This parameter is not keyframeable.**



Parameter	Description
T (top), B (bottom) L (left), R (right)	Set the top, bottom, left, and right edges of the Mask area. The limits of the Mask appear as a blue frame in the Effect Preview monitor.

Mode Parameters

Mode appears in FluidMotion Edit and in the Intraframe editing tools. For more information on the Mode parameter category for the Intraframe editing tools, see “Paint Effect Mode Parameters” on page 663. **This parameter is not keyframeable.**



Parameter	Description
Fast menu	<p>Determines how FluidMotion applies Vector X and Vector Y values to motion vectors in the area you are editing.</p> <ul style="list-style-type: none">Set Vector — Replaces motion vectors in the area you are editing with Vector X and Vector Y.Add Vector — Uses Vector X and Vector Y as an offset to the values calculated by FluidMotion, and applies the result in the selected region.Erase — Sets the motion vectors in the selected region to 0,0 (no motion).
Opac. (opacity)	<p>Appears only in Erase mode. Sets the relative weight given by FluidMotion Edit to the adjustments you make to motion vectors in Erase mode.</p> <p>At 0 opacity, FluidMotion Edit does not apply your adjustments. At 100 opacity, FluidMotion Edit completely replaces its motion vectors with your motion vectors. At levels between 0 and 100, FluidMotion Edit modifies the original motion vectors by an amount based on a percentage of the motion vectors you define.</p>
Object Visible	<p>Deselect Object Visible to remove the display of the object you drew and reveal the effects of your adjustments to the region. Select Object Visible to see the object superimposed on the image.</p>
Vector X	<p>The Set Vector and Add Vector commands use the Vector X and Vector Y values to calculate motion vectors. You can:</p> <ul style="list-style-type: none">Use the eyedropper to sample vectors in an area of the image. <p>The Color Preview window and the values of Vector X and Vector Y change as you move the eyedropper over the image.</p> <ul style="list-style-type: none">Use the thumbwheels to set values for Vector X and Vector Y.
Vector Y	

Rolling Title and Crawling Title Effect Parameters

Position Parameters

Crawling titles have a Y parameter in the Position parameter category. Use this parameter to move a crawling title up or down in the frame.

The number range refers to the position of the title relative to the middle of the screen:

- At 0, the middle of the title is aligned with the middle of the screen.
- At -999 (the slider at its leftmost position), the bottom of the title aligns with the top of the screen, so the title is completely off screen above the image.
- At 999 (the slider at its rightmost position), the top of the title aligns with the bottom of the screen, so the title is completely off screen below the image.

Rolling titles have an X parameter in the Position parameter category. Use this parameter to move a rolling title left or right in the frame.

The number range refers to the position of the title relative to the middle of the screen:

- At 0, the middle of the title is aligned with the middle of the screen.
- At -999 (the slider at its leftmost position), the right edge of the title aligns with the left of the screen, so the title is completely off screen to the left.
- At 999 (the slider at its rightmost position), the left edge of the title aligns with the right of the screen, so the title is completely off screen to the right.

Scroll Position Parameters

Crawling titles have an X parameter in the Scroll Position parameter category. Use this parameter to move the crawling title left or right in the frame.

The number range refers to the position of the crawling title relative to its overall length, where 0 represents the point at which the left edge of the crawling title is aligned with the left edge of the screen. The highest negative number (the slider at its leftmost position) places the left edge of the crawling title off the right side of the screen. The highest positive number (the slider at its rightmost position) places the right edge of the crawling title off the left side of the screen.

Rolling titles have a Y parameter in the Scroll Position parameter category. Use this parameter to move the rolling title up or down in the frame. The number range refers to the position of the roll relative to its overall length, where 0 represents the point at which the top of the roll is aligned with the top of the screen. The highest negative number (the slider at its

leftmost position) places the top of the roll off the bottom of the screen. The highest positive number (the slider at its rightmost position) places the bottom of the roll off the top of the screen.

To reverse the direction of a roll or crawl, adjust the keyframes to reverse the slope of the keyframe graph (so that it slopes down rather than up).



If you select all keyframes when changing the scroll position on a rolling or crawling title, all keyframes will be set to that position and the title will no longer move. Make sure you select the appropriate keyframes.

3D Effect Parameters

This section describes all 3D parameter categories, in alphabetical order.

Effect parameters are keyframeable unless otherwise noted. You can set keyframeable parameters to different values at different points in an effect's duration to alter the effect over time. If a parameter is not keyframeable, you cannot change its value over the duration of an effect.


3D parameter categories support RGB processing of color space information unless otherwise noted.

For information on the hierarchical order in which your Avid editing application applies 3D parameters, see [“Understanding 3D Parameter Hierarchy” on page 703](#). For an explanation of how to change a parameter, see [“Using the Effect Editor” on page 89](#). For information on which 3D parameter categories are available in each 3D effect, see [“Effects Reference” on page 555](#).

Understanding 3D Parameter Hierarchy

Your Avid editing application processes 3D effects parameters in a specific order. Knowing the order can help you understand why something looks a particular way or why an object behaves the way it does on a motion path.

The hierarchy of 3D effects parameters (from higher to lower) is as follows:



- Lower parameters in the hierarchy, for example, Crop, do not affect higher parameters, for example, Rotation. In an effect that has both rotation and cropping, for example, the same four edges are always cropped the same way no matter what angle you select for the rotation.
- Higher parameters always take into account lower parameters in the hierarchy when processing. For example, before your Avid editing application rotates an object, it looks to see where the object is positioned in the frame to display the correct 3D point of view with the new angle.
- The final effect is always the same no matter the order in which you change parameters. However, effects are easier to control if you build them from the bottom of the hierarchy up. If you rotate an object, for example, and then move the axis (a lower parameter), your object might jump off the screen. It is better to move the axis first, and then rotate the object.
- Parameters operate as 2D, 3D, and post-transformation. All these choices affect the 3D path of the object differently. 2D parameters, such as Scaling, are lower in the hierarchy and do not affect the path through space. 3D parameters, such as Position, directly affect the shape of the motion path. Post-transformation parameters, such as Target, move the entire path.

Axis

Axis moves the center of rotation relative to the image. There is no fixed rotation axis with an image. The axis is independent of the image and is movable. For example, you can place the rotation axis in the center of the image, on the edge, or off the picture. To move the center of rotation off the image, you might find it useful to zoom out and activate the wire-frame handles. For more information, see [“Effect Editor Controls” on page 90](#).




Axis parameter category (left) and Axis button (right)

Parameter	Description
X	Moves the center of rotation along the X axis (right or left). Values range from –999 to 999, where 0 is the center of the X axis.
Y	Moves the center of rotation along the Y axis (up or down). Values range from –999 to 999, where 0 is the center of the Y axis.
Z	Moves the center of rotation along the Z axis (towards or away from the viewer). Values range from –999 (farthest away) to 999 (closest), where 0 is the center of the Z axis (the plane of the video screen).

Background Color (3D)

Use Background Color to replace the bottom video track with a background color. For more information on the parameter controls, see [“Color Parameter Controls” on page 604](#).





You can achieve interesting effects on a two-track sequence by using a background color for the bottom track and a Luma Key effect on the top track.

Border (3D)

Border places a border around the image. The default border color is black for Plain borders and shades of gray for other border types. You can blend the foreground video with the background video if you turn on Border, use a zero width, and adjust the Soft parameter. You cannot change the border type and border color between keyframes.


Border supports RGB processing for the Plain border style only. If you select any other style from the Type menu, RGB processing is no longer available.



Parameter	Description
Other Options button 	Opens the Windows Color dialog box or the Macintosh Colors panel for precise color selection. For more information, see “Adjusting a Color Parameter for an Effect” on page 96 .
Hue	Identifies the border color. Hue is measured as values on a color wheel ranging from 0 to 255. The start (0) and ending (255) values are both red.
Sat (saturation)	Specifies the amount or intensity of the color. Values range from 0 to 255, where 0 is no chrominance and 255 is a fully saturated color.
Color controls	Define the color. For more information on the parameter controls, see “Color Parameter Controls” on page 604 .
Type menu	Selects a border style. <ul style="list-style-type: none">• Plain• Metal• Bevel 1• Bevel 2• 3D Frame• Round• Video
Wid (width)	Changes the width of the border. Values range from 0 (no border) to 100, where 50 is the default.
Sft (softness)	Changes the softness of the border edge. Values range from 0 (hard edge) to 255 (a very soft edge), where 0 is the default. Border softness blends the border with the background image, giving the border a soft appearance.

Corner Pin

Corner pinning is a way of positioning a 3D effect in a foreground video track over an object in a background video track. For example, you might want to have the foreground video appear to be playing on a TV screen in the background video.




Parameter	Description
Corner subcategories	<p>Each subcategory pins one corner of the image, as follows:</p> <ul style="list-style-type: none">• Corner 1 — top left corner of the untransformed image.• Corner 2 — top right corner of the untransformed image.• Corner 3 — bottom right corner of the untransformed image.• Corner 4 — bottom left corner of the untransformed image. <p>If the image is cropped, your Avid editing application uses the corners of the cropped image.</p>
X, Y	Pins the corner along the horizontal (X) or vertical (Y) axis.

Corner Tracking

Lets you use tracking data to control the effect. When you enable a selector, your Avid editing application maps a tracker to that selector. Trackers are named Point A, Point B, and so on. For more information, see [“Motion Tracking and Stabilization” on page 307](#).


Corner Tracking appears in tracking-enabled 3D Warp effects and Intraframe effects only. For Intraframe effects, you can enable trackers only when an Intraframe object is selected. Tracking is also an option under the [Position \(3D\)](#), [Rotation](#), and [Scaling \(3D\)](#) parameter categories.



Crop (3D)

Crop trims the edges of an image.

Crop is at the bottom of the 3D parameter hierarchy, so it always crops the same four edges of the object regardless of the object’s orientation. Cropping works only in 2D space so that 3D parameters such as Rotation and Position, which are higher in the hierarchy, take effect later in the processing. You do not need to adjust cropping before the other parameters, but it is often difficult to crop edges after other 3D transformations. For more information on the 3D parameter hierarchy, see [“Understanding 3D Parameter Hierarchy” on page 703](#).




Crop parameter category (left) and Crop button (right)

Parameter	Description
T (top)	Crops the top edge of the image. Values range from –999 (bottom) to 999 (top).
L (left)	Crops the left edge of the image. Values range from –999 (left) to 999 (right).
B (bottom)	Crops the bottom edge of the image. Values range from –999 (bottom) to 999 (top).
R (right)	Crops the right edge of the image. Values range from –999 (left) to 999 (right).

Defocus

Defocus gives you the ability to blur the image or to blur individual layers of a matte effect. You can use Defocus to create an effect in which the incoming media “fades in” to focus.



When you enable Defocus, the default command is Internal and default values are 10 for Horz (horizontal) and Vert (vertical). This produces a slight softening effect.

Defocus supports RGB processing for all defocus types except Key Blur. If you select Key Blur from the Type menu, RGB processing is no longer available.

Command	Description
Type menu	<p>Click to select the type of defocus that your Avid editing application applies. Key Only, FG and Key, and KeyBlur are available only on three track effects such as Matte keys and Titles promoted to 3D.</p> <p>The following options are available:</p> <ul style="list-style-type: none"> • Internal — blurs the entire image. • FG (foreground) Only — blurs only the foreground of a two-track or three-track effect. • Key Only — blurs only the key in a three-track effect. • FG and Key — blurs both the foreground and the key in a three-track effect. • Key Blur — uses alpha channel values as a template for blurring the foreground image. <p>When you select Key Blur, your Avid editing application blurs the foreground in proportion to the opacity of the matte. Black matte values cause no blurring, while white matte values cause maximum blurring.</p> <p>You might use this effect to selectively blur part of a foreground image, such as a face, by creating a moving matte for the area of the image you want to appear blurred. Use the Offset parameter to control how much of a blur Defocus applies to the face. You could also use a KeyBlur matte to create a soft-focus area around a foreground subject.</p>
Horz (horizontal), V (vertical)	<p>Increases or decreases horizontal or vertical blur. Values range from 0 to 15, where 0 represents no change.</p> <p>When the Type menu is set to Internal, the default value is 10 for both parameters. When the Type menu is set of FG Only, Key Only, or FG and Key, the default value is 0 for both parameters. When the Type menu is set to Key Blur, these parameters do not appear.</p>
Offset	<p>Increases or decreases the relative amount of blurring that Defocus applies. Values range from -100 (minimum blur) to 100 (maximum blur). When the value is 0, your Avid editing application makes no further adjustment to the foreground after it applies the KeyBlur option. This parameter is only available when the Type menu is set to Key Blur.</p>

Erode/Expand

Erode/Expand controls the blending of the edges on 3D Warp effects. **This parameter is not keyframeable.**

RGB processing is not available for Erode/Expand.



Parameter	Description
Filter	Specifies how many pixels on each side of the edge are smoothed. Values range from 1 to 7 (1 pixel on each side to 7 pixels on each side).
Center	Controls the amount of erosion or expansion your Avid editing application applies to the edges. Erosion shrinks the edges, and expansion enlarges the edges. Values range from 0 (maximum erosion) to 255 (maximum expansion).
Soft (softness)	Controls the slope of the edges. Values range from 0 (a vertical slope — no softness) to 255 (maximum softness).

Foreground (3D)

The Foreground parameter category lets you choose a key type and then control how your Avid editing application handles the foreground of the key. The parameters that appear in the category vary depending on the key type you select.



Parameters Common to All Key Types

Parameter	Description
Type menu	<p>Lets you select one of the following key types:</p> <ul style="list-style-type: none"> Full Key — Use to create dissolves (using the Opac parameter) or to switch an effect from one video track or segment to another (using the Swap Sources button). This is the default option. You cannot rotate the key independently of the image. Luma Key — Use to replace portions of the foreground video with the background video based on brightness or luminance. Your Avid editing application replaces the corresponding portions of the foreground video with background video. For information about the 2D version of this effect, see “Key: Luma Key” on page 577. Chroma Key — Use to replace one part of the video image with another video image based on color. Your Avid editing application replaces the key color in the video on the higher track with the video from the lower track. You often use chroma keys with a foreground image shot in front of a highly saturated color screen. For guidance on how to adjust a 3D Chroma Key, see “Suggested Workflow for Adjusting a Chroma Key” on page 713. For information about the 2D version of this effect, see “Key: Chroma Key” on page 576. SpectraMatte Key — Use this option to access all the parameters of the high-quality SpectraMatte chroma key effect. For information on the effect parameters available for the SpectraMatte key effect, see “Key: SpectraMatte Effect” on page 578. <p>This parameter is not keyframeable.</p>
Opac. (opacity)	Modifies the transparency of the foreground image. Values range from 0 (transparent) to 100 (opaque).
Invert	Inverts the key. Portions of the foreground that were visible are now invisible and vice versa.
Swap Sources	Switches the foreground and background sources for the effect.
Reverse Animation	Causes the entire effect to be reversed, including the direction of movement as well as the incoming and outgoing sources.
Show Alpha	Displays the grayscale alpha channel your Avid editing application uses to apply the key effect to the foreground and the background source. This lets you examine problem areas of the key while making adjustments.

Additional Parameters for Luma Key Key Type

Parameter	Description
Thresh (threshold)	Identifies either the brightness threshold for the foreground image or the center of the luma range.
Soft (luma softness)	Lets you soften the edge of the cutoff line. Pixel values slightly above or below the threshold are included, depending on the softness value.
Lum Range (luminance range)	Turns the Range slider on or off.
Range	<p>When Lum Range is not active, the Thresh value is a cutoff point. All brightness values above the Thresh value display (you see the foreground). Values below the Thresh value do not display (you see the background).</p> <p>When Lum Range is active, Thresh becomes the median point of a range that you adjust using the Range parameter. This lets you leave in a specific range of brightness values.</p>

Additional Parameters for Chroma Key Key Type

Parameter	Description
Color subcategory	Identifies the color that your Avid editing application replaces with video from the lower track. For more information on the parameter controls, see “Color Parameter Controls” on page 604 .
H Tol. (hue tolerance)	Controls how many similar shades of the hue your Avid editing application replaces with the background (the bottom video track). Use this option when the ranges of luminance and saturation of the chroma key color are too wide.
H Soft (hue softness)	Lets you soften edges that are too aliased or sharp.
S Low (low saturation)	Lets you remove low saturation colors by raising the lower limit. For example, sometimes portions of clothing or faces might contain subtle variations of a hue. To keep these portions of the image visible, you can try adjusting the S Low value.
L Tol. (luminance tolerance)	Specifies a tolerance level — your Avid editing application retains everything below the level.
L Soft (luminance softness)	Softens the key created by L Tol.
Lum Range (luminance range)	Turns the Range slider on or off.
Range	Lets you set a luminance range within which values are retained.

Suggested Workflow for Adjusting a Chroma Key


- 1. Use the eyedropper to select a hue.
For best results, pick a color that is well within the field of color.
- 2. Adjust H Tol. (hue tolerance) to replace the hue with the background.
- 3. If low-saturation grays are keyed out (for example, portions of faces or clothing), try adjusting S Low (low saturation) to put them back into the foreground.
- 4. Use L Soft (luminance softness) to fine-tune the edges of the key.
Typically the L Tol. and L Soft settings do not need adjustment.

 You can use the *Spill Suppression* parameter to correct spill for a Chroma Key. See “*Spill Suppression*” on page 724.

Highlight

Highlight lets you to enable automatic highlighting for shapes and adjust the intensity of automatic highlighting, or adjust the highlights for manual highlighting and Rev (reverse) manual highlighting. You can use manual highlights even when a shape is not active. The default manual highlight creates a blurred disk in the center of the image.

RGB processing is not available for Highlight.




Parameter	Description
Soft (softness)	Controls the softness of the highlight’s edge. Values range from 0 (hard edge) to 100 (a very soft edge), where 50 is the default softness.
Inty (intensity)	Controls the brightness of the highlight. Values range from 0 to 100, where 50 is the default intensity.
Rad (radius)	Controls the size of the highlight. Values range from 0 to 100, where 50 is the default radius.
Angle	Rotates the highlight. Values range from –180 degrees to 180 degrees, where 0 is the default angle.

Parameter	Description
Aspct (aspect ratio)	Changes the shape of the highlight from a perfect circle (0) to an oval or a band. Values range from –100 to 100, where 0 is the default. The –100 band is at right angles to the 100 band.
X	Moves the center of the highlight from left to right. Values range from –999 to 999, where 0 is the default. Positive values move the highlight to the right.
Y	Moves the center of the highlight from top to bottom. Values range from –999 to 999, where 0 is the default. Positive values move the highlight up.

Highlight Color

Highlight Color adds color to the highlighted portion of a 3D effect. For more information on the parameter controls, see [“Color Parameter Controls” on page 604](#).

RGB processing is not available for Highlight Color



Lowlight Color


Lowlight Color adds color to the shadowed portion of a 3D effect. For more information on the parameter controls, see [“Color Parameter Controls” on page 604](#).

RGB processing is not available for Lowlight Color.



Perspective


Perspective moves the perspective point (where parallel lines appear to converge) along the screen’s X, Y, and Z axes. This changes the way the image is visually projected onto the video screen.




Parameter	Description
X	Moves the projected screen image farther to the left or right. Values range from –999 to 999, where 0 is the default.
Y	Lets you view the image from a higher or lower angle. Values range from –999 to 999, where 0 is the default.
Z	Moves the perspective point closer to or farther from the observer. Perspective increases as the point moves inward and decreases as the point moves outward from the screen. Moving the perspective point in Z changes the amount of foreshortening on an image that is rotated around the X or Y axis.

Position (3D)

Position moves an image in 3D space. For information about the 2D version of this effect, see “Position” on page 613.



Parameter	Description
X	Moves the image along the screen’s X axis (horizontally). Values range from –3000 to 3000, where 0 is the zero-point of the X axis. Negative values move the image to the left and positive values move the image to the right.
Y	Moves the image along the screen’s Y axis (vertically). Values range from –3000 to 3000, where 0 is the zero-point of the Y axis. Negative values move the image down and positive values move the image up.
Z	Moves the image closer to or farther from the viewer along the Z axis. Values range from –3000 to 3000, where zero is the zero-point of the Z axis. Negative values move the image away from the viewer and positive values move the image toward the viewer.


 For an illustration of the XYZ coordinate system, see “Understanding 3D Geometry and Degrees of Rotation” on page 366.




Position Tracking subcategory


Parameter	Description
Tracker Selector menu	Lets you select the tracker your Avid editing application uses to control the Position parameter. By default, when Position Tracking is enabled, your Avid editing application maps a tracker named Point A to the T1 tracker selector.
Axis menu	Lets you use the data for both X and Y axes or for a single axis only. For more information, see “Limiting the Effect of Position Tracking Data to a Single Axis” on page 343.
Stabilize Tracking	Enables tracking for stabilizing the image. For more information, see “Stabilizing an Image” on page 346

Rotation

Rotation rotates the image around the X, Y, or Z axes.



Parameter	Description
Z	 Rotates the image around the Z axis (clockwise or counterclockwise). Values range from –720 to 720, where 0 is the default.
X	 Rotates the image around the X axis. Values range from –720 to 720, where 0 is the default.
Y	 Rotates the image around the Y axis. Values range from –720 to 720, where 0 is the default.


 *A value of 720 degrees lets you spin the image more than once between two keyframes. For more information, see [“Understanding 3D Geometry and Degrees of Rotation”](#) on page 366.*

Rotation Tracking subcategory

Tracker Selector menus	Lets you select the tracker your Avid editing application uses to control the Rotation parameter. By default, when Rotation Tracking is enabled, your Avid editing application maps a tracker named Point A to the T1 tracker selector and a tracker named Point B to the T2 tracker selector.
Stabilize Tracking	Enables tracking for stabilizing the image. For more information, see “Stabilizing an Image” on page 346.

Scaling (3D)

Scaling resizes the image or effect. For information about the 2D version of this effect, see [“Scaling” on page 614](#).




Scaling parameter category (left) and Scale button (right)

Parameter	Description
X	Controls the width of the image by stretching or compressing it along the X axis (horizontally). Values range from 0 to 400, where 100 indicates 100 percent scaling (normal size).
Y	Controls the height of the image by stretching or compressing it along the Y axis (vertically). Values range from 0 to 400, where 100 indicates 100 percent scaling (normal size).
Fixed Aspect	When Fixed Aspect is enabled, the aspect ratio of the image is locked so you cannot move the X and Y sliders independently. Your Avid editing application gangs the X and Y sliders and they move together to maintain the selected aspect ratio.
Scale Tracking subcategory	
Tracker Selector menus	Lets you select the tracker your Avid editing application uses to control the Scaling parameter. By default, when Scale Tracking is enabled, your Avid editing application maps a tracker named Point A to the T1 tracker selector and a tracker named Point B to the T2 tracker selector.
Stabilize Tracking	Enables tracking for stabilizing the image. For more information, see “Stabilizing an Image” on page 346

Shadow

Shadow places a shadow beneath an image, and lets you adjust the shadow’s offset and transparency.





Shadow, Trail, and Stamp are mutually exclusive, so you can have only one enabled at a time.

Parameter	Description
Opac. (opacity)	Changes the shadow's opacity from 0 (transparent) to 100 (opaque), where 50 is the default.
X	Changes the shadow's horizontal offset. Values range from –100 to 100, where 50 is the default.
Y	Changes the shadow's vertical offset. Values range from –100 to 0, where –50 is the default.

Shape




3D shape effects let you map the foreground video channel to various geometric shapes. You can create either a Page Fold, a Ball, or a Slats shape effect. Each shape effect displays a set of parameters specific to that shape in the Shape category. You can also adjust the effect with any of the other available 3D effects parameters.

Each shape effect contains a default template that makes use of the standard shape parameters. For example, when you first apply a Page Fold shape effect, your Avid editing application creates a simple page curl. You can adjust the parameters as needed.

RGB processing is not available for Shape.

For additional information about working with 3D Shape effects, see [“Considerations for 3D Shape Effects” on page 722](#).

The following illustration shows the three available shapes and the parameters available in the Shape parameter category for that shape.




Top to bottom: Page Fold, Ball, and Slats Shape types

Common Parameters for Shapes

Parameter	Description
Type menu	<p>Select one of the following shapes:</p> <ul style="list-style-type: none"> Page Fold — Treats the foreground video channel like a page in a book being turned to reveal another page beneath. You can see the video on either side when you rotate the image or curl the edges. The portion of the image that folds over is referred to as the flap. Ball — Lets you treat the video as a rubbery, rectangular sheet stretched around a sphere. If the radius of the sphere is very large, the corners of the sheet curve along the surface like a rubber patch on a ball. If the radius is small, the corners disappear, wrapping completely around the sphere's surface. Slats — Splits the image into alternating bands of video that enter the screen from opposite directions. <p>This parameter is not keyframeable.</p>

Parameter	Description
Highlight menu	<p>Controls highlighting. Select one of the following:</p> <ul style="list-style-type: none">• Auto Highlight — Lets your Avid editing application control the highlighting. You need to enable highlighting in the Highlight parameter category in order for highlights to appear. You can also vary the intensity of the highlight in the parameter category. Your Avid editing application positions the shape automatically. This option does not apply to the Ball shape.• Manual Highlight — Lets you use the Highlight parameter category to control the highlighting. In this case, you need to set parameters such as the angle, aspect ratio, and radius. For more information, see “Highlight” on page 713.• Reverse Manual Highlight — Reverses the effect of manual highlighting you set up.


Additional Parameters for the Page Fold Shape

Parameter	Description
Curl	<p>Controls the distance the page rolls up by specifying how far the rolling up has progressed. Values range from 0 to 100, where 0 represents no rollup.</p> <p>To take the page from a flat, centered image to one that is completely off the screen, animate the Curl value from 0 to 100 and keep the Radius parameter at its default value.</p>
Radius	<p>Controls the tightness of the curl or fold. Values range from 0 to 100, where 15 is the default.</p>
Angle	<p>Controls the direction of the curl or fold. Values range from –180 degrees to 180 degrees, where 45 degrees is the default. For illustrations of common angle values, see “Considerations for 3D Shape Effects” on page 722.</p>
Tuck and Flap menu	<p>Controls aspects of the appearance of the flap (the portion of the image that folds over). Select one of the following:</p> <ul style="list-style-type: none">• Tuck Over — Folds the flap over the top. This is the default option.• Tuck Under — Folds the flap under the top.• Show Top Only — Shows the top without the flap.• Show Bottom Only — Shows the flap (bottom) without the top. <p> For additional tips on using this parameter, see “Considerations for 3D Shape Effects” on page 722.</p>

Additional Parameters for the Ball Shape

Parameter	Description
Radius	Changes the size of the ball. Values range from 0 to 100.
Curve	Gives the ball a 3D effect. A value of 0 looks like a flat circle (you can use this as a Circle Wipe). Higher values give more depth to the ball's shape. Values range from 0 to 100.
X Pos (X position)	Moves the shape to the right or left in relation to the image. The values range from -999 to 999, where 0 is the center of the image. Values increase to the right and decrease to the left.
Y Pos (Y position)	Moves the shape up or down in relation to the image. Values range from -999 to 999, where 0 is the center of the image. Values increase as you go down and decrease as you go up.
Aspct (aspect ratio)	Changes the shape from perfectly round to a distorted shape. Values range from -100 to 100, where 0 is a circle.
Angle	Rotates the axis of the shape. This effect is visible only when the aspect ratio is not zero. Values range from -180 to 180.
Shape Tracking	Lets you use a tracker to control changes to the Ball shape over time. Select a tracker from the Tracker Selector menu.

Additional Parameters for the Slats Shape

Parameter	Description
Ampl (amplitude)	Controls the distance the shape moves. Increase the amplitude to take the effect off the screen.
Angle	Changes the line along which the video pieces move. Values can range from -180 to 180. Use 0 for horizontal and 90 for vertical.
Freq (frequency)	Controls how many copies of the shape appear on the screen.
 <i>When you experiment with Slats, start with a Frequency value of 1 and an Amplitude of 0. This makes it easier to see how changes in these values affect the image. Change the Amplitude slider to make the slats move in opposite directions.</i>	
Offset	Repositions the shape on the image.
Sk Amp (skew amplitude)	Weaves the image through the slats. Think of this as weaving a “video cloth” through a loom.
Sk Angl (skew angle)	Rotates the image through the slats.

Considerations for 3D Shape Effects

Shape Effects and the Location of the Position Indicator


When you apply a shape effect, what you see in the Effect Preview monitor depends on the location of the position indicator in the clip. If the position indicator is at the start or end of the clip it might look as if the effect is missing.

Softening the Edges of a Page Fold

To soften the edges of a Page Fold effect, enable the Border parameter and adjust the Soft slider. You can soften a border of zero width. For more information, see [“Border \(3D\)” on page 705](#).

Examples of Page Fold Angle Values

The following illustration shows how your Avid editing application interprets several angle values for the Page Fold. Experiment with incremental angle values and with changing angle values at different keyframes.



Examples of Page Fold angles. Top, left to right: -45 degrees, 45 degrees, 135 degrees, -135 degrees. Bottom, left to right: -90 degrees, 0 degrees, 180 or -180 degrees, 90 degrees.

While you are experimenting with angle and offset values, it is useful to scale down the top video layer. This lets you see the full effect as the video peels off the screen. For example, scaling 75 percent in both X and Y axes displays the page fold as a Picture-in-Picture effect.

Controlling the Image on the Flap of a Page Fold

Use the Show Top Only and Show Bottom Only commands in the Tuck and Flap menu when you want to control the image in the flap or top. You commonly use these with two video channels. One channel shows the top and the other shows the bottom (the flap).

For example, if you want an opaque top and a partially transparent flap, set a transparency value for the video channel containing Show Bottom Only. Use the Opac. slider in the Foreground parameter category to adjust transparency.

Show Top Only and Show Bottom Only are also useful when you want to apply an effect such as Defocus on just the flap or the top.

Limitations of Ball Shape Effects

The following limitations apply to Ball shapes:

- You cannot apply the Z perspective to a Ball.
- The X and Y direct manipulation handles do not work for a Ball. Use the parameters in the Rotation parameter category instead.

Once you use the sliders to rotate a Radial effect in X or Y, no direct manipulation other than XY position works. To regain access to the direct manipulation Z handle, reset the X and Y Rotation sliders to 0.

Skew


Skew moves or tilts an image in the X or the Y direction.



Parameter	Description
X	Skews the image along the X axis. The orientation of the top and bottom edges remains fixed, while the left and right edges are tilted along the X axis into a parallelogram. Values range from -999 to 999, where 0 represents no change.
Y	Skews the image along the Y axis. The orientation of the left and right edges remains fixed, while the top and bottom edges are tilted along the Y axis into a parallelogram. Values range from -999 to 999, where 0 represents no change.

Spill Suppression

Spill Suppression replaces one color with another color. You can use Spill Suppression to correct spill in keys.




Parameter	Description
Target Color and Replace Color subcategories	Set the target and replacement colors. For more information on the parameter controls, see “Color Parameter Controls” on page 604 .
Use Key Color	Uses the chroma key color as the color to replace.
Gain	<p>Spill Suppression affects contiguous pixels that fall within the specified color range, or tolerance, of the color you select. You adjust the tolerance with the Gain slider. Values range from 0 to 63.</p> <p>Decreasing the Gain decreases the color range and includes fewer pixels contiguous to the color selection. Increasing the Gain expands the range and includes more pixels surrounding the color selection.</p>
Soft (softness)	Determines how colors contiguous to the selected color are processed in the effect. Colors that border the selected color are displayed as a blend of the original color and the replacement color. The higher the softness value, the more of the replacement color is blended with the original color. Use the Soft slider to improve the appearance of the edges of the keyed areas. Values range from 0 to 63.

Stamp

Stamp lets you put a video or graphic element into an independent Stamp buffer that allows the image to remain on screen after the effect’s segment has ended. You cannot render Stamp effects. For more information, see [“Creating a Stamp” on page 377](#).

RGB processing is not available for Stamp.



Two of the most common uses for Stamp are:

- Real-time title builds.
Reveal multiple text, graphic, and video elements and stamp them over or under the foreground image when they come to rest. Once the image is stamped, you can add more layers.
- Video montage.
Bring in a variety of video images, where each one stays in place as you continue to add new ones.



The Stamp, Shadow, and Trail parameters are mutually exclusive, so you can enable only one at a time.

Parameter	Description
Stamp Image	Lets you add the stamp on one or more keyframes.
Clear	Lets you clear the stamp buffer of everything in it.
Opac. (opacity)	Changes the stamp’s opacity. Values range from 0 (transparent) to 100 (opaque), where 100 is the default.
Foregnd. On Top (foreground on top)	Switches the image in the Stamp buffer to the background. If Foregnd. On Top is not enabled, the Stamp buffer is always in the foreground.

Target

Target changes the X,Y positioning and sizing and lets you maintain the current perspective.



Target is a post-transformation parameter. It is at the top of the hierarchy and affects objects after all the other parameters have affected it. If an object is rotated and has perspective added to it, Target moves the object without changing the relationship of the other parameters. Think of it as moving the entire 3D world where point of view does not change.


You can use Target in many cases as a global parameter. If you create an effect and want the whole effect to move higher across the frame or to appear inside another frame, such as a television on a set, use Target to move it. It is also good for offsetting another track slightly if you want to use a black graphics image as a drop shadow.

Parameter	Description
X	Moves the image along the screen's X axis (horizontally). Values range from -999 to 999, where 0 is the default.
Y	Moves the image along the screen's Y axis (vertically). Values range from -999 to 999, where 0 is the default.
Size	Scales the image and maintains the aspect ratio. Values range from 0 to 400, where 100 is the default scale of 100 percent.

Trail

Use Trail to add a trail to an effect as it moves across the screen. You do not see the trail when you step through the effect because it is a cumulative effect. You cannot render a Trail effect.

RGB processing is not available for Trail.



Parameter	Description
Decay	Changes the rate of the trail's decay, or dissipation, during the effect's motion. Values range from 0 (a quick decay) to 100 (a slower decay), where 75 is the default.
Use Sparkle	Instructs your Avid editing application to paint a trail with sparkles. When Use Sparkle is deselected, your Avid editing application paints a trail by using the image itself.

19 Understanding Color Correction Mode

This chapter provides an overview of the color correction capabilities of your Avid editing application, and information on how to control and customize the Color Correction user interface.

- [Overview of Color Correction](#)
- [Reasons for Making Color Corrections](#)
- [Entering and Exiting Color Correction Mode](#)
- [The Color Correction Monitors](#)
- [The Color Correction Tool](#)
- [Working with Color Correction Effect Templates](#)

Overview of Color Correction

Your Avid editing application's color correction features let you adjust the color characteristics of video material that you have edited into a sequence. Color corrections, like effects, do not change your original master clips or media files in any way. You can modify or remove color corrections at any time. If you correct a segment in one sequence, that correction does not affect the same video material in any other sequence.

Color Correction Mode

You make most color corrections by entering Color Correction mode and adjusting controls in the Color Correction tool. Each control affects a specific aspect of the color in an image (for example, saturation) so these controls are like parameter controls for effects in the Effect Editor. Some color correction controls look very similar to effect parameter controls, while others have a more specialized appearance suitable for precise color adjustment. For more information, see the remainder of this chapter.

Automatic and Manual Color Correction

You can make either automatic or manual corrections. Automatic corrections are simpler to use because your Avid editing application calculates and makes the adjustments needed to correct a problem in an image for you. Manual corrections require you to have a more detailed understanding of the color correction controls but allow for more precision and creativity. For more information, see [“Performing Color Corrections” on page 747](#).

Keyframing Color Corrections

You can animate most color correction adjustments using advanced keyframes. For more information, see [“Keyframing Color Corrections” on page 782](#).

The Color Correction Effect

You can perform some kinds of color corrections by applying the Color Correction effect from the Image category in the Effect Palette. For more information, see [“Using the Color Correction Effect” on page 797](#).

Playback and Rendering of Color Corrections

You can play color corrections in real time in the desktop monitors or on a Client monitor, subject to the same real-time playback constraints that affect the playback of other effects on your system. For more information, see [“Real-Time Playback of Video Effects” on page 151](#).

Depending on the model of your Avid editing application, your hardware configuration, and the complexity of your sequence, you might need to render some or all of your color corrections before you can export your sequence or perform a digital cut. For more information, see [“Basics of Effects Rendering” on page 53](#).

Safe Colors

You can set safe limits for color characteristics, for example, to ensure that the colors in your program meet a particular broadcaster’s standard for broadcast. Your Avid editing application displays warnings when your images exceed these limits, and you can make corrections to solve the problem. For more information, see [“Safe Colors” on page 813](#).

Reasons for Making Color Corrections

Before you can make good color corrections, you need to determine which color problems are present in your video material or decide why you might alter existing color values.

The two most common color problems are:

- Poor contrast (or a lack of a full range of tones).
For example, parts of an image that should be black are only dark gray. If an image does not have a good range of tones, details do not stand out sharply.
- Poor color balance (or a color cast).
For example, parts of an image that should be pure white are instead pinkish, or parts that should be pure blue are instead greenish-blue.

The automatic color correction controls are designed specifically to correct these two problems.

Apart from correcting for these two problems, the other main reasons to alter color values in your video material are:

- To make the color characteristics of adjacent segments in a sequence match.
For example, adjacent segments in a sequence might have been shot under slightly different lighting conditions, or using two cameras with different color balance settings.
- To achieve a particular artistic or editorial effect.
For example, you might want to slightly brighten or darken a whole sequence, or increase saturation to make a scene seem warmer, or alter color balance to make it seem as though a scene is lit by evening sunlight.

For a more complete introduction to the process of analyzing the color in your video and deciding how to adjust it, including illustrated examples of typical corrections, see [“Color Correction Techniques” on page 801](#).

Entering and Exiting Color Correction Mode

You need to enter Color Correction mode to access the color correction controls that you use for most color correction work.

To enter Color Correction mode, do one of the following:

- ▶ Select Toolset > Color Correction.
For more information on toolsets, see “Using Toolsets” in the Help.
- ▶ Click the Color Correction Mode button, for example, in the Timeline palette.



To exit Color Correction mode, do one of the following:

- ▶ Select a toolset other than Color Correction from the Toolset menu.
- ▶ Click a mode button other than Color Correction, for example, the Effect Mode button.


The Color Correction Monitors

The monitor window in Color Correction mode displays three monitors that let you compare several shots and analyze your images as you correct.


The Client monitor is also an important tool for color correction work.

Understanding Color Correction Monitors

In Color Correction mode, the monitor window contains three monitors. By default, the center monitor shows the frame at the current location of the position indicator, while the left and right monitors show the last frame of the segment preceding the current segment, and the first frame of the segment following the current segment. This arrangement lets you compare the color characteristics of adjacent shots in your sequence. The following illustration shows a typical default display.



When you move the position indicator to another segment in the Timeline, all three monitors update to show the new arrangement of previous, current, and next shots.



Example of default update behavior in the monitor window. Left: the position indicator is on segment B in the Timeline, and the three monitors display segments A, B, and C. Right: the position indicator has moved to segment C, and the three monitors have updated so that they now display segments B, C, and D.

In most respects, the monitors in Color Correction mode work like other monitors in your Avid editing application. For example, operations such as activating monitors, showing and hiding the video, displaying timecode information, and using the position bar are the same. For more information, start with “Viewing and Marking Footage” in the Help.

The monitor window in Color Correction mode displays wide-screen 16:9 video as well as standard format 4:3 video in the monitors, depending on your project’s aspect ratio setting. For more information, see “Changing the Aspect Ratio for an SD Project” in the Help.

You can customize image display in each of the three monitors by selecting from the monitor’s Source menu. For more information, see [“Customizing Image Display in Color Correction Monitors” on page 731](#).


Customizing Image Display in Color Correction Monitors

You can customize the type of image that displays in each monitor in Color Correction mode. For example, you can display segments other than the default previous, current, and next segments, or you can display the entire sequence in one monitor. You can also replace video image display with a waveform or vectorscope display to help you analyze images as you correct.

To configure the display in a monitor:

- Click the monitor’s Source menu, and select one of the commands described in [“Source Menu Commands in Color Correction Monitors” on page 731](#).

Source Menu Commands in Color Correction Monitors

Command	Description
Empty	Displays no image (black).
Entire Sequence	<p>Makes the entire sequence available in the monitor. This is useful when you want to compare shots from many different places in a sequence. For example, you can display the current segment and the next segment in two monitors for immediate shot-to-shot comparison and display the entire sequence in the third monitor so that you can quickly navigate to any other part of the sequence you want to view. When you change the current segment, the entire sequence updates to that segment.</p> <p> <i>You can use the Play Loop button in the Command palette to play the whole sequence in the active monitor even if the monitor is not set to Entire Sequence. For more information, see “Using the Play Loop Button in Color Correction Mode” on page 734.</i></p>


Command	Description
Reference	<p>Locks the current frame (the frame the position indicator is on) in the monitor. When the other monitors update as you navigate in the Timeline, this frame continues to display as a reference. This is useful if you want to use a specific place in your sequence as a reference against which to compare all other shots, for example, a segment that contains optimal skin tones.</p> <p>To lock the current frame as a reference, right-click in the monitor window or the Color Correction tool, and select Reference Current.</p>
Current	<p>Displays the current segment. This option is not available in the Source menu if another monitor is already set to Current.</p>
Previous	<p>Displays the segment immediately before the current segment.</p>
Next	<p>Displays the segment immediately after the current segment.</p>
Second Previous	<p>Displays the segment two segments before the current segment.</p>
Second Next	<p>Displays the segment two segments after the current segment.</p>
Waveform and Vectorscope commands	<p>These commands configure the monitor as a Waveform monitor or Vectorscope monitor. Your Avid editing application displays the information for the currently active monitor. For more information, see “Working with the Waveform Monitors and Vectorscope Monitor” on page 786.</p> <ul style="list-style-type: none">• Quad Display• RGB Histogram• RGB Parade• Vectorscope• Y Waveform• YC Waveform• YCbCr Histogram• YCbCr Parade

Adjusting the Dual Split Image Display in Color Correction Monitors

You can use the Dual Split button below a monitor to split the image display so that it shows the image before and after the current color correction adjustments are applied. For more information, see [“Using Monitor Buttons in Color Correction Mode”](#) on page 733.

Most Avid editing applications support the display of this split-screen view in the Client monitor as well as in the monitor window.

When Dual Split is on, the uncorrected image appears on the left and the image with currently active corrections applied appears on the right.



Uncorrected image (left, with triangular adjustment handles) and corrected image in a monitor with Dual Split active in Color Correction mode

To resize the box that contains the split-screen image:

- Drag one of the box's triangular handles in the monitor.

Using Monitor Buttons in Color Correction Mode

Some of the buttons beneath the monitors in Color Correction mode have the same functions as they do in other modes. Several other buttons perform functions specific to color correction.



Left to right: Dual Split button, Go to Previous Uncorrected Shot button, Go to Next Uncorrected Shot button, and Remove Effect button below a monitor in Color Correction mode

To move to the previous or next segment on the active track that does not already have a color correction applied:

- Click the Go to Previous Uncorrected Shot or Go to Next Uncorrected Shot button.

To remove the color correction on the current segment:

- Click the Remove Effect button.

To split the monitor display and show the image both with and without the correction applied:

- Click the Dual Split button.

To turn off Dual Split display:

- Click the Dual Split button.

Using the Play Loop Button in Color Correction Mode



The Play Loop button has a specialized function in Color Correction mode. The Play Loop button does not appear in the monitor window but does control the playback of material in the monitors. You can access the Play Loop button from the Play tab of the Command palette or from the keyboard if you map it to a keyboard location.

When you click the Play Loop button, your Avid editing application plays the whole sequence in the active monitor, starting from the current position of the position indicator. Playback is not limited to the current segment alone, regardless of the Source menu command selected for the monitor. This is useful whenever you want to view the whole sequence quickly without switching monitors or making a new Source menu choice.

The Client Monitor in Color Correction Mode

If you have a Client monitor connected to your Avid editing application, you can see your corrections in the Client monitor. In most Avid editing applications, the dual split display also appears in the Client monitor when you have Dual Split selected for the current monitor. It is a good idea to use a Client monitor to view your color correction work because a Client monitor displays video colors more accurately than your computer screen.


The Color Correction Tool

In Color Correction mode, you adjust color using the Color Correction tool. The Color Correction tool is also where you control how much and what kind of material you are correcting at any one time.

Controls in the Color Correction tool are organized in tabs. The default display shows the controls in the Hue Offsets tab within the HSL (Hue, Saturation, Luminance) tab. The controls in this tab provide one set of tools to correct contrast and color balance problems.

The other two available tabs (the Controls tab within the HSL tab, and the Curves tab) provide additional sets of controls. For complete information on all color correction controls and other features in the Color Correction tool, see [“The HSL \(Hue, Saturation, Luminance\) Group” on page 762](#), and [“The Curves Group” on page 770](#).


The following illustration shows the Color Correction tool in its default configuration.



Components of the Color Correction tool in its default configuration. Top left: group tabs. Top right: Color Correction Tool buttons. Bottom, left to right: subdividing tabs, slider controls and Enable buttons, Color Match control and Color Correction buckets.

Understanding the Group and Subdividing Tabs

Your Avid editing application provides two groups of color correction controls, the HSL (Hue, Saturation, Luminance) group and the Curves group. The controls for each group are organized in a group tab. The HSL group tab has two further subdividing tabs on the left side of the tool that subdivide the controls for that group. The Curves group has no subdividing tabs. The following illustration shows the group and subdividing tabs.



Tabs in the Color Correction tool: HSL (left) with Controls and Hue Offsets subdividing tabs below, and Curves (right)

You can make both automatic and manual adjustments using one or both groups of controls. If you make adjustments in both groups, you can turn either group on or off independently to control which adjustments are active. When you view the sequence or render the Color Correction effect, your Avid editing application applies the adjustments from the active groups to create the final appearance. For more information on the interaction between the two groups, see [“Understanding Interaction Between Color Correction Groups” on page 736](#).

Each group uses a different kind of control for making adjustments. The HSL group provides controls for adjusting attributes such as hue, saturation, gain, and gamma. The Curves group lets you manipulate points on a graph that control the relationship between input and output color.

For detailed information on adjusting color using the controls within the color correction groups, see [“Performing Color Corrections” on page 747](#).

Displaying Group and Subdividing Tabs

To display a color correction group tab:

- Click the tab in the area containing the group name.



Do not click the Enable button when you want to display a color correction group tab.



Click the named area of a tab to display it

The tab is highlighted and moves to the front, and the specific controls for that tab appear.

Before clicking the Curves tab to display it. The Curves tab name appears dimmed, and the tab displays behind the currently active HSL tab. The active HSL tab appears blue.

After clicking the Curves tab to display it. The Curves tab appears blue, and the tab displays in front of the other group tabs. The curves controls are now visible in the tab.

To switch between group tabs using the keyboard:

- Press the Page Up key or the Page Down key.

To display an HSL subdividing tab:

1. Click the HSL group tab in the area containing the group name.
2. Click the subdividing tab in the area that contains the subdivision name.


The subdividing tab is highlighted and moves to the front, and the specific controls for that tab appear.

Understanding Interaction Between Color Correction Groups

It is important to understand how the color correction groups work together. Your Avid editing application applies adjustments that you make in each group cumulatively to the current segment and its related material. If you make an adjustment in one group and then make another in a different group, the image shows the cumulative effect of both adjustments.

This behavior provides you with a great deal of flexibility. For example, if you are unhappy with some of your adjustments, you can disable the group that contains those adjustments or reset its controls to default settings without disrupting other adjustments.

The following illustration shows an example of this kind of control over color correction groups.



Example of control over Color Correction groups. The Green and Blue ChromaCurve graphs are adjusted, but the Curves tab is turned off (the Enable button is off in the tab at the top), so the graph adjustments do not currently apply to the segment. Because the HSL tab is turned on, any adjustments in the HSL tab do currently apply to the segment, even though the HSL controls are not currently visible.

For more information on enabling, disabling, and resetting the groups, see [“Working with the Enable Buttons”](#) on page 737.



If you make adjustments in both groups, keep in mind how the cumulative adjustments affect the final image. Adjustments might accumulate, or cancel each other out, in ways that you do not want. Keep each stage of your correction distinct, and do not duplicate the same adjustment in both groups.

Working with the Enable Buttons

In the Color Correction tool, each group tab, subdividing tab, and individual control has an Enable button. These buttons provide an immediate visual guide to the status of the controls while you are making corrections. They also let you turn controls on and off in various combinations and quickly reset controls to their default values.

You cannot reset controls that are not currently displayed. If you Alt+click (Windows) or Option+click (Macintosh) the Enable button for a tab whose controls are not currently displayed, you display the controls but do not reset them. Alt+click (Windows) or Option+click (Macintosh) the button again to reset the controls.



Adjustments to the Gain, Gamma, and Setup controls in the Hue Offsets subtab of the HSL tab enable both the Hue Offsets and the Controls subtabs. This behavior is not consistent with the normal interaction between Enable buttons but is necessary to ensure that color corrections conform correctly if you move your project to an Avid Symphony system. To turn off adjustments to the Gain, Gamma, and Setup controls you must disable the controls individually by clicking one or more of their Enable buttons, or you must disable the entire HSL tab by clicking the HSL tab Enable button.

To turn a control or tabbed group of controls on, do one of the following:

- ▶ Click the Enable button for the control or tabbed group of controls.
- ▶ Adjust any individual control that is linked to the Enable button.

The Enable button highlights, and the control or tabbed group of controls becomes active. Your Avid editing application includes the adjustments in that control or group of controls when calculating the corrected color.

To turn a control or tab off:

- ▶ Click the Enable button for the control or tab.

The Enable button is no longer highlighted.

To reset a control or a tabbed group of controls to its default values:

1. Display the control or group of controls you want to reset.
2. Alt+click (Windows) or Option+click (Macintosh) the Enable button for that control or group of controls.

All controls linked to that button return to their default values.


Understanding Interaction Between Enable Buttons

The Enable buttons in the Color Correction tool are linked in a hierarchical relationship that mirrors the relationship of the tabs themselves. When you change the status of an Enable button, the change can affect several levels of the hierarchy.

When you Alt+click (Windows) or Option+click (Macintosh) an Enable button to reset controls, you automatically reset all controls at a lower level in the hierarchy. For example, if you Alt+click (Windows) or Option+click (Macintosh) the Enable button for the Red ChromaCurve™ graph in the Curves tab, only that one control resets to its default value. However, if you Alt+click (Windows) or Option+click (Macintosh) the Enable button for the Curves tab, all the controls in the Curves tab reset to their default values.

When you turn an Enable button off, your Avid editing application stops including controls below that button in the hierarchy when it calculates the corrected color for the segment. Individual controls below that button retain their values and can be reactivated at any time. Their Enable buttons remain highlighted.

In the following illustration, the Curves tab Enable button is turned off, so none of the adjustments in the Curves tab apply to the correction. Individual controls inside the tab retain their values, so you can reactivate them by clicking the Curves tab Enable button again.



Using the Color Correction Tool Buttons

In addition to the Enable buttons, and specific control buttons within groups, the Color Correction tool has a group of buttons on the right side that control several important operations.



Color Correction Tool buttons. Left to right: Effect Mode button, Color Correction Effect Template button, Correction Mode Settings button, Safe Color Settings button, Comments button.

Use these buttons to:

- Switch to Effect mode.
For more information, see [“Displaying the Effect Editor with Color Correction Mode” on page 783](#).
- Create Color Correction effect templates.
For more information, see [“Working with Color Correction Effect Templates” on page 742](#).
- Customize the operation of color correction.
For more information, see [“Customizing Color Correction Mode Settings” on page 740](#).
- Set Safe Color limit values.
For more information, see [“Safe Colors” on page 813](#).
- Add comments to color-corrected segments.
For more information, see [“Adding Comments to Color Correction Effects” on page 741](#).

Customizing Color Correction Mode Settings

You can customize the appearance and behavior of Color Correction mode by selecting options in the Correction Mode Settings dialog box.

To customize Color Correction mode:

1. Do one of the following:



- ▶ In the Color Correction tool, click the Correction Mode Settings button.
- ▶ In the Settings tab of the Project window, double-click Correction.

The Correction Mode Settings dialog box opens.

2. Select the options you want, as described in [“Correction Mode Settings” on page 740](#).
3. Click OK.

Correction Mode Settings

Tab	Option	Description
Features	Saved Color Labels	Controls how custom colors are named in bins. For information on saving custom colors, see “Saving Custom Colors to a Bin” on page 761 . <ul style="list-style-type: none">• None: Your Avid editing application does not supply a name.• RGB: Your Avid editing application uses the 8-bit values for the red, green, and blue components as the name.• Name: Your Avid editing application uses the name from the standard HTML color scheme that most closely matches the color you are saving.• Name and RGB: Your Avid editing application uses both the Name and the RGB information. This is the default option.
	Eyedropper 3 x 3 Averaging	When this option is selected, your Avid editing application calculates the color value to pick by averaging the values of a 3 x 3 sample of pixels centered on the eyedropper’s position. This is often useful for picking up a color accurately by sight because it compensates for shifts in color value from one pixel to another. When this option is deselected, the system selects the color value of the exact pixel at the eyedropper’s position.
	Show Eyedropper Info	When this option is selected, the numerical RGB values appear on the color swatches in the Color Match controls.
	Eyedropper Picks from Anywhere in Application	When this option is selected, the eyedropper can pick a color from anywhere in your Avid editing application’s interface, for example the swatch for a custom color in a bin.

Tab	Option	Description
AutoCorrect		Defines the automatic color corrections your Avid editing application makes when you apply the Color Correction effect from the Effect Palette. For more information, see “AutoCorrect Options” on page 798 .

Adding Comments to Color Correction Effects

You can add comments to color-corrected segments to assist you in your work. For example, you might want to briefly note the type of adjustment for a segment or to make notes during a preliminary correction pass of ideas for adjustments to perform later during a final pass.

The Comments button indicates whether a comment is present on a segment.



If the position indicator is on a segment that has a comment, the icon on the Comments button is yellow.



If the position indicator is on a segment that has no comment, the icon on the Comments button is not yellow.

To add a comment to a segment:


1. In Color Correction mode, move the position indicator to the segment to which you want to add a comment.

For information on entering Color Correction mode, see [“Entering and Exiting Color Correction Mode” on page 729](#).



2. In the Color Correction tool, click the Comments button.

The Comments dialog box opens.



3. Type your comment in the text window, and click OK.

To remove a comment:

1. In Color Correction mode, move the position indicator to the segment from which you want to remove the comment.

For information on entering Color Correction mode, see [“Entering and Exiting Color Correction Mode” on page 729](#).

2. In the Color Correction tool, click the Comments button.
The Comments dialog box opens.
3. Click Remove.

To view or edit a comment in the Comments dialog box:

1. In Color Correction mode, move the position indicator to the segment for which you want to view the comment.

For information on entering Color Correction mode, see [“Entering and Exiting Color Correction Mode” on page 729](#).

2. In the Color Correction tool, click the Comments button.
The Comments dialog box opens and displays the text of the comment.
3. (Option) To edit the comment, click in the text window and make your edits using standard word processing procedures.

To display comments in the Timeline:

- ▶ Click the Timeline Fast Menu button, and select Clip Text > Comments.
Your Color Correction comments appear in the Timeline.

Working with Color Correction Effect Templates

Your Avid editing application offers the following versions of Color Correction effect templates:

- The Color Correction buckets provide an easily accessible location within the Color Correction tool for the short-term storage of Color Correction effect templates.
- The Color Correction Effect Template button lets you create a template for any color correction and save it to a bin in the same way that you save other kinds of effect templates. The Save Correction button in the CC tab of the Command palette performs the same function.

Like templates for other effects, Color Correction effect templates save all the adjustment values for a color correction so you can apply those values quickly to another segment. You can apply all the values at once by dragging the template into the monitor containing the

current segment, or you can apply the values for the controls in a single tab in the Color Correction tool by dragging the template onto the tab that contains the group of controls you want to change.

You can also apply a Color Correction effect template to multiple segments at once by selecting the segments and then double-clicking the effect template icon in the bin or in the Effect Palette. To do this, you must be in editing or Effects mode.

You can also save custom colors to bins. For more information, see [“Saving Custom Colors to a Bin” on page 761](#).

How Color Correction Effect Templates Save Settings

When you create a Color Correction effect template, your Avid editing application saves all the Color Correction settings for the segment. Your Avid editing application remembers both the values set for each control and the status of each Enable button.

Templates that you save to a bin or a bucket do not update when you make new adjustments to the segment. To save new adjustments, you must save a new template to a bin or a bucket.



You can specify which settings you apply in a template by dragging the template to the active tab in the Color Correction tool. This changes only those settings contained within that tab. Using this method, you can, for example, apply settings one tab at a time without applying any other settings that are also in the template.

Saving a Color Correction Effect Template to a Bin

You can save a Color Correction effect template to a bin using either the Color Correction Effect Template button in the Color Correction tool or the Save Correction button in the CC tab of the Command palette.

Color correction templates that you save to a bin are saved permanently, unlike templates you save to a bucket, which are not saved beyond the current working session.

To save a Color Correction effect template to a bin:

1. In Color Correction mode, ensure that the position indicator is in the segment that contains the settings you want to save.

For information on entering Color Correction mode, see [“Entering and Exiting Color Correction Mode” on page 729](#).

2. Do one of the following:



- Click the Color Correction Effect Template button, press and hold the mouse button, and then drag the effect icon to a bin.

sc

- ▶ With Active Palette selected in the Command palette, click the Save Correction button in the CC tab.
- ▶ If the Save Correction button is mapped to a key, press that key.

A new effect template appears in the bin, containing all the color correction adjustment values for the segment. The new effect template is identified in the bin by its effect icon. By default, your Avid editing application names the template using the clip name of the segment. Effect icons for open bins also display in the Effect Palette.

3. (Option) To rename the template, click the template name and type a new name.

To permanently save a color correction effect template currently stored in a bucket:

- ▶ Click the color correction icon in the bucket and drag it to a bin.

For more information, see [“Saving a Color Correction Effect Template to a Bucket” on page 744](#).

Saving a Color Correction Effect Template to a Bucket

The Color Correction tool contains eight *buckets*, located below the Color Match control, that you can use to save Color Correction effect templates for the duration of a working session. You can then apply the template quickly to any segment.

The buckets are initially labeled C1 through C8. When you fill a bucket with a Color Correction effect template, a Color Correction icon appears on the bucket.

Color Correction effect templates that you save to buckets do not remain from one session to another. When you end your session, your Avid editing application deletes the templates. However, you can save an effect template from a bucket permanently by dragging it to a bin. For more information, see [“Saving a Color Correction Effect Template to a Bin” on page 743](#).



The Color Correction buckets are also available as buttons in the CC tab of the Command Palette. You can map these buttons to any mappable key on your keyboard or to any mappable button location in the user interface. For more information, see “The Command Palette” in the Help.



Examples of Color Correction buckets. Left: all buckets empty. Right: buckets C1 and C2 filled.

To save a Color Correction effect template in a bucket:

1. In Color Correction mode, ensure that the position indicator is in the segment that contains the settings you want to save.

For information on entering Color Correction mode, see [“Entering and Exiting Color Correction Mode” on page 729](#).

2. Alt+click (Windows) or Option+click (Macintosh) the bucket in which you want to save the template.

You can click any one of the eight buckets to save to it. Empty buckets have a label that begins with the letter “C,” for example, C5. Buckets that already contain a template have a Color Correction icon. If you Alt+click (Windows) or Option+click (Macintosh) a bucket that already contains a template, you overwrite the previous template with the new adjustment values.

Your Avid editing application saves the values as a template. If the bucket was previously empty, a Color Correction icon replaces the “C” label on the bucket.

Clearing Color Correction Effect Templates from Buckets

You can clear a Color Correction effect template from a bucket without having to overwrite the template with a new one.

To clear a Color Correction bucket of its saved correction during an editing session:

- ▶ Move the position indicator to any uncorrected segment in the Timeline and then Alt+click (Windows) or Option+click (Macintosh) the bucket.

Your Avid editing application clears the template information from the bucket. A label beginning with the letter “C,” for example, C3, replaces the Color Correction icon on the bucket.

Applying Color Correction Effect Templates

To apply all adjustment values in a Color Correction effect template to the current segment, do one of the following in Color Correction mode:

- ▶ Click the effect icon for the template in the bin, the Effect Palette, or the Color Correction bucket, and drag it to the monitor containing the current segment.

For information on entering Color Correction mode, see [“Entering and Exiting Color Correction Mode” on page 729](#).



For tips on working with templates in the Effect Palette, see [“Saving a Color Correction Effect Template to a Bin” on page 743](#).

- ▶ Select the template in the bin or the Effect Palette, and then press Enter (Windows) or Return (Macintosh).
- ▶ Click the appropriate Color Correction bucket.
- ▶ If you have mapped the Color Correction bucket to the keyboard, press the appropriate key.

Your Avid editing application applies all the Color Correction adjustments in the template to the segment that is the current location of the position indicator.

To apply adjustment values from a Color Correction effect template selectively to a single tab of color correction controls:

1. In the Color Correction tool, click the tab to which you want to apply the template.
2. Click the effect icon for the template in the bin, the Effect Palette, or the Color Correction bucket, drag it to the tab, and drop it anywhere in the tab.

The controls in that tab update to reflect the values in the template. Other color correction controls are not affected.

If you apply template settings to a subdividing tab in the HSL group, the image in the monitor does not reflect those settings until you enable the HSL group tab.

If you apply a saved Color Correction effect template to a segment that already has a color correction, you overwrite the existing correction. The existing Color Correction settings are lost. Make sure you want to replace the existing correction before you apply a saved Color Correction effect template to a clip that already has a correction. You can use the Undo command to undo the effect of a Color Correction effect template. However, once the Undo command is no longer available, you cannot recover the original Color Correction settings.

To apply all adjustment values in a Color Correction effect template to multiple segments:

1. In editing or Effect mode, select the segment to which you want to apply the Color Correction effect template.

For more information, see [“Applying Effects From the Effect Palette” on page 36](#).

2. Open the bin that contains the Color Correction effect template.
3. Double-click the Color Correction effect template icon in the bin or in the Effect Palette.

Your Avid editing application applies the Color Correction effect template to each of the selected segments.

20 Performing Color Corrections

This chapter describes procedures for making color corrections, and includes complete descriptions of all controls in the Color Correction tool.

- [General Workflow for Making Color Corrections](#)
- [Using Automatic Color Corrections](#)
- [Using the Color Match Control](#)
- [The HSL \(Hue, Saturation, Luminance\) Group](#)
- [The Curves Group](#)
- [Keyframing Color Corrections](#)
- [Working with the Waveform Monitors and Vectorscope Monitor](#)
- [Applying Color Corrections to an Entire Sequence](#)
- [Using the Color Correction Effect](#)

General Workflow for Making Color Corrections

The color correction tools in your Avid editing application give you a great deal of flexibility when you make color corrections. Your exact workflow depends on your individual methods, your degree of familiarity with the color correction controls, and the requirements of your project. However, the basic steps to take when making a correction are similar for all users.

The following steps outline a typical color correction operation. You can change the order in which you perform or repeat steps to meet your particular needs.



In general, do not make Source relationship corrections and Program relationship corrections as part of the same corrective operation, or use Program corrections for your first color correcting pass. If you do, you lose flexibility and control for later stages of your project and you reduce the power of the color correction tools. Even if you expect to need

only one color correction pass, you should make that pass using Source relationships. If your needs for the project change, you can still make a second set of corrections using Program relationships.

1. In Source/Record mode (editing mode on NewsCutter systems), load the sequence.
2. Enter Color Correction mode.
3. (Option) If necessary, configure the toolset and adjust Correction Mode Settings to suit the requirements of your project and editing style.

For more information, see [“Understanding Color Correction Mode” on page 727](#) and [“Customizing Color Correction Mode Settings” on page 740](#).

4. Preview the material in the sequence to develop a sense of the kinds of corrections that you need and your approach to making them.

For example, you might look for a shot to use as a reference for your adjustments and lock that shot in one of the monitors.



You might prefer to preview extensively and plan your corrections in advance. If you have more color correcting experience, you might prefer to work by moving back and forth frequently between making corrections and assessing the material on which they are working.

5. Make sure that the Record Track button for the track on which you want to make corrections is the topmost selected button in the Track Selector panel in the Timeline.
You can color correct any number of tracks, including nested tracks by stepping into the nest. However, you can correct only one track at a time. Color correction is applied to the topmost selected track in a sequence.
6. Use the monitor window buttons or the position indicator in the Timeline to move to a segment you want to correct.
7. Click the appropriate tabs in the Color Correction tool to display the controls you want to use to make the correction.

For more information, see [“Understanding the Group and Subdividing Tabs” on page 735](#).

8. Use the automatic color correction features or adjust the color correction controls manually until you are satisfied with the correction.

Remember that you can make successive adjustments using several different groups of controls and selectively turn them on and off while you assess their effect on the segment. You can use the Dual Split button in the monitors to view corrected and uncorrected images side by side.

9. (Option) Use the advanced keyframe interface in the Effect Editor to animate the correction.

For more information, see [“Keyframing Color Corrections” on page 782](#).

10. (Option) Add a comment for the correction.
11. Repeat steps 5 through 11 for each segment you want to correct.
12. When you are satisfied with the corrections throughout the sequence, exit Color Correction mode and return to other editing operations.

Using Automatic Color Corrections

The Color Correction tool lets you make automatic color corrections to correct contrast problems, balance color, or remove color casts by identifying areas of an image that should be color neutral.

You can also apply up to three automatic color corrections in a single operation by selecting options in the AutoCorrect tab of the Correction Mode Settings dialog box and applying the Color Correction effect from the Effect Palette to one or more segments in a sequence.

The Color Match control also corrects automatically by adjusting an image so that a poor color value matches a better one. You select the colors on which you want Color Match to operate using an eyedropper. For more information, see [“Using the Color Match Control” on page 756](#).

Understanding Automatic Color Correction

Automatic color correction simplifies the work of correcting common color problems in video images. When you use an automatic color correction, your Avid editing application analyzes the existing color characteristics of an image and adjusts color correction controls to either eliminate or significantly reduce a specific color problem.

You often want to begin your color correction work by using automatic color corrections. Automatic corrections are especially useful when you do not have time for detailed manual adjustments, if you only need to correct basic color problems such as color casts, or if you lack experience with the manual controls in the Color Correction tool.

Automatic color correction adjusts controls in the Color Correction tool just as you would when making manual corrections, so you can make additional adjustments manually if you need to fine-tune a correction. Also, automatic color corrections can help you learn how to recognize color problems in images and what kinds of adjustments you might make to correct images manually. For example, if the Auto Balance automatic correction in the Hue Offsets subdividing tab adjusts an image by adding yellow in the ChromaWheels, then your Avid editing application determined that the image has a blue color cast.

Automatic color corrections operate within normal limits for legal video levels. For example, an automatic color correction does not make an adjustment that takes a significant area of an image beyond legal luminance levels.

Considerations When Using Automatic Color Correction

Although automatic color corrections are much simpler to learn and perform than manual corrections, practice and experience still improves your ability to correct a range of images with different color characteristics. If one set of automatic corrections does not produce good results, remove it and try a different combination. Remember also that some images might require manual correction in addition to or instead of automatic correction.

The following tips and suggestions can help you to achieve the best possible results when using automatic color correction:

- The Auto Contrast correction is most useful for images that should have areas of strong highlight (white or close to white) and areas of strong shadow (black or close to black). If you make an Auto Contrast correction on an image that does not need a full tonal range (many close-ups fall into this category), the correction might introduce too much contrast. When an image requires strong highlights but not strong shadows (or the reverse), you can use the Auto White or the Auto Black button to set the white or black point without making the overall range of tones too extreme.
- When you perform both an Auto Contrast and an Auto Balance correction, the order in which you perform the two corrections affects the final quality. For most images, you achieve the best results by doing the following:
 - In the Hue Offsets subdividing tab of the HSL tab, use Auto Contrast first, and then use Auto Balance.
 - In the Curves tab, use Auto Balance first, and then use Auto Contrast.
- There is usually no gain in performing an automatic correction more than once on the same image, even if you make the second correction in a different group from the first. For example, after you perform an Auto Balance in the Curves tab, you do not usually see any improvement in the color balance of the image if you perform a second Auto Balance either in the Curves tab or in the Hue Offsets subdividing tab of the HSL tab.
- If an Auto Contrast and Auto Balance combination improves an image but some color cast remains, you can often fine-tune the correction using one or more of the Remove Color Cast buttons.
- Automatic corrections you make in the Hue Offsets subdividing tab of the HSL tab and those you make in the Curves tab do not produce identical results for most images, and sometimes produce very different results. This is because the methods for calculating the corrections are different and the controls in the two tabs operate differently. Automatic corrections in the Curves tab often work well for correcting basic problems caused by incorrect camera color balancing. Automatic corrections in the Hue Offsets

subdividing tab of the HSL tab are often better for more extreme problems such as bad lighting conditions. However, there are no rules that cover all situations. If automatic correction in one color correction group does not yield good results, remove it and try a correction in the other group.

Adjusting Contrast and Balance Automatically

You can adjust the contrast and balance the color automatically for an image simply by clicking buttons. An automatic contrast adjustment expands the tonal range of the image, which usually improves sharpness and detail. An automatic balance adjustment evens out the influence of the different color channels in the image, which usually greatly reduces or even eliminates any color cast.

Automatic contrast and balance buttons appear in the Color Correction tool as shown in the following illustrations.



Left to right: Auto Balance button, Auto Black button, Auto Contrast button, and Auto White button in the HSL > Hue Offsets tab



Auto Balance button (center) and Auto Contrast button (right) in the Curves tab

To make an automatic color correction in the Hue Offsets tab:

1. Enter Color Correction mode, for example, by selecting Toolset > Color Correction.
2. In the Timeline, ensure that the Record Track button for the video track on which you want to make corrections is the topmost selected track.
3. In the Timeline or in the monitor window, navigate to the segment you want to correct.
4. In the Hue Offsets tab of the Color Correction tool, click one of the Automatic Color Correction buttons.

For more information, see [“Automatic Color Correction Buttons in the Hue Offsets Tab” on page 752](#).

To make an automatic contrast or balance adjustment in the Curves tab:

1. Enter Color Correction mode, for example, by selecting Toolset > Color Correction.
2. In the Timeline, make sure that the Record Track button for the video track on which you want to make corrections is the topmost selected track.
3. In the Timeline or in the monitor window, navigate to the segment you want to correct.





4. In the Curves tab of the Color Correction tool, click either the AutoBalance or the AutoContrast button.


Option	Description
Auto Balance	Makes adjustments to the Red, Green, and Blue curves to balance the colors in the image. This eliminates any color cast for most images.
Auto Contrast	Makes an adjustment to the Master curve to maximize the tonal range in the image. The brightest areas of the image become as bright as possible and the darkest areas of the image become as dark as possible.

Your Avid editing application analyzes the currently selected frame in the segment and adjusts the appropriate color correction controls.

Automatic Color Correction Buttons in the Hue Offsets Tab

The following table describes the automatic color correction buttons available in the Hue Offsets tab of the Color Correction tool.

Button	Icon	Description
Auto Balance		Balances the colors in the image (eliminating any color cast for most images). Adjusts all three ChromaWheel controls.
Auto Black		Makes the darkest areas of the image as dark as possible. Adjusts the Setup slider control.
Auto White		Makes the brightest areas of the image as bright as possible. Adjusts the Gain slider control.
Auto Contrast		Maximizes the tonal range in the image, making the brightest areas of the image as bright as possible and the darkest areas of the image as dark as possible. Adjusts the Gain and Setup slider controls.

 *The four automatic color correction commands described in this table are also available as buttons in the CC tab of the Command Palette. You can map these buttons to any mappable key on your keyboard or to any mappable button location in the user interface. For more information, see “The Command Palette” in the Help.*


Understanding the Remove Color Cast Buttons

You can remove a color cast automatically by clicking a Remove Color Cast button and using an eyedropper to identify an area in your image that you want to be color neutral (white, black, or a shade of gray). Your Avid editing application analyzes the current color

characteristics of the area you select and then adjusts color correction controls to make that area color neutral. For step-by-step instructions, see [“Using the Remove Color Cast Buttons” on page 754](#).

Remove Color Cast buttons provide more precise control over color cast removal than Auto Balance buttons because their adjustments are limited either by luminance range or by the impact that they have on existing curve graphs. However, Remove Color Cast buttons are only useful when you are working with an image that has areas that should be color neutral.

Remove Color Cast buttons appear in the Color Correction tool as shown in the following illustrations.



Remove Color Cast button below a ChromaWheel color wheel in the HSL > Hue Offsets tab



Remove Color Cast button in the Curves tab

Each ChromaWheel Remove Color Cast button is associated with the wheel above it. When you use the button, your application adjusts only that wheel, so only the parts of the image that fall within the luminance range controlled by that wheel change. You choose which ChromaWheel to adjust based on the luminance level of the area you want to identify, as follows:

- To make white or light gray areas of an image color neutral and remove a cast throughout the lightest part of the image, use the Remove Color Cast button below the Highlights ChromaWheel.
- To make mid-gray areas of an image color neutral and remove a cast throughout the midtones of the image, use the Remove Color Cast button below the Midtones ChromaWheel.
- To make black or dark gray areas of an image color neutral and remove a cast throughout the darkest parts of the image, use the Remove Color Cast button below the Shadows ChromaWheel.

The Curves tab Remove Color Cast button works by adding a point to each of the Red, Green, and Blue curves that makes the area you identify with the eyedropper color neutral. You can use the Curves tab Remove Color Cast button repeatedly to identify multiple areas that you want to be color neutral. Each new use adds another point to each of the three curves. (You can add new points up to the 16 point limit. However, once several points are distributed along the curve, further points are unlikely to improve the image significantly).

The effect of each added point on the image as a whole varies depending on the shape of the entire curve. In general, each new point affects the image most in areas with similar luminance values to the area you identify with the eyedropper, and affects the image least in areas with very different luminance values.

Using the Remove Color Cast Buttons

To use a Remove Color Cast button:

1. Enter Color Correction mode, for example, by selecting Toolset > Color Correction.
2. In the Timeline, make sure that the Record Track button for the video track on which you want to make corrections is the topmost selected track.
3. In the Timeline or in the monitor window, navigate to the segment you want to correct.
4. Do one of the following:



- ▶ Click the Remove Color Cast button below a ChromaWheel in the Hue Offsets subdividing tab of the HSL tab.



- ▶ Click the Remove Color Cast button in the Curves tab.

The button appears highlighted.

5. Drag the pointer into the image.

The pointer changes to an eyedropper.

6. Continue to drag the eyedropper until it is over the part of the image you want to become color neutral, and then release the mouse button.

Your Avid editing application analyzes the part of the image you have identified and adjusts the controls to remove the color cast.

Correcting Color Automatically Using the Color Correction Effect

You can use the Color Correction effect in the Effect Palette to apply up to three automatic color corrections at one time simply by applying the effect to selected segments just like any other Avid effect.

Because you do not have to use any controls in the Color Correction tool, or even enter Color Correction mode, this is the simplest way to correct basic color problems on any or all of the segments in your sequence.

For more information on working with the Color Correction effect, see [“Using the Color Correction Effect” on page 797](#).


You determine which automatic color corrections your Avid editing application makes by setting options in the AutoCorrect tab of the Correction Settings dialog box. A common setting that often solves most basic color problems applies two automatic corrections, one to correct contrast and one to correct color balance. The procedure in this topic describes how to set up this setting. For information on the full range of options for the type and number of automatic corrections that you can set, see [“Selecting AutoCorrect Options” on page 798](#).

To set basic AutoCorrect options:

1. Do one of the following:

- ▶ In the Settings tab of the Project window, double-click Correction.
- ▶ In the Color Correction window, click the Correction Mode Settings button.

The Correction Mode Settings dialog box opens.



Top to bottom: First Correction menu, Second Correction menu, and Third Correction menu in the Correction Mode Settings dialog box

2. Click the AutoCorrect tab.
3. Click the First Correction menu and select HSL Auto Contrast
4. Click the Second Correction menu and select HSL Auto Balance
5. Ensure that the Third Correction menu is set to Nothing.

To correct a single segment with the Color Correction effect:

1. In Source/Record mode (editing mode on NewsCutter systems), Effect mode, or Color Correction mode, click the Effect tab in the Project window.
2. In the Effect Palette, click the Image category.
3. Click the Color Correction Effect icon, and drag it to the segment in the Timeline to which you want to apply corrections.



To correct multiple segments with the Color Correction effect:

1. In Source/Record mode (editing mode on NewsCutter systems) or Effect mode, select the segments in the Timeline that you want to correct.

For more information on selecting multiple segments, see “Selecting and Deselecting Segments” in the Help.

2. Click the Effect tab in the Project window.
3. In the Effect Palette, click the Image category.



4. Double-click the Color Correction Effect icon.

Using the Color Match Control

Each Color Correction group includes a Color Match control. This control lets you quickly make a correction by selecting input and output colors from your images, from the Windows Color dialog box, or from the Macintosh® Colors panel. If “Eyedropper Picks from Anywhere in Application” is selected in the Correction Mode Settings dialog box, you can also select colors from any other location within your Avid editing application, such as a custom color swatch saved in a bin.

When you use the Color Match control, your Avid editing application replaces the input color value with the output color value and adjusts all the other color values in the image proportionally. Your Avid editing application also automatically adjusts the other controls in the group to reflect the change. You can set the combination of color channels or components your Avid editing application uses to determine the match by making menu selections.

For example, if you want to replace the blue sky tone in one image with that in another to match the two shots, you can use the Color Match control to pick the two colors and automate the color adjustment. For more information, see [“Making a Correction with the Color Match Control” on page 757](#) and [“Match Type Options” on page 759](#).

When you are working in the Curves group, the Color Match control also includes the NaturalMatch™ feature. NaturalMatch lets you replace the hue values in an image with new output values without distorting the saturation and luminance values in the image. For more information, see [“Understanding NaturalMatch” on page 760](#) and [“Color Match Example Using NaturalMatch” on page 760](#).

You can also save colors to a bin as custom colors that you can drag into the Color Match control at any time. If “Eyedropper Picks from Anywhere in Application” is selected, you can also select a custom color from its swatch in the bin using the eyedropper. For more information, see [“Saving Custom Colors to a Bin” on page 761](#).

Because the Color Match control can display the RGB color values for any point in an image, it is also useful as an information palette that lets you check how far the colors in an area of an image depart from the color values you want to achieve. For more information, see [“Getting RGB Information Using the Color Match Control” on page 762](#).

Making a Correction with the Color Match Control

The following illustration shows the Color Match control.



Components of the Color Match control: input color swatch (top left), output color swatch (top right), Match Type button (center), Match Color button (bottom)

To make a correction using the Color Match control:

1. If you have not already done so, enter Color Correction mode, for example, by selecting Toolset > Color Correction..
2. In the Color Correction tool, click the tab that includes the Color Match control with which you want to work.

For more information on the Color Correction tool tabs, see [“Understanding the Group and Subdividing Tabs” on page 735](#).

3. (Option) If necessary, select either of the following options in the Correction Mode Settings dialog box:

Option	Description
Eyedropper 3 x 3 Averaging	When this option is selected, your Avid editing application calculates the color value to pick by averaging the values of a 3 x 3 sample of pixels centered on the eyedropper's position. This is often useful for picking up a color accurately by sight because it compensates for shifts in color value from one pixel to another. When this option is deselected, your Avid editing application selects the color value of the exact pixel at the eyedropper's position.
Eyedropper Picks from Anywhere in Application	When this option is selected, you can pick colors from anywhere in your Avid editing application using the Color Match eyedroppers. For example, you can pick a target color for a Color Match correction, such as a desirable skin tone, from the swatch that appears beside a custom color saved in a bin or from one of the ChromaWheels.

For complete information on the Correction Mode Settings dialog box, see [“Customizing Color Correction Mode Settings” on page 740](#).

4. Select the input color (the color to be replaced):

- a. Move the pointer over the input color swatch.

The pointer changes to an eyedropper.

- b. Press and hold the mouse button, and then drag the eyedropper to the area of the image in the monitor from which you want to select an input value.

The input color swatch in the Color Match control updates as you move the pointer in the image.

If “Eyedropper Picks from Anywhere in Application” is selected in the Correction Mode Settings dialog box, you can select an input color from another location in your Avid editing application using the eyedropper. Also, you can pick from the Windows Color dialog box or the Macintosh Colors panel by double-clicking the input color swatch. However, you usually want to select your input color from the current segment.

- c. Release the mouse button to complete the selection.

The input color appears in the input color swatch.

5. Select the output color:

- a. Move the pointer over the output color swatch.

The pointer changes to an eyedropper.

- b. Press and hold the mouse button, and then drag the eyedropper to the area of the image in the monitor from which you want to select an output value.

The output color swatch in the Color Match control updates as you move the pointer in the image.

You usually select your output color from an image other than the current segment, such as the next segment or a reference frame. If “Eyedropper Picks from Anywhere in Application” is selected in the Correction Mode Settings dialog box, you can select an input color from another location in your Avid editing application, such as a custom color swatch in a bin. You can also double-click the output color swatch and select a color from the Windows Color dialog box or the Macintosh Colors panel. These alternatives are useful for selecting a saved “ideal” replacement color such as a completely neutral gray or an optimal skin tone. For more information on using the Windows Color dialog box or the Macintosh Colors panel, see [“Adjusting a Color Parameter for an Effect” on page 96](#).

- c. Release the mouse button to complete the selection.

The output color appears in the output color swatch.

6. Click the Match Type button, and select a Match Type to determine the type of match your Avid editing application makes.

The options available in the Match Type menu depend on the group in which you are working. For more information on Match Type options, see [“Match Type Options” on page 759](#).

7. Click the Match Color button to make the correction.

Your Avid editing application adjusts the current segment and resets the group controls to reflect the adjustment. The corrected image displays in the monitor that contains the current segment.

Match Type Options

The options available in the Match Type menu reflect the way in which color is handled in the group in which you are working. The following table describes the options available in the Match Type menu.

Group	Description
HSL (Controls tab)	<ul style="list-style-type: none"> • H + S + L: Your Avid editing application matches based on the hue, saturation, and luminance of the color you select in the output color swatch. • Hue: Your Avid editing application matches based on only the hue of the color in the output color swatch. • Saturation: Your Avid editing application matches based on only the saturation of the color in the output color swatch. • Luminance: Your Avid editing application matches based on only the luminance of the color in the output color swatch.
HSL (Hue Offsets tab)	<ul style="list-style-type: none"> • Highlight: Your Avid editing application matches based on both the hue and the saturation across the highlights portion of the tonal range. • Midtones: Your Avid editing application matches based on both the hue and the saturation across the midtones portion of the tonal range. • Shadows: Your Avid editing application matches based on both the hue and the saturation across the shadows portion of the tonal range.

Group	Description
Curves	<ul style="list-style-type: none">• Master: Your Avid editing application matches based on the luminance of the color in the output color swatch.• R + G + B: Your Avid editing application matches based on the values of all three color channels of the color in the output color swatch.• NaturalMatch: Switches the NaturalMatch feature on and off. Choose NaturalMatch to select or deselect the NaturalMatch feature. <p>When this command is selected, all the match types in the Curves group use the NaturalMatch feature when making a correction and match types appear in the Color Match control with the extension (Nat). For more information on NaturalMatch, see “Understanding NaturalMatch” on page 760.</p>

Understanding NaturalMatch

Color matching is often complicated by differences in lighting between one shot and another. For example, you might want to match the skin tone in Shot A, which is in shadow, with that in Shot B, which is brightly lit. To achieve a natural-looking correction, you need to replace the hue of Shot A, but preserve the luminance and saturation characteristics that suggest shadow.

NaturalMatch solves this problem by making calculations that compensate for the luminance and saturation qualities of the original image. The correction your Avid editing application makes when you use NaturalMatch adopts the new hue value, preserves the original luminance value, and adjusts the saturation value in relation to the other values. NaturalMatch lets you use the quick correction method offered by the Color Match control even when images show significant differences in lighting.

Color Match Example Using NaturalMatch

The following illustrations show an example of the use of the Color Match control and the NaturalMatch feature to correct color from shot to shot.



Top left: uncorrected image. This image is very gray and shows poor skin tones. The RGB values at the center of the man's forehead are R: 61, G: 62, B: 66 — an almost completely neutral gray.

Top right: reference image. This image shows much better color, including good skin tones (RGB values of R: 110, G: 70, B: 56) and a better color for the canvas of the tent. You can use the Color Match control to make the color characteristics of the two shots match better. A Color Match that uses values from the center of the foreheads in each image and that uses NaturalMatch automatically generates Curves adjustments for all three color channels.

Bottom: corrected image. Further corrections (for example, to improve contrast ratio) are still possible, but the image improves dramatically after the color match. The skin tones and the color of the tent in the background now match the reference image well.

Saving Custom Colors to a Bin


You can save a color that you select in the Color Match control as an item in a bin. For example, you might want to save a skin tone that you want to match throughout your sequence. You can then load that color back into the Color Match control whenever you need to make a match based on that color.

To save a color to a bin:

1. In the Color Match control, Alt+drag (Windows) or Option+drag (Macintosh) the swatch that contains the color you want to save to a bin.

While you drag, the pointer changes to a hand, and a rectangular outline appears.

The color appears in the bin as a rectangular color swatch icon. Your Avid editing application assigns the color a name based on the current Saved Color Labels settings in the Correction Mode Settings dialog box. For more information, see [“Customizing Color Correction Mode Settings” on page 740](#).



Examples of custom color swatches as they appear in a bin

2. (Option) If you want to rename the custom color, click the existing name in the bin and type a new name.

To load a custom color into the Color Match control, do one of the following:

- ▶ Drag the color icon from the bin to the appropriate color swatch in the Color Match control.
- ▶ If “Eyedropper Picks from Anywhere in Application” is selected in the Correction Mode Settings dialog box, select the saved color from its swatch in the bin using the Color Match eyedropper.

Getting RGB Information Using the Color Match Control

By default, the color swatches in the Color Match control display the RGB values for the selected color. This makes the Color Match control useful as an information palette to check the exact RGB value of a sample area in your image.

For example, if you have an area in your image that you know should appear white, you can sample that area using the Color Match eyedropper and check how far its RGB values depart from a true white. If the values are R:231, G:217, B:229, then you know that you need to add a little green to achieve white (the image has a magenta cast). If you want this area in the image to be exactly reference white (R,G,B:235), you know that you also need to adjust the white point slightly to increase the RGB values.

The HSL (Hue, Saturation, Luminance) Group

The HSL (Hue, Saturation, Luminance) group provides controls that let you alter attributes such as hue, saturation, gain, and gamma. These controls resemble those found in the Video Input tool and in the Color Effect.

The HSL group also lets you specify an offset for the hue of an image, which is especially useful for correcting a color cast. For example, when an object in an image that should be a neutral gray appears tinged with a color, you can use the offset adjustment to restore the correct gray color.


You can make Hue Offset adjustments in three different luminance ranges — highlights, midtones, and shadows. This gives you more precise control over color cast corrections. You can also invert both the chrominance and luminance values in an image with a single click, and set clipping values for both the High and Low ends of the luminance range.

The HSL controls can correct a wide range of problems. If you are comfortable working with the HSL group and gain some experience using it, you might be able to make most of your common corrections without needing to use any other tools.

Making Corrections Using the Controls Tab in the HSL Group

The Controls tab of the HSL group includes sliders for making adjustments to hue, saturation, and luminance values. It also includes the Color Match control for making adjustments automatically, based on selected input and output color values. For more information, see [“Using the Color Match Control” on page 756](#).

The following illustration shows the Controls tab.



To make a correction using the Controls tab:

1. If you have not already done so:
 - a. Move the position indicator to the segment you want to correct.
 - b. Click the HSL tab.
 - c. On the left side of the Color Correction tool, click the Controls subdividing tab.
2. Make your adjustments by doing one of the following:
 - ▶ Adjust one or more of the individual sliders or buttons.


For more information, see [“Using the Sliders in the Controls Tab of the HSL Group” on page 764](#) and [“Controls Tab Reference” on page 765](#).

- ▶ Use the Color Match control to make a correction by selecting input and output colors.

For more information, see [“Using the Color Match Control” on page 756](#).

Using the Sliders in the Controls Tab of the HSL Group

The following illustration shows the components of the HSL controls.



Components of a control in the Controls tab. Left to right: Enable button, text box, direction button, slider, direction button

For information on using the Enable button for a control to turn the control on or off or to reset the control to its default value, see [“Working with the Enable Buttons” on page 737](#).

To adjust the HSL sliders, do one of the following:

- ▶ Type a value in the text box, and then press Enter (Windows) or Return (Macintosh).
- ▶ Drag the slider.
- ▶ Click one of the direction buttons to change the value in small increments.
- ▶ Click one of the direction buttons, and press and hold the mouse button to change the value quickly over a large range.

To change the numerical value of a control by small increments:

- ▶ Click in the text box, and then press the Up Arrow key to increase the value or the Down Arrow key to decrease the value.

To use the mouse scroll wheel to change values for a control:

1. Click the slider or click in the text box.
2. Do one of the following:
 - ▶ Press and hold the Ctrl key, and use the scroll wheel to change the value in small increments.
 - ▶ Press and hold the Ctrl and Shift keys (or the Ctrl and Alt keys), and use the scroll wheel to change the value in increments of -10 or +10.

Controls Tab Reference

The following table describes the individual controls available in the Controls tab of the HSL tab.

Control	Description
Hue	Shifts the hues in the image around the color wheel. Values range from -180 to 180 , where 0 is the default and causes no change in the image. A value of 120 shifts red to blue, and a value of -120 shifts red to green.
Saturation	<p>Specifies the amount or intensity of color. Values range from 0 to 200, where 100 represents no change to the image, 0 represents complete desaturation (monochrome image), and 200 represents maximum saturation.</p> <p>This control is also available in the Curves tab as Master Saturation.</p>
Brightness	<p>Adjusts the luminance of the image by shifting the luminance value of every pixel by the value set in the control. Values range from -100 to 100, where -100 subtracts 100 from the 8-bit luminance value of every pixel, and 100 adds 100 to the 8-bit luminance value of every pixel.</p> <p>The effect of the Brightness control is very similar to that of the Setup control (on the Hue Offsets tab). One important difference, however, is that the Brightness control interacts with the Contrast control, while the Setup control interacts with the Gain and Gamma controls. If you make a Contrast adjustment, it is better to adjust luminance further using the Brightness slider. If you make an adjustment using the Gain or Gamma controls, it is better to adjust luminance further using the Setup control.</p>
Contrast	Increases or decreases the amount of contrast in the image. Values range from -100 to 100 , where -100 represents no contrast (all pixels mapped to neutral gray) and 100 represents maximum contrast.
Clip Low Clip High	Sets the Low clip and the High clip for the image. All pixels with the Low clip value or less are clipped to black. All pixels with the High clip value or more are clipped to white. The default settings for these controls are 16 and 235 on an 8-bit scale (the normal broadcast values for black and white).
Invert Chroma	Replaces the color value of every pixel in the image with the opposite color value on the color wheel. This is the equivalent of setting the Hue control to 180 or -180 .
Invert Luma	Reverses the brightness level of every pixel in the image. Dark areas become light, and light areas become dark.

Understanding the Hue Offsets Tab

The Hue Offsets subdividing tab of the HSL group contains controls for adjusting hue and saturation values at the same time using ChromaWheel™ color wheels and linked text boxes. These controls are especially well-suited for correcting color casts in images. For more information, see [“Understanding ChromaWheel Color Wheels”](#) on page 766 and [“Using the ChromaWheel Crosshair Pointers”](#) on page 769.




The ChromaWheel color wheels provide controls similar to the physical controllers on traditional color correction equipment, so experienced colorists might use them as their preferred controls for many color adjustments.

The Hue Offsets tab also contains slider controls for adjusting Gain, Gamma, and Setup. These sliders offer one of the best ways to control the tonal range of your images. For more information, see [“Hue Offsets Tab Reference”](#) on page 770.

The Hue Offsets tab also contains automatic color correction buttons and a Color Match control. For more information, see [“Using Automatic Color Corrections”](#) on page 749 and [“Using the Color Match Control”](#) on page 756.

The following illustration shows the Hue Offsets tab.



ChromaWheel color wheels (left), slider controls (center), Color Match control (right), and automatic color correction buttons (across the bottom) in the HSL > Hue Offsets tab.

Understanding ChromaWheel Color Wheels

The ChromaWheel color wheels let you make adjustments across the same luminance ranges as the Controls tab. The wheels appear in the following order from left to right: Shadows, Midtones, and Highlights.

ChromaWheel Displays

The ChromaWheel color wheels show outlines that resemble the design of a vectorscope monitor, overlaid on full-color depictions that show the color represented by each area of the wheel.



The Hue Offsets color wheels create a familiar environment for users by duplicating the general appearance of a vectorscope monitor. They are not calibrated in the same way as a vectorscope monitor.

ChromaWheel Crosshair Pointers

Each ChromaWheel control contains a crosshair pointer that identifies the currently selected point on the wheel. Each pointer has a distinctive appearance to help you distinguish them from one another. The following table shows the pointers.

ChromaWheel Type	Pointer
Shadows	
Midtones	
Highlights	


How ChromaWheels Work

A ChromaWheel color wheel is a circular graph that represents hue and saturation values. Hue values are mapped around the circumference of the wheel, with colors in the same positions that they occupy on a vectorscope. Red is at the 0° point on the wheel, and cyan is at the 180° point.

As you move around the wheel counterclockwise from red to cyan, you move through positive degree values. For example, green is at +120°. As you move around the wheel clockwise from red to cyan, you move through negative degree values. For example, blue is at -120°

Saturation values are mapped along the radius of the wheel. The center point of the wheel represents zero saturation (neutral gray), while the edge of the wheel represents maximum saturation. As you move out from the center of the wheel, you shift from less to more saturation. Saturation values range from 0 (zero saturation) to 100 (maximum saturation).

When you pick a specific point on the wheel, you select an exact combination of hue and color intensity to add to your image. You can select a gray with a slight yellow tinge near the center of the wheel, for example, or an intensely saturated blue at the outer edge.



A ChromaWheel color wheel: hue changes as you move around the wheel, saturation increases from the center of the wheel toward the edge, and the graphical outline shows the degree values for measuring hue

When you use a ChromaWheel, you use a basic principle of color theory — you can cancel out one color in an image by adding an equal amount of the opposite color on the wheel. For example, to remove a red cast, add some cyan. To remove a yellow cast, add some blue. You do not even need to remember which colors are opposite when you have the color wheel as a control. Simply add some color from the opposite side of the wheel from the color you want to remove, and then fine-tune your adjustment until you are satisfied with the result.

Making Corrections Using the Hue Offsets Tab

To make a correction using the Hue Offsets tab:

1. If you have not already done so:
 - a. Move the position indicator to the segment you want to correct.
 - b. Click the HSL tab.
 - c. Click the Hue Offsets subdividing tab.
2. Make your adjustments by doing one or more of the following:
 - ▶ Click one or more of the automatic color correction buttons.
For more information, see [“Adjusting Contrast and Balance Automatically” on page 751](#).
 - ▶ Use one or more of Remove Color Cast buttons below the ChromaWheels.
For more information, see [“Using the Remove Color Cast Buttons” on page 754](#).
 - ▶ Use the Color Match control to calculate an offset automatically, based on input and output colors.
For more information, see [“Using the Color Match Control” on page 756](#).

- ▶ Drag the crosshair pointer on the appropriate ChromaWheel.
As you move the pointer in the wheel, the Hue and Amount text boxes update to display numerical values for the adjustment. For more information, see [“Using the ChromaWheel Crosshair Pointers” on page 769](#).
- ▶ Type values in the Hue and Amount text boxes for the appropriate ChromaWheel to set the offset you want. You must press Enter (Windows) or Return (Macintosh) after typing a value for it to take effect.
Hue values range from -180° to 180° where 0° is the position of red on the wheel. Amount values range from 0 to 100. When you change the Hue and Amount values, the pointer on the ChromaWheel updates to represent the adjustment.
- ▶ Change the Hue or Amount value in small increments by clicking in the text box, and then pressing the Up Arrow key to increase the value or the Down Arrow key to decrease the value.
- ▶ Use the mouse scroll wheel to change the Hue or Amount values by clicking in the text box, then pressing the Ctrl key and using the scroll wheel to change the value in small increments. Press the Ctrl and Shift keys (or the Ctrl and Alt keys) and use the scroll wheel to change the value in increments of -10 or +10.
- ▶ Adjust one or more of the Gain, Gamma, and Setup controls.
For more information, see [“Using the Sliders in the Controls Tab of the HSL Group” on page 764](#) and [“Hue Offsets Tab Reference” on page 770](#).

3. Fine-tune your adjustments until you are satisfied with the result.

Remember that you can make adjustments on more than one ChromaWheel and turn them on and off individually to assess their effect on the image.

Using the ChromaWheel Crosshair Pointers

To move the crosshair pointer in a ChromaWheel color wheel:

1. Click anywhere in the wheel, and press and hold the mouse button.
The standard mouse pointer disappears, and the crosshair pointer is dynamically linked to the mouse.
2. Drag the crosshair pointer around in the wheel until you are satisfied with the adjustment, and then release the mouse button.
For more precise control over the movement of the crosshair pointer in the central area of the wheel, press and hold the Shift key while performing the actions in this procedure.

Hue Offsets Tab Reference

The following table describes the individual controls available in the Hue Offsets tab of the HSL tab.

Control	Description
Gain	<p>Adjusts the gain or white point for the image. Values range from 0 to 200, where 100 represents the unchanged image.</p> <p>The main difference between Brightness (on the Controls tab) and Gain is that Brightness adjusts by adding to the 8-bit luminance value of every pixel, while Gain makes an adjustment based on a percentage of the original luminance.</p> <p>This control is also available in the Curves tab as Master Gain.</p>
Gamma	<p>Adjusts the midpoint of the luminance range. Values range from 0.1 to 10, where 1 represents the unchanged image. Lowering the value darkens the midtones and brings the image closer to black. Raising the value lightens the midtones and brings the image closer to white.</p> <p>This control is also available in the Curves tab as Master Gain.</p>
Setup	<p>Adjusts the setup or black point for the image. Values range from -255 to 255, where 0 represents the unchanged image (no offset).</p> <p>The effect of the Setup control is very similar to that of the Brightness control (on the Controls tab). One important difference, however, is that the Setup control interacts with the Gain and Gamma controls, while the Brightness control interacts with the Contrast control. If you make an adjustment using the Gain or Gamma controls, it is better to adjust luminance further using the Setup control. If you make a Contrast adjustment, it is better to adjust luminance further using the Brightness slider.</p> <p>This control is also available in the Curves tab as Master Gain.</p>

The Curves Group

The Curves group contains four ChromaCurve graphs that let you control color and luminance by placing up to sixteen control points on a graph and then adjusting the points. For more information on ChromaCurve graphs and how they operate, see [“Understanding ChromaCurve Graphs” on page 771](#).


The Curves tab also contains four slider controls — Master Saturation, Master Gain, Master Gamma, and Master Setup. These sliders work in exactly the same way as the Saturation, Gain, Gamma, and Setup sliders in the HSL group, so you can make some HSL-type adjustments without leaving the Curves tab. When you adjust any of these sliders, you

enable the equivalent slider in the HSL group and the tab hierarchy containing it. For more information on the function of these controls, see [“Controls Tab Reference” on page 765](#) and [“Hue Offsets Tab Reference” on page 770](#).

The Curves tab also contains automatic color correction buttons that adjust one or more of the ChromaCurve graphs automatically, and the Color Match control, which lets you automatically add or modify a control point based on selected input and output colors. For more information, see [“Using Automatic Color Corrections” on page 749](#) and [“Using the Color Match Control” on page 756](#).

For examples showing how various curves affect an image, see [“Examples of ChromaCurve Graph Adjustments” on page 777](#).


The following illustration shows the Curves tab.



Understanding ChromaCurve Graphs

A ChromaCurve graph shows the relationship of input values (on the horizontal axis) to output values (on the vertical axis). A background grid indicates the quartile points on each axis.


The following illustration shows the Red ChromaCurve graph.



The default curve (before you make any adjustments) is an ascending 45 degree straight line, because input and output values are the same across the entire range. The control points for the two ends of the curve are set by your Avid editing application, but you can change their location.

If you make an adjustment that moves part of the line below the 45 degree angle, you make the output values for that part of the image lower than the input values. If you make an adjustment that moves part of the line above the 45 degree angle, you make the output values for that part of the image higher than the input values.

If you make an extreme adjustment to a curve so that it becomes a horizontal line, you are converting all input values to the same output value of 128. When you make this adjustment across all three color channels, the result is a uniform, midgray image.



When you make less extreme adjustments, your Avid editing application calculate a true curve in the graph based on the values of the control points and their positions with respect to one another.

In each of the Red, Green, and Blue ChromaCurve graphs, the background color indicates what color in the image changes when a curve passes through that part of the graph. The upper left corner of the graph is the color of the graph name (red, green, blue) and represents complete saturation in that color. The lower right corner of the graph is the complementary color (cyan, purple, yellow). The upper right corner is white and the lower left corner is black.

The Master ChromaCurve graph controls overall luminance in the image. The grayscale tone of its background indicates the luminance range that is affected by that part of the graph but does not directly indicate the result of an adjustment. Adjustments that move parts of the graph above the default 45 degree angle make those areas of the image brighter. Adjustments that move parts of the graph below the default 45 degree angle make those areas of the image darker.

For examples showing how various curves affect an image, see [“Examples of ChromaCurve Graph Adjustments” on page 777](#).

Making Corrections Using the Curves Tab

To make corrections using the Curves tab:


1. If you have not already done so:
 - a. Move the position indicator to the segment you want to correct.
 - b. Click the Curves tab.
2. Do one or more of the following:
 - ▶ Use one or more of the automatic color correction buttons to adjust the ChromaCurve graphs.
For more information, see [“Adjusting Contrast and Balance Automatically” on page 751](#) and [“Using the Remove Color Cast Buttons” on page 754](#).
 - ▶ Use the Color Match control to adjust the ChromaCurve graphs.
For more information, see [“Using the Color Match Control” on page 756](#).
 - ▶ Adjust the ChromaCurve graphs manually, either by clicking and dragging to add and move control points or by entering values in the Input and Output text boxes, until you are satisfied with the results.
For more information, see [“Adjusting ChromaCurve Graphs” on page 773](#).
 - ▶ Adjust the Master Saturation, Master Gain, Master Gamma, or Master Setup slider controls.
For more information, see [“Controls Tab Reference” on page 765](#) and [“Hue Offsets Tab Reference” on page 770](#).

Adjusting ChromaCurve Graphs

You can have sixteen control points in a Curves tab ChromaCurve graph. Graphs must always have at least two control points. Your Avid editing application sets default control points such that input and output values are the same across the entire range of colors.

To add a control point:

- ▶ Click the curve line in the graph at the point where you want the new point to appear.
A new control point appears with a circle around it to indicate that it is the active control point.



To select a control point:

- ▶ Click the control point you want to select.

A circle appears around the control point to indicate that it is the active control point.




Active control point (top) and inactive control point (bottom)

To move a control point, do one of the following:

- ▶ Click the control point and drag it to the location on the graph where you want to place the point.

The curve updates as you drag the control point.

- ▶ Type input and output values for the position of the control point in the Input and Output text boxes below the ChromaCurve graph. You must press Enter (Windows) or Return (Macintosh) after typing a value for it to take effect.



Selected control point at 100 on the input (horizontal) axis and at 69 on the output (vertical) axis

- ▶ Click in one of the text boxes, and then press the Up Arrow key to increase the value or the Down Arrow key to decrease the value by small increments.

- ▶ Click in one of the text boxes, then press the Ctrl key and use the mouse scroll wheel to change the value by small increments.
- ▶ Click in one of the text boxes, then press the Ctrl and Shift keys (or the Ctrl and Alt keys) and use the mouse scroll wheel to change the value by increments of -10 or +10.

To delete a control point:


1. Select the control point you want to delete.
A circle appears around the control point.
2. Make sure the pointer is over the ChromaCurve graph that contains the control point you want to delete.
3. Press the Delete key.



A curve requires at least two control points. If you have only two control points set in a ChromaCurve graph, you cannot delete one.


To anchor part of a curve so it does not move when you make other adjustments:

1. Place two control points at either end of the part of the curve you want to anchor.
2. Place a third control point very close to the point that separates the portion of the curve you want to anchor from the portion of the curve you want to adjust.
3. Place a fourth control point on the portion of the curve you want to adjust.



Example of anchoring part of a curve. The bottom two control points define the part of the curve you want to anchor. The third point (immediately above the second) lets the rest of the curve adjust. Drag the fourth point (selected) to adjust the upper part of the curve.

When you drag the new control point to adjust the curve, the portion of the curve between the first two control points does not move.




ChromaCurve Graphs and the Color Match Control

When you use the Color Match control in the Curves tab, a gray crosshair marker appears in each appropriate ChromaCurve graph to mark the intersection of the input value defined by the input color swatch in the Color Match control and the output value defined by the output color swatch.

When you click the Match Color button, your Avid editing application adds a new control point and updates the ChromaCurve graphs to reflect the color match. If you are not using NaturalMatch or if you have not adjusted the ChromaCurve graphs previously, the new control point appears at the location of the crosshair marker. If you are using NaturalMatch or if you have already adjusted the ChromaCurve graphs, your Avid editing application makes a more complex calculation to reflect the input saturation and luminance values or to take earlier ChromaCurve graph adjustments into account. In these cases, the new control point does not appear at the location of the crosshair marker.

The following illustrations show this behavior both before and after you click the Match Color button.



The crosshair marker on the Green ChromaCurve graph (left) represents the values for Green in the color swatches (center) — Input 131, Output 105. Because R+G+B is selected as the Match Type, similar crosshair markers appear in the Red and Blue graphs also. When you click the Match Color button, your Avid editing application creates a new control point and updates the curve to reflect the color match (right). For this


example, NaturalMatch is selected and the calculation is not complicated by other control points, so the new point is created at the exact location of the crosshair marker. The Green input and output values from the color swatches appear in the Input and Output text boxes below the graph.

Examples of ChromaCurve Graph Adjustments

The following illustrations show a series of simple adjustments that use the Red ChromaCurve graph in the Curves tab. You can compare the results of these adjustments to learn how curves control color across different parts of the brightness range.

Each example shows the new corrected image, the curve that produces it, and one other image from the series for comparison.

In each example, the background color behind the control point represents the color change to the image. In the first example, the curve passes through the darker cyan area, which reduces reds in the darker parts of the image.



Uncorrected image (left) and result of adjustment 1 (right)

20 Performing Color Corrections

Adjustment 1 reduces red primarily in the shadows range (the lower part of the curve). Much of the red tone is lost from the background grass, the shirt, and the lower red signpost. The shirt loses much of its detail. The higher red signpost is relatively less desaturated, however, and some of the red highlights are still present on the clouds in the top right.




Image from adjustment 1 (left) and result of adjustment 2 (right)

Adjustment 2 reduces red primarily in the highlights range (the upper part of the curve). The differences between this adjustment and adjustment 1 are most apparent in the lower signpost, which retains more redness and detail, and in the background, where the crop in the lower right retains more red tones, but the clouds in the top right have lost their red highlights.




Image from adjustment 2 (left) and result of adjustment 3 (right)

Adjustment 3 reduces red more evenly across the entire luminance range but with the largest change in the midtones. The differences between this adjustment and adjustment 2 are subtle. The strong midtone reduction in red is most noticeable in the skin tones, which appear more gray than in either adjustment 1 or adjustment 2. However, adjustment 3 retains both some detail in the lower signpost and some of the red highlights on the clouds.




Image from adjustment 3 (left) and result of adjustment 4 (right)

Adjustment 4 boosts red evenly across the entire luminance range but with the largest change in the midtones. Here the difference from adjustment 3 is obvious throughout the image. The most extreme differences appear in the midtone range, for example, in the hands.




Image from adjustment 4 (left) and result of adjustment 5 (right)

Adjustment 5 boosts red primarily in the highlights range. The most noticeable difference is in the crop in the background. In adjustment 4, which boosts red more in the lower ranges, the crop looks more orange. In adjustment 5, which boosts red very little in the shadows range, the crop looks more yellow-green.




Image from adjustment 5 (left) and result of adjustment 6 (right)

Adjustment 6 boosts red primarily in the shadows range. In comparison with adjustment 5, there is much more red and orange in the darker parts of the image (for example the crop in the lower right and the lower part of the shirt). The clouds, however, have much less of a red highlight.

Keyframing Color Corrections

You can use the advanced keyframes interface in the Effect Editor to animate most color correction adjustments. You can:

- Manipulate many color correction parameters in the Effect Editor using sliders or parameter Enable buttons.
- Add and adjust keyframes for many color correction parameters in keyframe graphs, using the same methods you use for advanced keyframes in other effects.
- View keyframe markers in the position bar below the Current monitor in Color Correction mode.

- Automatically add keyframes by moving the position indicator below the Current monitor and then adjusting any keyframeable color correction parameter.
- Check how your animated color corrections are working by scrubbing through clips in Color Correction mode. Color correction parameter controls and graphs update as you scrub to show the parameter values at each point in the clip.

You can also adjust effects other than color corrections in the Effect Editor while in Color Correction mode.

To support keyframing, color corrections in the current version of your Avid editing application store parameter information differently from color corrections created in some older versions. You must promote color corrections in sequences that were created with these older versions to work with them in the current version. For more information, see [“Updating and Reverting Existing Effects in Sequences” on page 44](#).

Displaying the Effect Editor with Color Correction Mode

You have several options for using buttons to display the Effect Editor with Color Correction mode.

An alternative approach, particularly if you need to work frequently with the Effect Editor in Color Correction mode, is to save the Color Correction toolset in a configuration that includes the Effect Editor.

To open the Effect Editor when you are in Color Correction mode:

- ▶ Click the Effect Mode button.

The most convenient locations for the Effect Mode button when you are in Color Correction mode are the top right corner in the Color Correction tool and the Timeline palette.

The Effect Editor opens.



When you are in Color Correction mode, the Effect Mode button simply opens the Effect Editor. It does not display the standard Effect Mode layout, including the Effect Preview monitor.

To close the Effect Editor when you are in Color Correction mode:

- ▶ Click the Effect Editor’s Close button.

The Effect Editor closes.



When you are in Color Correction mode and the Effect Editor is open, you cannot close the Effect Editor by clicking the Effect Mode button again.

To enter Color Correction mode from Effect mode:

- ▶ Click the Color Correction Mode button, for example, in the Timeline palette.
The Color Correction mode layout appears and the Effect Editor remains open.

To enter the standard Effect Mode layout from Color Correction mode:

- ▶ Click the Effect Mode button.

To create a Color Correction toolset that includes the Effect Editor:

1. Select Toolset > Color Correction.
2. Click the Effect Mode button.
3. Size and position the Effect Editor according to your preference.
4. Select Toolset > Save Current.
5. (Option) Map the Color Correction toolset menu command to your keyboard.


For more information, see “Mapping Menu Commands” in the Help.

You can now open a layout that includes all the standard Color Correction tools along with the Effect Editor by selecting Toolset > Color Correction or, if you have completed step 5, by pressing the mapped key on your keyboard.

Keyframeable Color Correction Parameter Reference

The following table explains which color correction parameters are keyframeable and the extent of the control available for them in the Effect Editor.

Parameter Types	Description
All parameters in the HSL > Controls tab	<p>These parameters are fully adjustable and keyframeable in the Effect Editor.</p> <p>Slider controls appear in the Effect Editor, so you can adjust each parameter either in the Effect Editor or in the Color Correction tool. Controls and Enable buttons in the Effect Editor and in the Color Correction tool are ganged together, so changes in one are immediately represented in the other.</p> <p>You can also display keyframe graphs for these parameters, and add and manipulate keyframes using normal advanced keyframe techniques.</p>
All parameters in the HSL > Hue Offsets tab	<p>These parameters are fully keyframeable in the Effect Editor, as described in the previous row of this table.</p> <p>Each ChromaWheel in the Color Correction tool is represented as two sliders in the Effect Editor, one for the Hue and the other for the Hue Amount.</p>


Parameter Types	Description
	<i>Advanced keyframe graphs use a larger range of numerical values for Hue parameters than the Color Correction tool. In the Effect Editor, values range from -360 degrees to +360 degrees. In the Color Correction tool, values range from -180 degrees to +180 degrees. Hue adjustments in the Effect Editor might display with different numerical values from those in the Color Correction tool, even though the color represented is the same. For example, a value of +340 in the Effect Editor displays as -20 in the Color Correction tool — the two numerical values are just different ways to represent the same angle on a color wheel.</i>
All parameters in the Curves tab	You can enable and disable these parameters in the Effect Editor. You can also keyframe these parameters in their keyframe tracks. However, because these parameters require specialized controls, you cannot open keyframe graphs or adjust the parameter values directly in the Effect Editor. Make your adjustments in the Color Correction tool.

Working with Keyframes in the Color Correction Monitor

Keyframe markers display in the position bar below the Current monitor in Color Correction mode. In general, these keyframe markers behave like those you see in the position bar below the Effect Preview monitor when in Effect mode. For example, you can:

- Click keyframe markers to select them.
- Delete selected keyframes.
- Alt-drag (Windows) or Option+drag (Macintosh) keyframe markers to move them.

You cannot add keyframes manually in the Color Correction monitor (as you can in the Effect Preview monitor using the Add Keyframe button). However, you can add keyframes automatically once you add an initial keyframe in the Effect Editor.

 *Complex color corrections with many parameter adjustments might result in many keyframe markers in the Color Correction monitor that are hard to distinguish. In many cases when your color corrections are complex, it is easier to identify and manipulate the keyframe markers in the Effect Editor.*

To automatically add keyframes to color corrections in the Color Correction monitor:

1. Add a keyframe in the Effect Editor using normal advanced keyframe techniques.
For example, if you want to adjust the Hue control in HSL > Controls, or have already made a first adjustment to that parameter, you need to add a keyframe to that parameter in the Effect Editor.

Consider adding a starting keyframe to more than one parameter, for example, to all of the parameters in the group you want to adjust. You then have a starting point for further adjustments to any parameter. You can use the Remove Redundant Keyframes command when you complete your adjustments to remove any keyframes that have no effect on the finished appearance.

2. If necessary, adjust the appropriate color correction parameter in either the Effect Editor or the Color Correction tool to set the parameter value for the keyframe you created in step 1.
3. In the Effect Editor or in the position bar below the Current Color Correction monitor, Ctrl-click (Windows) or Command+click (Macintosh) the keyframe added in step 1 to deselect it.
4. In the position bar below the Current Color Correction monitor, move the position indicator to the location where you want to set a new keyframe.
5. Make an adjustment to the appropriate parameter in the Color Correction tool.

A new keyframe appears below the Current Color Correction monitor at the location of the position indicator. If you scrub in the monitor, you see how the animated color correction changes the image over time and how the parameter control moves over time in the Color Correction tool.

6. Repeat steps 3 through 5 to create additional keyframes as necessary.

Depending on where you added keyframes in step 1, you might also need to return to the Effect Editor to add a first keyframe for any parameter you want to adjust that does not yet have any keyframes.

7. (Option) When you complete all your adjustments, use the Remove Redundant Keyframes command in the Effect Editor to remove any keyframes that have no effect on the finished appearance.

For more information, see [“Removing Redundant Keyframes” on page 116](#).

Working with the Waveform Monitors and Vectorscope Monitor

The waveform and vectorscope commands in the Source menu configure the monitor to graphically display color information about your sequence. Your Avid editing application displays the information for the currently active monitor.

A waveform indicates the brightness of the image. The higher the green trace goes on the scale, the brighter that part of the image is.

Waveform monitors display all the information for the current field or frame overlaid in the waveform. Each left-to-right trace in the waveform represents one scan line. If you see a bright object on the left side of the image, you see its peak on the left side of the waveform. A bright object in the top left of the image produces the same waveform if it is in the bottom left of the image.

Displaying a Waveform Monitor or Vectorscope Monitor

To display a Waveform monitor or Vectorscope monitor:

1. Click in the monitor for which you want to display color information.

The monitor becomes the active monitor.

2. In one of the other monitors, click the Source menu and select a waveform or vectorscope command.


The monitor displays the selected waveform or vectorscope information.

For more information, see [“Waveform and Vectorscope Commands” on page 787](#) and [“Using the Waveform and Vectorscope Information” on page 795](#).

Waveform and Vectorscope Commands


The following table describes the waveform and vectorscope commands available in the Source menu for monitors in Color Correction mode.

Command	Description
Quad Display	Displays the following waveform and vectorscope information in a single monitor (clockwise from the top left corner): <ul style="list-style-type: none">YC WaveformVectorscopeRGB HistogramRGB Parade




For information on each display, see its individual entry in this table.

Command	Description
RGB Histogram	<p>Displays a graph that shows which RGB values in the image appear most frequently. The darkest values of red, green, and blue in the image appear as peaks on the left of the graph, and the brightest values appear as peaks on the right. The height of a peak indicates the number of pixels of that value. The width of a peak indicates how many pixels in the image have similar values.</p> <p>For example, if the blue histogram has many tall peaks at the left side, the image has many pixels with low blue values. However, these pixels might appear in the image as many different colors because they might have any red and green values.</p>




For information on using the RGB Histogram display, see [“Using the Waveform and Vectorscope Information”](#) on page 795.

Command	Description
RGB Parade	<p>Displays waveforms of the RGB components side by side. Because video cameras capture in RGB, this display helps to show camera problems. You can also use it for general reference to the three primary colors.</p> <p>RGB signals combine to create all other colors. A white area in the image appears as peaks in all three waveforms at the same relative location. A high red level does not mean a red image unless the green and blue levels are low.</p> <p>RGB Parade incorporates any safe color limits you have set. Your Avid editing application displays RGB values in white when the values fall outside the RGB Gamut limits. For more information on color limits, see “Safe Color Limits with Waveform and Vectorscope Information” on page 821.</p>





For information on using the RGB Parade display, see [“Using the Waveform and Vectorscope Information”](#) on page 795.

Command	Description
Vectorscope	<p>Displays chroma information without luma information as a circular graph where the center represents no chroma and chroma increases as the trace moves away from the center.</p> <p>All white, black, and gray parts of the image appear at the center. Areas with more saturation appear further out from the center. Images with an overall color cast produce a vectorscope trace that is generally off-center. Colors created by various positive and negative combinations of Cb and Cr appear around the circle.</p> <p>Small squares mark the location of standard color bar vectors. Inner squares represent the proper values for 75% color bars, and outer squares represent 100% color bars.</p>





For information on using the Vectorscope display, see [“Using the Waveform and Vectorscope Information”](#) on page 795.

Command	Description
Y Waveform	<p>Displays a Waveform monitor with luma information. Luma is the brightness of an image without regard to color.</p> <p>The scale on the left is a digital level scale using a 256-step (eight-bit) range; 16 is the level for black, and 235 is the level for white.</p> <p>The scale on the right shows the amount of white in the image as a percentage; 0% represents black, and 100% represents white.</p> <p>Parts of an image can have values outside the 0% to 100% range. The digital video standard allows for <i>headroom</i> and <i>footroom</i> so you can correct a mistake in level in the postproduction process. The minimum is digital 0 or –8%, and the maximum is digital 255 or 108%.</p> <p> <i>Some external software or hardware processing can clip a signal that is outside the 0% to 100% range.</i></p> <p>Y Waveform incorporates any safe color limits you have set. Your Avid editing application displays Luma values in white when the values fall outside the Luminance limits. For more information on color limits, see “Safe Color Limits with Waveform and Vectorscope Information” on page 821.</p>




For information on using the Y Waveform display, see [“Using the Waveform and Vectorscope Information”](#) on page 795.

Command	Description
YC Waveform	<p>Displays composite video information. Composite video has the C (chroma) waveform, which is derived from Cb and Cr components, riding on the Y (luma) waveform. The Y trace is green and the C waveform is a cyan (blue-green) envelope around the green trace. Because the C signal of composite video has equal positive and negative energy, the cyan bands are at an equal distance above (Y+C) and below (Y-C) the green waveform.</p> <p>The left side of the YC Waveform shows a scale marked either for NTSC or PAL, depending on your project.</p> <p>NTSC black is 7.5 IRE (except in Japan), and NTSC white is 100 IRE.</p> <p>PAL black is 0 millivolts (mV), and PAL white is 700 mV.</p> <p> <i>This tool does not display actual composite video output. It is an accurate software model of a perfect encoder. If you convert your material to composite form, you see similar results.</i></p> <p>The scale on the right shows the amount of white in the image as a percentage — 0% represents black, and 100% represents white.</p> <p>A red edge on the display indicates composite video values above or below these limits. In addition, YC Waveform incorporates any safe color limits you have set. Your Avid editing application displays Composite values in yellow and Luma values in white when the values fall outside the safe color limits. For more information on color limits, see “Safe Color Limits with Waveform and Vectorscope Information” on page 821.</p>




For information on using the YC Waveform display, see [“Using the Waveform and Vectorscope Information”](#) on page 795.

Command	Description
YCbCr Histogram	<p>Displays a graph showing which YCbCr values in the image appear most frequently. The height of a peak indicates the number of pixels of that value. The width of a peak indicates how many pixels in the image have similar values.</p> <p>The upper bar of the histogram represents Y values. The darkest values are on the left and the brightest values on the right. An image with good contrast shows a good spread of values from darkest to lightest.</p> <p>An image with a great variety of colors appears as a wide spread in the Cb and Cr histograms. If they extend too far from the center, there is too much saturation.</p>



For information on using the YCbCr Histogram display, see [“Using the Waveform and Vectorscope Information”](#) on page 795.

Command	Description
YCbCr Parade	<p>Displays waveforms of Y, Cb, and Cr side by side. The Y in YCbCr is the same luma that the Y Waveform shows. In this display, the Y waveform shows in white on the left side.</p> <p>Cb and Cr are color difference signals that represent just the color information of a signal with the luma removed. Cb and Cr values can be negative or positive. For images that are black and white, Cb and Cr are zero, and you see a flat white line halfway up the two right bands. As they increase, Cb and Cr show in the colors representing those vectors. The more the values increase, the more saturated are the colors used to display them. Positive Cb is represented by blue hues, and negative Cb is represented by yellow hues. Positive Cr is represented by red hues, and negative Cr is represented by cyan hues.</p> <p>If the Cb or Cr waveforms are not centered, the cause might be a color cast to the image.</p>



For information on using the YCbCr Parade display, see [“Using the Waveform and Vectorscope Information”](#) on page 795.

Using the Waveform and Vectorscope Information

The following are examples of the ways you can use the waveform and vectorscope information:

- Aligning levels of sources using test patterns.

If you capture some color bars from your source footage, you can measure them and set the color correction you need to restore the video levels to the way the program was created. Import the Test Patterns from the SupportingFiles folder of your Avid editing application to become familiar with the proper Waveform, Parade, and Vectorscope readings. Histograms are not as useful on test patterns. For example, with 75% color bars, the Y+C envelope for the yellow and cyan bars should match the 100% white level.

- Identify problems with source video.

Typical problems include:

- Color levels too high or too low (see [“Safe Color Limits with Waveform and Vectorscope Information”](#) on page 821).
- Missing channels in YCbCr or RGB, indicating an equipment problem or a damaged cable.
- Clipping in YCbCr, RGB, or YC channels. The trace appears chopped at a certain level. If this appears at a level below the maximum, it occurred before the footage was captured.
- Images imported at the wrong level settings. If you import images at RGB levels of 0–255 that you should have imported at 601 levels of 16–235, the images lack contrast. If the images have too much contrast, with levels exceeding the 0% and 100% markings, the opposite is likely.

With experience, you learn how to read not only test patterns but actual content on the instruments. This lets you:

- Match scene brightness across a cut in Y Waveform.
- Put your flesh tones along a certain hue axis in the vectorscope.
- Watch the spread of the Y histogram to identify a good contrast range without clipping.
- Watch the top of the YC Waveform to ensure you do not have too much bright chroma.
- Fix white balance and black balance problems by identifying and centering those vectorscope traces.



Waveform and vectorscope monitors show you the values of only one frame or field at a time. Move around in the clip to find the most extreme levels or those most representative of the scene.

You can also use the information in the Waveform monitors and Vectorscope monitor to monitor safe color limits. For more information, see [“Safe Color Limits with Waveform and Vectorscope Information”](#) on page 821.

Applying Color Corrections to an Entire Sequence

You can apply a single color correction to an entire sequence by adding a video track above all other video tracks and selecting the Record Track button for that track. This is a simple and flexible way to make a final color adjustment to an entire program. For example, you might want to brighten all of your material slightly, or increase saturation a little to create a warmer look, or tint your whole program.

Once you make a color adjustment, your Avid editing application fills the entire length of the empty track with filler material and applies a Color Correction effect. The filler in this case is not opaque material but simply a container for the Color Correction effect. The result is that you see the color adjustment applied to whatever combination of images and effects exists in the lower video tracks.



In most situations, do not use this technique to make automatic color corrections, because your Avid editing application bases the color correction for the entire sequence on its analysis of the single frame that is active when you make the correction. This does not result in a good correction for the whole sequence unless all of the segments in it have very similar color characteristics. A better method for applying automatic color corrections to the entire sequence is to select every segment and then apply a Color Correction effect from the Effect Palette. For more information, see “Correcting Color Automatically Using the Color Correction Effect” on page 754.

To apply a color correction effect to an entire sequence:

1. In Source/Record mode (editing mode on NewsCutter systems), add a new video track to the sequence.
For more information, see “Adding and Deleting Tracks” in the Help.
2. Enter Color Correction mode, for example, by selecting Toolsets > Color Correction.
3. Ensure that the Record Track button for the topmost video track is selected.
4. Make one or more color adjustments in the Color Correction tool.

Filler material and a Color Correction effect appear in the topmost video track.

Using the Color Correction Effect

The Color Correction effect appears in the Image category of the Effect Palette. Any Color Correction effect templates in open bins also appear in the Effect Palette. Because your Avid editing application automatically applies a Color Correction effect in the Timeline when you make a correction, you apply Color Correction effects from the Effect Palette only for the following special purposes:

- To quickly apply automatic color corrections to one or more segments in a sequence.
- To apply a Color Correction saved as an effect template to one or more segments in a sequence. For more information, see “Working with Color Correction Effect Templates” on page 742.

Once you render a Color Correction effect, you can move the sequence to a system without color correction and the rendered correction plays successfully. In a system without color correction capability, a Color Correction effect is an unknown effect. The effect icon appears blank in the Timeline, and you cannot make any adjustments to it.


Selecting AutoCorrect Options

You control how your Avid editing application makes automatic corrections when you apply the Color Correction effect from the Effect Palette by choosing options in the AutoCorrect tab of the Correction Mode Settings dialog box.

To set AutoCorrect options:

1. Do one of the following:
 - ▶ In the Settings tab of the Project window, double-click Correction.
 - ▶ In the Color Correction window, click the Correction Mode Settings button.

The Correction Mode Settings dialog box appears.



Top to bottom: First Correction menu, Second Correction menu, and Third Correction menu in the Correction Mode Settings dialog box

2. Click the AutoCorrect tab.
3. Select an option from each of the three menus to define the first, second, and third automatic color correction that your Avid editing application makes when you apply the Color Correction effect from the Effect Palette.

For detailed information on the options, see [“AutoCorrect Options” on page 798](#).

For information to help you decide on the best order for these corrections, see [“Considerations When Using Automatic Color Correction” on page 750](#).

AutoCorrect Options

The following table describes the available options in the AutoCorrect tab of the Correction Mode Settings dialog box.

Option	Description
Nothing	Makes no adjustment. For example, if you only want to make two automatic corrections when you drag the Color Correction effect from the Effect Palette, set the Third Correction menu in the AutoCorrect tab to Nothing.
HSL Auto Balance	Makes adjustments to the three ChromaWheels to balance the colors in the image. This is the equivalent of clicking the Auto Balance button in the Hue Offsets subdividing tab of the HSL tab.
HSL Auto Black	Adjusts the Setup slider in the Hue Offsets subdividing tab of the HSL tab to make the darkest areas of the image as dark as possible. This is the equivalent of clicking the Auto Black button in the Hue Offsets subdividing tab of the HSL tab.
HSL Auto Contrast	Adjusts the Gain and Setup sliders in the Hue Offsets subdividing tab of the HSL tab to maximize the tonal range in the image. This is the equivalent of clicking the Auto Contrast button in the Hue Offsets subdividing tab of the HSL tab.
HSL Auto White	Adjusts the Gain slider in the Hue Offsets subdividing tab of the HSL tab to make the brightest areas of the image as bright as possible. This is the equivalent of clicking the Auto White button in the Hue Offsets subdividing tab of the HSL tab.
Curves Auto Balance	Makes adjustments to the Red, Green, and Blue curves to balance the colors in the image. This is the equivalent of clicking the Auto Balance button in the Curves tab.
Curves Auto Contrast	Makes an adjustment to the Master curve to maximize the tonal range in the image. This is the equivalent of clicking the Auto Contrast button in the Curves tab.

Working with the Color Correction Effect

You can work with a Color Correction effect in the same way that you work with any other effect that you apply from the Effect Palette and that appears in the Timeline with an effect icon.

You can save the effect as a template by entering Effect mode, clicking the effect icon in the Effect Editor, and dragging it to a bin in the standard way. You can then apply the template to other segments in the sequence or to other sequences. This is useful for applying a Color Correction Effect template quickly to multiple segments. For more information, see [“Working with Effect Templates” on page 47](#).

You can also delete the effect in the standard way by selecting it in Effect mode and pressing the Delete key. For more information, see [“Deleting Effects in a Sequence” on page 39](#).

If color corrections that you did not apply from the Effect Palette are in the same segment — indicated by colored lines if Color Correction is selected in the Timeline Fast menu — you cannot delete those corrections in Effect mode. To remove those color corrections, you must enter Color Correction mode and use the Remove Effect button.

21 Color Correction Techniques

This chapter provides an introduction to color correction techniques. It suggests some general principles to keep in mind when you are assessing footage and making color corrections, and then presents examples of corrections to shots with typical color problems.

- [Guiding Principles for Color Correction](#)
- [Examples of Color Correction Problems](#)

Guiding Principles for Color Correction

One useful way to think about the color correction process is to define the overall goals of the process. Another, slightly more practical and detailed, is to break down the typical color correction workflow into clearly defined stages of adjustment. The following topics use these two approaches to provide you with a set of guiding principles for color correction.

Goals of Color Correction: Restoration and Adaptation

You can think of color correction as having two main goals:

- Restoring the original look of the scene.
- Adapting the look of the scene to meet the demands of the project.

In some cases, color correction is complete when you have met the first goal. Often, however, there is some departure from the restored look to achieve shot-to-shot consistency or to convey creative concepts. So when you apply color corrections to any particular shot you usually have two different contexts in mind: the original scene at the time the camera captured it and the final situation of the shot within a program that has particular creative or communicative aims.

Restoring the Original Look

The first task in color correction is to restore the original look of the scene, that is, to make the image match as closely as possible what an observer standing beside the camera would have perceived when the scene was shot.

This is important because viewers typically have little tolerance for images that have unrealistic color values. For example, when a skin tone departs from our normal expectations of what skin should look like, we notice. Even when the final image is intentionally a distortion of reality, it is useful to restore the original look before you make subsequent alterations.

The color characteristics of a given shot can depart from the look of the original scene for a number of reasons. At the time of shooting, the camera might not be correctly balanced or the scene might be imperfectly lit. During transfers (from film to tape, from one tape to another, or from tape to captured media), inconsistencies in materials, processing methods, or calibration might alter the colors.

When you work on an uncorrected shot, you should make intelligent decisions about what the scene originally looked like and then adjust the shot accordingly. Although you probably were not present when the scene was shot, you can accomplish this with sufficient accuracy using the following two basic guidelines.

- The human visual system generally maximizes the tonal range available in a scene. For example, in low light we adjust to perceive a greater range of dark tones.
- The human visual system generally perceives color accurately and compensates for color casts. For example, we perceive a white shirt as white even if it is being illuminated by slightly pink light.

Generally, you can restore the original look of a shot (or at least create an acceptable approximation of the original look) by opening up the tonal range as much as reasonably possible and by ensuring that colors look accurate. For more detailed information on how to achieve this with adjustments, see [“Correcting Tonal Range” on page 803](#) and [“Neutralizing Color” on page 804](#).

Adapting the Original Look

An adaptive adjustment deliberately departs from the original look of the scene in some way. For example, you might lighten one shot to make it match another. In this case, you are departing from the original look in order to achieve shot-to-shot consistency in your sequence. A more dramatic adaptive adjustment might be to apply a gold tint to an entire sequence for an advertising spot or to apply extreme adjustments such as posterization or chroma inversion for a music video.

It is good practice to make restorative adjustments before you begin adaptive adjustments. You can then build on an image that has good color characteristics. Most viewers can probably perceive the difference between a restored, well-balanced image with a strong blue tint applied and an unrestored, poorly lit image with a strong blue tint applied (and prefer the former).

Stages of Color Correction

A typical color correction for a shot might include the following main stages of adjustment:

- Correcting the tonal range (or contrast ratio).
- Neutralizing color casts.
- Achieving consistency between the shots in a sequence.
- Achieving a final look.

Different kinds of projects lead to different emphases among these stages and might even make some unnecessary. Different working habits also affect how you handle these stages. A more experienced colorist might work in a manner that blurs the distinctions between them. A beginner might prefer to keep them distinct and achieve an acceptable result for each one before moving on to the next.

Correcting Tonal Range

Correcting the tonal range usually requires two steps. First, you reset the white and black points to make the range of values between the lightest part of the image and the darkest part of the image as large as possible. Second, you adjust the gray point to control how much of the total tonal range falls above and how much below the middle value.

Setting White and Black Points

Setting the white point and the black point is simple when a shot includes an area that should obviously be very light and another area that should be very dark. You look for what should be the lightest area of the image and adjust controls until it becomes as light as possible, and then do the same for the area that needs to be black. You can dramatically improve the quality of shots taken using insufficient or excessive light just by making white and black point adjustments.

In some cases, however, the shot should have a smaller brightness range (for example, when the whole scene was originally in shadow or was shot at sunset). In such cases, you need to be careful to expand the range as much as possible without making parts of the image unrealistically light or dark.

Do not clip any significant part of the image. You want the range between your lightest value and your darkest value to be as large as possible, but you don't want to lose detail by reducing all your very light values to white or all your very dark values to black.

Do not use intense reflected spots of light — speculars — to judge where your white point should be. If you do so, you define white by an artificial standard that probably occurs in only a tiny fraction of the image. A true white object such as an item of clothing might appear dull and gray by this standard.

You have a number of choices for controls to use to make white point and black point adjustments, including the Gain and Offset sliders in the Hue Offsets subdividing tab of the HSL group and the Master curve in the Curves tab. You can set all of these controls automatically using the Auto Black, Auto Contrast, and Auto White buttons. If necessary, you can begin with an automatic correction and then fine-tune the adjustment manually.

Adjusting the Gray Point

Once you establish the range from the brightest part of the image to the darkest part, you can adjust the gray point if necessary. When you make a gray point adjustment, you define how much of the overall tonal range is between black and midgray, and how much is between midgray and white.

The most obvious effect of a gray point adjustment is that it either lightens or darkens the overall look of the image. Large adjustments of the gray point toward either the black point or the white point are almost always undesirable because they leave the whole image much too dark or too light.

Smaller, well-chosen gray point adjustments, however, are useful for fine-tuning the overall brightness of the image. Also, because a gray point adjustment expands the tonal range on one side of the midpoint and contracts it on the other, it can be useful for improving contrast and detail overall. For example, some images look better if more contrast is available in the range between gray and white, even though this reduces the contrast between gray and black.

The main control for making gray point adjustments is the Gamma slider in the HSL group.

Neutralizing Color

Neutralizing color returns the colors in an image to the colors that a viewer would have perceived when standing beside the camera. Most film or video images depart from that ideal to some degree.

One way to think about neutralizing color is to imagine working on a project where every shot includes a large card that we know is a perfectly neutral midgray color when viewed in ideal lighting conditions. If you can correct each image so the card appears midgray when your audience views the final program, all other colors in the images should be correct also.

You cannot normally have such a perfect measuring device in your images, but you can select one area of each image as a target for your color neutralizing adjustments. If you focus on getting the color in that area right, color in the rest of the image should fall into place. In some images, there might be an object or area that should be neutral gray, or nearly so, and you can use that area as your principal target as you make adjustments. In fact, this is exactly how you make corrections to remove color casts using the Remove Color Cast buttons. In

other images, you might not have any gray color at all, but you will probably have some other area where even a small departure from neutral color is noticeable. Human skin is the most common example. Or you might choose to focus on an area where you know the true color, such as a person's hair.

In addition to identifying parts of your image on which to concentrate your attention, it is useful to establish how the uncorrected image departs from neutral color before you attempt to correct it.

Sometimes this is obvious. You cannot mistake an image with an extreme pink or yellow cast. When the problem is more subtle, you can sample a few areas with the Color Match eyedropper to get information about the color characteristics of the image. Areas that should be white or black are particularly helpful, since these are easily identifiable colors that should have nearly identical values for red, green, and blue. If the red value is higher than the other two, the image has a red cast. If red and green are higher than blue, the image has a yellow cast.

You can neutralize color using different controls in the Color Correction tool. For example, you can use the Curves tab to adjust the proportions of each color. Or you can use the Hue Offsets ChromaWheel controls, which let you quickly locate the sector of the wheel that represents the color cast in the image, and then adjust in the opposite direction to that color. You can make either of these adjustments automatically using the Auto Balance buttons, and then fine-tune manually if necessary.

The more experienced you become as a colorist, the better you get at judging even subtle color problems by eye and knowing intuitively what kinds of adjustments to make.

Achieving Shot-to-Shot Consistency

The most common reason for departing from the look of the original shot is to achieve simple shot-to-shot consistency in the finished program. If a scene in a drama that is supposed to take place at one time is shot over two days, and lighting conditions have changed from one day to the next, you probably want to adjust all the shots so they appear to be taking place at the same time.

Adjustments for shot-to-shot consistency are straightforward in most cases. You simply need to compare shots in the Composer window and then adjust them to match. If you have already adjusted tonal range and neutralized color well, a small change to relative brightness might be all that you need.

Depending on the requirements of your project, you might choose to make adjustments for shot-to-shot consistency as Source or as Program relationship corrections. If you have made a lot of earlier Source relationship adjustments and you know you do not need to make overall adjustments for a finished look, you might choose to move to Program relationships

to make shot-to-shot corrections. If you expect to need Program relationships for significant finishing adjustments that apply across all the segments in your sequence, you should stay with Source relationships when making shot-to-shot adjustments.

Achieving a Final Look

Some projects might require final adjustments to create a finished look. For example, you might slightly increase saturation across the whole sequence to create richer-looking colors or slightly darken all the shots to enhance a mood of tension or suspense. In certain circumstances, you might make substantial changes to the color values of the whole sequence or remove color entirely from some parts of it.

One way to make final corrections of this kind is to apply color correction to a filler track that is the topmost track in the Timeline. It is not possible to generalize about which controls to use to make such adjustments. You might need to use any combination of color correction controls. The only effective preparation for such work is practice using the Color Correction tool and a good understanding of the more specific corrections discussed in the sections above.

Examples of Color Correction Problems

The original images in the following examples require corrections to improve tonal range and to neutralize color casts.

Each example provides the following information:

- An analysis of the original image.
- Step-by-step descriptions of the corrections with illustrations (including split-screen displays in some instances).
- Sample RGB values that illustrate the results of the corrections.
- Suggestions for alternative ways to achieve similar results with the Color Correction tool.

These examples are intended as aids to learning, not as inflexible instructions for making corrections or models of what a perfect correction looks like. Each example shows only one possible way of making a correction and one possibility for a corrected image. As you develop your own color correcting skill and judgment, you might prefer to use different combinations of controls and to aim for a slightly different final look.

Example 1

Analysis of Original Image



Uncorrected image

This image has two obvious problems. First, it lacks contrast and detail because it does not have a full tonal range. A correction will improve sharpness and detail in areas such as the shirt and the man's hair. Second, the image has a strong yellow-green cast. This leads in particular to a very unnatural skin tone.

Step 1: Contrast Correction




The first step of this correction adjusts the Contrast slider in the Controls tab of the HSL group. This adjustment, which sets the Contrast slider value to 11, illustrates one of the simplest ways to affect the tonal range of an image. Despite its simplicity, the correction improves the image noticeably. Compare the look of the man's hair on either side of the split-screen dividing line.



Split screen: uncorrected image and image after Contrast correction

Step 2: ChromaWheel Correction



The second step of this correction removes the color cast by making a single adjustment on the Midtones ChromaWheel control on the Hue Offsets tab of the HSL group. Because the image is obviously too green, the correction moves the crosshair pointer away from the green sector of the wheel. The adjustment shown is Hue: -94, Amount: 11. This places the crosshair between the magenta and blue parts of the wheel, opposite a point between green and yellow. This successfully restores a good skin tone and reveals the man's shirt to be blue.

A sampling of an area of the man's shirt before and after the corrections shows the following RGB values:

- Before — R:37, G:56, B:61
- After — R:14, G:26, B:55

These numbers reinforce the nature of the corrections. The hue offset adjustment reduces the red and green levels significantly while preserving the amount of blue in the image.



Split screen: uncorrected image and image after both corrections

Alternative Techniques

There are several alternate ways to make the tonal range adjustments to this image. You could use the Gain, Gamma, and Setup sliders as an alternative to the basic adjustment on the Contrast slider. You could also use the Master ChromaCurve graph in the Curves tab.

Example 2

Analysis of Original Image



Uncorrected image and reference image

In this example, two different cameras have been used to shoot the rock climbers. The second camera is correctly balanced and shows good color characteristics, but the images from the first camera show a strong blue cast and are too dark. Corrections can neutralize color and raise the brightness level in the first image so that it more nearly matches the second. You can use the image from the good camera as a reference for the corrections. In this example, the corrections use the Curves tab. One advantage of Curves tab adjustments is that you can make quite complex changes without having to alter many controls. The corrections in this example add and then move a single control point in each of two ChromaCurve graphs.

Step 1: Blue ChromaCurve Correction



The first step of this correction removes the excess blue in the image by adjusting the Blue ChromaCurve graph in the Curves tab. A control point is placed near the center of the curve because the adjustment must apply relatively evenly across the whole luminance range. The control point is then moved down to reduce blue. The input and output values for this adjustment are 142 and 104 respectively.



Split screen: uncorrected image and image after Blue ChromaCurve correction

Step 2: Master ChromaCurve Correction



The second step of this correction increases the brightness of the image by making an adjustment on the Master ChromaCurve graph in the Curves tab. The control point is placed three-quarters of the way up the curve and moved up and to the left. The input and output values for this adjustment are 178 and 213 respectively. The resulting curve increases brightness throughout the image but increases it most in the highlights range. This creates more contrast in the lower three-quarters of the luminance range (in a ChromaCurve graph, contrast is greater where the curve is steeper).



Split screen: uncorrected image and image after both corrections

The following illustration compares the corrected image to the reference image from the good camera. You could still fine-tune to match the shots more precisely, but the images from the two cameras are now much closer to one another.



Reference image and corrected image

A sample of one of the climber's white helmets before and after the correction and in the reference image shows the following RGB values:

- Before — R:113, G:139, B:211
- After — R:142, G:152, B:174
- Reference — R:146, G:174, B:185

21 Color Correction Techniques

Though these samples might not be from precisely the same part of the helmet in all three cases, they clearly confirm the nature of the correction. They indicate a relative gain in red and green levels, a reduction in blue levels, and a much closer match with the levels in the reference frame.

Alternative Techniques

You could make the Blue ChromaCurve graph correction in the Hue Offsets tab or even with a series of adjustments to the HSL sliders in the Controls tab. You could make the brightness and contrast adjustment in the HSL tab (using similar techniques to those in example 1).

22 Safe Colors

This chapter provides information about the Safe Colors feature of your Avid editing application.

- [Overview of Safe Color Limits](#)
- [Safe Color Settings Options](#)
- [Understanding the Graphical View of Safe Color Settings](#)
- [Understanding Safe Color Warnings](#)
- [Managing Safe Color Warnings](#)
- [Making Adjustments to Achieve Safe Color Values](#)
- [Safe Color Limits with Waveform and Vectorscope Information](#)
- [Working with the Safe Color Limiter Effect](#)

Overview of Safe Color Limits

Your Avid editing application can warn you when the color values in your sequence fall outside of a range that you specify. Your Avid editing application can also limit all or part of your sequence to the safe color range that you specify. Your Avid editing application lets you set three different types of safe color limits — for the composite signal range, for the luminance range, and for the RGB gamut.

Typically, safe color limits are useful to ensure that your sequence stays within a range of values acceptable for broadcast or for additional processing such as DVD encoding, or more generally to ensure that colors display well on television screens.

Most broadcasting companies set specific limits for the composite signal and the luminance range. Programs that do not meet these limits are not normally accepted for broadcast. For example, a typical set of limits for broadcast in the United States might restrict the composite signal to a range from –20 IRE to 110 IRE and limit the maximum luminance to approximately 100 IRE..



The composite signal for a program intended for broadcast should never exceed 120 IRE, which is the highest level that can be broadcast.

If you are working on a program intended for broadcast, you should determine what the safe limits for composite and luminance are and type them in the appropriate areas of the Safe Color Settings dialog box. You can then instruct your Avid editing application to warn you when those limits are exceeded. For more information, see [“Safe Color Settings Options” on page 814](#).

RGB gamut refers to the intensity of each individual color channel — red, green, and blue. This measure of a safe color is less likely to be subject to specific broadcast standards, but it is still an important limit type. Colors that have extremely low or high gamut values might not display well on television screens.


Safe Color Settings Options

You set safe color limits and control how your Avid editing application applies those limits by selecting options in the Safe Color Settings dialog box. For information on how to open the Safe Color Settings dialog box and set limits and options, see [“Managing Safe Color Warnings” on page 819](#).

The Safe Color Settings button in the Color Correction tool provides a visual indication of the status of the Safe Colors feature. If Warn is selected in one or more of the Actions menus, the icon on the Safe Color Settings button appears orange to indicate that at least some of the Safe Colors options are active. Otherwise, the icon on the Safe Color Settings button appears black.

The following table describes the available limit types, units of measurement, and types of action in the Safe Color Settings dialog box.


Option	Description
Composite	Defines safe color values for the composite video signal.
Luminance	Defines safe color values based on brightness.
RGB Gamut	Defines safe color values based on color range.

Option	Description
Units buttons	<p>Define the units of measurement for the three types of safe color values.</p> <p>Click the Composite Units button and select either IRE or mVolts (millivolts).</p> <p>Click the Luminance and RGB Gamut buttons and select from the following options:</p> <ul style="list-style-type: none">• 8 Bit: Measures the adjustment on a scale from 0 to 255.• % (percent): Measures the adjustment on a percentage scale. Percentage values can be lower than 0 or higher than 100..• IRE: Measures the adjustment in IRE units.• mVolts: Measures the adjustment in millivolts. <p> <i>The RGB value for a color in the Color Correction tool is not identical to the RGB value for the same color in a graphics application such as Adobe® Photoshop®. For example, the 8-bit RGB values for reference black and reference white are 16 and 235 respectively.</i></p>
Actions buttons	<p>Define how your Avid editing application implements the safe color settings. The top button controls both the Composite and the Luminance limit types. The bottom button controls the RGB Gamut limit type.</p> <p>Click an Actions button and select from the following options:</p> <p>Ignore: Your Avid editing application does not limit based on these settings. This is the default setting.</p> <p>Warn: Your Avid editing application provides warnings when these limits are exceeded. For more information on safe color warnings, see “Understanding Safe Color Warnings” on page 817.</p>

Understanding the Graphical View of Safe Color Settings

The Safe Color Settings dialog box provides a graphical display of the current limit values in relation to the default values. This lets you quickly check that your limits are consistent with one another and within an acceptable range without having to read all the numerical limit values and remember the default values.

The following illustration shows the location of this graph within the Safe Color Settings dialog box. All settings in this illustration are at their default values.




Safe Color Settings graph in the Safe Color Settings dialog box


The graph shows colored bars that represent the current low and high levels for each limit type. The colors are the same as those used to display safe color warnings in the monitors. It also displays gray vertical lines that represent the default high and low levels for each limit type.

The following illustrations present two graphs in detail — the first showing default levels and the second showing adjusted levels — and explain how to interpret the graphs.

	Low	High
Composite	-20.00	100.00
Luminance	7.50	100.00
RGB Gamut	0.00	255.00



Default Safe Color Settings values (top) and their representation in the Safe Color Settings graph (bottom). The colored bars represent (top to bottom) the Composite, Luminance, Red, Green, and Blue levels. Bars on the left indicate the low limit, while bars on the right indicate the high limit.



Adjusted Safe Color Settings values (top) and their representation in the Safe Color Settings graph (bottom). Colored bars that extend past the gray lines toward the center of the graph indicate a setting that is more restrictive than the default. Colored bars that retreat from the gray lines toward the edges of the graph (as the top two bars on the right do) indicate a setting that is less restrictive than the default.

Understanding Safe Color Warnings

If you select the Warn option for one or more of the types of safe limit, your Avid editing application displays warnings when material exceeds the limits you have set. You select the Warn option using the Actions button (see [“Managing Safe Color Warnings” on page 819](#)).

Warnings appear in the monitors for all limit types — Composite, Luminance, and RGB Gamut. The warning indicators do not appear unless color levels exceed at least one of the limits currently set to Warn. Warnings appear in the Color Match control for RGB Gamut limits only.




Safe color warnings appear when you exceed limits in either field of the frame if you are working with two-field media. To move through video material one field at a time and see safe color information for every field, use the Step Forward One Field button or the Step Backward One Field button. In Color Correction mode, these buttons are available on the Move tab of the Command palette. You can also map these buttons to your keyboard to use them quickly while using Color Correction mode.

Safe Color Warnings in the Monitor Window

When your Avid editing application is set to provide safe color warnings, warning information appears in the monitor window for any image whose color values are outside the safe range. You see an orange safe color warning triangle in the top left corner of the image, along with warning indicators for each of the safe color value types that are currently set to warn. Warning color bars appear in one of three places in a column:

- At the top (indicating a level that is too high)
- At the bottom (indicating a level that is too low)
- In the center (indicating a level that is within limits)

The following illustration shows a typical warning indicator display.



Safe Color warning indicators for monitors. In this example, the Composite (yellow), Red, and Green levels exceed the current limits at the high end, while the Red and Green levels also exceed the current limits at the low end. The Luminance (white) and Blue levels are within limits.

If a warning indication displays in the monitor for an image, you can choose to leave the image with color values that exceed your safe limits, or you can make one or more color corrections to bring the levels back within safe limits. Once all levels are within safe limits, the warning triangle and warning indicators no longer display in the monitor.

For suggestions on specific correction steps you might take to bring color values within safe limits, see [“Making Adjustments to Achieve Safe Color Values” on page 820](#).

Safe color warning information might also appear in the Color Match color swatches and in waveform and vectorscope displays. For more information, see below and [“Safe Color Limits with Waveform and Vectorscope Information” on page 821](#).

Safe Color Warnings in the Color Match Control

If you select the Warn option for the RGB Gamut limit type, your Avid editing application displays warnings in the color swatches of the Color Match control when values exceed the limits you have set. If you use the eyedropper to select an input or output color that exceeds limits, a warning triangle appears beside the color information in the appropriate color swatch. The following illustration shows a swatch with typical Safe Color warnings.

R:254
G:245
B:232




In this example of a Color Match swatch for an intense white color, both the Red and Green levels exceed the High RGB Gamut setting of 235 and warning triangles appear. The Blue value remains just within the limit.

Managing Safe Color Warnings

You turn safe color warning on or off, and set the range of values your Avid editing application should consider safe, in the Safe Color Settings dialog box.

For more information about the Safe Color Settings dialog box, including information about safe color value ranges and unit types, and about the graphical display of safe color settings that appears at the bottom of the dialog box, see [“Safe Color Settings Options” on page 814](#) and [“Understanding the Graphical View of Safe Color Settings” on page 815](#).

The following illustration shows the Safe Color Setting dialog box.



Units buttons (left) and Actions buttons (right) in the Safe Color Settings dialog box

To open the Safe Color Settings dialog box, do one of the following:

- ▶ In the Settings list of the Project window, double-click Safe Colors.
- ▶ In the Color Correction tool, click the Safe Color Settings button.



To turn safe color warning on or off:

- ▶ Click one of the Actions buttons in the Safe Color Settings dialog box, and select Warn to turn safe color warning on or Ignore to turn safe color warning off.

The top Actions button controls Composite and Luminance warnings. The bottom Actions button controls RGB Gamut warnings.

To set a safe color value range for one of the value types (Composite, Luminance, or RGB Gamut):

1. Click the Units button for the value type you want to set in the Safe Color Settings dialog box, and select a unit of measurement for your values.
2. Type low and high values in the text boxes for the value type.

For example, you might enter values supplied by a broadcaster or encoder.

Making Adjustments to Achieve Safe Color Values

If some of your color levels exceed limits, you can return them to safe color values by adjusting the color correction controls in any combination. The following example procedures show how to make various adjustments using the Controls subdividing tab of the HSL group and the Curves group.



You can also use the Safe Color Limiter effect to achieve safe color values automatically. For more information, see “Working with the Safe Color Limiter Effect” on page 823.

To bring luminance within safe limits:

1. Click the Controls subdividing tab in the HSL group.
The Controls tab opens.
2. Click the Enable button for the HSL group and the Controls subdividing tab.
3. Click the Enable button for Clip Low and Clip High controls to activate them.
4. Type **16** in the Clip Low text box, and press Enter (Windows) or Return (Macintosh).
5. Type **235** in the Clip High text box, and press Enter (Windows) or Return (Macintosh).

Your Avid editing application clips Luma values to safe levels.

To bring RGB values within safe limits:

1. In the Master ChromaCurve graph of the Curves tab, click the lower left control point to select it.

A circle appears around the point.

2. Under the Master ChromaCurve graph, type **16** in both the input text box and the output text box.

The control point moves to 16, 16. Your Avid editing application adjusts RGB values under 16 up to 16.

3. In the Master ChromaCurve graph of the Curves tab, click the upper right control point to select it.

A circle appears around the point.

- Under the Master ChromaCurve graph, type 235 in both the input text box and the output text box.

The control point moves to 235, 235. Your Avid editing application adjusts RGB values above 235 down to 235.

To bring composite levels within safe limits:

- First adjust luminance and RGB levels using the previous procedures.
If composite levels do not fall within safe limits, continue with step 2.
- Click the Curves tab.
- If the composite high warning is on, do the following:
 - ▶ In the Master ChromaCurve graph, Shift+click the upper right control point, and drag it down the curve until the composite high warning turns off.
- If the composite low warning is on, do the following:
 - ▶ In the Master ChromaCurve graph, Shift+click the lower left control point, and drag it up the curve until the composite low warning turns off.

Safe Color Limits with Waveform and Vectorscope Information

Broadcasters or distributors often issue safe color limits for video levels. Video levels outside safe color limits are generally known as “illegal” A program with illegal levels might be rejected on technical grounds or the image quality might suffer with further processing. You might want to set reasonable limits for yourself even if you are not aware of specific limits that you must meet.

In Y (luma only) waveforms, reference white of 100% corresponds to a digital level of 235, an NTSC level of 100 IRE, and a PAL level of 700 mV. White excursions up to 108% are technically possible.

In Y (luma only) waveforms, reference black of 0% corresponds to a digital level of 16, an NTSC level of 7.5 IRE, and a PAL level of 0 mV. Black excursions down to –8% are technically possible.



With both white and black levels, further signal processing after output from your Avid editing application might clip the peaks in your material. In addition, delivery specifications might require you to limit the white peaks to a lower level and the black peaks to a higher level.

Use Y Waveform to see the black and white levels of your image. Sometimes, particularly with white levels, keeping the white peaks within the 100% limit does not produce a pleasing level for the rest of the image. This is particularly common with backlit subjects, where the sky or a window is in the background and the lighting on the foreground is insufficient. In these cases, you might want to adjust for the foreground and leave the background too bright.

Chroma peaks are easiest to see on the vectorscope. The theoretical maximum is the circle around the outer edge, but to be safe you might like to keep vectors closer to the center than the 75% color bar squares.

Saturated bright or dark colors might have very low or high luma values, together with a lot of chroma. Even if neither luma nor chroma alone is excessive, the combination can be illegal. For example, vivid yellow and cyan in an image can produce composite levels that are too high, and those from vivid blue might be unacceptably low. The YC Waveform is a good way to see how far these levels extend. In general, avoid levels above approximately 120 IRE or 850 mV, and those below -20 IRE or -200 mV.



If you are producing a master for broadcast delivery, ask for delivery specifications. To ensure you meet particular standards, use a legalizer such as the Safe Color Limiter effect or a third-party AVX™ plug-in.

These instruments do not measure analog outputs. If your Avid editing system or other device uses analog connections, use an external Waveform monitor to verify levels.

The Y Waveform, YC Waveform, and RGB Parade displays incorporate any safe color limits you have set. The following table describes the colors used to represent various conditions. “Legal” means the value is within the safe color limits. “Illegal” means the value is outside (either above or below) the safe color limits.

Display	Component	Value	Display Color
Y Waveform	Luma	Legal	Green
		Illegal	White
YC Waveform	Composite	Legal	Cyan
		Illegal	Yellow
	Luma	Legal	Green
		Illegal	White
	Composite or Luma	Outside display boundaries	Red

Display	Component	Value	Display Color
RGB Parade	Red	Legal	Red
		Illegal	White
	Green	Legal	Green
		Illegal	White
	Blue	Legal	Blue
		Illegal	White

Working with the Safe Color Limiter Effect

In addition to the safe color warning system, you can also limit colors to safe ranges by applying the Safe Color Limiter effect. The Safe Color Limiter effect modifies color and luminance values in video material to bring the material within the safe color limits you define. If you use the Safe Color Limiter effect, you do not have to make manual adjustments in the Color Correction tool to ensure that video is within limits.

Understanding the Safe Color Limiter Effect

The Safe Color Limiter effect has effect parameters that control high and low color limits for luminance, composite signal, and red, green, and blue color gamut. It also lets you change the units for measuring these limits. These parameters parallel the options available in the Safe Color settings.

When you first apply a Safe Color Limiter effect, its parameters default to the current limits in the Safe Color settings. In the simplest situation, you can set limits in the Safe Color settings that meet your needs (for example, luminance or composite signal standards set by a broadcaster), and then apply the Safe Color Limiter effect to the video material you need to limit. Without any further adjustment, the effect modifies the color and luminance values of any pixels in the video material that exceed your limits, ensuring that the video meets the required standards. For more information on safe color limit values and possible reasons for using them, see [“Overview of Safe Color Limits” on page 813](#).

When you want to make adjustments to the safe color limits that a Safe Color Limiter effect is using, you do so using parameter controls in the Effect Editor. You can also view an analysis of the image in the Source monitor that makes it easy to see exactly which pixel areas in an image are outside the limits set for the effect. For more information, see [“Using the Safe Color Limiter Analysis Display” on page 825](#).

The following information provides important additional details on how the Safe Color Limiter effect operates:

- The Safe Color Limiter automatically takes variations in broadcast formats into account, for example the differences between PAL and NTSC material, and the difference in the setup offset between NTSC and NTSC-J.
- Because the primary purpose of safe color limiting is to ensure that video is acceptable for SD broadcast, all limiting by the Safe Color Limiter effect is performed in the 601 color space. When you are working with HD material in the 709 color space, the Safe Color Limiter converts the material to the 601 color space to apply limiting, and then converts back to the 709 color space.
- Like many other Avid effects, the Safe Color Limiter effect supports both 8-bit and 16-bit processing. For more information, see [“Using 16-Bit Processing Support for Rendered Effects” on page 172](#).

Applying the Safe Color Limiter Effect

A common scenario for applying the Safe Color Limiter effect is to apply it to filler on the top track in the Timeline so that the effect acts on the entire duration of the sequence.

Depending on your needs, you might also want to apply a Safe Color Limiter effect to a single segment in a sequence, or to multiple selected segments.

To apply the Safe Color Limiter effect:

1. Set the default safe color limits you want the Safe Color Limiter effect to use.
For more information, see [“Managing Safe Color Warnings” on page 819](#).
2. (Option) If you want to apply the effect across the entire duration of the sequence, add a new video track in the Timeline, for example, by selecting **Clip > New Video Track**.
3. Do one of the following:

- ▶ If you are applying the Safe Color Limiter effect to the entire duration of the sequence, drag the effect from the Image category of the Effect Palette, and drop it on the empty top video track.

The top video track shows filler material with the Safe Color Limiter effect applied to it, and your Avid editing application limits all of the video material in the sequence according to the limit values you set in step 1.

- ▶ Apply the effect to one or more segments using standard methods, as described in [“Applying Effects From the Effect Palette” on page 36](#).

Your Avid editing application limits the video in the segment or segments to which you applied the effect according to the limit values you set in step 1.


By default, when the Effect Editor is open, the effect changes the display in the Source monitor to an analysis mode that highlights pixels in the image that fall outside the current safe color limits. For more information on using and understanding this display, see [“Using the Safe Color Limiter Analysis Display” on page 825](#).

4. If necessary, enter Effect mode and adjust effect parameters in the Effect Editor.

For more information, see [“Adjusting Effects” on page 41](#). You can adjust the low or high limit values for each limit type (composite, luminance, or RGB gamut). You can select the units used to measure the limit values. You can also turn the effect analysis display on or off. For reference information on all the Safe Color Limiter effect parameters, see [“Image: Safe Color Limiter” on page 574](#).

Using the Safe Color Limiter Analysis Display

An effect analysis display appears by default in the Source monitor when you apply a Safe Color Limiter effect. The following illustration shows a typical display.



The effect analysis display has two layers. The background layer is a copy of the image with luminance reduced to allow the foreground information to stand out clearly. The foreground layer highlights those pixels in the image whose color values fall outside the limits currently being used by the effect — that is, pixels that are being modified by the effect.

The color scheme used for the highlighting is the same as that used for the safe color warning indicators that can appear in the monitors in Color Correction mode:

Color	Description
Yellow	Indicates pixels that fall outside composite limits.
White	Indicates pixels that fall outside luminance limits.

Color	Description
Red	Indicates pixels that fall outside RGB gamut limits for red.
Green	Indicates pixels that fall outside RGB gamut limits for green.
Blue	Indicates pixels that fall outside RGB gamut limits for blue.

In the illustration above, the pixels highlighted in yellow have color values that fall outside the composite limits currently being used by the effect.

When you adjust the limit parameters in the Effect Editor, the analysis display updates. For example, if you adjust a limit parameter so that it permits a larger range of values, fewer pixels are highlighted in the analysis display.



If a pixel in the image falls outside current limits for multiple limit types, the analysis display uses the color for only one of the types to highlight the pixel. As a result, for example, you might adjust the RGB gamut limits so that a pixel no longer has a blue highlight and find that the display highlights the pixel using yellow. This is because that pixel is still being limited by the composite limits.

Index

Numerics

0% to 100% Timewarp effect [593](#)
 1:66 Mask Film effect [562](#)
 1:85 Mask Film effect [562](#)
 10 bit units for color correction [740](#)
 100% to 0% Timewarp effect [593](#)
 10-bit effects processing [154](#), [156](#)
 14:9 Letterbox Reformat effect [586](#)
 16:9 display
 Color Correction monitors [730](#)
 in the Title tool [385](#), [385](#)
 16:9 Letterbox Reformat effect [586](#)
 16:9 Mask Film effect [562](#)
 16-bit effects rendering [172](#)
 24p or 25p editing projects
 finding flaws from telecine transfer [505](#)
 3D effect parameters
 overview of reference information [703](#)
 3D parameters
 hierarchy of [703](#)
 3D Promote button (Effect Editor) [90](#)
 3D Warp Blend effect [557](#)
 3D Warp effect
 applying [362](#)
 3rd-party plug-in effects [185](#)
 4 Corners Shape Wipe effect [588](#)
 4:3 Sidebar Reformat effect [586](#)
 422 Safe effect parameter (Safe Color Limiter effect)
 [672](#)
 601 levels option
 Avid Pan & Zoom effect [656](#)
 8 bit units for color correction [740](#)
 8-bit effects processing [154](#)

A

Acceleration effect parameter [605](#)
 Acceleration parameter [531](#)
 Achieving a final look with color correction [806](#)
 Achieving safe color limits [820](#)

Achieving shot-to-shot consistency with color
 correction [805](#)
 Actions effect parameters (Pan and Scan effect) [698](#)
 Activating
 Render settings [167](#)
 Adaptive color correction guidelines [802](#)
 Adaptive deinterlacing
 Timewarp and Motion Adapter effects option [219](#)
 Add Edit function
 Submaster effects [275](#)
 Add Keyframe button [148](#)
 Add Keyframe button (Effect Editor, Effect Preview
 monitor) [113](#)
 Add Keyframe button (Effect Preview monitor) [79](#)
 Add Keyframe command (Keyframe track shortcut
 menu) [113](#)
 Add Keyframes commands (Effect Editor shortcut
 menu) [146](#)
 Add Keyframes to Active Group (Effect Editor
 shortcut menu) [117](#)
 Add Keyframes to Active Parameter (Effect Editor
 shortcut menu) [117](#)
 Add Keyframes to All Parameters (Effect Editor
 shortcut menu) [117](#)
 Add Keyframes to Enabled Groups (Effect Editor
 shortcut menu) [117](#)
 Add Keyframes to Open Graphs (Effect Editor
 shortcut menu) [117](#)
 Add Keyframes to Open Groups (Delete Keyframe
 Mode menu) [117](#)
 Add Page command (Object menu) [405](#)
 Add To Active Group command (Add Keyframe
 Mode menu) [117](#)
 Add To Active Parameter command (Add Keyframe
 Mode menu) [117](#)
 Add To All Parameters command (Add Keyframe
 Mode menu) [117](#)
 Add To Enabled Groups command (Add Keyframe
 Mode menu) [117](#)
 Add To Open Graphs command (Add Keyframe
 Mode menu) [117](#)

- Add To Open Groups command (Add Keyframe Mode menu) [117](#)
- Adding
 - comments to color corrections [741](#)
 - highlights to 3D effects [713](#)
 - keyframes to keyframe graphs [113](#)
 - pages to a rolling or crawling title [405](#)
- Adjusting
 - colors for effects [96](#)
 - effects [43](#)
 - Pan and Scan effect [291](#)
 - Render settings [167](#)
 - shadow softness in titles [416](#)
- Advanced effect parameters (Avid Pan & Zoom effect) [656](#)
- Advanced keyframes
 - Add Keyframe Mode menu and Delete Keyframe Mode menu [117](#)
 - adding [113](#)
 - aligning [126](#)
 - and nested effects [272](#)
 - copying and pasting [128](#), [130](#)
 - deleting [115](#)
 - described [101](#)
 - Effect Editor shortcut menu [146](#)
 - Effect Editor toolbar controls [142](#)
 - Effect Preview monitor [111](#)
 - extrapolating parameter values [139](#)
 - hiding graph display [104](#)
 - holding parameter values [139](#)
 - interpolation options [133](#)
 - moving [123](#)
 - nested effects [271](#)
 - opening graphs and tracks [104](#)
 - removing redundant [116](#)
 - reversing [137](#)
 - showing graph display [104](#)
 - slipping [126](#)
 - trimming effects with [138](#)
- After Effects
 - Avid After Effects External Monitor Preview plug-in [194](#)
- Align Keyframe command (shortcut menu for keyframe track) [126](#)
- Align to Frame commands (Alignment menu) [418](#)
- Aligning
 - advanced keyframes [126](#)
- Alignment
 - of titles and objects [418](#)
 - title text [397](#)
- Alpha channel
 - in 3D Matte Key effect [364](#)
 - Matte Key effects [265](#)
 - title creation with [389](#)
- Anamorphic Mask Film effect [562](#)
- Animation
 - imported [265](#)
- AniMatte effect [85](#)
- AniMatte effect (2D)
 - animating [527](#)
 - applying [470](#)
 - described [467](#)
 - exporting as PICT file [503](#)
 - matte wipe example [528](#)
 - modes [474](#)
 - rendering [469](#)
 - using Magic Mask parameters [519](#)
- AniMatte Key effect [576](#)
- Anti-alias option (Blur and Mosaic effects) [532](#)
- Anti-aliased elements in title [389](#)
- Anti-aliasing
 - limitations with rolling titles and Acceleration effect parameter [605](#)
- Applying
 - color correction effect templates [745](#)
 - color correction to an entire sequence [796](#)
 - Dissolve effects [63](#), [64](#)
 - Effect Palette Color Correction effect [754](#)
 - effect templates [47](#)
 - effects [36](#), [69](#)
 - Pan and Scan effect [284](#)
 - Submaster effects [275](#)
 - title styles [429](#)
- Arrowheads in titles [408](#)
- Aspect ratio
 - Avid Pan & Zoom effect [296](#)
 - controlling in 3D effects [717](#)
 - fixed aspect [614](#)
 - image size [725](#)
 - image size control with Target parameters [725](#)
 - Pan and Scan effect [282](#)
 - Reformat effects [281](#)
- Aspect Ratio effect parameters (Pan and Scan effect) [697](#)

Auto Balance button (Color Correction tool) [751](#)
 Auto Contrast button (Color Correction tool) [751](#)
 Auto Size mode (Title tool) [402](#)
 Auto Size Mode command (Object menu) [402](#)
 AutoCorrect options (Correction Mode settings) [798](#)
 Automatic color correction
 See Color correction
 Automatic Color Correction effect templates
 update behavior [743](#)
 Automatic color corrections
 adjusting contrast and balance [751](#)
 considerations when using [749](#)
 differences between groups [749](#)
 order of corrections [749](#)
 overview [749](#), [749](#)
 removing color casts [752](#)
 setting AutoCorrect options [798](#)
 Avid
 online support [18](#)
 training services [19](#)
 Avid After Effects External Monitor Preview plug-in
 [194](#)
 Avid DS caption file format [447](#)
 Avid Pan & Zoom effect [293](#), [294](#), [296](#), [298](#), [300](#),
 [302](#), [303](#), [304](#)
 importing to [652](#)
 zooming [653](#)
 Avid Pan & Zoom effect parameters [652](#)
 Avid Pan & Zoom Image effect [570](#)
 Avid Pan and Zoom effect
 See Avid Pan & Zoom effect
 Avid Unity [154](#), [181](#)
 Avid Visual Extensions
 See AVX
 AVX (Avid Visual Extensions) plug-in effects [185](#)
 defined [21](#), [185](#)
 installing [187](#)
 locating folders (Macintosh) [187](#)
 locating folders (Windows) [188](#)
 memory usage [186](#)
 multiple tracks [190](#)
 promoting [189](#)
 troubleshooting [192](#)
 upgrading [189](#)
 user interfaces [191](#)
 Axes in rotation (3D) [366](#)
 Axis effect parameters [704](#)

B

Background color
 selecting [390](#)
 Background Color effect parameters [705](#)
 Background effect parameter (Avid Pan & Zoom
 effect) [656](#)
 Background effect parameters [605](#)
 Background effect parameters (Illusion FX Pattern
 Generator effect) [641](#)
 Ball Shape effect [718](#)
 limitations [722](#)
 Bézier curves
 described [485](#)
 manipulating [485](#)
 Bézier keyframe interpolation option [133](#)
 Bins
 effect templates in [47](#)
 revising titles in [424](#)
 saving color correction effect templates in [743](#)
 saving custom colors to [761](#)
 titles in [431](#)
 viewing fast-saved titles in [421](#)
 Bit depth for effects processing [154](#), [156](#)
 Black lines
 removing with the Effect Aperture setting [31](#)
 Black point adjustments
 guidelines for [803](#)
 Blend effects
 3D Warp [557](#)
 Dip to Color [557](#)
 Dissolve [557](#)
 Fade from Color [557](#)
 Fade to Color [557](#)
 overview of reference information [556](#)
 Picture-in-Picture [558](#)
 Superimpose [558](#)
 Blend effects (3D)
 3D Warp [362](#)
 Blowup effect [85](#)
 Blowup effects parameter [616](#)
 Blowup Film effect [562](#)
 Blue dot [25](#)
 Blur effect (2D)
 creating [532](#)
 described [467](#)
 parameters [531](#)

Blur Effect Image effect [571](#)
 Blur effect parameters [658](#)
 Blur mode, Paint Effect example [522](#)
 Blurring images with Defocus parameters [708](#)
 Bold button (Title tool) [396](#)
 Bold command (Object menu) [396](#)
 Bold text
 in titles [396](#)
 Border (3D) effect parameters [705](#)
 Border effect parameters [606](#)
 Border effect parameters (Illusion FX) [626](#)
 Bottom Centered Squeeze effect [591](#)
 Bottom Left Corner Peel effect [582](#)
 Bottom Left L-Conceal effect [579](#)
 Bottom Left Squeeze effect [591](#)
 Bottom Left to Top Right Box Wipe effect [559](#)
 Bottom Left to Top Right Conceal effect [560](#)
 Bottom Left to Top Right Push effect [585](#)
 Bottom Right Corner Peel effect [582](#)
 Bottom Right L-Conceal effect [579](#)
 Bottom Right Squeeze effect [591](#)
 Bottom Right to Top Left Box Wipe effect [559](#)
 Bottom Right to Top Left Conceal effect [560](#)
 Bottom Right to Top Left Push effect [585](#)
 Bottom to Top Box Wipe effect [559](#)
 Bottom to Top Conceal effect [560](#)
 Bottom to Top Peel effect [582](#), [582](#)
 Bottom to Top Push effect [585](#)
 Bottom to Top Squeeze effect [591](#)
 Box Wipe effects
 Bottom Left to Top Right [559](#)
 Bottom Right to Top Left [559](#)
 Bottom to Top [559](#)
 Left Box [559](#)
 overview of reference information [559](#)
 Right Box [559](#)
 Top Box [559](#)
 Top Left to Bottom Right [559](#)
 Top Right to Bottom Left [559](#)
 Brightness (luminance)
 defined [604](#)
 Bring Forward button (Effect Editor) [501](#)
 Bring Forward command (Object menu) [418](#), [501](#)
 Bring to Front command (Object menu) [418](#), [501](#)
 Brush effect parameters [607](#)
 Brush effect parameters (FluidMotion Edit) [698](#)
 Brush tool

 creating a custom shape for [476](#)
 painting with [474](#)
 saving a template [478](#)
 Buckets (Color Correction tool)
 clearing templates from [745](#)
 saving templates to [744](#)
 Buttons
 Bring Forward (Effect Editor) [501](#)
 Centered on Cut (Quick Transition dialog box) [74](#)
 Color Correction tool [739](#)
 Crawling Title (Title tool) [386](#), [403](#)
 Ending at Cut (Quick Transition dialog box) [74](#)
 mapping in Effect mode [81](#)
 Rolling Title (Title tool) [386](#), [403](#)
 Scratch Removal [509](#)
 Send Backward (Effect Editor) [501](#)
 Starting at Cut (Quick Transition dialog box) [74](#)
 Bypass effect parameter (SpectraMatte effect) [680](#)

C

Cache effect parameters (Avid Pan & Zoom effect)
 [657](#)
 Caption file formats [447](#)
 Caption files
 exporting from SubCap effect [458](#)
 importing into the SubCap effect [453](#)
 Captioning
 See SubCap effect
 Center Box Shape Wipe effect [588](#)
 Center effect parameters (Illusion FX Kaleidoscope effect) [632](#)
 Centered on Cut button (Quick Transition dialog box)
 [74](#)
 Centered on Cut effect parameter [615](#)
 Centered Zoom Squeeze effect [591](#)
 Changing perspective of 3D effects [714](#)
 Character mapping in Title tool [445](#)
 Chroma Adjust [661](#)
 Chroma Adjust effect parameters [661](#)
 Chroma Control effect parameters (SpectraMatte effect) [684](#)
 Chroma Key effect (3D)
 creating [378](#)
 Chroma Key effect parameters (RGB Keyer effect)
 [679](#)
 Chroma Key Key effect [576](#)

ChromaCurve graphs (Curves group in Color Correction tool)
 described 770, 771
 making adjustments to 773
 setting color background 740

ChromaWheel controls (HSL group in Color Correction tool)
 correcting color cast with 766
 crosshair pointers 769
 setting color background 740
 understanding 766

Chrominance
 of Color Effect 661

Circle and Oval tool (Title tool) 400

Circle effect parameters (Illusion FX Pattern Generator effect) 642

Circle Shape Wipe effect 588

Clear Monitor command (Clip Name menu in Source monitor) 434

Clear Renders command (Clip menu) 58

Clearing
 color correction effect templates from buckets 745
 rendered effects 58

Clearing a stamp 377

Client monitor 287
 color correction with 734

Clock Shape Wipe effect 588

Close command (File menu)
 exiting Title tool with 421

Collapse button 277

Collapsing layers with Submaster effect 277

Color
 blending, in titles 411, 412
 for Paint Effect 475
 safe limits for titles 389, 391
 selecting for titles 411, 412

Color adjustment for effects 96

Color background for titles 390

Color balance
 automatic color correction of 751

Color casts
 automatic color correction of 751, 752
 correcting with ChromaWheel controls 766

Color coding for effects 25

Color coding of playback information in Timeline 152

Color correction

See also listings by specific controls and concepts, for example, Automatic color correction or Custom colors

applying to entire sequence 796

automatic, applying from Effect Palette 754

automatic, from Effect Palette 754

automatic, with Color Correction effect 754

Client monitor, using for 734

examples of typical problems 806

keyframeable parameters 784

overview 727

playing sequences with Play Loop button 734

reasons for using 728

using IN and OUT marks with 740

workflow 747

Color Correction command (Toolset menu) 729

Color Correction effect (Effect Palette)
 applying 754
 deleting 799
 described 797
 saving as a template 799

Color Correction effect parameters (RGB Keyer effect) 680

Color Correction Effect Template button (Color Correction tool) 743

Color Correction Effect templates
 applying 745
 clearing from buckets 745
 saving to buckets 744

Color Correction effect templates
 automatic template update behavior 743
 described 742
 save behavior 743

Color correction groups
 color correction, displaying 735

Curves 770
 described 735
 displaying 736

HSL (Hue, Saturation, Luminance) 762

interaction between 736

Color correction guidelines
 achieving a final look 806
 achieving shot-to-shot consistency 805
 adapting the original look of a shot 802
 black point adjustments 803
 correcting tonal range 803
 gray point adjustments 803

- neutralizing color [804](#)
- restoring an original look [801](#)
- stages of correction [803](#)
- white point adjustments [803](#)
- Color Correction Image effect [571](#)
- Color Correction mode
 - Composer Window in, described [730](#)
 - customizing [740](#)
 - Effect Editor in [783](#)
 - entering and leaving [729](#)
- Color Correction Mode button (Timeline) [729](#)
- Color Correction monitor
 - keyframes [785](#)
- Color Correction monitors
 - 16:9 display in [730](#)
 - customizing image display [731](#)
 - Dual Split display in [732](#)
 - reference frame display in [731](#)
 - Source menu in [731](#), [731](#)
- Color Correction tool
 - buckets, clearing templates from [745](#)
 - buckets, saving templates to [744](#)
 - buttons [739](#)
 - Controls tab (HSL group), described [763](#)
 - Controls tab (HSL group), using [763](#)
 - customizing histogram display [740](#)
 - described [734](#)
 - displaying subdividing tabs [736](#)
 - displaying tabs in [736](#)
 - Enable buttons in [737](#)
 - Hue Offsets tab (HSL group), described [766](#)
 - overview [734](#)
 - resetting controls in [737](#)
 - tabs in [735](#)
 - turning controls on or off [737](#)
- Color Effect Image effect [572](#)
- Color effect parameters (Paint Effect) [672](#)
- Color Gain effect parameters [663](#)
- Color Match control
 - 3 x 3 averaging of pixels, using [757](#)
 - correcting with [757](#)
 - Curves tab, using in [776](#)
 - described [756](#)
 - displaying RGB values [762](#)
 - example of use [760](#)
 - Match Type options for [759](#)
 - safe color warnings in [817](#)
 - Color Match control in Paint Effect mode [664](#)
- Color Mix Illusion FX effect [565](#)
- Color Style effect parameters [662](#)
- Command palette [81](#)
- Comments
 - adding to color corrections [741](#)
 - displaying in the Timeline [741](#)
- Comments button (Color Correction tool) [741](#)
- Comments command (Timeline Fast menu) [741](#)
- Comparison of similar 2D effects [601](#)
- Composer window
 - in Color Correction mode [730](#)
- Composite limits for broadcast [813](#)
- Composite/Luma Levels effect parameters (Safe Color Limiter effect) [673](#)
- Conceal effects
 - Bottom Left to Top Right [560](#)
 - Bottom Right to Top Left [560](#)
 - Bottom to Top [560](#)
 - Left to Right [560](#)
 - overview of reference information [560](#)
 - Right to Left [560](#)
 - Top Left to Bottom Right [560](#)
 - Top Right to Bottom Left [560](#)
 - Top to Bottom [560](#)
- Console window
 - AVX plug-in effect messages [192](#)
- Constant Velocity option
 - Avid Pan & Zoom effect [653](#)
- Contrast
 - automatic color correction of [751](#)
- Control points
 - manipulating in ChromaCurve graphs [773](#)
- Control points in Intraframe objects
 - adding [492](#)
 - deleting [492](#)
 - described [485](#)
 - moving [493](#)
 - removing [492](#)
 - selecting [493](#)
- Controlling
 - playback quality of effects [156](#), [157](#)
 - real-time effects playback [154](#)
- Controlling image sharpness with Defocus
 - parameters [708](#)
- Controls tab (HSL group in Color Correction tool)
 - controls in [765](#)

- described 763
 - making corrections with 763
 - Converting
 - formats with Timewarp effect 248
 - Coordinate system for 3D effects 366
 - Coordinates display for effects 84
 - Copy command
 - for graphic objects 418
 - for title elements (Edit menu) 418
 - Copying
 - advanced keyframes 128, 130
 - keyframes 148
 - tracking data 354
 - Core effect parameters (Illusion FX Lightning effect) 634
 - Core effect parameters (Illusion FX Sparkler effect) 649
 - Corner Pin effect parameters 706
 - Corner pinning an image 374
 - Correcting color
 - See* Color correction
 - Correction Mode settings
 - AutoCorrect options 798
 - Correction Mode Settings button (Color Correction tool) 740
 - Correction Mode Settings dialog box 754
 - Crawling Title button (Title tool) 386, 403
 - Crawling Title effect 598
 - Crawling titles
 - See also* Rolling titles
 - See also* Titles
 - adding pages 405
 - adding pages to 405
 - copying or moving objects to 405
 - creating 401
 - defined 401
 - deleting pages from 405
 - formatting text in 407
 - going to a page in 405
 - inserting a blank page into 405
 - Make Crawl command 404
 - page count limits for 401
 - resizing width of 404
 - scrolling through 404
 - setting marks in 437
 - setting text formatting for 403
 - trimming 438
 - typing text for 403
 - workflow options for 401
 - Creating
 - motion effects 199, 204
 - new Render settings 167
 - stamp 377
 - Timewarp effects 213
 - trackers 321, 322
 - Creating 3D effects
 - Corner Pin 374
 - cropped foreground 373
 - Page Curl transition 371
 - Stamp 377
 - Crop (3D) effect parameters 707
 - Crop effect parameters 607
 - Cropped foreground effect
 - 3D example 373
 - Crosshair pointers in ChromaWheel controls 769
 - Crystal Illusion FX effect 565
 - Curve tool, for Intraframe editing 482
 - Curves group (Color Correction tool) 770
 - Curves tab (Color Correction tool)
 - Color Match control 776
 - examples of adjustments in 777
 - making corrections in 773
 - Custom colors
 - customizing names of 740
 - saving to bins 761
 - Custom Grid effect parameters 608
 - Custom Start effect parameter 615
 - Customizing
 - color correction histogram display 740
 - Color Correction mode 740
 - Cut command
 - for title elements (Edit menu) 418
 - Cut list 85
 - with Previsualization Marker tool information 494
- ## D
- Defining
 - color correction units of measurement 740
 - Defocus effect parameters 708
 - Delete From Active Group command (Delete Keyframe Mode menu) 117
 - Delete From Active Parameter command (Delete Keyframe Mode menu) 117

- Delete From All Parameters command (Delete Keyframe Mode menu) [117](#)
- Delete From Enabled Groups command (Delete Keyframe Mode menu) [117](#)
- Delete From Open Graphs command (Delete Keyframe Mode menu) [117](#)
- Delete From Open Groups command (Delete Keyframe Mode menu) [117](#)
- Delete Keyframe command (Keyframe track shortcut menu) [115](#)
- Deleting
 - effect media files [183](#)
 - keyframes [148](#)
 - keyframes from keyframe graphs [115](#)
 - pages from rolling or crawling titles [405](#)
 - tracking data points [338](#)
- Demoting
 - effects [44](#)
- Deselect All Keyframes command (shortcut menu for keyframe track) [122](#)
- Diamond Shape Wipe effect [588](#)
- Dip to Color Blend effect [69](#), [557](#)
- Display effect parameter (Avid Pan & Zoom effect) [652](#)
- Display effect parameters (FluidMotion Edit) [699](#)
- Display Options effect parameter (Avid Pan & Zoom effect) [652](#)
- Display rate
 - when processing effects [151](#)
- Displaying
 - color correction comments in the Timeline [741](#)
 - color correction groups [735](#), [736](#)
 - estimated render time [57](#)
 - subdividing tabs in Color Correction tool [736](#)
 - tabs in Color Correction tool [736](#)
 - waveform and vectorscope monitors (color correction) [787](#)
- Dissolve Blend effect [557](#)
- Dissolve effects [69](#)
- Dissolve Icons command (Timeline Fast menu) [29](#)
- Distribute Objects commands (Alignment menu) [418](#)
- Distributing titles [418](#)
- Drawing environment
 - preparation in Title tool [389](#), [391](#)
- Drawing tools (Title tool)
 - Arrowhead tool [408](#)
 - Border Width [408](#)

- Box Corner tool [408](#)
- circles and ovals [400](#)
- lines [400](#)
- squares and rectangles [400](#)
- Drop and Depth Shadow button (Title tool) [415](#)
- Drop shadows
 - 3D effects [717](#)
- Dropped frames [24](#)
- Dual Split button (Color Correction Composer window) [733](#)
- Dual Split button (Effect Editor) [90](#)
- Dual Split button (Effect Preview monitor) [79](#)
- Dual Split display
 - Color Correction mode [732](#)
- Duplicate command (Edit menu)
 - for title elements [418](#)

E

- Ease In and Ease Out Velocity options
 - Avid Pan & Zoom effect [653](#)
- EBU N19 caption file format [447](#)
- Edge Wipe effects
 - Horizontal [561](#)
 - Horizontal Open [561](#)
 - Lower Left Diagonal [561](#)
 - Lower Right Diagonal [561](#)
 - overview of reference information [561](#)
 - Upper Left Diagonal [561](#)
 - Upper Right Diagonal [561](#)
 - Vertical [561](#)
 - Vertical Open [561](#)
- Edit decision list (EDL)
 - See* EDL (edit decision list)
- Editing
 - segments with tracking data [352](#)
 - title text [394](#)
 - titles into sequence [432](#)
- EDL (edit decision list)
 - and fast-saved titles [421](#)
 - Submaster effects [275](#)
 - video mixdown [278](#)
- Effect categories
 - Blend [556](#)
 - Box Wipe [559](#)
 - Conceal [560](#)
 - Edge Wipes [561](#)

- Film [562](#)
- Generator [564](#)
- Illusion FX [564](#)
- Image [570](#)
- Key [575](#)
- L-Conceal [579](#)
- Matrix Wipe [580](#)
- Motion effects [581](#)
- Peel [582](#)
- PlasmaWipe [584](#)
- Push [585](#)
- Reformat [586](#)
- Sawtooth Wipes [587](#)
- Shape Wipe [588](#)
- Spin [590](#)
- Squeeze [591](#)
- Timewarp effects [592](#)
- Title effects [598](#)
- Xpress 3D [599](#)
- Effect Editor [89](#), [89](#), [90](#), [90](#), [94](#), [95](#), [96](#),
[104](#), [110](#), [117](#), [142](#), [146](#), [312](#), [319](#)
displaying in Color Correction mode [783](#)
for adjusting titles [438](#)
for Intraframe editing [470](#)
nested effects [271](#)
transition parameters [64](#)
- Effect Editor command (Tools menu) [47](#)
- Effect Grid [83](#), [84](#), [287](#)
setting options [30](#)
- Effect Icons command (Timeline Fast menu) [29](#)
- Effect mode [41](#), [42](#)
- Effect Mode button [41](#)
- Effect Palette
applying effects [36](#)
automatic color correction from [754](#)
color coding [25](#)
described [26](#)
displaying [26](#)
displaying effect templates [26](#)
resizing [26](#)
- Effect Palette Color Correction effect
applying [754](#)
deleting [799](#)
described [797](#)
saving as a template [799](#)
- Effect parameters
3D, overview of reference information [703](#)
- 422 Safe (Safe Color Limiter effect) [672](#)
- Acceleration [605](#)
- Actions (Pan and Scan effect) [698](#)
- Advanced (Avid Pan & Zoom effect) [656](#)
- Aspect Ratios (Pan and Scan effect) [697](#)
- Avid Pan & Zoom effect [652](#)
- Axis [704](#)
- Background [605](#)
- Background (Avid Pan & Zoom effect) [656](#)
- Background (Illusion FX Pattern Generator effect) [641](#)
- Background Color [705](#)
- Blur [658](#)
- Border [606](#)
- Border (3D) [705](#)
- Border (Illusion FX) [626](#)
- Brush [607](#)
- Brush (FluidMotion Edit) [698](#)
- Bypass (SpectraMatte effect) [680](#)
- Cache (Avid Pan & Zoom effect) [657](#)
- Center (Illusion FX Kaleidoscope effect) [632](#)
- changes at advanced keyframes [133](#)
- Chroma Adjust [661](#)
- Chroma Control (SpectraMatte effect) [684](#)
- Chroma Key (RGB Keyer effect) [679](#)
- Circle (Illusion FX Pattern Generator effect) [642](#)
- Color (Paint Effect) [672](#)
- Color Correction (RGB Keyer effect) [680](#)
- Color Gain [663](#)
- Color Style [662](#)
- common 2D, overview of reference information
[605](#)
- Composite/Luma Levels (Safe Color Limiter effect) [673](#)
- Core (Illusion FX Lightning effect) [634](#)
- Core (Illusion FX Sparkler effect) [649](#)
- Corner Pin [706](#)
- Crop [607](#)
- Crop (3D) [707](#)
- Custom Grid [608](#)
- Defocus [708](#)
- Display (Avid Pan & Zoom effect) [652](#)
- Display (FluidMotion Edit) [699](#)
- Display Options (Avid Pan & Zoom effect) [652](#)
- Erode/Expand [709](#)
- extrapolating values with advanced keyframes
[139](#)

- Feathering [608](#)
- Feathering (FluidMotion Edit) [698](#)
- Filtering (Avid Pan & Zoom effect) [655](#)
- FluidMotion Edit [698](#)
- for transitions [615](#)
- Foreground [609](#)
- Foreground (3D) [710](#)
- Freeze Frame [694](#)
- Generation (Illusion FX Lightning effect) [633](#)
- Generation (Illusion FX Ripple effect) [645](#)
- Generation (Illusion FX Sparkler effect) [648](#)
- Generator [616](#)
- Glow (Illusion FX Lightning effect) [634](#)
- Glow (Illusion FX Sparkler effect) [649](#)
- Grid [610](#)
- Highlight [713](#)
- Highlight Color [714](#)
- holding values in keyframe graphs [139](#)
- Illumination (Illusion FX Ripple effect) [646](#)
- Illusion FX [626](#)
- Image [652](#)
- Input (Illusion FX Color Mix effect) [626](#)
- Input (Illusion FX Crystal effect) [627](#)
- Input (Illusion FX Film Grain effect) [627](#)
- Input (Illusion FX Flare effect) [628](#)
- Input (Illusion FX FluidBlur effect) [628](#)
- Input (Illusion FX FluidColor effect) [629](#)
- Input (Illusion FX FluidMorph effect) [631](#)
- Input (Illusion FX Iris effect) [631](#)
- Input (Illusion FX Kaleidoscope effect) [632](#)
- Input (Illusion FX Melt effect) [634](#)
- Input (Illusion FX Motion Blur effect) [635](#)
- Input (Illusion FX Pagecurl effect) [635](#)
- Input (Illusion FX Particle Blast effect) [637](#)
- Input (Illusion FX Particle Orbit effect) [638](#)
- Input (Illusion FX Particle Wind effect) [639](#)
- Input (Illusion FX Pinch effect) [643](#)
- Input (Illusion FX Radial Blur effect) [643](#)
- Input (Illusion FX Random Blend effect) [644](#)
- Input (Illusion FX Rollup effect) [646](#)
- Input (Illusion FX Shear effect) [647](#)
- Input (Illusion FX Sphere effect) [649](#)
- Input (Illusion FX Swirl effect) [650](#)
- Input (Illusion FX Twist effect) [650](#)
- Input (Illusion FX Wave effect) [651](#)
- Key [676](#)
- Key (Chroma Key and Luma Key effects) [676](#)
- Key Color (RGB Keyer effect) [678](#)
- Key Color (SpectraMatte effect) [681](#)
- Lowlight Color [714](#)
- Luma Adjust [658](#)
- Luma Clip [660](#)
- Luma Control (SpectraMatte effect) [687](#)
- Luma Range [659](#)
- Magic Mask [612](#)
- Mask (FluidMotion Edit) [700](#)
- Matte Analysis (SpectraMatte effect) [681](#)
- Matte Control (RGB Keyer effect) [679](#)
- Matte Processing (SpectraMatte effect) [689](#)
- Mode (AniMatte effect) [676](#)
- Mode (FluidMotion Edit) [701](#)
- Mode (Paint effect) [663](#)
- Mosaic [663](#)
- Motion [694](#)
- Motion (Illusion FX Ripple effect) [644](#)
- Movement (Illusion FX Sparkler effect) [649](#)
- Number (Illusion FX Pattern Generator effect) [641](#)
- Offset (Illusion FX Kaleidoscope effect) [632](#)
- Other Options (Avid Pan & Zoom effect) [652](#)
- overview of reference information [603](#)
- Path (Avid Pan & Zoom effect) [654](#)
- Perspective [714](#)
- Position [613](#)
- Position (3D) [715](#)
- Position (Avid Pan & Zoom effect) [653](#)
- Position (Rolling Title and Crawling Title effects) [702](#)
- Position H (14:9 Letterbox Reformat effect) [697](#)
- Profile [677](#)
- Reformat [697](#)
- Render Mode (Avid Pan & Zoom effect) [658](#)
- RGB Levels (Safe Color Limiter effect) [673](#)
- Rotation [716](#)
- Scaling [614](#)
- Scaling (3D) [717](#)
- Scratch (Scratch Removal effect) [674](#)
- Scroll Position H (Crawling Title effect) [702](#)
- Secondary Key (Chroma Key effect) [678](#)
- Shadow [717](#)
- Shape [718](#)
- Size (Avid Pan & Zoom effect) [653](#)
- Skew [723](#)
- Source (Illusion FX FluidMorph effect) [630](#)

- Source Monitor Analysis (Safe Color Limiter effect) [672](#)
- Spill (SpectraMatte effect) [690](#)
- Spill Suppression (3D effects) [724](#)
- Spill Suppression (Chroma Key effect) [678](#)
- Stamp [724](#)
- Strobe Motion [695](#)
- SubCap [616](#)
- Target [725](#)
- Timecode [621](#)
- Title [702](#)
- Tracking [614](#), [707](#)
- Trail [726](#)
- Variable Speed [695](#)
- Velocity (Avid Pan & Zoom effect) [653](#)
- Effect Preview monitor [42](#), [44](#), [78](#), [79](#), [81](#), [82](#), [83](#), [87](#), [98](#), [111](#), [312](#), [324](#)
- Effect templates [47](#), [69](#)
 - displaying in Effect Palette [26](#)
- Effect templates for color correction
 - automatic template update behavior [743](#)
 - described [742](#)
 - save behavior [743](#)
- Effects
 - See also* Effects (2D)
 - See also* Effects (3D)
 - 16-bit rendering [172](#)
 - 2D, promoting to 3D [364](#)
 - 3D, real-time playback [366](#)
 - adjusting [43](#)
 - adjusting in Quick Transition dialog box [66](#), [72](#), [74](#)
 - adjusting in Timeline [74](#)
 - Aperture settings [31](#)
 - applying [36](#), [69](#)
 - applying dissolves [63](#), [64](#)
 - applying Intraframe [470](#)
 - applying to multiple transitions [72](#)
 - Avid Pan & Zoom [293](#), [294](#), [296](#), [298](#), [300](#), [302](#), [303](#), [304](#)
 - AVX plug-in [185](#)
 - AVX plug-in, upgrading [189](#)
 - bit depth for processing [154](#), [156](#)
 - categories in Effect Palette [26](#)
 - changing parameters at keyframes [148](#)
 - changing position within [44](#)
 - clearing rendered [58](#)
 - color coding [25](#)
 - Color Correction [797](#)
 - deleting [39](#)
 - deleting media files [183](#)
 - demoting [44](#)
 - differences by project type [27](#)
 - dropped frames [24](#)
 - fading [38](#)
 - field processing [505](#)
 - frame processing [505](#)
 - Grid settings [30](#)
 - HD projects [27](#)
 - key [251](#), [259](#), [260](#), [262](#), [265](#), [273](#)
 - layered [251](#)
 - managing media files [181](#)
 - mapping buttons [81](#)
 - motion tracking [311](#)
 - motion tracking examples [356](#)
 - nested [267](#), [269](#), [270](#), [271](#), [273](#)
 - overview of reference information [555](#)
 - overview of types [21](#)
 - Pan and Scan [282](#), [284](#), [287](#), [288](#), [289](#), [290](#), [291](#), [292](#)
 - parameters [89](#), [90](#), [94](#), [95](#), [96](#)
 - PlasmaWipe [535](#)
 - playback capabilities [24](#), [51](#)
 - playback with tracking data [344](#)
 - playing [50](#), [50](#)
 - position coordinates [84](#)
 - preview with Render On-the-Fly [52](#)
 - processing in real time [151](#)
 - processing when using Scratch Removal [508](#)
 - promoting [44](#)
 - real-time and non-real-time [24](#)
 - real-time playback [151](#), [152](#), [153](#), [154](#), [156](#), [157](#)
 - Reformat [281](#)
 - Region Stabilize [350](#), [352](#)
 - rendering [53](#), [54](#)
 - rendering options [168](#)
 - replacing existing [78](#)
 - rerendering [60](#)
 - resize handles [98](#)
 - revealing media files [181](#)
 - Safe Color Limiter (Image category) [823](#)
 - Safe Color Limiter, adjusting [824](#)
 - Safe Color Limiter, analysis display [825](#)
 - Safe Color Limiter, applying [824](#)

- sizing to fit media [40](#)
 - SpectraMatte [252](#), [253](#), [255](#), [257](#)
 - Stabilization [317](#)
 - SubCap [447](#)
 - Submaster [275](#), [277](#)
 - Timeline View settings [29](#)
 - Timewarp [210](#)
 - Trim settings [30](#)
 - wire frames [98](#)
 - Effects (2D)
 - PlasmaWipe [535](#)
 - promoting to 3D [364](#)
 - Effects (3D)
 - adjustment handles [368](#)
 - applying [362](#)
 - applying 3D Warp [362](#)
 - compatibility between Avid applications [363](#)
 - coordinate system for [366](#)
 - creating Chroma Key [378](#)
 - creating Corner Pin [374](#)
 - creating cropped foreground [373](#)
 - creating Page Curl [371](#)
 - creating Stamp [377](#)
 - matte key [364](#)
 - motion path in [368](#)
 - overview [361](#)
 - parameter adjustments [368](#)
 - promoting from 2D [364](#)
 - real-time playback [366](#)
 - Xpress 3D Effect category [363](#)
 - Effects Editing command (Toolset menu) [36](#), [41](#)
 - Effects parameters
 - Blowup [616](#)
 - Elastic command (shortcut menu for keyframe track) [138](#)
 - Elastic keyframes [138](#)
 - Ellipse Shape Wipe effect [588](#)
 - Enable button (Effect Editor) [95](#)
 - Enable buttons (Color Correction tool)
 - described [737](#)
 - interactions between [738](#)
 - Enable Tracker button (Tracking window) [315](#)
 - Ending at Cut button (Quick Transition dialog box) [74](#)
 - Ending at Cut effect parameter [615](#)
 - Enlarge button (Effect Editor) [90](#), [98](#)
 - Enlarge button (Effect Preview monitor) [79](#)
 - Enlarged image
 - moving in Effect Preview monitor [87](#)
 - Erode/Expand effect parameters [709](#)
 - Error messages
 - Video Underrun [154](#)
 - Examples
 - correction with Color Match control [760](#)
 - correction with NaturalMatch [760](#)
 - Curves tab color corrections [777](#)
 - typical color correction problems [806](#)
 - ExpertRender [152](#), [158](#), [158](#), [160](#), [162](#), [164](#), [166](#)
 - ExpertRender commands (Clip menu) [160](#)
 - Export Title command (File menu) [430](#)
 - Exporting
 - AniMatte effect as a PICT file [503](#)
 - caption files from SubCap effect [458](#)
 - matte key as PICT file [503](#)
 - titles as graphics files [430](#)
 - Extrapolate command (shortcut menu for keyframe track) [139](#)
 - Extrapolate option for keyframe graph parameter values [139](#)
 - Eyedropper [96](#)
 - 3 x 3 averaging of pixels for color correction [740](#)
 - 3 x 3 averaging of pixels, using [757](#)
 - adjusting a color with [412](#)
 - in Color Match control [757](#)
 - options for color correction [740](#)
 - selecting a color with [475](#)
- ## F
- Fade Effect button [38](#)
 - fading titles with [437](#)
 - Fade from Color Blend effect [69](#), [557](#)
 - Fade to Color Blend effect [69](#), [557](#)
 - Fading
 - effects [38](#)
 - titles [437](#)
 - Fast Forward button (Effect Preview monitor) [79](#)
 - Fast Frame Display command (Special menu) [505](#)
 - Fast Menu button (Effect Editor) [94](#)
 - Fast Save option for titles [421](#)
 - Feathering
 - for Blur and Mosaic effects [531](#)
 - for Intraframe effects [484](#)
 - using [532](#)
 - Feathering effect parameters [608](#)

Feathering effect parameters (FluidMotion Edit) 698
 Field parameter for Blowup effects 616
 Field processing 505
 Film Dissolve Film effect 563
 Film effects
 1:66 Mask 562
 1:85 Mask 562
 16:9 Mask 562
 Anamorphic Mask 562
 Blowup 562
 Film Dissolve 563
 Film Fade 563
 Mask 562
 overview of reference information 562
 Film Fade Film effect 563
 Film Grain Illusion FX effect 565
 Film projects
 position information 85
 Filtering effect parameter (Avid Pan & Zoom effect) 655
 Finding
 tracking data points 338
 Fit to Fill button 204
 Fixed Aspect effect parameter 614
 Fixed Aspect option
 Blur effect 532
 Mosaic effect 532
 Fixed Aspect parameter
 in 3D Target parameters 725
 Fixed command (shortcut menu for keyframe track) 138
 Fixed keyframes 138
 Flare Illusion FX effect 565
 Flaws 505
 Flip Image effect 572
 Flip-Flop Image effect 572
 Flop Image effect 572
 FluidBlur Illusion FX effect 569
 FluidColorMap Illusion FX effect 569
 FluidFilm 2:3 Cadence Timewarp effect 594
 FluidFilm Progressive Timewarp effect 594
 FluidMorph Illusion FX effect 569
 FluidMotion 238, 239, 246, 247
 FluidMotion Edit effect parameters
 overview of reference information 698
 FluidStabilizer 327, 346
 Font Selection button (Title tool) 395

Fonts
 compatibility between systems 384
 installing 384
 selecting 395
 setting point size 396
 substituting 384
 Foreground (3D) effect parameters 710
 Foreground effect parameters 609
 Formatting
 rolling or crawling titles 407
 title text 394
 Frame processing 505
 Freeze Frame command (Clip menu) 199
 Freeze Frame effect 199
 Freeze Frame effect parameters 694
 Freeze Frame Motion effect 581
 Freezing a rolling clip 201
 Full Quality 10-bit command (Video Quality menu) 154, 156
 Function keys
 using with title styles 427

G

Gain
 with Color Effect 663
 with key effects 676
 Generating
 tracking data 328
 Generation effect parameters (Illusion FX Lightning effect) 633
 Generation effect parameters (Illusion FX Ripple effect) 645
 Generation effect parameters (Illusion FX Sparkler effect) 648
 Generator effect parameters
 overview of reference information 616
 Generator effects
 overview of reference information 564
 SubCap 564
 Timecode Burn-In 564
 Global Properties reference for SubCap effect 620
 Glow effect for titles 416
 Glow effect parameters (Illusion FX Lightning effect) 634
 Glow effect parameters (Illusion FX Sparkler effect) 649

Go to Next Uncorrected Shot button (Color Correction Composer window) [733](#)
Go to Previous Uncorrected Shot button (Color Correction Composer window) [733](#)

Graphics

imported [265](#)
Graphics for titles
displaying grid for [389](#), [391](#)

Graphics in titles

drawing [400](#)
Graphics tablet [473](#)

Gray point adjustments

guidelines for [803](#)

Greek language

Title tool [445](#)

Green dot

in Timeline [53](#)

Grid

for title alignment [389](#), [391](#)
snapping to in Title tool [391](#)

Grid button (Effect Editor) [82](#), [84](#)

Grid display for effects [83](#)

Grid effect parameters [610](#)

Grid Matrix Wipe effect [580](#)

Group command (Object menu) [418](#), [501](#)

Grouping and ungrouping

Intraframe objects [501](#)
objects in titles [418](#)

Groups

See Color correction groups

H

Halo effect for titles [416](#)

Handles

for adjusting 3D effects [368](#)

HD projects

PlasmaWipe effects [553](#)

HD resolutions

behavior with AVX plug-ins [185](#)

HDTV aspect ratio

in the Title tool [385](#)

Head Fade button [64](#)

Hiding

advanced keyframe graph display [104](#)

Hierarchy of 3D parameters [703](#)

High-contrast images [265](#)

Highest Quality (HQ) button (Effect Editor) [90](#)

Highlight Color effect parameters [714](#)

Highlight effect parameters [713](#)

Histogram

working with PlasmaWipe effects [542](#)

Histograms

color correction, display options for [740](#)

Hold command (shortcut menu for keyframe track)

[139](#)

Hold option for keyframe graph parameter values [139](#)

Hold Velocity option

Avid Pan & Zoom effect [653](#)

Hollow drag handles, for locked objects [418](#)

Horizontal Bands Shape Wipe effect [588](#)

Horizontal Blinds Shape Wipe effect [588](#)

Horizontal Centered Squeeze effect [591](#)

Horizontal Edge Wipe effect [561](#)

Horizontal Open Edge Wipe effect [561](#)

Horizontal Open Sawtooth Sawtooth Wipe effect [587](#)

Horizontal Sawtooth Sawtooth Wipe effect [587](#)

Horizontal zoom slider for keyframe graphs [107](#)

HQ (Highest Quality) button (Effect Editor) [176](#)

HQ button (Effect Editor) [90](#)

HQ rendering [176](#)

HSL (Hue, Saturation, Luminance) group (Color Correction tool) [762](#)

HSL sliders (Color Correction tool)

described [765](#)

making adjustments with [764](#)

Hue

defined [604](#)

Hue Offsets tab (HSL group in Color Correction tool)

ChromaWheel controls in [769](#)

described [766](#)

making corrections with [768](#)

I

Illumination effect parameters (Illusion FX Ripple effect) [646](#)

Illusion FX

Background effect parameter for Pattern Generator effect [641](#)

Border parameters [626](#)

Center effect parameter for Kaleidoscope effect [632](#)

- Circle effect parameter for Pattern Generator effect [642](#)
- Core effect parameter for Lightning effect [634](#)
- Core effect parameter for Sparkler effect [649](#)
- Generation effect parameter for Lightning effect [633](#)
- Generation effect parameter for Ripple effect [645](#)
- Generation effect parameter for Sparkler effect [648](#)
- Glow effect parameter for Lightning effect [634](#)
- Glow effect parameter for Sparkler effect [649](#)
- Illumination effect parameter for Ripple effect [646](#)
- Input effect parameter for Color Mix effect [626](#)
- Input effect parameter for Crystal effect [627](#)
- Input effect parameter for Film Grain effect [627](#)
- Input effect parameter for Flare effect [628](#)
- Input effect parameter for FluidBlur effect [628](#)
- Input effect parameter for FluidColor effect [629](#)
- Input effect parameter for FluidMorph effect [631](#)
- Input effect parameter for Iris effect [631](#)
- Input effect parameter for Kaleidoscope effect [632](#)
- Input effect parameter for Melt effect [634](#)
- Input effect parameter for Motion Blur effect [635](#)
- Input effect parameter for Pagecurl effect [635](#)
- Input effect parameter for Particle Blast effect [637](#)
- Input effect parameter for Particle Orbit effect [638](#)
- Input effect parameter for Particle Wind effect [639](#)
- Input effect parameter for Pinch effect [643](#)
- Input effect parameter for Radial Blur effect [643](#)
- Input effect parameter for Random Blend effect [644](#)
- Input effect parameter for Rollup effect [646](#)
- Input effect parameter for Shear effect [647](#)
- Input effect parameter for Sphere effect [649](#)
- Input effect parameter for Swirl effect [650](#)
- Input effect parameter for Twist effect [650](#)
- Input effect parameter for Wave effect [651](#)
- Motion effect parameter for Ripple effect [644](#)
- Movement effect parameter for Sparkler effect [649](#)
- Number effect parameter for Pattern Generator effect [641](#)
- Offset effect parameter for Kaleidoscope effect [632](#)
- Source effect parameter for FluidMorph effect [630](#)
- Illusion FX effect parameters
 - overview of reference information [626](#)
- Illusion FX effects
 - Color Mix [565](#)
 - Crystal [565](#)
 - Film Grain [565](#)
 - Flare [565](#)
 - FluidBlur [569](#)
 - FluidColorMap [569](#)
 - FluidMorph [569](#)
 - Iris [568](#)
 - Kaleidoscope [565](#)
 - Lightning [565](#)
 - Melt [568](#)
 - Motion Blur [565](#)
 - overview of reference information [564](#)
 - Pagecurl [568](#)
 - Particle Blast [568](#)
 - Particle Orbit [568](#)
 - Particle Wind [568](#)
 - Pattern Generator [565](#)
 - Pinch [565](#)
 - Radial Blur [565](#)
 - Random Blend [568](#)
 - Ripple [565](#)
 - Rollup [568](#)
 - Shear [568](#)
 - Sparkler [565](#)
 - Sphere [565](#)
 - Swirl [565](#)
 - Twist [565](#)
 - Wave [565](#)
- Image effect parameters
 - overview of reference information [652](#)
- Image effects
 - Avid Pan & Zoom [570](#)
 - Blur Effect [571](#)
 - Color Correction [571](#)
 - Color Effect [572](#)
 - Flip [572](#)
 - Flip-Flop [572](#)
 - Flop [572](#)
 - Mask [573](#)
 - Mosaic Effect [571](#)
 - overview of reference information [570](#)

- Paint [573](#)
- Resize [573](#)
- Safe Color Limiter [574](#)
- Scratch Removal [574](#)
- Stabilize [575](#)
- Submaster [575](#)
- Importing
 - caption files into the SubCap effect [453](#)
 - to the Avid Pan & Zoom effect [652](#)
- Indent Rows command (Effect Editor shortcut menu) [146](#)
- Input effect parameters (Illusion FX Color Mix effect) [626](#)
- Input effect parameters (Illusion FX Crystal effect) [627](#)
- Input effect parameters (Illusion FX Film Grain effect) [627](#)
- Input effect parameters (Illusion FX Flare effect) [628](#)
- Input effect parameters (Illusion FX FluidBlur effect) [628](#)
- Input effect parameters (Illusion FX FluidColor effect) [629](#)
- Input effect parameters (Illusion FX FluidMorph effect) [631](#)
- Input effect parameters (Illusion FX Iris effect) [631](#)
- Input effect parameters (Illusion FX Kaleidoscope effect) [632](#)
- Input effect parameters (Illusion FX Melt effect) [634](#)
- Input effect parameters (Illusion FX Motion Blur effect) [635](#)
- Input effect parameters (Illusion FX Pagecurl effect) [635](#)
- Input effect parameters (Illusion FX Particle Blast effect) [637](#)
- Input effect parameters (Illusion FX Particle Orbit effect) [638](#)
- Input effect parameters (Illusion FX Particle Wind effect) [639](#)
- Input effect parameters (Illusion FX Pinch effect) [643](#)
- Input effect parameters (Illusion FX Radial Blur effect) [643](#)
- Input effect parameters (Illusion FX Random Blend effect) [644](#)
- Input effect parameters (Illusion FX Rollup effect) [646](#)
- Input effect parameters (Illusion FX Shear effect) [647](#)
- Input effect parameters (Illusion FX Sphere effect) [649](#)
- Input effect parameters (Illusion FX Swirl effect) [650](#)
- Input effect parameters (Illusion FX Twist effect) [650](#)
- Input effect parameters (Illusion FX Wave effect) [651](#)
- Installing
 - AVX plug-in effects [187](#)
- Insufficient Source message [40](#), [370](#)
- Interaction between color correction groups [736](#)
- Interface
 - motion tracking [312](#)
- Interpolation options for keyframe graphs [133](#)
- Interrupting
 - Render On-the-Fly [52](#)
 - rendering of effects [171](#)
- Intraframe editing
 - Brush tool [474](#)
 - changing effect parameters [484](#)
 - creating polygon shapes [479](#)
 - Curve tool [482](#)
 - customizing Brush shape [476](#)
 - described [467](#)
 - drawing tools [473](#)
 - examples of [519](#), [522](#), [525](#), [527](#), [528](#)
 - graphics tablet [473](#)
 - modes described [474](#)
 - Oval tool [479](#)
 - pen tool [473](#)
 - Polygon tool [479](#)
 - Previsualization Marker tool [494](#)
 - Rectangle tool [479](#)
 - rendering during [469](#)
 - saving a brush template [478](#)
 - summary of line and curve modification [491](#)
 - using control points [492](#)
 - using keyframes [500](#)
 - using Selection tool [483](#)
 - with Magic Mask [519](#)
- Intraframe objects
 - grouping and ungrouping [501](#)
 - layering [501](#)
 - locking and unlocking [501](#)
 - moving [496](#)
 - reshaping [497](#)
 - rotating along Z axis [498](#)
 - scaling [499](#)
- Invert Key option [609](#)

Inverting
 color effects [658](#)
 Inverting keys
 Full [710](#)
 IRE units for color correction [740](#)
 Iris Illusion FX effect [568](#)
 Isolating flaws for removal [509](#)
 Italic button (Title tool) [396](#)
 Italic command (Object menu) [396](#)
 Italic text
 in titles [396](#)

J

Join
 in Intraframe objects [485](#)
 Justifying
 title text [397](#)

K

Kaleidoscope Illusion FX effect [565](#)
 Kerning
 title text [397](#)
 Kerning button (Title tool) [397](#)
 Key Color effect parameters (RGB Keyer effect) [678](#)
 Key Color effect parameters (SpectraMatte effect)
 [681](#)
 Key effect parameters
 overview of reference information [676](#)
 Key effect parameters (Chroma Key and Luma Key effects) [676](#)
 Key effects [251](#), [259](#), [260](#)
 AniMatte [576](#)
 Chroma Key [576](#)
 luma [262](#)
 Luma Key [577](#)
 Matte Key [262](#), [265](#), [273](#), [577](#)
 overview of reference information [575](#)
 RGB Keyer [578](#)
 SpectraMatte [578](#)
 Key effects (3D)
 3D matte keys [364](#)
 Keyboard shortcuts
 saving titles with [421](#)
 Keyframe graphs [101](#), [104](#), [105](#), [106](#), [107](#)
 [110](#), [123](#), [128](#), [130](#), [133](#), [138](#), [139](#), [146](#)

Keyframe tracks [101](#), [104](#)
 Keyframes
 See also Advanced keyframes
 adding in keyframe graphs [113](#)
 changing parameters [148](#)
 copying and pasting [148](#)
 creating [148](#)
 defined [101](#)
 deleting [148](#)
 for adjusting titles [438](#)
 moving [148](#)
 selecting [148](#)
 with Intraframe effects [500](#)
 Keyframes, advanced
 Color Correction monitor [785](#)
 color correction parameters [784](#)

L

Large Text command (Effect Editor shortcut menu)
 [146](#)
 Layered effects [251](#)
 Layering
 Intraframe objects [501](#)
 titles [418](#)
 L-Conceal effects
 Bottom Left [579](#)
 Bottom Right [579](#)
 overview of reference information [579](#)
 Top Left [579](#), [579](#)
 Top Right [579](#)
 Leading
 title text [399](#)
 Left Box Box Wipe effect [559](#)
 Left Centered Squeeze effect [591](#)
 Left to Right Conceal effect [560](#)
 Left to Right Peel effect [582](#)
 Left to Right Push effect [585](#)
 Left to Right Squeeze effect [591](#)
 Letterboxing [281](#)
 Levels effect parameter
 Avid Pan & Zoom effect [656](#)
 Lightning Illusion FX effect [565](#)
 Limitations
 playing fast rolling titles [438](#)
 Line tool (Title tool) [400](#)
 Linear keyframe interpolation option [133](#)

- Linear Path option
 - Avid Pan & Zoom effect [654](#)
 - Linear Velocity option
 - Avid Pan & Zoom effect [653](#)
 - Lines
 - attribute options [408](#)
 - in titles [400](#)
 - Locating AVX_Plug-Ins folder (Macintosh) [187](#)
 - Locating AVX_Plug-Ins folder (Windows) [188](#)
 - Lock command (Object menu) [418](#), [501](#)
 - Locked objects
 - hollow handles indicating [418](#)
 - Locking and unlocking
 - Intraframe objects [501](#)
 - objects in titles [418](#)
 - Lower Left Diagonal Edge Wipe effect [561](#)
 - Lower Right Diagonal Edge Wipe effect [561](#)
 - Lowlight Color effect parameters [714](#)
 - Luma Adjust effect parameters [658](#)
 - Luma Clip effect parameters [660](#)
 - Luma Control effect parameters (SpectraMatte effect) [687](#)
 - Luma Key Key effect [577](#)
 - Luma Range effect parameters [659](#)
 - Luminance
 - defined [604](#)
 - of color effect [658](#)
 - Luminance limits for broadcast [813](#)
- ## M
- Macintosh Colors panel [96](#), [412](#)
 - using with Color Match control [756](#)
 - Magic Mask effect parameters [612](#)
 - Magic Mask parameters (2D)
 - colorizing with [519](#)
 - Magnified image
 - moving in Effect Preview monitor [87](#)
 - Make Crawl command
 - for crawling titles [404](#)
 - Mapping
 - trackers [321](#), [322](#)
 - Mark IN and Mark OUT buttons
 - using in titles [437](#)
 - Marks
 - using with color correction [740](#)
 - Marquee Title tool
 - converting title styles to [428](#)
 - described [383](#)
 - opening [382](#)
 - promoting titles to [440](#)
 - Mask effect parameters (FluidMotion Edit) [700](#)
 - Mask Film effect [562](#)
 - Mask Image effect [573](#)
 - Master clips
 - imported [265](#)
 - Match Frame button [201](#)
 - Match Type menu
 - in Color Match control [759](#)
 - Matrix Wipe effects
 - Grid [580](#)
 - One-Way Row [580](#)
 - overview of reference information [580](#)
 - Speckle [580](#)
 - Spiral [580](#)
 - Zig-Zag [580](#)
 - Matte Analysis effect parameters (SpectraMatte effect) [681](#)
 - Matte Control effect parameters (RGB Keyer effect) [679](#)
 - Matte key
 - exporting as PICT file [503](#)
 - Matte Key effect (2D)
 - applying [525](#)
 - promoting to 3D [364](#)
 - Matte Key effect (3D)
 - using [364](#)
 - Matte Key Key effect [577](#)
 - Matte Processing effect parameters (SpectraMatte effect) [689](#)
 - Mattes
 - preparing for key effects [265](#)
 - Media Creation tool [172](#)
 - Media drives
 - speed limitations with real-time effects preview [152](#)
 - Media files [181](#), [183](#)
 - Media Station
 - rendering effects for [177](#)
 - Melt Illusion FX effect [568](#)
 - Memory usage
 - Avid Pan & Zoom effect [304](#)
 - Memory usage for AVX plug-in effects [186](#), [192](#)
 - Menu commands

- Add Page (Object menu) 405
- Auto Size Mode (Object menu) 402
- Bring Forward (Object menu) 501
- Bring to Front (Object menu) 501
- Copy to Page (Object menu) 405
- Export Title (File menu) 430
- Fast Frame Display (Special menu) 505
- Group (Object menu) 501
- Insert Page (Object menu) 405
- Lock (Object menu) 501
- Move to Page (Object menu) 405
- Re-create Titles and Mattes (Clip menu) 442
- Remove Page (Object menu) 405
- Send Backward (Object menu) 501
- Send to Back (Object menu) 501
- UnGroup (Object menu) 501
- Unlock (Object menu) 501
- Millivolt units for color correction 740
- Mode effect parameters (AniMatte effect) 676
- Mode effect parameters (FluidMotion Edit) 701
- Mode effect parameters (Paint effect) 663
- Modes
 - for Intraframe editing 474
- Modes for Paint Effect 664
- Modifying
 - ExpertRender results 164
 - results of Render to Media Station 177
 - rolling or crawling titles 407
- Monitors
 - 16:9 display in Color Correction mode 730
 - Avid After Effects External Monitor Preview
 - plug-in 194
 - color correction, customizing image display 731
 - Pan and Scan effect 287
 - reference frame display in Color Correction mode 731
 - safe color warnings in 817
 - source menu in Color Correction mode 731, 731
- Mosaic effect (2D)
 - creating 532
 - described 467
 - parameters 531
- Mosaic Effect Image effect 571
- Mosaic effect parameters 663
- Motion Adapter effects
 - Adaptive deinterlacing option 219
- Motion Blur Illusion FX effect 565
- Motion Effect button 201
- Motion Effect Editor 215, 219, 226, 228
- Motion effect parameters
 - overview of reference information 694
- Motion effect parameters (Illusion FX Ripple effect) 644
- Motion effects
 - creating 199, 213
 - Freeze Frame 199, 581
 - freezing a rolling clip 201
 - overview 198
 - overview of reference information 581
 - playback 207
 - promoting to Timewarp 213
 - rendering 207, 210
 - reversing 695
 - sizing to fit 204
 - Strobe Motion 204, 581
 - Timewarp 210
 - traditional, playback of 581
 - Variable Speed 201, 204, 581
- Motion path
 - Pan and Scan effect 290
- Motion path editor 368
- Motion paths for effects 98
- Motion tracking
 - available effects and parameters 311
 - conforming data from Symphony Meridien
 - system 356
 - copying and pasting data 354
 - editing segments with tracking data 352
 - enabling 319
 - examples 356
 - generating data 328
 - interface 312
 - manipulating data points 338
 - offset tracking 330, 331, 332
 - overview 308
 - playback of effects 344
 - preparations for generating tracking data 318
 - reference frames 335
 - reusing data 354
 - selecting image areas 325
 - set-up 317, 324, 326
 - smoothing data 336, 337
 - trackers 321, 322, 323
 - tracking data 332, 334

- tracking engines [327](#)
- Tracking window [314](#), [315](#)
- workflow [310](#)
- Movement effect parameters (Illusion FX Sparkler effect) [649](#)
- Moving
 - advanced keyframes [123](#)
 - keyframes [148](#)
 - perspective point of 3D effects [714](#)
 - tracking boxes [324](#)
 - tracking data points [338](#)
- Multiformat titles [282](#)
- Multilayer effects (3D)
 - 3D Matte Key [364](#)
- Multiple tracks in AVX plug-in effects [190](#)
- mVolt (millivolt) units for color correction [740](#)

N

- NaturalMatch
 - described [760](#)
 - example of use [760](#)
- Nested effects [267](#), [269](#), [270](#), [271](#), [273](#)
 - changing the order of [272](#)
- Nesting Priority icon [272](#)
- New Title command (Clip menu) [382](#)
- New Tracker button (Tracking window) [315](#)
- New Video Track command (Clip menu) [433](#), [434](#), [435](#)
- NTSC (National Television System Committee) video
 - frame size and safe title/action guidelines [390](#)
- Number effect parameters (Illusion FX Pattern Generator effect) [641](#)

O

- Objects
 - aligning in the Title tool [418](#)
 - locking and unlocking [418](#)
- Offset effect parameters (Illusion FX Kaleidoscope effect) [632](#)
- Offset tracking [330](#), [331](#), [332](#)
- One-Way Row Matrix Wipe effect [580](#)
- Online support [18](#)
- OpenGL [154](#)
- Opening

- keyframe graphs and tracks [104](#)
- Marquee [382](#)
- Title tool [382](#)
- Tracking window [314](#)
- Optical list [85](#)
 - with Previsualization Marker tool information [494](#)
- Other Options (Avid Pan & Zoom effect) [652](#)
- Other Options button (Effect Editor) [90](#), [96](#)
- Outline/Path button (Effect Editor) [90](#)
- Oval tool for Intraframe editing [479](#)

P

- Page count limits
 - for rolling and crawling titles [401](#)
- Page Curl effect (3D)
 - as transition [371](#)
- Page Fold Shape effect [718](#)
 - angle value examples [722](#)
 - controlling image on flap [722](#)
 - softening edges [722](#)
- Page number display
 - in Title tool [405](#)
- Pagecurl Illusion FX effect [568](#)
- Paint Effect [85](#)
 - modes [664](#)
- Paint Effect (2D)
 - applying [470](#)
 - creating signature effect [478](#)
 - described [467](#)
 - example of Blur mode [522](#)
 - modes [474](#)
 - painting with Brush tool [475](#)
 - parameters for [470](#)
 - rendering [469](#)
 - selecting color [475](#)
 - using Magic Mask parameters [519](#)
- Paint Image effect [573](#)
- PAL (Phase Alternating Line) video
 - frame size and safe title/action guidelines [390](#)
- Pan & Zoom
 - See* Avid Pan & Zoom effect
- Pan and Scan effect [282](#), [284](#), [287](#), [288](#), [289](#), [290](#), [291](#), [292](#)
- Pan and Scan Reformat effect [586](#)
- Pan and Zoom
 - See* Avid Pan & Zoom effect

- Panning
 - Avid Pan & Zoom effect [296](#), [653](#)
 - keyframe graphs [110](#)
- Parameters
 - Blur effect [532](#)
 - Mosaic effect [532](#)
- Parameters (2D)
 - Acceleration [531](#)
 - Blur effect [531](#)
 - Feathering [531](#), [532](#)
 - Mosaic effect [531](#)
 - Paint Effect [470](#)
- Parameters (3D)
 - accessing [361](#)
 - adjustment handles [368](#)
 - Target [725](#)
- Parameters for effects [89](#), [90](#), [94](#), [95](#), [96](#), [96](#)
 - See Effect parameters
- Partial render [171](#)
- Particle Blast Illusion FX effect [568](#)
- Particle Orbit Illusion FX effect [568](#)
- Particle Wind Illusion FX effect [568](#)
- Paste command
 - for title elements (Edit menu) [418](#)
- Pasting
 - advanced keyframes [128](#), [130](#)
 - keyframes [148](#)
- Path
 - in effect motion [368](#)
- Path effect parameter (Avid Pan & Zoom effect) [654](#)
- Path effect parameter for Intraframe editing [607](#)
- Pattern Generator Illusion FX effect [565](#)
- Peel effects
 - Bottom Left Corner [582](#)
 - Bottom Right Corner [582](#)
 - Bottom to Top [582](#), [582](#)
 - Left to Right [582](#)
 - reference [582](#)
 - Right to Left [582](#)
 - Top Left Corner [582](#)
 - Top Right Corner [582](#)
- Pen tool for intraframe editing [473](#)
- Perspective effect parameters [714](#)
- Picture-in-Picture Blend effect [558](#)
- Picture-in-Picture effect [98](#)
- Pinch Illusion FX effect [565](#)
- PlasmaWipe effects [584](#)
- applying [538](#)
- creating from a custom image [538](#)
- creating from an existing image [540](#)
- default values [548](#)
- folder structure [537](#), [546](#)
- frame and border effects [548](#)
- HD project versions [553](#)
- PAL and NTSC versions [538](#), [545](#)
- testing an animation [544](#)
- threshold point [535](#), [535](#)
- tips for adjusting [546](#), [547](#)
- using the Adobe Photoshop histogram [542](#)
- using the Adobe Photoshop Pencil tool [541](#)
- using the Level value [535](#)
- working with Adobe Photoshop [538](#)
- working with gradient images [538](#)
- Play button [50](#)
- Play button (Effect Editor) [90](#)
- Play button (Effect Preview monitor) [79](#)
- Play button (Motion Effect Editor) [219](#)
- Play Loop button [50](#)
 - function in Color Correction mode [734](#)
- Play Loop button (Effect Editor) [90](#)
- Play Loop button (Effect Preview monitor) [79](#)
- Play Loop button (Motion Effect Editor) [219](#)
- Play Preview button [50](#)
- Play Preview button (Effect Preview monitor) [79](#)
- Playback
 - video effects [151](#), [152](#), [153](#), [154](#), [156](#), [157](#), [162](#)
- Playback capabilities for effects [51](#)
- Playback of effects
 - Submaster restriction [575](#)
- Playing
 - 3D effects [366](#)
 - effects [50](#), [50](#)
- Plug-in effects [185](#)
- Point size
 - setting for title text [396](#)
- Point size button (Title tool) [396](#)
- Polygon shape creation [479](#)
- Polygon tool for Intraframe editing [479](#)
- Position (3D) effect parameters [715](#)
- Position bar [44](#)
- Position coordinates for effects [84](#)
- Position display for two-field media [81](#)
- Position effect parameter (Avid Pan & Zoom effect) [653](#)

Position effect parameters [613](#)
Position effect parameters (Rolling Title and Crawling Title effects) [702](#)
Position Graph display button (Timewarp effect) [215](#)
Position graph for Timewarp effects
 activating [215](#)
 scale bars [217](#)
Position H effect parameter (14:9 Letterbox Reformat effect) [697](#)
Position information for film projects and effects [85](#)
Posterization
 of Color Effect [662](#)
Post-key color correction [260](#)
Precompute
 for title effect clip [431](#)
Preview command (Object menu) [389](#)
Previewing
 anti-aliased titles [389](#)
 video effects [151](#)
Previsualization Marker tool
 described [494](#)
 using [494](#)
 with cut list [494](#)
Processing
 effects in real time [151](#)
Profile effect parameter [677](#)
Progressive projects
 Avid Pan & Zoom effect [302](#)
Project window
 managing title styles in [429](#)
Projects
 effects considerations [27](#)
 moving from Macintosh to Windows [384](#)
 moving from Windows to Macintosh [384](#)
Promoting
 2D effects to 3D effects [364](#)
 AVX plug-in effects [189](#)
 effects [44](#)
 traditional motion effect to Timewarp [213](#)
Pulldown Insertion Timewarp effect [594](#)
Pulldown Removal Timewarp effect [594](#)
Push effects
 Bottom Left to Top Right [585](#)
 Bottom Right to Top Left [585](#)
 Bottom to Top [585](#)
 Left to Right [585](#)
 overview of reference information [585](#)

 Right to Left [585](#)
 Top Left to Bottom Right [585](#)
 Top Right to Bottom Left [585](#)
 Top to Bottom [585](#)

Q

Quad Display command (Color Correction monitor Source menu) [731](#)
Quick Transition button [69](#), [72](#)
Quick Transition dialog box [66](#), [72](#), [74](#)
 creating transitions [69](#)
Quick Transitions [66](#)
Quick Transitions custom bin [69](#)
QuickTime [264](#)

R

Radial Blur Illusion FX effect [565](#)
Random Blend Illusion FX effect [568](#)
Real-time moving mattes [264](#)
Real-time playback of effects [151](#), [152](#), [153](#), [154](#), [156](#), [157](#), [162](#)
Real-Time Update command (Effect Editor shortcut menu) [146](#)
Recalling
 title styles [428](#)
Re-create Titles and Mattes command (Clip menu) [442](#)
Re-creating
 titles [442](#)
Rectangle tool for Intraframe editing [479](#)
Reduce button (Effect Editor) [90](#), [98](#)
Reduce button (Effect Preview monitor) [79](#)
Reference command (Color Correction monitor Source menu) [731](#)
Reference Current command (Color Correction shortcut menu) [731](#)
Reference frames
 displaying in Color Correction monitors [731](#)
Reference frames for motion tracking [335](#)
Reformat effect parameters
 overview of reference information [697](#)
Reformat effects
 14:9 Letterbox [586](#)
 16:9 Letterbox [586](#)
 4:3 Sidebar [586](#)

- overview of reference information 586
- Pan and Scan 586
- Region Stabilize effect 350, 352
- Remove Color Cast buttons (Color Correction tool) 752
- Remove Effect button 39
- Remove Effect button (Color Correction Composer window) 733
- Remove Redundant Keyframes command (Keyframe track shortcut menu) 116
- Removing
 - redundant keyframes 116
 - titles from a sequence 436
- Removing color casts
 - guidelines for 804
- Render at Position command (Clip menu) 54, 60
- Render Effect button 54
- Render Effect button (Effect Editor) 90
- Render In/Out command (Clip menu) 54, 60
- Render Mode effect parameter (Avid Pan & Zoom effect) 658
- Render On-the-Fly 52
- Render On-the-Fly command (Special menu) 52
- Render Ranges command (Timeline Fast menu) 171
- Render settings 167, 168, 172, 176
- Rendered effects
 - viewing in bins 431
- Rendering
 - 16-bit effects processing 172
 - after real-time playback attempt 162
 - AniMatte effects 469
 - Avid Pan & Zoom effect 302
 - AVX plug-in effects 192
 - clearing rendered effects 58
 - defined 24
 - displaying estimated time 57
 - during Intraframe editing 469
 - effects 53, 54
 - HQ effects 176
 - interrupting 171
 - motion effects 168
 - Paint Effect 469
 - partial 171
 - Submaster restriction 575
 - Timewarp effects 210, 223
 - titles 441
 - using ExpertRender 160
 - using Render to Media Station 177
- Rendering on-the-fly
 - while trimming 30
- Replacing
 - existing effects 78
 - title fill tracks 441
 - titles in a sequence 437
- Repositioning
 - title text 393
- Rerendering
 - effects 60
- Reset Graph View command (shortcut menu for keyframe track) 110
- Resetting
 - Color Correction tool controls 737
 - keyframe graph view 110
- Reshape tool for Intraframe effects 497
- Resize handles for effects 98
- Resize Image effect 573
- Resizing
 - Effect Palette 26
 - keyframe graphs 106
 - rolling or crawling titles 404
 - title text 393
 - tracking boxes 324
- Restorative color correction guidelines 801
- Reusing
 - tracking data 354
- Reveal File command (File menu) 181
- Revealing
 - effect media files 181
- Reverse Animation option 609
- Reverse Motion Timewarp effect 595
- Reversing
 - advanced keyframes 137
 - motion effects 201, 695
- Reviewing a stabilized image 348
- Revising
 - titles in a bin 424
 - titles in a sequence 440
- Rewind button (Effect Preview monitor) 79
- RGB gamut limit type
 - described 813
- RGB Histogram command (Color Correction monitor Source menu) 731
- RGB Histogram display (Color Correction monitors) 787

RGB Keyer Key effect [578](#)
 RGB Levels effect parameters (Safe Color Limiter effect) [673](#)
 RGB levels option
 Avid Pan & Zoom effect [656](#)
 RGB Parade command (Color Correction monitor Source menu) [731](#)
 RGB Parade display (Color Correction monitors) [787](#)
 RGB values
 displaying with the Color Match control [762](#)
 Right Box Box Wipe effect [559](#)
 Right Centered Squeeze effect [591](#)
 Right to Left Conceal effect [560](#)
 Right to Left Peel effect [582](#)
 Right to Left Push effect [585](#)
 Ripple Illusion FX effect [565](#)
 Rolling Title button (Title tool) [386](#), [403](#)
 Rolling Title effect [598](#)
 Rolling titles
 See also Crawling titles
 See also Titles
 adding pages [405](#)
 creating [401](#)
 defined [401](#)
 deleting pages from [405](#)
 duration [437](#)
 formatting text in [407](#)
 going to a page in [405](#)
 inserting a blank page into [405](#)
 page count limits for [401](#)
 playback limitations [438](#)
 resizing width of [404](#)
 scrolling through [404](#)
 setting marks in [437](#)
 setting text formatting for [403](#)
 trimming [438](#)
 typing text for [403](#)
 Rollup Illusion FX effect [568](#)
 Rotation axes (3D) [366](#)
 Rotation effect parameters [716](#)

S

Safe Color Limiter effect
 adjusting [824](#)
 analysis display [825](#)
 applying [824](#)

 described [823](#)
 Safe Color Limiter Image effect [574](#)
 Safe Color Settings button [819](#)
 Safe Color Settings dialog box [819](#)
 Safe Colors
 adjusting color to achieve safe limits [820](#)
 graphical view of settings [815](#)
 overview [813](#)
 setting options for [814](#), [819](#)
 understanding warnings [817](#)
 warnings in monitors [817](#)
 warnings in the Color Match control [817](#)
 Safe Colors button (Color Correction tool) [814](#)
 Safe Colors command (Object menu) [391](#)
 Safe Title Area/Global Grid command (Object menu) [390](#)
 Safe title/action area [82](#)
 for aligning objects [418](#)
 Title tool [390](#)
 Saturation
 defined [604](#)
 of colors in titles [389](#), [391](#)
 Save Title As command (File menu) [421](#), [424](#)
 Save Title command (File menu) [421](#)
 Save Title dialog box [421](#)
 Saving
 color correction effect templates to buckets [744](#)
 effect templates [47](#)
 multiple titles [421](#)
 partially completed renders [171](#)
 title styles [427](#)
 titles, basic procedure [421](#)
 titles, overview [421](#)
 titles, with a keyboard shortcut [421](#)
 titles, with Fast Save option [421](#)
 Sawtooth Wipe effects
 Horizontal Open Sawtooth [587](#)
 Horizontal Sawtooth [587](#)
 overview of reference information [587](#)
 Vertical Open Sawtooth [587](#)
 Vertical Sawtooth [587](#)
 Scaling
 keyframe graphs [107](#)
 Scaling (3D) effect parameters [717](#)
 Scaling effect parameters [614](#)
 Scaling Intraframe objects [499](#)

- Scratch effect parameters (Scratch Removal effect) 674
- Scratch removal
 - finding flaws from telecine transfer 505
 - frame or field processing 508
 - isolating flaws 509
 - parameter setting examples 516
 - removing flaws 510, 512
 - selecting clean material 505
 - using effect parameters 515
 - using IN and OUT points 514
 - using nearby frame or field 505
 - within single frame or field 505
 - workflow for 505
- Scratch Removal button 509
- Scratch Removal effect (2D)
 - described 467
- Scratch Removal Image effect 574
- Scroll Position H effect parameter (Crawling Title effect) 702
- Scroll thumbwheel for keyframe graphs 110
- Scrolling
 - keyframe graphs 110
 - through rolling or crawling titles 404
- Secondary Key effect parameters (Chroma Key effect) 678
- Segment
 - in Intraframe objects 485
- Select Unrendered Title command (Bin menu) 421
- Selecting
 - keyframes 148
 - tracking data points 338
- Selection tool
 - for grouping objects 418
 - for ungrouping objects 418
 - with Intraframe editing 483
- Selection tool (Title tool)
 - defined 388
 - text options for titles 395
 - viewing attributes with 394
- Send Backward button (Effect Editor) 501
- Send Backward command (Object menu) 418, 501
- Send to Back command (Object menu) 418, 501
- Sequences
 - applying color correction to 796
 - promoting and demoting effects 44
 - removing redundant keyframes 116
 - removing titles from 436
 - replacing titles in 437
 - title editing in 432
- Set Bin Display command (Bin menu) 181, 431
- Set Position To Keyframe command (Effect Editor shortcut menu) 146
- Settings
 - Effect Aperture 31
 - Render 167
 - Title Styles 429
- Shadow Depth and Direction button (Title tool) 415
- Shadow effect parameters 717
- Shadow softness
 - adjusting in titles 416
 - viewing current setting 416
- Shadows
 - title 415
- Shape effect parameters 718
- Shape effects
 - Ball 718
 - effect visibility 722
 - location of position indicator 722
 - Page Fold 718
 - Slats 718
- Shape Wipe effects
 - 4 Corners 588
 - Center Box 588
 - Circle 588
 - Clock 588
 - Diamond 588
 - Ellipse 588
 - Horizontal Bands 588
 - Horizontal Blinds 588
 - overview of reference information 588
 - Vertical Blinds 588
- Sharpness of focus for 3D effects 708
- Shear Illusion FX effect 568
- Shelf keyframe interpolation option 133
- Shortcuts
 - saving titles with keyboard 421
- Show Action Safe option for Avid Pan & Zoom 652
- Show Add Keyframe Mode Menu command (Effect Editor shortcut menu) 146
- Show Alignment Grid command (Alignment menu) 391
- Show Alpha option 609
- Showing

- advanced keyframe graph display [104](#)
- Single-field step [88](#)
- Size effect parameter (Avid Pan & Zoom effect) [653](#)
- Size of effect
 - adjusting [725](#)
- Sizing
 - effects [40](#)
- Skew effect parameters [723](#)
- Slats Shape effect [718](#)
- Slider controls (Effect Editor) [94](#)
- Slip Keyframe command (shortcut menu for keyframe track) [128](#)
- Slipping
 - advanced keyframes [126](#)
- Slow motion effect [201](#)
- Smooth Selected Points button (Tracking window) [315](#)
- Snap to Grid command (Alignment menu) [391](#)
- Soft shadows
 - adding to titles [416](#)
- Soften Shadow command (Object menu) [416](#)
- Softness effect parameter for borders [606](#)
- Solarization
 - of Color Effect [662](#)
- Source Anchor Frame for Timewarp effects [218](#)
- Source effect parameters (Illusion FX FluidMorph effect) [630](#)
- Source Has Square Pixels option
 - Avid Pan & Zoom effect [656](#)
- Source menu (Color Correction monitors) [731](#)
- Source mode
 - Avid Pan & Zoom [652](#)
- Source Monitor Analysis effect parameters (Safe Color Limiter effect) [672](#)
- Sparkler Illusion FX effect [565](#)
- Speckle Matrix Wipe effect [580](#)
- SpectraMatte effect [252](#), [253](#), [255](#), [257](#)
- SpectraMatte Key effect [578](#)
- Speed Boost Timewarp effect [596](#)
- Speed Bump Timewarp effect [596](#)
- Speed Graph display button (Timewarp effect) [215](#)
- Speed graph for Timewarp effects
 - activating [215](#)
 - reference [226](#), [228](#)
 - scale bars [217](#)
- Sphere Illusion FX effect [565](#)
- Spill effect parameters (SpectraMatte effect) [690](#)
- Spill Suppression effect parameters (3D effects) [724](#)
- Spill Suppression effect parameters (Chroma Key effect) [678](#)
- Spin effects
 - overview of reference information [590](#)
 - X Spin [590](#)
 - Y Spin [590](#)
 - Z Spin [590](#)
- Spiral Matrix Wipe effect [580](#)
- Spline keyframe interpolation option [133](#)
- Spline Path option
 - Avid Pan & Zoom effect [654](#)
- Square and Rectangle tool (Title tool) [400](#)
- Squeeze effects
 - Bottom Centered [591](#)
 - Bottom Left [591](#)
 - Bottom Right [591](#)
 - Bottom to Top [591](#)
 - Centered Zoom [591](#)
 - Horizontal Centered [591](#)
 - Left Centered [591](#)
 - Left to Right [591](#)
 - overview of reference information [591](#)
 - Right Centered [591](#)
 - Top Centered [591](#)
 - Top Left [591](#)
 - Top Right [591](#)
 - Top to Bottom [591](#)
- Stabalized image
 - adjusting [348](#)
- Stabilization [349](#)
 - overview [344](#)
- Stabilize Image effect [575](#)
- Stabilized image
 - reviewing [348](#)
- Stabilizing images [346](#)
- Stages of typical color correction [803](#)
- Stamp (3D)
 - clearing [377](#)
 - creating [377](#)
- Stamp effect parameters [724](#)
- Standard keyframes
 - See* Keyframes
- Starting at Cut button (Quick Transition dialog box) [74](#)
- Starting at Cut effect parameter [615](#)
- SteadyGlide [336](#), [337](#)

Step Backward One Field button (Effect Preview monitor) [79](#), [88](#)
 Step Forward One Field button (Effect Preview monitor) [79](#), [88](#)
 Step In button (Timeline) [269](#)
 Step Out button (Timeline) [269](#)
 Stepping
 two-field media [88](#)
 Stretch Points Mode button (Tracking window) [315](#)
 Stretching
 tracking data points [341](#)
 Strobe Motion effect [204](#)
 Strobe Motion effect parameters [695](#)
 Strobe Motion Motion effect [581](#)
 Stylesheets
 for SubCap effect [461](#)
 SubCap effect
 adding information and custom data [455](#)
 adjusting parameters [456](#)
 applying [451](#)
 described [447](#)
 editing text in the Master Caption list [456](#)
 entering text in Effect Editor [452](#)
 exporting data to caption files [458](#)
 global properties [455](#), [457](#), [461](#)
 Global Properties reference [620](#)
 importing caption files [453](#)
 interaction with caption files [449](#)
 parameter adjustment examples [463](#)
 stylesheets [461](#)
 synchronizing parameters and information [457](#)
 Unicode text support [460](#)
 SubCap effect parameters [616](#), [621](#)
 SubCap Generator effect [564](#)
 Subdividing
 Pan and Scan effect [289](#)
 Submaster effect [53](#), [158](#)
 Submaster effects [275](#), [277](#)
 Submaster Image effect [575](#)
 Substituting fonts [384](#)
 Subtitling
 See SubCap effect
 Superimpose Blend effect [558](#)
 Swap Sources option [609](#)
 Swapping effect tracks [710](#)
 Swirl Illusion FX effect [565](#)
 Symphony

conforming tracking data from Meridien systems
[356](#)

T

Tabs

Color Correction tool, described [735](#)
 Color Correction tool, displaying [736](#)
 Controls (HSL group in Color Correction tool)
[763](#)
 Hue Offsets (HSL group in Color Correction tool)
[766](#)

Tail Fade button [64](#)

Target effect parameters [725](#)

Target mode

 Avid Pan & Zoom [652](#)

Target parameters (3D) [725](#)

Templates

color correction, applying [745](#)
 color correction, described [742](#)
 color correction, save behavior for [743](#)
 for titles [425](#)
 saving Effect Palette Color Correction effects as
[799](#)

Templates, effect

See Effect templates

Text

copying and pasting into Title tool [392](#)
 creating in Title tool [392](#)
 title, editing [394](#)
 title, formatting [394](#)
 title, justifying [397](#)
 title, kerning [397](#)
 title, leading [399](#)
 title, repositioning [393](#)
 title, resizing [393](#)

Text formatting

 setting for rolling and crawling titles [403](#)

Text Justification buttons (Title tool) [397](#)

Text tool (Title tool)

 defined [388](#)

Thai language

 Title tool [445](#)

Third-party plug-in effects [185](#)

Threshold point

 PlasmaWipe effects [535](#)

Thumbwheel controls (Effect Editor) [94](#)

- Thumbwheels command (Effect Editor shortcut menu) [146](#)
- Timecode Burn-In Generator effect [564](#)
- Timeline
 - adjusting effects [74](#)
 - changing nested effect order [272](#)
 - color coding for effects [25](#)
 - deleting effects [39](#)
 - dragging titles into [434](#), [435](#)
 - effect icon display [29](#)
 - expanding nested effects [269](#)
 - real-time playback information bars [152](#), [153](#)
- Timeline Settings dialog box [153](#)
- Timeline View Name button (Timeline) [29](#)
- Timewarp effect
 - creating [213](#)
 - customizing [215](#)
- Timewarp effects
 - 0% to 100% [593](#)
 - 100% to 0% [593](#)
 - Adaptive deinterlacing option [219](#)
 - converting formats [248](#)
 - creating [213](#)
 - described [210](#)
 - FluidFilm 2:3 Cadence [594](#)
 - FluidFilm Progressive [594](#)
 - FluidMotion [238](#), [239](#), [246](#), [247](#)
 - FluidMotion Edit effect parameters [698](#)
 - overview of reference information [592](#)
 - Pulldown Insertion [594](#)
 - Pulldown Removal [594](#)
 - reference for Motion Effect Editor [219](#)
 - rendering [223](#)
 - Reverse Motion [595](#)
 - Source Anchor Frame [218](#)
 - Speed Boost [596](#)
 - Speed Bump [596](#)
 - Trim to Fill [598](#)
 - using control graphs [215](#)
- Title effect [599](#)
- Title effects
 - Crawling Title [598](#)
 - overview of reference information [598](#)
 - Rolling Title [598](#)
 - Title [599](#)
- Title styles
 - applying [429](#)
 - converting to Marquee [428](#)
 - defined [426](#)
 - managing in Project window [429](#)
 - recalling [428](#)
 - saving [427](#)
 - using function keys with [427](#)
- Title templates
 - creating and using [425](#)
- Title tool
 - 16:9 display option [385](#)
 - adjusting transparency in [411](#), [412](#)
 - Auto Size mode [402](#)
 - background options [390](#)
 - blending colors in [411](#), [412](#)
 - blending transparency in [411](#)
 - character mapping [445](#)
 - Color Picker [412](#)
 - Crawling Title button [403](#)
 - creating text [392](#)
 - described [385](#)
 - drawing graphics [400](#)
 - editing text [394](#)
 - formatting text [394](#)
 - opening [382](#)
 - overview [383](#)
 - pasting text into [392](#)
 - preparing drawing environment [389](#), [391](#)
 - repositioning text [393](#)
 - resizing text [393](#)
 - Rolling Title button [403](#)
 - safe title/action area display [390](#)
 - selecting fonts in [395](#)
 - Selection tool, defined [388](#)
 - setting color in [411](#), [412](#)
 - setting point size in [396](#)
 - setting transparency in [411](#), [412](#)
 - Text tool, defined [388](#)
 - toolbar overview [386](#)
 - updating video background in [390](#)
 - video tracks as background [390](#)
 - working with shadows [415](#)
- Title Tool command (Windows menu) [382](#)
- Titles
 - See also* Crawling titles
 - See also* Rolling titles
 - adding pages to [405](#)
 - adding shadows to [415](#)

- adjusting in Effect Editor 438
- adjusting using keyframes 438
- aligning 418
- applying styles 429
- bold text in 396
- color of background 390
- copying or moving objects to 405
- crawling, defined 401
- creating a glow or halo effect 416
- creating color background for 390
- creating media for unrendered 443
- creating rolling or crawling 401
- distributing 418
- dragging into Timeline 434, 435
- editing into a sequence 432
- effect clips, described 431
- exporting as a graphics file 430
- fading 437
- fast saving 421
- fast-saved, and EDLs 421
- formatting rolling or crawling 407
- grouping and ungrouping 418
- inserting a blank page into a rolling or crawling 405
- italic text in 396
- kerning of text in 397
- layering of 418
- locking and unlocking 418
- managing fonts for 384
- managing styles in Project window 429
- overview of creation 383
- page count limits for rolling or crawling 401
- previewing 389
- promoting to Marquee 440
- recalling styles 428
- re-creating 442
- removing from a sequence 436
- rendering 441
- replacing fill tracks 441
- replacing in a sequence 437
- resizing rolling or crawling width of 404
- revising in a sequence 440
- revising in bin 424
- rolling or crawling, adding pages 405
- rolling or crawling, deleting pages from 405
- rolling or crawling, going to a page in 405
- rolling, defined 401
- saving 421
- saving multiple 421
- saving styles 427
- saving with keyboard shortcut 421
- saving, overview 421
- scrolling through rolling or crawling 404
- setting marks in rolling or crawling 437
- setting text formatting for rolling or crawling 403
- soft shadows with 416
- splicing into a sequence 433
- templates for 425
- troubleshooting 443
- typing rolling or crawling text for 403
- unrendered 421
- viewing Fast saved in bin 421
- workflow options for crawling 401
- Tonal range
 - automatic color correction of 751
 - guidelines for correcting 803
- Toolbars
 - Title tool 386
- Top Box Box Wipe effect 559
- Top Centered Squeeze effect 591
- Top Left Corner Peel effect 582
- Top Left L-Conceal effect 579
- Top Left Squeeze effect 591
- Top Left to Bottom Right Box Wipe effect 559
- Top Left to Bottom Right Conceal effect 560
- Top Left to Bottom Right Push effect 585
- Top Right Corner Peel effect 582
- Top Right L-Conceal effect 579
- Top Right Squeeze effect 591
- Top Right to Bottom Left Box Wipe effect 559
- Top Right to Bottom Left Conceal effect 560
- Top Right to Bottom Left Push effect 585
- Top to Bottom Conceal effect 560
- Top to Bottom Push effect 585
- Top to Bottom Squeeze effect 591
- Tracker Close button (Tracking window) 315
- Tracker regions 331
- Tracking boxes 325
- Tracking button (Tracking window) 315
- Tracking data 332, 334, 338, 341
 - conforming from Symphony Meridien systems 356
 - copying and pasting 354
 - generating 328

- preparing to generate 318
 - reusing 354
 - smoothing 337
- Tracking effect parameters 614, 707
- Tracking engines
 - described 327
- Tracking information 81
- Tracking window 314, 315
 - setting up tracking 326
- Tracks
 - video, as background in Title tool 390
- Tracks of video
 - gain levels 676
 - swapping 3D effects on 710
 - swapping background and foreground (3D) 370
- Trail effect parameters 726
- Training services 19
- Transition Corner Display button 74
- Transition Effect Alignment button 64
- Transition Effect Alignment button (Effect Editor) 90
- Transition Effect Duration box (Effect Editor) 90
- Transition effect parameters 615
 - Centered on Cut alignment 615
 - Custom Start alignment 615
 - Ending at Cut alignment 615
 - Starting at Cut alignment 615
- Transition effects
 - Pan and Scan effect 292
- Transition effects (3D)
 - with Page Curl (3D) 371
- Transition parameters
 - using to apply dissolve effects 64
- Transitions
 - creating with the Quick Transition dialog box 69
- Transparency
 - adjusting in titles 411, 412
 - blending in titles 411
 - setting for titles 411, 412
- Transparency of effects
 - controlling with Foreground effect parameter 609
- Triangular opener
 - keyframe graphs and tracks 104
- Triangular opener (Effect Editor) 90
- Trim Left 1 Frame button 148
- Trim Left 10 Frames button 148
- Trim Right 1 Frame button 148
- Trim Right 10 Frames button 148

- Trim to Fill Timewarp effect 598
- Trimming
 - crawling titles 438
 - rendering on-the-fly 30
 - rolling titles 438
 - segments with tracking data 352
- Troubleshooting 18
 - AVX plug-in effects 192
 - titles 443
- True Type fonts 384
- Twist Illusion FX effect 565
- Two-field media
 - safe color warnings with 817
- Typing text for rolling and crawling titles 403

U

- UnGroup command (Object menu) 418, 501
- Unicode text
 - in SubCap effect 460
- Units of measurement
 - defining for Color Correction tool 740
- Unlock command (Object menu) 418, 501
- Unrendered titles
 - creating media for 443
 - saving 421
- Update Position While Playing command (Effect Editor shortcut menu) 146
- Update rate of Strobe effect 695
- Upgrading
 - AVX plug-in effects 189
- Upper Left Diagonal Edge Wipe effect 561
- Upper Right Diagonal Edge Wipe effect 561
- Use Tracking button (Effect Editor) 319
- User interfaces for AVX plug-in effects 191

V

- Variable Speed effect parameters 695
- Variable Speed Motion effect 581
- Vector-based objects
 - creating 485
 - described 485
- Vectorscope command (Color Correction monitor Source menu) 731
- Vectorscope display (Color Correction monitors) 787
- Vectorscope monitor (Color correction)

- displaying [787](#)
- Vectorscope monitors (Color Correction)
 - using to achieve safe color limits [821](#)
- Vectorscope monitors (Color correction)
 - described [787](#)
 - guidelines for use [795](#)
- Velocity effect parameter (Avid Pan & Zoom effect) [653](#)
- Vertical Blinds Shape Wipe effect [588](#)
- Vertical Edge Wipe effect [561](#)
- Vertical Open Edge Wipe effect [561](#)
- Vertical Open Sawtooth Sawtooth Wipe effect [587](#)
- Vertical Sawtooth Sawtooth Wipe effect [587](#)
- Vertical zoom slider for keyframe graphs [107](#)
- Video
 - background, updating in Title tool [390](#)
 - tracks, as background in Title tool [390](#)
 - using as fill for titles and graphics [441](#)
- Video background
 - Avid Pan & Zoom effect [656](#)
- Video Background button (Title tool) [390](#)
- Video Display Settings dialog box [154](#)
- Video mixdown [278](#)
- Video Quality button and menu (Timeline bottom toolbar) [157](#)
- Video Quality Menu button (Timeline bottom toolbar) [156](#)
- Video Underrun error messages [154](#)

W

- Warnings
 - in monitors [817](#)
 - safe color [817](#)
 - safe color, in Color Match control [817](#)
- Wave Illusion FX effect [565](#)
- Waveform commands (Color Correction monitor Source menu) [731](#)
- Waveform display (Color Correction monitors) [787](#)
- Waveform monitors (Color Correction)
 - using to achieve safe color limits [821](#)
- Waveform monitors (Color correction)
 - described [787](#)
 - displaying [787](#)
 - guidelines for use [795](#)
- White point adjustments
 - guidelines for [803](#)

- Wide-screen display
 - in the Title tool [385](#)
- Windows Color dialog box [96](#), [412](#)
 - using with Color Match control [756](#)
- Wire frame
 - Pan and Scan effect [290](#)
- Wire frames for effects [98](#)
- Workflows
 - color correction [747](#)
 - Media Station [177](#)
 - motion tracking [310](#)
 - options for crawling titles [401](#)

X

- X Only button (Effect Editor Position parameter) [343](#)
- X Spin Spin effect [590](#)
- X Y Z coordinate system [366](#)
- Xpress 3D effect category [363](#)
- Xpress 3D effects [599](#)

Y

- Y Only button (Effect Editor Position parameter) [343](#)
- Y Spin Spin effect [590](#)
- Y Waveform command (Color Correction monitor Source menu) [731](#)
- Y Waveform display (Color Correction monitors) [787](#)
- YC Waveform command (Color Correction monitor Source menu) [731](#)
- YC Waveform display (Color Correction monitors) [787](#)
- YCbCr Histogram command (Color Correction monitor Source menu) [731](#)
- YCbCr Histogram display (Color Correction monitors) [787](#)
- YCbCr Parade command (Color Correction monitor Source menu) [731](#)
- YCbCr Parade display (Color Correction monitors) [787](#)

Z

- Z Spin Spin effect [590](#)
- Zig-Zag Matrix Wipe effect [580](#)
- Zoom Factor for Avid Pan & Zoom effect [653](#)

Zoom to Curve Height button (Effect Editor keyframe graphs) [108](#)

Zooming

Avid Pan & Zoom [296](#)

Avid Pan & Zoom effect [653](#)

Effect Preview monitor [98](#)

keyframe graphs [107](#)

Z-Rotation [532](#)

Z-rotation tool for intraframe effects [498](#)



Avid
75 Network Drive
Burlington, MA 01803-2756 USA

Technical Support (USA)
Visit the Online Support Center at
www.avid.com/support

Product Information
For company and product information,
visit us on the web at www.avid.com